


JULY 1986

VOL. 4, No. 6 \$3.95

FOR IBM PERSONAL COMPUTER USERS

TECH JOURNAL.



ANIMATION TECHNIQUES

Optimal Performance on the CGA



5251 EMULATION

PASCAL COMPILERS

DATA MANAGER: METAFILE



0



TALL TREE SYSTEMS. A Technological Innovator. Always a Step Ahead!

For true industry leadership, look no further than Tall Tree Systems.

We have a history of being first.

We were the first to introduce bankswitching. The first with two megabyte memory boards. The first with I/O modularity in a single slot. The first with 8 MHz speed capabilities. The only maker of single

command EMS boards. The first with a laser printer solution — JLASER — that allows you to do full-page graphics and multiple type fonts on any Canon® or Ricoh® laser engine.

Now, we're first again with memory expansion for the IBM® RT.

Innovation is our tradition. Our trademark is superior technology at the lowest possible price.



TALL TREE SYSTEMS



1120 San Antonio Road • Palo Alto, CA 94303 • (415) 964-1980

CIRCLE NO. 197 ON READER SERVICE CARD

©1986 by Tall Tree Systems. All rights reserved. IBM, RT are registered trademarks of International Business Machines Corp. Canon and Ricoh are registered trademarks of Canon Corp. and Ricoh Corp., respectively.

QNX vs UNIX

A QUESTION OF ARCHITECTURE



What do QNX and UNIX have to do with architectural design?

The design determines the environment in which you and your applications must survive. If the sheer weight of the UNIX operating system brings the PC to its knees, all applications running under it will suffer. Unix was conceived more than a decade and a half ago and the product today is the result of modifications, additions and patches by hundreds of programmers. The result is a large and convoluted piece of software which needs the resources of an AT or more.

QNX's superb performance and compact size is the result of one dedicated design team with a common purpose, and complete understanding of both the software and the environment in which it must run. It runs quickly and efficiently on PC's and soars on an AT. Unlike Unix, QNX is capable of real time performance and is the undisputed choice for real time process control, and office systems. You can buy an OS that offers you a 1 to 3 user dead end on an AT, OR, you can consider QNX which allows you anywhere from 1 to 10 users on both PC's and AT's. And we don't stop there. Unlike other Unix-type systems for PC's, QNX is also a networked operating system. Not a patch-on network, but a fully integrated networking system for up to 255 micros. QNX allows you to start with a single machine and grow if and as required. There are no dedicated file servers and you can attach terminals (users) to any machine. To choose a solution which ignores networking, is closing the door on your future.

Everyone is talking about Unix like systems, but no one wants to abandon the tremendous amount of DOS software available. QNX does not force you to make that decision. You can run either PC DOS 2.1 or 3.1™ as one of QNX's many tasks. (DOS File compatibility and DOS development tools are also available). Don't misunderstand us. We at Quantum have a great deal of respect for Unix. It was a major force in moving operating systems out of the 1960's and into the 70's. QNX however, was designed in

the 80's and will be a driving force of the 1990's. Over 20,000 systems have been sold since 1982.

Quantum strongly believes that there are good reasons for buying QNX, DOS and Unix. If you want more than DOS and a working alternative to PC Unix, give us a call and we will discuss your needs.

End-Users, VAR's, OEM's and software developers are invited to take the QNX challenge.

- **MULTI-USER:** -10 serial terminals per PC, AT.
- **MULTI-TASKING:** -40 tasks per PC, AT.
- **NETWORKING:** -255 machines.
-up to 10,000 tasks and 2000 users/network.
-2.5 Megabit token ring.
- **REAL TIME:** -2800 task switches/sec (AT).
- **MESSAGE PASSING:** -Intertask communication between any of 1000's of tasks on any machine.
-88K to 110K for QNX.
- **MEMORY:** -Executes as a task under QNX.
- **PC DOS:** -Standard Kernighan and Ritchie.
- **C Compiler:** -Single machine or networked. One to thousands of users. Full resource sharing of disks and devices on all machines.
- **Flexibility:**
- **Support:** -Online update system allows downloading of new releases over the phone.
-Technical support hot line.
- **COST:** -From US \$450
-Call for runtime prices.
- **HARDWARE SUPPORT:** -IBM PC, XT, AT™ (both real & protected) and compatibles.



Moodie Drive HiTech Park 215 Stafford Rd. Ottawa, Ontario, Canada. K2H 9C1 Phone (613) 726-1893

IBM PC, AT, XT AND PC-DOS ARE REG. TM OF INTERNATIONAL BUSINESS MACHINES CORP. UNIX IS A REG. TM OF AT&T BELL LABS

CIRCLE NO. 239 ON READER SERVICE CARD

If you're tired of waiting, you're using the wrong file manager.



Be fast. Btrieve.[®]

If batch jobs and reports turn waiting time to nighttime, then wake up! You're using the wrong file manager.

Btrieve[®] file management hates waiting as much as you do. It's written in assembly language especially for the IBM PC. And based on b-tree file indexing, with automatic balancing for access speed that won't degrade as your database grows. With Btrieve, your applications always run fast. So you'll be out the door faster.

The standard for networking. When your application requires multi-user file sharing, Btrieve/N (network version) sets the standard for the industry's most popular LANs: IBM's PC Network, Netware, PC Net and EtherSeries. And now Btrieve sets the standard for multi-user systems: XENIX, Multi-Link Advanced and others. Btrieve/N offers *safe* network file management that coordinates simultaneous updates and prevents lost data.

Automatic file recovery. Btrieve pro-

vides automatic file recovery after a system crash, so accidents and power failures don't turn into database disasters. Your Btrieve data always comes back intact.

Fully-relational data management. Using SoftCraft's entire family of products gives you a complete, fully-relational database management system. Rtrieve[™] adds report writing capabilities for generating the reports you need. Xtrieve[™] speeds users through database queries with interactive, on-screen menus—no command language or special syntax.

For professional programmers. Btrieve is the fast, reliable answer for all your application development. In any development language—BASIC, Pascal, COBOL, C, FORTRAN and APL. With multikey access to records. Unlimited records per file. Duplicate, modifiable, and segmented keys. With Btrieve, you can develop better applications faster. And know they'll run—*fast*.


NO ROYALTIES

Suggested retail prices: Btrieve, \$245; Btrieve/N, \$595; Xtrieve, \$245; Xtrieve/N, \$595; Rtrieve, \$145; Rtrieve/N, \$345. Requires PC-DOS or MS-DOS 1.X, 2.X, or 3.X.


Btrieve is a registered trademark and Xtrieve and Rtrieve are trademarks of SoftCraft Inc.

SC
SoftCraft Inc.


P.O. Box 9802 #917
Austin, Texas 78766
(512) 346-8380 Telex 358 200

*Data Manager: Metafile*

142

*Approaching the Optimum Pascal*

94

*The 5251 Connection*

76

ANIMATION TECHNIQUES / MICHAEL ABRASH and DAN ILLOWSKY

Realtime animation device drivers, in which performance takes precedence over other considerations such as portability and readability, may require a little more than standard programming practices. A number of drivers for the IBM Color Graphics Adapter are presented, beginning with a conventional implementation and proceeding to some unconventional techniques.

46

THE 5251 CONNECTION / GERRY KAPLAN

Now the PC, PC/XT, and PC/AT can double as an IBM 5251 display station simply by installing an emulation board and its attendant software. Twin-axial 5251 emulation products are reviewed from AST Research, CXI, Digital Communications Associates, IDEAssociates, Quadram Corporation, Ampak Business Systems, and Techland Systems.

76

APPROACHING THE OPTIMUM PASCAL / JEFF DUNTEMANN

Pascal compilers have evolved from ignominious beginnings packaged in plastic bags with no documentation, to a slightly more complete implementation but still with an unfinished feel, and finally to the current, more mature contenders. Seven compilers are evaluated in terms of their effectiveness as an applications language for the professional developer.

94

A BETTER CGA / MICHAEL COVINGTON

A little soldering and wiring will modify the IBM Color Graphics Adapter to improve its display in two ways: The first removes the striping effect that occurs on monochrome monitors running color programs by rendering the CGA's 16 colors as distinct shades of gray; the second selects an alternative character set to the standard font supported by the CGA.

137

A DATA MANAGER THAT SYNTHESIZES TEXT AND DATA / V. JOSEPH BOWMAN

Metafile offers a unique integration of text and data that allows the user to handle text in much the same way that data are manipulated. Another strength of this data manager is its sophisticated user interface. In these areas, Metafile provides the developer with a great deal of power, but these features are tempered by a few weaknesses.

142

9

DIRECTIONS*Objects and Attributes*

15

LETTERS

29

PRODUCT OF THE MONTH*Language Integration*

30

TECH RELEASES

41

TECH NOTEBOOK*Video Function Call Fix*

167

PRODUCT WATCH*XTREE**The Nibbler**Macro Assembler 4.0**KSH-1 Scientific Calculator*

179

READER SERVICE CARD

181

MAIL ORDER

188

TECH BOOK

194

TECH MART

196

CALENDAR

PRODUCTIVITY TOOLS

From Opt-Tech Data Processing

NEW
Version

Opt-Tech Sort™

NEW
Version

ALL NEW Version 3.0 features even faster sorting, record selection, output record reformatting, dBASE III files, comma delimited fields, and much more. This high performance sort/merge/record selection utility can be used as a stand-alone program or called as a subroutine from most languages.

Supports unlimited filesizes, multiple input files and fixed or variable length records. Many special file types are supported including Btrieve and dBASE. Up to nine sort control fields (ascending or descending), all common data types supported. Output files can be combinations of full records, keys or pointers, subsets of the input file fields, and literal values.

Written in assembly language for **high performance**. Example: 4,000 128 byte records sorted to give key and pointer in 30 seconds. **\$149.**

On-Line Help™

A comprehensive utility for adding help windows to your programs. It provides efficient utilities and routines for interfacing your programs with the help system routines and help message libraries.

Help windows are displayed in a fraction of a second. You have total control over the contents of the window, its size and its position on the screen, including the display and border colors.

On-Line Help can be interfaced with interpreted Basic and all popular compilers. **\$149.**

Scroll & Recall™

Allows you to conveniently scroll back through data that has gone off the top of your display screen. Up to 27 screens of data can be recalled or written to a disk file (great for documenting systems operations).

Allows you to easily recall and edit your previously entered DOS commands and data lines without re-typing.

Scroll & Recall is very easy to use. It's a resident utility that's always there when you need it! **\$69.**

All programs IBM PC/XT/AT & MS-DOS compatible.

Visa, M/C, AMEX, Check, Money Order, COD or Purchase Orders accepted.

Quantity and Dealer Discounts Available

To order or to receive additional information write or call:

Opt-Tech Data Processing

P.O. Box 678 - Zephyr Cove, NV 89448
(702) 588-3737

TECH JOURNAL.

VOL. 4, NO. 7

PUBLISHER: Newton Barrett
EDITOR: Will Fastie

EDITORIAL

MANAGING EDITOR: Marjory Spraycar
EXECUTIVE EDITOR: Julie Anderson
TECHNICAL EDITORS: Jeff Dumtemann, Caroline Halliday
ASSOCIATE TECHNICAL EDITOR: Dan Beale
SENIOR COPY EDITOR: Susan Holly
COPY EDITOR: Gail Shaffer
PROOFREADERS: Kathleen Peddicord, Elizabeth Wardlaw
NEW PRODUCTS EDITOR: Carole Autenzio
ADMINISTRATIVE ASSISTANT: Diana Carey
CONSULTING EDITORS: Thomas V. Hoffmann, Richard M. Foard
CONTRIBUTING EDITORS: Steven Armbrust, Michael Covington, Ted Forgeron, Augie Hansen, Ted Mirecki, Max Stul Oppenheimer

ART & PRODUCTION

ART DIRECTOR: Ina Saltz
ASSOCIATE ART DIRECTOR: Sharon Reuter
ASSISTANT ART DIRECTOR: Monique Cubicciotti
ART SECRETARY: Sabrina Reynolds
ADVERTISING PRODUCTION MANAGER: Lisa Franey Ducey
EDITORIAL PRODUCTION COORDINATOR: Eve Hinderer

ADVERTISING SALES

ADVERTISING DIRECTOR: Rita Burke
MARKETING DIRECTOR: Gayl Sorota
MARKETING COORDINATOR: Julie Henderson
ADVERTISING COORDINATOR: Michele Fischetti
DISTRICT MANAGERS: Rosemarie Caruso, Jan Schultz—East Coast; Ted Babr, Bill Bush, Phyllis Egan—West Coast
ACCOUNT REPRESENTATIVES: Pat Toobey, Jane Anderson—East Coast; Arlene Braithwaite—Midwest; Pam Sigal, Jane Anderson—West Coast

CIRCULATION

CIRCULATION MANAGER: Charles Mast
CIRCULATION SALES DEVELOPMENT: Daniel Rosensweig
MEDIA MANAGER: Melinda Kendall

ZIFF-DAVIS PUBLISHING COMPANY

PRESIDENT: Kenneth H. Koppel
SENIOR VICE PRESIDENT, Marketing: Paul Chook
VICE PRESIDENT, Operations: Baird Davis
VICE PRESIDENT, Controller: John Vlachos
VICE PRESIDENT, Creative Services: Herbert Stern
VICE PRESIDENT, Circulation: Alicia Marie Ivans
VICE PRESIDENT, Circulation Services: James Ramaley
VICE PRESIDENT, Marketing Services: Ann Pollak Adelman
VICE PRESIDENT, Development: Seth Alpert
VICE PRESIDENT: Hugh Tietjen
BUSINESS MANAGER: Gary A. Gustafson
PRODUCTION DIRECTOR: Walter J. Terlecki

ZIFF COMMUNICATIONS COMPANY

PRESIDENT: Philip B. Korsant; **EXECUTIVE VICE PRESIDENT:** James D. Dunning, Jr.; **SENIOR VICE PRESIDENTS:** Philip Sine, Kenneth H. Koppel; **VICE PRESIDENTS:** Laurence Usdin, William L. Phillips, J. Malcolm Morris, Steven C. Feinman; **TREASURER:** Selwyn Taubman; **SECRETARY:** Bertram A. Abrams

EDITORIAL OFFICE

PC TECH JOURNAL, The World Trade Center, Suite 211, Baltimore, MD 21202.
301/576-0770. FAX (group 3): 301/576-9603. MCIMail: PCTECH. PCTECHline:
301/576-PCTJ (7285). Telex: 6502565932 MCL

ADVERTISING OFFICES

(East Coast/Midwest) One Park Ave., New York, NY 10016. 212/503-5185.
(West Coast) 3460 Wilshire Blvd., Los Angeles, CA 90010. 213/387-2100;
11 Davis Drive, Belmont, CA 94002. 415/598-2290.

SUBSCRIPTION INQUIRIES


PC TECH JOURNAL, P.O. Box 2968, Boulder, CO 80321. Subscription service:
800/525-0643, 303/447-9330. Back issues: send \$7/copy (\$8 outside U.S.) to
Ziff-Davis Publishing, One Park Ave., 4th floor, New York, NY 10016.

PC TECH JOURNAL (ISSN 0738-0194) is published monthly, \$29.97 for one year, \$52.97 for two years, \$69.97 for three years. Additional postage \$6 for Canada & Foreign by Ziff-Davis Publishing Company, One Park Avenue, New York, NY 10016. Second-Class Postage paid at New York, NY and at additional mailing offices. POSTMASTER: Send address changes or subscription inquiries to P.O. Box 2968, Boulder, CO 80321.

PC TECH JOURNAL is an independent journal, not affiliated in any way with International Business Machines Corporation. IBM is a registered trademark of International Business Machines Corp. Entire contents Copyright © 1986 Ziff-Davis Publishing Company. All rights reserved; reproduction in whole or in part without permission is prohibited. Direct written requests to Jean Lamensdorf, Licensing Manager, Reprints/Rights & Permissions, One Park Avenue, New York, NY 10016.



Save On New Model of Periscope



"A marvelous debugging tool..." says Peter Norton.

SUMMER SALE.

You don't have to spend thousands, or even hundreds, of dollars to buy a high-performance debugger. Through August 31, the new software-only Periscope II-X is yours for only \$95! Periscope II, normally \$145, is only \$125!

NEW MODEL.

Periscope I includes both a break-out switch for "spontaneous" debugging and a RAM board to protect the debugger from programs that overwrite memory. Periscope II includes a break-out switch that doesn't require an extra slot to install. And the new Periscope II-X is Periscope II without the break-out switch. So you can now get Periscope with no hardware at all!

NEW RELEASE.

The new version 2.1 enhances all models with many of the features users have requested. Call for details.

CHECK OUT THE REVIEWS.

- ✓ *"Periscope strikes a balance of power and features that will please serious PC programmers."* — Jeff Dunte-mann, PRODUCT OF THE MONTH, *PC Tech Journal*, 1/86
- ✓ *"This symbolic debugger, with its breakout button and powerful command options, stands unrivaled for its flexibility . . . Periscope's diverse features, affordable price, and portability place it in a class by itself."* — Ward Christensen, "Breaking out with Periscope," *PC Tech Journal*, 3/86
- ✓ *"Periscope represents the finest software debugger available in its class."* — Andrew Fried, *Computer Shopper*, 4/86

Other reviews have appeared in *Computer Language* (3/86), the Boston Computer Society's *PC Report* (1&2/85), and *Programmer's Journal* (Vol. 3, No. 1).



I'M CONVINCED PERISCOPE IS FOR ME!

Please send me the following:

Periscope II-X _____ @ \$95* _____

Periscope II with
Switch _____ @ \$125* _____

Periscope I with Board
& Switch _____ @ \$295 _____

Add Shipping Cost (see below) _____

Total Order Amount _____

Shipping—\$3 UPS; \$5 COD; \$8 Canada; \$24 Foreign

We accept qualified PO's in the U.S.

*Prices good through August 31, 1986

Ship to:

Name _____

Company _____

Address _____

City/State/Zip _____

Telephone _____

Payment: ☐ Check enclosed ☐ COD ☐ MC ☐ Visa

Card No. _____

Expires _____

Signature _____

PERISCOPE REQUIRES an IBM PC, XT, AT, Compaq, or other close compatible; 128K RAM; DOS 2.0 or later; one disk drive; and an 80-column monitor.

Take advantage of the low sale prices while they last . . . Order your Periscope today! To order, clip the coupon, or call TOLL-FREE



800/722-7006




30-Day Money-Back Guarantee

Get Your Programs Up and Running;


UP PERISCOPE!

Data Base Decisions
14 Bonnie Lane
Atlanta, GA 30328
404/256-3860

CIRCLE NO. 215 ON READER SERVICE CARD



EGA Mode



Plantronics Mode

Finally, An EGA Card Responds To You

Introducing The Paradise AutoSwitch™ EGA Card.

You've decided you want an EGA Video Card because it offers the best quality text with high resolution color graphics. The problem is that older versions of popular software, like Lotus 1A, (and some current versions too) won't work with the EGA standard. That's a problem because in the course of your workday you'll need to use software written for different video modes.

Paradise has the answer. The Paradise AutoSwitch

EGA works with every popular PC video mode. And is smart enough to switch to the right mode every time you change programs. Automatically.


AutoSwitch. Only Paradise has it.

The Paradise AutoSwitch EGA changes video modes automatically to work with your software. No Mode commands. No special software to run. On RGB monitors it "autoswitches" between EGA, CGA (IBM Color Graphics) and Plantronics modes; on monochrome


monitors between EGA, MDA (IBM Mono Text) and Hercules modes. The Paradise AutoSwitch EGA runs any PC software you want. Immediately. Automatically. That's something ordinary EGA Cards can't do.

Runs all EGA, CGA, MDA and Hercules Software with true hardware level compatibility.

True hardware compatibility makes the Paradise AutoSwitch EGA Card different from other EGA Cards. No other EGA Card offers the



CGA Mode



Hercules Mode

And That Automatically Runs in Every Mode.

6845 CRT controller included on the IBM Monochrome, IBM Color and Hercules Cards. The Paradise-designed PEGA video controller chip has the equivalent of a 6845 inside. That means when the Paradise AutoSwitch EGA runs EGA software, it's an EGA card; when it runs IBM Color Graphics (CGA) software, it's a CGA card; when it runs Hercules software, it's a Hercules card. No "batch files," special software or complicated installation. No incompatibility hassles. EGA with true 6845 hardware compatibility.

The Simpler the Better.


Paradise's exclusive AutoSwitch feature and true 6845 hardware compatibility make using the Paradise AutoSwitch EGA simple and hassle free. The Paradise-designed single chip EGA video controller makes possible all this functionality and intelligence on a short card. In fact, even the users manual is short. Only 24 pages.

The Paradise AutoSwitch EGA Card. Just what you would expect from the innovators in Video Technology.

PARADISE

SYSTEMS, INC.

The Paradise AutoSwitch EGA Card



CIRCLE NO. 137 ON READER SERVICE CARD

For more information call 800-527-7977 Ext. 350, toll free. From California, 800-822-2020 Ext. 350. Or stop by your favorite computer store.

ATRON BUGBUSTERS GREASE BORLAND LIGHTNING

"If I were starting a software company again, from scratch, Atron's AT PROBE™ would be among my very first investments. Without Atron's hardware-assisted, software debugging technology, the flash of Turbo Lightning™ would be a light-year away."
Philippe Kahn, President, Borland

HOW BORLAND DOES SO MUCH, SO WELL, SO FAST

We asked Borland International president Philippe Kahn to share his secrets for rapidly taking a good idea and turning it into rock-solid reality. How does the Borland team do so much, so well, so fast?

He begins, "I remember when Atron used the June 24, 1985 *Wall Street Journal* chart of top-selling software in an ad." [Note: At that time, seven of the top ten software packages were created by Atron customers; it's now now nine out of ten.] "SideKick was number four, and I let Atron quote me in saying that there wouldn't have been a SideKick without Atron's hardware-assisted debuggers.

"You might say lightning has literally struck again. Turbo Lightning made number four on *SoftSel's Hotlist* within weeks of its introduction! And again, I say we couldn't have done it without Atron debugging technology.

"Cleverly written code is, by definition tight, recursive, and terribly complex," he continues. "Without the ability to externally track the execution of this code, competent debugging becomes very nearly impossible."

Concludes Philippe, "And after Turbo Lightning was solid and reliable, Atron tuning software turned our Probes into performance analyzers. How do you think we greased our lightning?"

Philippe, along with a couple million or so of your satisfied customers, we say congratulations on yet another best-selling product. We can't wait to see what awesomely useful technology will come shooting out of Borland International next.

Copyright © 1985 by Atron Corp. PC PROBE™ and AT PROBE™ Atron. SideKick™ and Turbo Lightning™ Borland International, Inc., Adv. by TRBA, 408/258-2708.

HOW BUGBUSTERS KEEP YOU FROM GETTING SLIMED

The AT PROBE is a circuit board that plugs into your PC/AT. It has an umbilical which plugs into the 80287 socket and monitors all 80286 activity.

Since AT PROBE can trace program execution in real time, and display the last 2048 memory cycles in symbolic or source-code form, you can easily answer the questions: "How did I get here?" and "What are those silly interrupts doing?"

It can solve spooky debugging problems. Like finding where your program overwrites memory or I/O - impossible with software debuggers.

You can even do source-level debugging in your favorite language, like C, Pascal or assembler. And after your application is debugged, the AT PROBE's performance measurement software can isolate performance bottlenecks.

Finally, the AT PROBE has its own 1-MByte of memory. Hidden and write-protected. How else could you develop that really large program, where the symbol table would otherwise take up most of memory.


LOOK AT IT THIS WAY.

History shows that non-Atron customers don't stand a very good chance of making the Top Ten list. Lightning really does have a way of striking twice!

The PC PROBE™ is \$1595 and the AT PROBE is \$2495. So call Atron today. You can be busting some really scary bugs tomorrow. And maybe, just like Borland, you can also bust some records.

atron
THE DEBUGGER COMPANY

20665 Fourth Street • Saratoga, CA 95070 • 408/741-5900



Objects and Attributes

Our operating systems need to get smarter.

One of my computer science professors gave me an assignment that I now look back on with some satisfaction. It involved a network routing program to be written in LISP, and it came with a challenge: the fastest program would earn extra credit. The speed challenge spurred me on to read the MIT "blue book" (the bible of LISP) inside and out in an effort to learn anything that would help. As it turns out, I learned something very important.

In LISP, I had been taught, the atom was the smallest object, indivisible. What I discovered in the blue book was that the property list (or p-list) attached to each atom could be modified to attach arbitrarily complex data structures "below" that lowly atom. The long-term effect on my thinking was significant. I had learned to attach attributes to objects.

In simple terms, objects can be manipulated. They have certain characteristics, or attributes, that are inherent and some that can be induced. A baseball, for example, is an object that is often manipulated. Some of its attributes that come quickly to mind are color, texture, weight, shape, and surface tension; a baseball also can be considered to have these perhaps less obvious attributes: position in space, spatial orientation, velocity, and acceleration. Although some attributes remain fixed, some can be altered. Manipulation of a baseball with a device called a bat, for example, can alter its attributes.

The manipulation of computer-based objects may be less satisfying than clobbering a small orb, but certainly no less difficult. Worse, computers and software do a poor job of managing an object's attributes.

The object of most interest to most computer users is the file. Files hold all of the data upon which spreadsheets, word processors, and data management programs operate. Those files are packed full of information, but what do




ILLUSTRATION • MACIEK ALBRECHT

we actually know about them? We can tell if the file is a file or a file of files (a directory). We can determine the file's size, although the number is ambiguous for directories (that is, should it be the size of the directory file itself or the total of all that is contained in the directory?). Files usually are stamped with the date and time of their creation or last modification. Additionally, most operating systems allow a small set of other attributes to be attached to the file, such as those provided by DOS (archive, hidden, read-only, system, label, and subdirectory).


The set of attributes for files is hardly enough. Recognizing this, DOS developers devised a file name that consists of the name itself and an extension to the name, intended to be the file type. Microsoft Windows allows files to be displayed by name, size, date, and *kind*, another way of saying type. Using a file extension as a type is widely practiced by individual software products but is in no way standardized or supported by the underlying operating system. For example, spreadsheet files have no standard type, but rather a plethora of extensions chosen by each manufacturer (.WKS, .SS, .CAL, .VC, .MP, .MPW, etc.). File name extensions are thus used as attributes but not supported as such by DOS.

What other kinds of attributes might a file object need? The answer, which may sound flippant, is whatever attribute a user might choose to attach to a particular file. Many spring to mind, but here is a simple one. How about a set of attributes that tells a backup program how frequently files need to be archived? For example, the set of attributes could consist of DAILY, WEEKLY, MONTHLY, ALWAYS, and NEVER. The backup program could be invoked with an appropriate parameter and only those files with the related attributes would be manipulated; files with no backup attribute might default to a strong attribute, such as ALWAYS.

It is tempting to say, "OK, let's add 16 more bits to the attribute field in the directory and add some specific attributes for the backup process." I am suggesting something more radical, however. Let's add a general facility for attaching arbitrarily complex, *symbolic* attributes to the file object.

For some objects on the standard desktop computer, this is now done, albeit in a complex and technical way. The computer I am using to write this editorial has a mouse attached to COM2: and a device driver installed in memory that, in effect, attributes a mouse to that serial port. What is missing from this configuration is anything

BEST COMPUTER MAGAZINE: PC TECH JOURNAL!




The Computer Press Association, an alliance of people who write about computers for magazines, newspapers, and books, named *PC Tech Journal* the Best Computer Magazine for 1985 during COMDEX in Atlanta. To be so honored by an association of our peers is high praise indeed.

The citation read, in part, "*PC Tech Journal* has substance, style, and clear writing combined with superior information value and contemporary graphics. Each issue contains useful techniques for PC users. Its graphics are clear and consistent and show good magazine technique. Its covers are designed with imagination, even though they are highly technical."

As proud as I was of the beautiful trophy pictured here, I accepted the award on behalf of everyone who contributes to the magazine: our staff, authors, advertisers, and readers—all of whom rely on *PC Tech Journal* to address and analyze the technical issues surrounding the PC family.

PC Tech Journal also was singled out for an award in quite another arena. Our April 1985 cover (also pictured here) netted a Merit Award from the Society of Publication Designers, an association of magazine art directors. The winning entries in this competition are published in book form;



many art directors consult this annual publication for inspiration and ideas, so we are delighted to be part of it. Deciding how to illustrate some of our more abstract and technical subjects is often a real challenge, so we are especially proud of this honor.

—WF

that really *knows* that I have a mouse attached. Wouldn't it be nice if I could run the ATTRIBUTES program and assign the attribute "MOUSE ATTACHED" to COM2:? Then I could attach the attribute "MOUSE DEVICE DRIVER" to the file holding the device driver. Even if I had to write a configuration file that said "LOAD MOUSE DRIVER," I could do so symbolically rather than writing "DEVICE = \UTIL\MOUSE.SYS". The operating system would know it had to load mouse software and would simply search until it found the right combination of software and ports.

A clear advantage of this strategy is that it is no longer dependent upon specific file names or specific hardware. If I wished to test a new driver for the mouse or even a new and different mouse, I could simply attach the attributes and reboot the system.

Critics of this idea might correctly argue that my fictional ATTRIBUTES program involves as much work as running a text editor in order to modify CONFIG.SYS or AUTOEXEC.BAT. While true, the argument begs the issue of more complex attributes that might be useful for files. One example of particular contemporary importance is that of a collection of files that form the object. Data managers often place data in one file, indices in one or more files, and other kinds of information in still more

files. Yet the set of files is what is important to the user. If a particular database is to be archived, the user would want to order a backup of the database object, not each individual element. The user might not even *know* the name of each individual element and should certainly not be required to. In such cases, a user (or the program itself) might define a new object (the database) with a set of attributes (the names of the files that make up the database).

A new product attempts to address this need in an interesting, although not entirely successful, way. SmartNotes is an electronic version of the immensely popular Post-it notes from 3M. This program, which allows a user to attach a little note anywhere, is intended to be used just as its paper counterpart: the user can "stick" a note on a page of a document in a word processor or in a cell of a spreadsheet. The contents of the note are arbitrary, and the note pops up when the page or cell is next examined. A note even can be attached to a file name in a file listing generated by the DIR command. Although other programs cannot operate based on the contents of notes that may be so attached, the user is given visual cues that can be quite helpful.

SmartNotes' major weakness is that the attached notes must be stored somewhere, and that somewhere is

most decidedly not with the file to which the notes are attached. For example, if I attach a note to this editorial's manuscript file and then copy the file onto diskette, the note stays on my hard disk and will be lost to the person who reads the diskette.

Consider what would happen if attributes could be attached to file objects and other objects defined. First, a file could be tagged with an attribute indicating that notes were attached. A group object could be created that consisted of the file and its associated note file. Then when the COPY command was used, the group would move to the diskette. Better yet, the notes could be stored as attributes themselves, automatically following the file with no additional work from the user.


This concept can be extended to include the attachment of attributes to just about every object associated with the desktop computer. While some may argue that such methodology adds up to considerable overhead, I contend that the rising performance and capacity of the desktop, coupled with the fact the attributes do not have to be assigned if the user prefers to operate without them, make this concept viable.

By the way, I won the LISP speed challenge. How? By being the only student to discover the COMPILE function of LISP 1.5.




Orchid's TurboEGA™

The world's *fastest* EGA



**FREE
MS WINDOWS™**



Introducing the only Enhanced Graphics Adapter with Pcturbo™ speed.

The experts agree: the EGA is the breathtaking new graphics standard, but the sophisticated software written for it places a big burden on the PC's processing speed. Beautiful graphics, crisp text, but too slow.

Everyone else rushed their EGAs to the market, but Orchid Technology took the time to do it right. Orchid's TurboEGA™, from the *inventors* of PC TurboProcessing, packs a high-speed Turbo and an EGA into one slot, for the world's fastest EGA.

Graphics with Speed

TurboEGA makes IBM PCs and XT's run faster than an AT. It brings dazzling speed to sluggish graphics programs. *All* types of software run faster, so you finish more quickly. Transparent to the user, you won't know it's there *until you see its speed*.

We are so confident that our TurboEGA is the ultimate graphics card that we decided to give away a *free* copy of Microsoft's Windows™ with each TurboEGA*. Even Microsoft recommends that you run Windows on an AT. Now Orchid's TurboEGA gives you AT speed so XT users can use this number one windowing software at the speed they demand.

The Complete Solution

Only Orchid puts this much performance into one slot *and* comes fully loaded with 256K of RAM, so there's no hidden cost. TurboEGA is the *complete* graphics solution.

Pick up the phone and find out how you can have the EGA the competition wishes *they* had: Orchid's TurboEGA, the world's fastest.

If you have an AT or a system with 80286 speed, ask about the Orchid EGA™—four graphic-card compatibility in one slot.

Features:

- Powered by 7.2MHz 80286
- Optional 5 or 8MHz 80287
- 256K of on-board RAM
- Four graphics modes: EGA, CGA, MDA, Hercules
- Supports the long list of EGA software:
 - Microsoft Windows & Word
 - Lotus 1-2-3 & Symphony
 - Topview
 - Framework
 - Chart-Master
 - AutoCAD
 - PC Paint Plus
 - and more...




47790 Westinghouse Dr.
Fremont, CA 94536
415/490-8586
Tlx: 709289

TurboEGA, OrchidEGA, and Pcturbo and trademarks of Orchid Technology. Microsoft Windows is a trademark of the Microsoft Corporation. All other product names are trademarks of their manufacturers. CGA screen by PC Paint Plus.

*Offer good only on TurboEGA purchases until July 31, 1986. Please allow two weeks for delivery.

CIRCLE NO. 142 ON READER SERVICE CARD

**YOUR
COMPUTER LANGUAGE
IS QUIETLY
BREEDING REAL BATS
IN YOUR
BELFRY.**



WE'RE OUT TO SAVE ONE MILLION FRUSTRATED PROGRAMMERS

You're on a roll, really pumped, writing the best code you have ever written and then—AAARGHHH!

Freeze dried in your tracks because the language you're using just won't let you achieve what you can conceive.

And you wanted to be a programmer.

So your choices are:

1) write around the problem by creating six pages of emetic code...

2) leave out that incredible idea that really puts your stamp of excellence on this program or...

3) get yourself a world class headache (or a stroke) by dropping into assembler.

Whatever you choose, by now you feel the language is out to get you—because it is.

Sure, no language is perfect, but you have to wonder, "Am I getting all I deserve?"

And, like money, you'll never have enough.

Pretty dismal, huh?

We thought so, too.

So we did something about it.

We call it CLARION.

You'll call it incredible.

With CLARION you can write, compile, run and debug complex applications in a New York afternoon.

Even if you're in Savannah.

It gives you the power and speed to create screens, windows and reports of such richness and clarity you would never attempt them with any other language.

Because YOU would have to write the code.

With CLARION you simply design the screens using our SCREENER utility and then CLARION writes the source code AND compiles it for you.

In seconds.

Likewise, you can use REPORTER to create reports. Remember, only CLARION can recompile and display a screen or report layout for modification.

And with no time wasted.

All the power and facilities you need to write great programs, faster

than you ever dreamed of.

Programs that are easy to use.

Programs that are a pleasure to write.

And to you that means true satisfaction.

You've coveted those nifty pop-up help windows some major applications feature. But you can't afford the time and energy it takes to write them into your programs.

That's the way it used to be.

So we fixed that, too.

CLARION HELPER is an interactive utility that let's you design the most effective pop-up help screens that you can imagine. And they're "context sensitive," meaning you can have help for every field in your application.

Unlike the other micro languages, CLARION provides declarations, procedures and functions to process

dates, strings, screens, reports, indexed files, DOS files and memory tables.

Imagine making source program changes with the CLARION EDITOR. A single keystroke terminates the EDITOR, loads the COMPILER, compiles the program, loads the PROCESSOR and executes the program. It's that easy!

Our data management capabilities are phenomenal. CLARION files permit any number of composite keys which are updated dynamically.

A file may have as many keys as it needs. Each key may be composed of any fields in any order. And key files are updated whenever the value of the key changes.

Like SCREENER and REPORTER, CLARION's FILER utility also has a piece of the CLARION COMPILER. To create a new file, you name the Source Module. Then you name the Statement Label of a file structure within it.

FILER will also automatically rebuild existing files to match a changed file structure. It creates a new record for every existing record, copying the existing fields and initializing new ones.

Sounds pretty complicated, huh?

Not with CLARION's documentation and on-line help screens. If you are currently competent in Basic, Pascal or "C" you can be writing CLARION applications in a day. In two days you won't believe the eloquence of your CLARION programs.

Okay, now for the best part of all. You can say it in CLARION for \$295.00—complete. All you need is an IBM® PC, XT, AT or true compatible, with 320 KB of memory and a hard disk drive.

And we'll allow a full 30 day evaluation period. If you're not satisfied with CLARION, simply return it in its original condition for a full refund.

If you're not ready to take advantage of this no-risk opportunity, ask for our detailed 16 page color brochure. It vividly illustrates the elegance of CLARION. Consider it a preview of programming in the fast lane.

Either way, the call's a freebie.



SAY IT IN

CLARION™

DEPT. A1TJ/2

1-800-354-5444



CIRCLE NO. 105 ON READER SERVICE CARD

BARRINGTON SYSTEMS, INC. • P.O. BOX 5580 • POMPANO BEACH, FL 33074 • 305/785-4555

IBM® is a registered trademark of International Business Machines Corporation. CLARION™ is a trademark of Barrington Systems, Inc. ©1986 Barrington Systems.

Now You Know Why **BRIEF**™ is **BEST**

"BRIEF, The Programmer's Editor, is simply the best text editor you can buy." John Dvorak, INFOWORLD 7/8/85

The Program Editor with the **BEST** Features

Since its introduction, BRIEF has been sweeping programmers off their feet. Why? Because BRIEF offers the features **MOST ASKED FOR** by professional programmers. In fact, BRIEF has just about every feature you've ever seen or imagined, including the ability to configure windows, keyboard assignments, and commands to **YOUR** preference. One reviewer (David Irwin, DATA BASED ADVISOR) put it most aptly, "(BRIEF)... is quite simply the best code editor I have seen."

"A bona fide Undo..."

Steve McMahon, BYTE 3/85

As Mark Edwards describes in DR. DOBB'S JOURNAL (11/85), "BRIEF has an outstanding undo facility. The default configuration allows the last 30 editing commands to be undone. This number can be raised to a maximum of 300 commands. Until you reach this maximum or run out of RAM, every command you issue can be undone. So if you make ten changes and then realize that the first one was an error, you can undo all the changes back to the mistake... Needless to emphasize, this facility can save endless grief."

No other editor has this capability.

Every Feature You Can Imagine

Compare these features with your editor (or any other for that matter).

- FAST
- Full UNDO (N Times)
- Edit Multiple Large Files
- Compiler-specific support, like auto indent, syntax check, compile within BRIEF, and template editing
- Exit to DOS inside BRIEF
- Uses all Available Memory
- Tutorial
- Repeat Keystroke Sequences
- 15 Minute Learning Time
- Windows (Tiled and Pop-up)
- Unlimited File Size – (even 2 Meg!)
- Reconfigurable Keyboard
- Context Sensitive Help
- Search for "regular expressions"
- Mnemonic Key Assignments
- Horizontal Scrolling
- Comprehensive Error Recovery
- A Complete Compiled Programmable and Readable Macro Language
- EGA and Large Display Support
- Adjustable line length up to 512

Program Editing **YOUR** Way

A typical program editor requires you to adjust your style of programming to its particular requirements – NOT SO WITH BRIEF. You can easily customize BRIEF to your way of doing things, making it a natural extension of your mind. For example, you can create ANY command and assign it to ANY key – even basic function keys such as cursor-control keys or the return key.

The Experts Agree

Reviewers at BYTE, INFOWORLD, DATA BASED ADVISOR, and DR. DOBB'S JOURNAL all came to the same conclusion – **BRIEF IS BEST!**

Further, of 20 top industry experts who were given BRIEF to test, 15 were so impressed they scrapped their existing editors!

NOT COPY PROTECTED

Solution Systems™


MONEY-BACK GUARANTEE

Try BRIEF (\$195) for 30 days – If not satisfied get a full refund.

TO ORDER CALL (800-821-2492)

SOLUTION SYSTEMS, 335-P WASHINGTON ST., NORWELL, MA 02061, 617-659-1571

BRIEF is a trademark of UnderWare



TRAITS REVEALED

Thank you for the review of Revelation in the February 1986 issue ("A Data Manager Designed for Complex Applications," Kent Phelps, p. 160). It was generally well done, although I think more attention could have been given to multivalued fields, a powerful and distinctive Revelation trait.

I have been working with Revelation for approximately a year and a half, yet Mr. Phelps has managed to write about some things of which I was not aware. For one thing, I do not think Cosmos would agree that "Backups are allowed for personal use." On another point, R/LIST does not change from columnar to vertical format if the total column widths exceed the device width. I wish it did. The only way that I know to produce a vertical format is to create a symbolic field.

Also, I have never heard of REFORMAT. The description of it reminds me a little of INVERT.ALL, a supplemental program to R/DESIGN's cross-reference function, which, by the way, is one of Revelation's more powerful features (and, unfortunately, was not mentioned in the review). Essentially, the feature allows the automatic maintenance of inverted indexes that may be linked with other files. This means that when one-to-many relationships exist between records in different files, dynamic links may be created between the records allowing all of the data from either file to be available to the related records in the other file. This involves creating symbolic fields, but complex networks of data relationships may be created and automatically maintained by R/DESIGN.

Finally, listing 1, BENCH3.LST, has an error: the line of code that reads 'ARRAY(POS) = STATE' replaces the contents of the POS element of ARRAY with the value of STATE. What is desired is that the value of STATE be inserted into the middle of ARRAY at posi-

tion POS, effectively increasing the position of all subsequent elements by one. To achieve this, the line should be replaced by the following lines:

```
ARRAY = INSERT(ARRAY,POS,0,0,STATE)
ARRAY1 = INSERT (ARRAY1,POS,0,0,0)
```

Stephen Montgomery
Systems Consultation
Chicago, IL

Mr. Montgomery is correct. The ability to use multivalued fields is an important feature of Revelation: coupled with variable length fields and the practical lack of restraints on how many multivalues may exist, quite complex data structures may be implemented.

Cosmos has employed a reasonable approach to the issue of software protection, relying on a sticker that accompanies the product and which is to be affixed by the user to the CPU that is designated to operate Revelation. The copy protection does not prevent or restrict use from a hard disk, but the start-up message informs and reminds the operator each time that the use of the system does not conform to the licensing agreement—that is, if the sticker is not present on the machine. I believe that Cosmos has done what it can to establish and assert its right without burdening the legal owner of the product; most other copy-protection solutions fall short in one direction or the other.

You are correct concerning the vertical format of R/LIST reports. The description given in the article is true of real PICK systems, and it would be preferable if Revelation performed this way also: more readable reports would be produced for those times when the total column width needed exceeds screen size, or for when the total report width is unpredictable. Presently, Revelation wraps the output of each field within the column space allocated for it.

REFORMAT is also a PICK feature that is an inverting tool, but not specifi-

cally for the purpose of maintaining inverted indexes, because full PICK systems are seldom index-driven. REFORMAT is a verb that, when executed at command level using R/LIST syntax, builds a work file with items selected from primary file, each item consisting of any array of dictionary items in the order specified. The first dictionary item becomes the item id, followed by as many other attributes as needed. Thus an ad hoc work file can be created as needed for a special task and then discarded upon its completion.

Thank you for the correction of the section of code in listing 1.

—Kent Phelps


CHIPS IN QUESTION

Bob Smith's article "Chips in Transition" (April 1986, p. 56) was a useful review of the idiosyncracies of the chips in the 8086 family. Readers should be made aware, however, that one of the work-arounds presented for an 8086/88 problem is flawed.

Mr. Smith correctly notes that a multiprefix instruction (REP MOVSW ES:) will not restart properly if interrupted. But two failure modes can occur, and checking the CX register following these instructions catches only the one in which all repeats have not been performed. If all of the programmed repeats have been completed, the instruction may be executed one more time. In the case of a MOV instruction, this will cause the first location beyond the destination to be clobbered. CX will be zero, as usual, but SI and DI will have been advanced to reflect the unprogrammed execution, which makes their values following the multiprefix instruction unreliable for chained operations.

This can be demonstrated easily on any 8088-based PC. Simply construct a loop to perpetually execute a REP MOVSW ES: instruction, testing each time to see if the location following the

Visual COBOL



It's a high performance native code COBOL compiler for IBM PCs.

It features the best integrated screen management system available in a micro-based COBOL compiler.

It comes with the fastest COBOL sort you can get on an IBM PC.

It produces some of the fastest executable code generated by a micro-based COBOL compiler.

It comes with the most comprehensive COBOL documentation available.

It was developed by a company committed to service and support AFTER the sale.

It's priced at only \$1150 and it's available now!

To learn more about Visual COBOL, contact mbp today. Call **1-800-231-6342**. In California, call **1-800-346-4848**.

Visual COBOL...
It can make the difference
between ordinary software, and
software that sells.

mbp Software and Systems
Technology, Inc.
1131 Harbor Bay Parkway, Suite 260
Alameda, California 94501

mbp

LETTERS

destination has been altered. Including a counter in the loop will indicate that this second failure mode is relatively rare. Due to the synchronous nature of the processor and the interrupt source (the 8253), some loops may take longer than others to fail. Pressing a key at the keyboard will alter the phase relationship of the loop relative to the interrupt source and may reduce the time required before a failure occurs.

It is best not to use string moves with a segment override unless interrupts are disabled *and* NMIs are not possible. (Hardware-assisted debuggers generally use the NMI.) Those programmers who must use segment overrides while interrupts remain enabled should be certain that the information in the location following the destination is not important to their program, and that they do not rely upon the expected register values resulting from the execution of these instructions.

Michael Liebert
North Caldwell, NJ

We downloaded and assembled CPUID.ASM from "Chips in Transition." When we ran it, it hung up our IBM ATs. We went into debug and found that the `fstenv NDP_ENV` instruction was causing the bug. The problem is that the AT has no NDP and when the address was put on the bus, some other piece of hardware filled memory from the address in the instruction through the end of the data segment with a pattern of repeating double words. The data segment is the same as all the other segments in CPUID so the stack that builds from the end of the segment down was overwritten. The program continues to run until the `ret` at address 223 line 712. The return pops the `ip` of the corrupted stack and execution begins at a random address. We do not know what causes the garbage to fill RAM—however, it does not happen on the AT that has the new-design motherboard (256KB RAM chips).

Our revision of the source code prevents the crash and prints a message indicating that the problem was detected: Just before the `cli` that precedes the `fstenv` we added 4,096, the number of 16-byte paragraphs in 64K, to the data segment so it points past the current segment. We filled that segment with zeros, then we go through the original code until we are past the `sti`. We check the rest of the new segment to see if the zeros have been altered. If they have, then we set a new flag and jump to `cpu_exit`. Otherwise we copy

the 14-byte environment to its initial storage place, restore the data segment to its original value and continue with the original code. In the main line we added a TAB macro to check the new flag and print a message. When we run the new code on a machine that used to crash, it usually detects the condition, but not always. The new code never crashes. We would like to know exactly what causes the error and why it is asynchronous. Is there an error in the design of the AT?

John Lodge
Tim Oliver
Roseland, NJ

Mr. Liebert correctly points out that any work-around based upon post-MOVs tests still can fail. This is yet another reason to avoid using segment overrides with repeated string operations.

Mr. Lodge and Mr. Oliver have encountered an odd problem, one that I ran into recently on an IBM 3270-PC/AT without an 80287. Despite Intel's recommendation on how to tell if a numeric processor is installed, IBM has introduced a hardware anomaly that invalidates Intel's technique. In the short time I had to work on this problem on the 3270, I was unable to construct a work-around, so I am pleased to read of Lodge and Oliver's success. I do not understand why some (but not all) PC/ATs without a 80287 turn and run when confronted with a floating-point instruction. According to the Intel specifications, the 80286 is supposed to execute an INT 07H whose default handler (in the BIOS) contains no hint that it might run amok. On the 3270-PC/AT, I tried installing my own INT 07H handler within CPUID, but the machine still trampled my code. An alternative solution to the problem is to skip the test for a numeric processor when on an 80286. That goes against the take-nothing-for-granted attitude I adopted when writing CPUID, but it is preferable to crashing the machine.

On another matter, I since have discovered one more minor difference between the Intel 8086/88 and the NEC V20/30. As pointed out in the article, the NEC chips correctly disallow interrupts for the single instruction that follows a MOV to or POP into any segment register. However, NEC has taken that prohibition one step further by also disallowing interrupts after a MOV from a segment register. That is, when single-stepping through your code on an NEC CPU, expect it not to trace (but, of course, still execute) the instruction that



1432 Main Street, Waltham, MA 02154

- ☐ Send me more information about the Alsys PC AT compiler.
☐ Send me more information about Ada.

Name _____

Title _____

Company _____

Address _____

City _____ State _____ Zip _____

Telephone _____

PCT _____

At this point, we suspect you might be tempted to pull out a credit card and give us a call.

Or at least fill out the coupon.

Write:

Alsys, Inc.,
1432 Main Street, Waltham,
MA 02154, U.S.A., Telephone:
(617) 890-0030, Telex: 948536.
Other offices located in both
England and France.


We have some very good news for you.
You can now get a validated, full Ada[®] compiler for the IBM[®] PC AT. From the people who designed the language. For just \$3,000.

Which means you and your company can now program in the language that the DoD has mandated for their software, without tying up a big, expensive computer.


The Alsys[™] Ada compiler is not only validated, it's actually written in Ada. And produces code so efficient it executes faster than C or Pascal on tested benchmarks.

And if that's not enough, the Alsys PC AT Ada compiler runs in protected mode. So you can use the full amount of memory available to the PC AT.

Lastly, this compiler comes with a 4-megabyte memory upgrade board. That, by itself, is worth the price of admission.



Knowledge is good.
Especially when it's free.



Ada just moved into a smaller place.

Alsys' validated PC AT compiler is designed to run on Compaq, Goupil, H-P Vectra, Sperry, Tandy, Zenith and other PC AT compatible machines.
Ada[®] is a registered trademark of the U.S. Government (Ada Joint Program Office). IBM[®] and PC AT are registered trademarks of International Business Machines Corporation.
Alsys is a trademark, service mark, and trade name of Alsys S.A.

CIRCLE NO. 200 ON READER SERVICE CARD

follows code such as MOV AX,DS as well as MOV [...],DS. It would appear that NEC just wants to be careful.

—Bob Smith

OF MICE AND USERS

In regards to Jeff Duntemann's review of the new Microsoft Mouse in the March 1986 issue (see Product Watch, p. 179), his complaints about the non-click buttons are ridiculous. His comment is "Without a solid, snappy click from the mouse switch, the user must watch the screen to see if the desired selection took place." Mr. Duntemann sees this as a disadvantage. My comment would be that without clairvoyant powers beyond my ken, if the user is not already watching the screen, he has very little chance of landing the mouse in the proper place before he clicks it. He therefore will see a response from the system if he has successfully clicked the mouse. Personally, I would rather not have a mouse that makes sounds like a child's click toy (or the IBM PC keyboard, for that matter).

Kudos for Ted Mirecki's review of Peter Norton's *Programmer's Guide to the IBM PC* ("Keeping the Family Straight," Book Reviews, March 1986, p. 193). I share his sentiments exactly

regarding the completeness of the coverage of the subjects in this volume. I often find that, in his articles, Mr. Norton has a tendency to stop discussing things when they begin to become interesting. It leaves the feeling that he does not want us to know as much as he does. I got the same feeling from reading this book, and I am glad to see that someone else has noticed this.

Matt Richards
Baltimore, MD

A tactile/audible mouse click is a way of passing some of the necessary feedback of an interactive task from my eyes onto my hands. The visual channel of the man/machine interface is already taken up by my application—I do not want to be obliged to monitor system matters (like whether or not the mouse button has closed) in the visual channel if my hand can do the job as well.

Furthermore, nothing obligates an application to give a visual indication when a mouse selection is made. Good design would require it—but good design is far from universal. The snappy mouse click tells me that I have not fumbled; that I have, in fact, pressed hard enough on the button to make it connect. Microsoft's new buttons some-

times leave me wondering, and that is a most unwelcome distraction from whatever job is at hand.

The IBM keyboard is noisier than it has to be—much noisier than any mouse I have ever used. And let's not forget the XT and AT power supply fans, which also are extremely loud and obtrusive. You seem to have a preference for computing in silence, something I also wish for from time to time. Perhaps IBM will consider the virtues and problems of silent computing in designing future members of the PC family.

—JD

NOT JUST A REFLEX

Your recent Product Watch review of Reflex (William Casey, April 1986, p.189) omitted several of that program's more important features.

Reflex has an excellent mouse interface. For example, the width of a column can be changed simply by clicking and dragging the column's right border. Similarly, when designing a report, the position of an item can be changed by dragging it to the desired location. Reflex flies with a mouse. In addition, field length is not fixed, but is as long as needed for each record; thus, disk and memory space are not wasted

FOR C
AND UNIX

WINDOWS FOR DATA™

MS WINDOWS
COMPATIBILITY


DATA ENTRY WINDOWS MENUS HELP

Windows for Data does the hard jobs that others can't — we **guarantee** it. Makes standard display and entry tasks easy. Reliable. Compact. Portable.

DATA ENTRY: The most complete and flexible data entry system on the market. Pop-up data-entry windows; field types for all C data types, plus decimals, dates, and times; auto conversion to and from strings for all field types; system and user-supplied validation functions; range-checking; scrollable context-sensitive help; required and must-fill fields; programmer-definable edit keys, field types, and field masks. Read field by field or auto-read all fields. Branch and nest window forms. **Virtually every capability of WFD can be modified to meet special needs.**

WINDOWS: WFD is built upon and includes **Windows for C**, the windowing system rated #1 in PC Tech Journal (William Hunt, July 1985). WFC now has more features than ever, including automatic full compatibility with Microsoft Windows and TopView.

UNPRECEDENTED FLEXIBILITY



As many possibilities as Vermont in June.

MENUS: Build multi-level menus in the format of Lotus 1-2-3, Macintosh, or a style of your own choosing.

HELP: Build context-sensitive or menu-driven help systems. Display text in pop-up, scrollable windows.

UNIX, DOS, OR BOTH

WFC and WFD provide source code compatibility between PCDOS and UNIX.

OUR CHALLENGE AND GUARANTEE

If you have an application where no other tool can do the job, try **Windows for Data**. If it doesn't help you solve your problem, RETURN FOR A FULL REFUND. YOU MUST BE SATISFIED.

WINDOWS FOR DATA WINDOWS FOR C

PC DOS*	\$295	\$195
XENIX-286	\$595	\$395
UNIX	CALL	CALL

Call for **FREE Demo diskette.**

*All popular C compilers; no royalties.



**Vermont
Creative
Software**

21 Elm Ave.
Richford, VT 05476
**802-848-7738,
ext. 21.**

MasterCard & Visa Accepted. Shipping \$3.50
VT residents add 4% tax.



Hercules compatible graphics:
720x348.



Plantronics compatible graphics:
640x200x4 colors.

Introducing The Paradise Hi-Res Graphics Card.TM Two Upgrades For The Price Of One.

Now you can have much higher resolution than your current video card gives you. Without buying new software. Or an expensive monitor.

All you need is the new Paradise Hi-Res Graphics Card.

It gives you the highest resolution possible on a standard monitor. With monochrome displays, you get Hercules compatible 720x348 graphics. With RGB and composite displays, you get Plantronics compatible graphics: 16 colors in 320x200, and 4 colors in 640x200. That's two upgrades for the price of one.

And no matter which monitor

you choose, the Paradise Hi-Res Graphics Card gives you full compatibility with standard video modes.

Better yet, you can use your existing software to its best advantage. Because Hercules and Plantronics graphics are widely supported by packages like Lotus 1-2-3, Symphony, Framework, and lots more.


And Paradise gives you all this, plus a parallel port. On one short card.

If you'd like to know more, we'll send you full information. Including a free Hi-Res software compatibility guide. Just call (800) 527-7977, Ext. 333, toll-free. From California,

(800) 822-2020, Ext. 333. Or check it out at the best PC dealers.

PARADISE
SYSTEMS, INC

The Paradise Hi-Res Graphics Card



Trademarks: Paradise, Hi-Res Graphics Card-Paradise Systems Inc.; Lotus 1-2-3, Symphony-Lotus Development Corporation; Symphony, Framework-Ashton-Tate, Inc. Registered trademark: IBM-International Business Machines Corp.

CIRCLE NO. 230 ON READER SERVICE CARD

The DataFlex logo is positioned at the top of the advertisement. It features the word "DATA" in blue and "FLEX" in a multi-colored, striped font. Below the logo is a large, stylized funnel graphic that tapers downwards, with its body colored in a gradient of blue, orange, red, and purple. The funnel's opening is at the top, just below the logo, and it narrows to a point just above the main headline.

DATA FLEX[®]

*The World's
Best Selling
Multi-User
Database
For Five Years
Running.*

A smaller version of the DataFlex logo is located at the bottom of the funnel graphic, just above the contact information. It consists of the word "DATA" in blue and "FLEX" in a multi-colored, striped font.

DATA FLEX

DataFlex versions are available
for all popular single-user and multi-user
operating systems, including Xenix.

For a free copy of this poster
(minus ad copy), write Data Access Corp.
or leave a message on our
Bulletin Board System: (305) 238-0640.

DATA ACCESS CORPORATION
8525 S.W. 129th Terrace—Miami—FL—33156-6565 (305) 238-0012—Telex 469021 DATA ACCESS CI

CIRCLE NO. 118 ON READER SERVICE CARD

See us at PC Expo Booth #1609

storing mostly empty records. For example, a 98,000-byte dBASE II file was reduced to less than 50,000 bytes when translated to Reflex format. The updated version of Reflex (available to current owners for \$10) supports the LIM expanded memory specification, so memory limitations should be no problem. Finally, the report generator allows you to preview the appearance of the printed report on the screen. This feature, particularly when used with a mouse, permits the easiest and fastest report design I have ever seen.

As your review noted, Reflex has no relational capabilities and should be considered as a file management system. At any price it would be a great program, but at \$99, it is a steal.

*Peter G. Aitken
Durham, NC*

HIGH C

I have been using Lattice C 2.15 for several months to develop a data entry program for a client. The program is split into 33 source code files, most containing two or more C functions, plus three assembly language functions. The compiler has performed without problem during development.

After reading the excellent review of C compilers in your January 1986 issue ("The State of C," William J. Hunt, p. 82), I could not wait to get my copy of Lattice C 3.0. As soon as I received it, I made a copy of my client's program and began a mini evaluation of my own. Here are my findings:

I compiled the program using the LC command and was immediately impressed. The compiler began issuing warning messages for variables that I had defined and never used and for variables I was using before a value had been assigned to them. In one of the source files, the compiler issued the message "statement has no effect." That statement, `x = 1;` was a data entry error on my part. Thus, the compiler found a bug in my program that I did not know about (the program was executing "correctly" despite this error).

I linked the program without error and attempted to execute it. It failed immediately. I isolated the failure to the use of the escape sequence `\\` in a character string in a `sprintf` statement. This was a problem known to Lattice and was fixed in the next version. I exchanged my diskettes (at no charge other than some postage) for the next version. I apparently exchanged 3.0e for 3.0g or 3.0h—it is difficult to identify exactly which of these two I had, be-

cause the compiler does not display its complete version number.

The next program failure I found is a problem with the C language. My program cannot read the data files created by its 2.15 cousin because the data records in the files are defined as **structs**, and the 3.0 compiler aligns **structs** differently than the 2.15 compiler (2.15 generated fill bytes, 3.0 did not). The compilers do have options on the command line to change the way data alignment is done, but this is the wrong place to control alignment. These options are global and do not help if, in the same program, some **structs** need to be aligned and some do not. This is a real problem if your C program is trying to read the output of other programs. This is not a problem that was caused by or can be corrected by Lattice. The ANSI C committee should add an unaligned modifier that can be used like the unsigned modifier, to all data types. (I have not seen the ANSI C standard document; perhaps something like this has been done already.)

I recreated the data files and immediately found another problem. This time it was the **strncpy** function that was not working the same as it did in 2.15. The 3.0 **strncpy** does not null terminate the result string. I created my own version of **strncpy** that is 2.15 compatible and now the program really does work. Lattice changed **strncpy** to conform with the ANSI standard.

Overall I am impressed with the Lattice C 3.0 compiler. I feel safe using it for any future development; however, great care must be taken when users are converting an existing program from the 2.x to the 3.0 compiler.


While I was evaluating the Lattice compiler, my client was evaluating the Microsoft C 3.0 compiler using the same program. The Microsoft compiler does not produce any of the nice warning messages that the Lattice compiler produced, and the program cannot be linked because it uses the **peek** and **poke** functions. Microsoft removed these functions from its 3.0 library. In addition, in order to execute the program, I would have to modify the assembly language subroutines (because Microsoft uses a different functions calling sequence on the stack).

*Hale Landis
Louisville, CO*

BUGGED

Your Product of the Month for January 1986, entitled "Structured Debugging" (Jeff Duntemann, p. 29) makes me won-

SQUEEZED FOR SLOTS?



I-Bus Expansion Chassis for IBM PC, PC/XT, PC-AT, Compaq, and other compatibles!

If you want the most from your PC but you've run out of places to put your add-on cards, an I-Bus Expansion Chassis is the right solution.

Choose our popular 6-slot mini-chassis or the larger 12-slot chassis with room for two half-height drives. Both come fully tested, complete with power supply and interface. (The interface card requires one slot in your PC.) Prices start at \$795.

They're ideal for portable PC's: a new quick-release 18" or 48" cable lets you leave the chassis (and all the connections to its cards) in place while removing the PC for travel. Or the reverse: move an expansion chassis with special-purpose cards from PC to PC in labs or test facilities.

There's no special addressing or software required to access expansion cards, and *no added wait states* for memory access. I-Bus expansion chassis works with all add-on cards—including display, memory, networking, communications and disk drive cards.

Call today
TOLL FREE:
(800) 382-4229
in California
call (619)
569-0646



I-BUS SYSTEMS

9235 Chesapeake Drive
San Diego, CA 92123

CAD — \$299 !

Finally you can get a complete CAD package at a reasonable price! For only \$299, ProDesign II provides the advanced features you get on CAD systems costing thousands of dollars. But there is another, very important reason you should get ProDesign II. ProDesign II is very unique among CAD packages. It is easy to learn and use. When we call ProDesign II "The Easy to Use CAD System", we're not joking. You will be productive with ProDesign II in an hour or two instead of a week or two.

What else does ProDesign II offer? Compatibility. Compatibility with over 100 printers. Compatibility with over 50 plotters. Compatibility with most graphics adapters, digitizing tablets, and mice. Compatibility with most display adapters. Compatibility with any software that can produce HP plotter commands. Compatibility with mainframe CAD systems (IGES). All at no extra charge!

What additional hardware do you need? None! An IBM PC compatible and 512K RAM is all you

need. ProDesign II produces high resolution drawings on your dot matrix printer — better than .005" resolution on an IBM/Epson compatible printer. In fact, the drawings on this page were printed on a \$299 dot matrix printer! You don't have to get a mouse or digitizing tablet. ProDesign II is designed for easy and efficient keyboard use. You won't even need a math coprocessor, although it is supported. From a small drawing on a dot matrix printer to an E-Size drawing on a large plotter, ProDesign II is the one to use!

ProDesign II
Affordable, Compatible, and Usable!

Where can you get ProDesign II?
See your local computer dealer, or contact:


American Small Business Computers

**118 South Mill
Pryor, OK 74361
(918) 825-4844**

IN GERMANY CALL 69-295111

1. BRADOME
2. 28MM ROTARY CANNON
3. AMMUNITION MAGAZINE
4. WINDSCREEN
5. INSTRUMENT PANEL
6. HEADS-UP DISPLAY
7. CANOPY
8. EJECTION SEAT
9. AVIONICS EQUIPMENT
10. SECOND SEAT SPACE
11. LEADING EDGE ROOT EXTENSION
12. FUSELAGE TANKS
13. LEADING EDGE FLAP
14. WING TANK
15. SIDEWINDER AIR-AIR MISSILE
16. MISSILE LAUNCH RAIL
17. NAVIGATION LIGHT
18. WING FOLD HINGE JOINT
19. AILERON
20. FLAP VANE
21. FLAP
22. HYDRAULIC RESERVOIRS
23. STROBE LIGHT
24. RUDDER HYDRAULIC ACTUATOR
25. NAVIGATION LIGHT
26. RADAR WARNING ANTENNA
27. FUEL JETTISON
28. MOVING TAILPLANE
29. ECM ANTENNA
30. RADAR WARNING ANTENNA
31. FORWARD LIGHTING STRIP
32. AFTERBURNER NOZZLE
33. AFTERBURNER NOZZLE ACTUATORS
34. MOVING TAILPLANE
35. TAILPLANE PIVOT MOUNTING
36. TAILPLANE HYDRAULIC ACTUATOR
37. TURBOFAN ENGINE
38. AILERON HYDRAULIC ACTUATOR
39. WING FOLD ACTUATOR
40. SIDEWINDER AIR-AIR MISSILE
41. LEADING FLAP ACTUATOR
42. WING TANK
43. LEADING FLAP DRIVE SHAFT
44. EQUIPMENT GEARBOX
45. AUXILIARY POWER TURBINE
46. REAR LANDING GEAR
47. SPARROW AIR-AIR MISSILE
48. LEADING FLAP DRIVE MOTOR
49. MAIN RETRACT ACTUATOR
50. FORWARD RETRACT ACTUATOR
51. LIQUID OXYGEN CONVERTER
52. BOMBING LADDER
53. FORWARD LANDING GEAR
54. CATAPULT LAUNCH STRAP
55. CONTROL COLUMN
56. RUDDER PEDALS
57. AMMUNITION FEED CHUTE
58. ANGLE OF ATTACK SENSOR
59. PITOT HEAD
60. FORWARD LIGHTING STRIP
61. RADAR EQUIPMENT BAY
62. FORWARD ECM ANTENNA
63. RADAR PIVOT MECHANISM
64. RADAR SCANNER

F-18 HORNET DRAWN USING PRODESIGN II



der whether you go beyond the manufacturers' press releases when you make your selection for this column.

You say that the product's most noteworthy feature is its protected memory board, which contains debugger code and is thus protected from the unruly behavior of the program being observed. Granted, this line is in the advertising copy of many debuggers on the market today. However, my experience (which includes the use of DEBUG, SYMDEB, ATRON PC Probe, and Intel ICE) indicates that it actually does not count for very much.

First, the path to the protected debugger code still lies in RAM, either at the breakpoint location where debuggers temporarily place an INT 03H instruction or at the vectors for the INT 03H or NMI interrupts. These locations could be hardware protected, but the article implies that this product does not have such a feature, and, of course, if a required RAM location gets wiped out, the protected code will not do much good. Second, claims about protected debugger code imply that overwriting is a frequent failing of untested software, yet in six months of ATRON use I cannot recall trapping because of an attempted access to the ATRON protected locations. (I even had to verify that such a trap would occur by writing test code.) Third, even if one were to get back to the debugger, he would not have much to look at if his code, data, and/or DOS had been overwritten.

The baseline product to which the Product of the Month is compared is DOS DEBUG. To my mind, this is almost like comparing it to switches and lights, as SYMDEB (supplied free with the Microsoft Assembler) is certainly the minimum (a very high minimum at that) debugger now used for any serious work. In fact, most of the features of the reviewed product are also features of SYMDEB.

The ATRON PC Probe is used as the top-of-the-line for comparison purposes. Certainly this is a good product and its realtime trace capability is superb. But it is not a "true hardware-breakpoint debugger" as any attempt to set an execution breakpoint in the BIOS will prove. So it is not clear what it is that the reviewer had in mind when using ATRON as a yardstick.

The review claims that the debugger can break on register values. Perhaps this is so. But Intel's ICE cannot perform such a break, and given the rest of the article, my guess is that neither can the reviewed product.

I have avoided mentioning the product's name because it might be a useful tool. Bad arguments on the product's behalf cast doubts on any good qualities it might have, and they make me wonder about the rest of the magazine, as well.

Michael Liebert
North Caldwell, NJ

Periscope was chosen as the January Product of the Month because it represents what we felt was an excellent bal-

ance between power and cost and it has an extraordinarily clean and innovative design. Associate technical editor Dan Beale and I used Periscope for a period of several weeks, tracing idiosyncratic software such as Microsoft Windows, and the overall aura of quality was too strong to ignore. All Product of the Month candidates are tested in-house without the knowledge of the vendor, and the winner is not notified until the issue containing the column is published. (Also note that Periscope was

Why debug your Program in Assembly Language when you wrote it in one of these...

Without source level debugging, the programmer must spend time mentally making translations between assembly language and the C or Pascal in which the program was written. These tedious translations burn up valuable time which should be spent making critical product schedules. Lower level debugging tools are superseded by Atron's **SOFTWARE SOURCE PROBE**. This is the debugging tool used by professionals. Why? — Because it has the features they need to solve complex debugging problems. **SOFTWARE SOURCE PROBE** has the same command interface as the Atron hardware assisted software debuggers — so you can fill your lab with compatible debugging tools and minimize new learning.

How To Single Step Your Source Code And Keep Critical Data In View

With **SOFTWARE SOURCE PROBE**, you can step your program by source code statements. While stepping, a window which you define can display critical high level data structures in your program. The next several source code statements are also displayed to give you a preview of what the program will do.

Software
Probe Source

How To Display Data In Meaningful Formats

Why look at program data in hex when you defined it to be another data type in your program. **SOFTWARE SOURCE PROBE** provides a formatted print statement to make the display of your variables look like something you would recognize. You can specify data symbolically, too.



Solving The Tough Bugs

When the others fail, **SOFTWARE SOURCE PROBE** keeps on debugging. When you need isolation between the debugger and the program — you get screen switching, dual monitor support, or you can run the debugger from a totally separate CRT. When you need to get out of a program lock up state — you get recovery through the optional crash recovery switch box. When you want to trace a procedure calling sequence — you get a command to unthread stack nesting. When you want conditional sequential breakpoints — you get powerful LOOP, LOOP COUNT and IF/THEN/ELSE debug commands. When you want to build complex command sequences, you get Macro commands. And when you need an affordable debugging tool — you get **SOFTWARE SOURCE PROBE — \$129** **CRASH RECOVERY SWITCH BOX — \$99**. Then when you want to optimize the performance of your program — get Atron's **SOFTWARE PERFORMANCE AND TIMING ANALYZER (also \$129)**. It gives you histograms of your executing program, counts events, and shows you all the execution times of given procedures.

So why waste more time. Call Atron and get one of our **BUGBUSTERS** today...



atron
THE DEBUGGER COMPANY

20665 Fourth Street • Saratoga, CA 95070 • 408/741-5900

CIRCLE NO. 249 ON READER SERVICE CARD

HELP

is at hand

HELP/Control™ - an online help subsystem for the IBM-PC. Increase product marketability. Reduce product development time.

HELP/Control is more than just context-sensitive help. It lets you build tutorial sessions, bill-of-material parts catalogs, inventory-driven cross selling... The sky's the limit.

And, **HELP/Control** is **fast**. Screens - up to full display size - appear almost instantaneously because the runtime system is written in assembler and accesses the screen memory directly. Smaller screens appear as windows. Once they've helped, the original display is restored just as quickly.

HELP for the programmer. A few simple subroutine calls add a full-featured online help subsystem to your application because **HELP/Control** is a runtime system linked or loaded with that application. (**HELP/Control** has been fully tested with IBM COBOL, IBM BASIC Compiler, Lattice C, Microsoft FORTRAN, Turbo Pascal, IBM BASIC Interpreter, and assembler. It is distributed with sample programs in each language.)

HELP for the documentation writer. Build screens. Define captions. Associate each caption with a screen. **HELP/Control** includes a screen generation language, HELPGEN, that reads your sources, creates a runtime file, and lets you use your favorite editor. Our **HELP/Control** reads that file and displays help screens when the user activates the help function.

HELP for the end user. Use the cursor control keys to select a caption. Press return. That's it. Each screen has a number of highlighted captions which indicate other screens with information on that subject. Lotus 1-2-3 users will feel right at home. We've even made the entire **HELP/Control** manual available as a set of screens so you can browse without ever cracking a book.

HELP for the procrastinator. Your system's complete? You may be able to add our slimmed down version of **HELP/Control** to your existing application. It provides all the user functions of our full system with a keyboard intercept for first rate help support with minimal effort without looking like an afterthought. (Some site or technical restrictions may apply.)

HELP/Control comes complete with a detailed manual, both online and printed, with information for the programmer and documentation writer. It also includes instructions for the end user which may be incorporated into the application documentation.

The Standard **HELP/Control** system implements the online documentation for our MDS Outline product.

PC-DOS 2.0 or greater required for developing **HELP/Control** applications. Applications using **HELP/Control** will run under PC-DOS 1.0 or greater. The runtime system requires approximately 9K for code and buffers for full size help screens.

The Complete **HELP/Control** package (software, both manuals, demo programs) is \$125.00. A demonstration diskette, including the online manual, is available for \$15.00. To order or for more information, complete this form and return it with your check. (Maine residents, please add 5% sales tax.) Or, call MDS, Inc. at (207) 772-5436. MasterCard and VISA accepted.

Please send me _____ copies of **HELP/Control** at \$125. each.

Name _____

Address _____

Phone _____

MC/VISA No. _____

Expiration Date _____

Return to:

MDS, INC., P.O. BOX 1237, PORTLAND, MAINE 04104



LETTERS

reviewed in detail in the March 1986 issue; see "Breaking Out With Periscope," Ward Christensen, p. 65.)

—JD

STICKING OUT HIS NEC

I would like to comment on Ted Mirecki's sidebar "V20 Compatibility and Performance" to the article "8088 vs V20" in the April 1986 issue (Juan Jimenez and Steve King, p. 73). I have an NEC V20 microprocessor installed in my PC compatible in place of the Intel 8088, and I have never had any compatibility problems. I also wrote my own set of Turbo Pascal benchmarks for the Intel 8088 versus the V20. My results for numeric calculations match those in the article, but I also ran two tests involving string manipulation.

The first test repeatedly concatenated five 51-byte strings to produce one 255-byte string; the second test repeatedly assigned one 255-byte string to another. The results from both of these tests indicated that the V20 is almost twice as fast as the 8088. It is possible that a similar instruction mix is used in the Norton SI program, which would account for the high performance rating.

David A. Hough
Littleton, CO

ERRATUM

With regard to information about communications links that appears on page 93 of "Controlling from Afar" (Augie Hansen, April 1986, p.84), please note the following corrections:

The maximum distance for unconditioned, unbalanced lines conforming to the RS-232 specification is 50 feet (about 15 meters), at a maximum data rate of 20 kilobits per second. The maximum distance may be extended beyond 50 feet by the use of special low-capacitance cabling or by reducing the data rate. As measured from the connection point at the data terminal equipment (DTE), the total equivalent load capacitance presented by the cabling and by the signal termination at the data communications equipment (DCE) or another DTE device must not exceed 2,500 picofarads.

To obtain reliable, direct connections over still longer distances and at high data rates, electronics and cabling should be used that conform to a balanced-circuit digital interface such as the RS-232 specification. In practice, distances of several miles are attainable under favorable conditions.

—CH



Mark Williams

Now the biggest name
in C compilers comes in a size
everybody can afford.

Let's C.™
\$75

Introducing Mark Williams' \$75 C compiler. Want to explore C programming for the first time? Or just on your own time? Now you can do it in a big way without spending that way. With Let's C.

This is no little beginner's model. Let's C is a powerful programming tool, packed with all the essentials of the famous Mark Williams C Programming System. The one chosen by Intel, DEC, Wang and thousands of professional programmers. The one that wins the benchmarks and the reviewers' praise:

Mark Williams Let's C

- For the IBM-PC and MS-DOS
- Fast compact code plus register variables
- Full Kernighan & Ritchie C and extensions
- Full UNIX™ compatibility and complete libraries
- Small memory model
- Many powerful utilities including linker, assembler, archiver, cc one-step compiling, egrep, pr, tail, wc
- MicroEMACS full screen editor with source
- Supported by dozens of third party libraries
- Upgradeable to C Programming System for large scale applications development

Let's C Benchmark Done on an IBM-PC/XT, no 8087.
Program: Floating Point
from BYTE, August, 1983.

Exec Time in Seconds

Let's C	134.20
MS 3.0	347.45

"(This compiler) has the most professional feel of any package we tested..."—BYTE
"Of all the compilers reviewed, (it) would be my first choice for product development."—David W. Smith, PC WORLD

And now for more big news. Get our revolutionary csd C Source

Debugger for just \$75, too.
You can breeze through debugging at the C source level ignoring clunky assembler code.

Affordable, powerful, debuggable. Mark Williams Let's C is the big name C compiler at a price you can handle. Get your hands on it now.

 **Mark Williams Company**

1430 West Wrightwood
Chicago, Illinois 60614

ORDER NOW! 60-DAY MONEY BACK GUARANTEE!

Mark Williams Let's C

Please send me:

_____ copies of Let's C and _____ copies of csd (C Source Debugger)
at \$75 each. (Ill. residents add 7% sales tax.)

☐ Check ☐ Money Order ☐ Visa, MasterCard or American Express

Name _____

Address _____

City _____ State _____ Zip _____

Card # _____ Exp. Date _____

Signature _____ TJ0786

TECH PC TWIN MULTIUSER

Starting From \$1699

TECH PC/XT BASE UNIT WITH 640K, AND TWO 360K DISK DRIVES.

TWO HIGH RESOLUTION MONITORS, TWO SELECTRIC STYLE HI-TEK KEYBOARDS, 50 FEET OF SHIELDED CABLE TO SEPARATE THE TWO STATIONS. SYSTEM SUPPORTS UP TO SIX PRINTERS.

FULL SOFTWARE SUPPORT WITH MULTI-LEVEL FILE SECURITY, ELECTRONIC MESSAGE FACILITY TO SEND AND RECEIVE MESSAGE BETWEEN USERS, PASSWORD LOGON SYSTEM, AND SYSTEM OPERATOR COMMAND LEVEL.

SYSTEM SUPPORTS ALL POPULAR SOFTWARE SUCH AS WORDSTAR, DBASEIII, LOTUS 123, MULTIMATE, ETC.



TECH PC TRIAD MULTIUSER

Starting From \$2599

TECH PC/XT BASE UNIT WITH 640K, AND TWO 360K DISK DRIVES.

SEPARATE INTEL 80188 MICROPROCESSOR RUNNING AT 8 MHZ AND 512K FOR EACH TERMINAL.

THREE HIGH RESOLUTION MONITORS, THREE SELECTRIC STYLE HI-TEK KEYBOARDS, 50 FEET OF SHIELDED CABLE TO SEPARATE THE THREE STATIONS.

SYSTEM EXPANDABLE TO 32 WORKSTATIONS.

SYSTEM SUPPORTS UP TO SIX PRINTERS.

FULL SUPPORT FOR MULTITASKING MULTITERMINAL USE WITH PRINT SPOOLING FOR MULTIPLE PRINTERS, BACKGROUND MONITORING OF THE SYSTEM, DIAL UP BULLETIN BOARD SUPPORT, PASSWORD PROTECTION, AND FILE/RECORD LOCKING SUPPORTING PC NETWORK PROTOCOL.

SYSTEM SUPPORTS ALL POPULAR SOFTWARE SUCH AS WORDSTAR, DBASEIII, LOTUS 123, MULTIMATE, ETC.



THE TECH PC



TECH PC

714/754-1170

2131 South Hathaway, Santa Ana, California 92705

Telex 272006 Answer Back - TECH FAX: 71415568325

MULTIPLE THIRD PARTY AVAILABLE THROUGH


TECH PC QUAD MULTIUSER

Starting From \$4499

TECH TURBO PC/AT BASE UNIT IN PORTABLE OR DESKTOP CONFIGURATION WITH 512K, MULTIPLE SERIAL PORTS, THREE TECH PC TERMINALS, CONNECTING CABLES, AND NETWORKING SOFTWARE.

FOUR USERS EXPANDABLE TO NINE USERS OVER DUMB TERMINALS OR PC'S WITH TERMINAL EMULATION SOFTWARE. CAPACITY FOR UP TO 16 PRINTERS AT REMOTE SITES WITH UP TO 6 LOCAL PRINTERS ATTACHED TO THE MAIN UNIT. EACH USER CAN ACCESS 512K OF RAM WITH MEMORY EXPANSION BOARDS.


FULL SUPPORT FOR MULTITASKING MULTITERMINAL USE WITH PRINT SPOOLING FOR CENTRAL OR TERMINAL PRINTING, BACKGROUND MONITORING OF THE SYSTEM, DIAL UP BULLETIN BOARD SUPPORT, PASSWORD PROTECTION, AND FILE/RECORD LOCKING USING PC NETWORK PROTOCOL. SYSTEM SUPPORTS ALL POPULAR SOFTWARE SUCH AS WORDSTAR, DBASEIII, LOTUS 123, MULTIMATE, ETC.



TECH PC TURBO QUAD MULTIUSER

Starting From \$5999

MULTIUSER SYSTEM



TECH PC/XT BASE UNIT IN PORTABLE OR DESKTOP CONFIGURATION WITH 640K, MULTIPLE SERIAL PORTS, THREE TECH PC TERMINALS, CONNECTING CABLES, AND NETWORKING SOFTWARE.

SEPARATE NEC V20 8088 INTEL COMPATIBLE 8 MHZ CPU AND UP TO 1 MB RAM FOR EACH TERMINAL ON THE SYSTEM.

TWO FULLY FUNCTIONAL SERIAL PORTS PER TERMINAL.

FOUR USERS EXPANDABLE TO 32 USERS OVER DUMB TERMINALS OR PC'S WITH TERMINAL EMULATION SOFTWARE. CAPACITY FOR UNLIMITED NUMBER OF LOCAL PRINTERS.

FULL SUPPORT FOR MULTITASKING MULTITERMINAL USE WITH PRINT SPOOLING FOR MULTIPLE PRINTERS, BACKGROUND MONITORING OF THE SYSTEM, DIAL UP BULLETIN BOARD SUPPORT, PASSWORD PROTECTION, AND FILE/RECORD LOCKING SUPPORTING PC NETWORK PROTOCOL.

SYSTEM SUPPORTS ALL POPULAR SOFTWARE SUCH AS WORDSTAR, DBASEIII, LOTUS 123, MULTIMATE, ETC.

**CHOICE
MAINTENANCE
MOHAWK DATA SCIENCES**

News about the Microsoft Language Family

Microsoft® muMATH™ used as a tool for teaching college calculus

In the fall of 1985, Cornell University began using Microsoft muMATH in its sophomore level math course that is taught to over 500 students. Professor Richard H. Rand and his colleagues at Cornell have developed a series of computer lessons that introduce the students to the power of computer algebra. Dr. Rand says that without a powerful product like muMATH, "...the point of the problem can be lost in the detail of the solution." Microsoft muMATH makes it possible to ... "assign 'tough' homework problems and to reinforce and clarify the mathematical principles with practice on the computer."

The lessons involving muMATH include (a) an introduction to its symbolic capabilities, (b) solving differential equations, (c) computing Fourier series coefficients, (d) computing eigenvalues and eigenvectors, and (e) deriving Laplace's equation in orthogonal curvilinear coordinate systems. For additional information, see "Teaching Engineering Analysis Using Symbolic Algebra and Calculus," *Engineering Education*, November 1985.

Microsoft muMATH is a symbolic algebra manipulation system. Calculations in typical scientific and engineering languages are arithmetic evaluations, requiring variables to have known values before they can be used. In contrast, calculations in muMATH are algebraic evaluations, performed symbolically. "?" prompts the user for an input. "@" identifies the answer determined by muMATH. The example shows how intermediate muMATH results can be used in later calculations.

```
A> MUSIMP MATSOL
?  LOAD (CALCULUS);
?  E1:EXPAND ((107-4 X^2 Y)^3);
@:  1225043-137388 Y X^2+5136 Y^2 X^4-64 Y^3 X^6
?  E2: DIF (LN COS(A Z^2),Z);
@:  -2 A Z SIN (A Z^2)/COS(A Z^2)
?  E1+E2;
@:  1225043-2 A Z SIN (A Z^2)/COS(A Z^2)-137388 Y X^2+5136 Y^2 X^4-64 Y^3 X^6
```

T.N.T. Software Develops Low Cost—High Function Applications in Microsoft QuickBASIC

Bruce Tonkin, president, says, "I wrote MY WORD!, a complete word processor with mail merge, macros, undelete, sort, calculator, and device-independent I/O, using the Microsoft QuickBASIC Compiler. I think Microsoft QuickBASIC is the best available language for any product needing dynamic character string operations. The new structured language features make for efficient, modular, and exceptionally readable code. Also, the Microsoft QuickBASIC Compiler takes advantage of the full capabilities of the latest versions of DOS. This increased efficiency can make the difference between a mediocre product and a good one, or between a good product and an outstanding one. I want to sell the best software I can. That's why I use Microsoft QuickBASIC."

T.N.T. Software also distributes a spelling checker and sort utility routines written in Microsoft QuickBASIC. Source code is available.


For more information on the products and features discussed in the Newsletter,
write to: Microsoft Languages Newsletter
 16011 NE 36th Way, Box 97017, Redmond, WA 98073-9717
Or phone:
 (800) 426-9400. In Washington State and Alaska,
 call (206) 882-8088. In Canada, call (416) 673-7638.

Latest DOS Versions:

Microsoft C Compiler	3.00
Microsoft COBOL	2.10
Microsoft FORTRAN	3.31
Microsoft Macro Assembler	4.00
Microsoft Pascal	3.31
Microsoft QuickBASIC	1.02

Microsoft is a registered trademark of Microsoft Corporation.
 IBM is a registered trademark of International Business Machines Corporation.
 muMATH is a trademark of The Soft Warehouse.

Look for the Microsoft Languages Newsletter every month in this publication.



Language Integration

Microsoft has developed methods that allow one language to call subprograms from another alien language.

FORTRAN programmers are getting scarce these days.

The brightest computer science graduates are choosing to work in C, and many others are lining up behind COBOL. FORTRAN code seems best supported by rewriting old FORTRAN into C or Pascal. This task, however, requires a person fluent in *both* of the languages involved.

The problem cries out for a means of preserving stable, shaken-out code in its original language and calling it from the language being used in development. The fundamental stumbling block to this process is that low-level calling conventions usually are not defined in high-level language standards. Two vendors can produce standard versions of the same language without providing the ability for one implementation to call subprograms in the other.

The situation is not hopeless. Perhaps a vendor of several languages could create a rational low-level calling convention understandable by each language, thereby making code in one language callable from all the others. Two vendors are moving in this direction: Microsoft with its latest releases of C, FORTRAN, and Pascal for DOS; and Pecan Software Systems with UCSD Pascal, UCSD FORTRAN, and UCSD BASIC running under Pecan's DOS-based p-System. Both vendors offer solid products, but Microsoft has addressed more of today's professional developer audience by including a C compiler in its product. For this reason, *PC Tech Journal* has named Microsoft's method of high-level language integration Product of the Month for July 1986.

Even when dealing only with languages under the control of a single vendor, the problem of language integration still exists. The question of the 8086 memory model used by a language must be considered. Calling across memory model boundaries is impossible because of the assumptions

made by the caller and the subprogram that is called about the nature of the code and data addresses involved. Microsoft C supports the small, medium, and large memory models, but, until recently, Microsoft Pascal supported only the medium model and FORTRAN only the large model. Pascal's memory model, however, was changed to large in release 3.3, so the three languages now can link using the large model.

Far more difficult is the question of calling conventions. FORTRAN and Pascal push parameters onto the stack in the order that they appear in subprogram declaration. C places parameters on the stack in reverse order. This allows a C subprogram to have a varying number of parameters because the first parameter declared is the last one on the stack and always at the same offset from the stack frame's base pointer. In FORTRAN and Pascal, the subprogram removes the parameters and return address from the stack as it returns; in C the calling logic cleans up the stack after a subprogram returns.

Microsoft has built attribute key words into the three languages. This feature allows all of them to use either the C or the FORTRAN/Pascal calling convention on a declaration-by-declaration basis. This control is available for both external (imported) and public (exported) subprograms.

The most difficult consideration in calling subprograms across language boundaries is parameter passing. Microsoft has given its three languages the ability to pass parameters either by value (pushing a copy of the data item passed onto the stack) or by reference with a long or short address. This involves extending FORTRAN with VALUE and NEAR attributes for parameters (the default has been to pass by reference with a long address) and extending Pascal with the VARS reserved word for declaring a reference parameter with a long address.

The final question to be answered when attempting language integration is the interpretation of data passed as parameters across language boundaries. C automatically converts single-byte parameters (such as Pascal's Char and Boolean types) to two-byte integer types before passing by value; Pascal and FORTRAN code must anticipate this conversion. Microsoft provides several options and ample documentation. Real number values are encoded differently depending on precision and language, and transferring real values across language bounds demands that much attention be given to detail.

Microsoft has provided an appendix entitled "Mixed Language Programming" with the documentation. Half of the 41 pages of this appendix is devoted to mixed-language programming considerations; the remaining half is a matrix that details how each major type from each language can be transferred to other languages. Only FORTRAN's large arrays (those that exceed 64KB) cannot be used by C or Pascal code.


Microsoft has not yet commented on whether it will incorporate its BASIC compiler into language integration. The prospects for COBOL and LISP are not good, because they are both interpreters. Nonetheless, the seamless integration of two languages as alien as C and FORTRAN is a major achievement and bodes well for the continuing struggle to advance software technology without losing the investment already made in past development.



High-Level Language Integration
 Microsoft C, 3.0: \$395
 Microsoft FORTRAN, 3.31: \$350
 Microsoft Pascal, 3.31: \$300
 Microsoft Corporation
 16011 N.E. 36th Way
 Redmond, WA 98052-6399
 800/426-9400; in Washington,
 206/882-8088

CIRCLE 336 ON READER SERVICE CARD

*Hardware, software, and other developments
for the IBM PC family*



IBM Proprinter XL



DOS version 3.2

FROM IBM

A wide-carriage model of the desktop IBM Proprinter has been announced by **IBM**. The all-points-addressable **Proprinter XL** features a three-button operator panel that lets users change print quality, choose character sizes and spacing, and print drafts in a quiet mode in 10 characters per inch. This nine-wire dot-matrix printer accommodates cut sheets or multipart forms up to 16½ inches wide and continuous forms up to 15 inches wide. \$799.

Enhancements to the IBM

Token-Ring Network enable users to share the resources of a wider range of information processing equipment and extend the distances over which networks can operate. PC users on the Token-Ring Network can access System/370 host applications through the 3725 communications controller directly attached to the network. As many as eight Token-Ring Networks can be connected to host systems through a single controller. System/36 computers can attach to the Token-Ring Network via a dedicated PC/AT operating as a LAN communications controller using the 5360 and 5362 LAN attachment feature. The 8219 optical fiber repeater extends the reach of the network to 2 kilometers (6,600 feet). The 8218 copper repeater extends the distance between wiring closets in a building to 750 meters (2,500 feet). The new IBM Type 9 media specification, introduced for the IBM Cabling System, is a thinner, more flexible version of Type 1 plenum cable.

IBM Series/1 Office Connect is a licensed program that enables Series/1 computers to distribute documents created on PCs. Documents may be stored on Series/1 direct access storage devices and printed on IBM 5219 letter-quality printers. This program offers electronic mail and messaging capabilities to PC users connected via the Se-

ries/1 to IBM System/370 hosts, System/36 and System/38 computers, and other IBM and non-IBM systems. \$6,600.

IBM Corporation, Information Systems Group, 900 King Street, Rye Brook, NY 10573; Contact the local IBM dealer, 800/426-2468

CIRCLE 301 ON READER SERVICE CARD

IBM also has announced **DOS version 3.2** as well as upgrades to four products that act as extensions to the operating system. **IBM TopView version 1.1** lets the user run several applications at the same time and switch among them easily. New functions include the ability to increase the number of programs users can start by allowing them to swap programs to disk or extended memory, the ability to process batch files, support for COMMAND.COM, resource management for up to five printers, and coexistence with all other system extensions. DOS 3.2, \$95; TopView 1.1, \$175.

The **IBM PC LAN Program version 1.1** permits the connection of two or more PCs, PC/XTs, PC/ATs, or PC Portables on the Token-Ring Network and PC Network. The upgraded program features the ability to use an IBM PC LAN server as an IBM 3270 emulation gateway, increased message editor functions, support for the Token-Ring adapter and the NETBIOS program for the Token-Ring adapter, and coexistence with all other system extensions. \$125.

IBM PC 3270 Emulation Program version 2.0, which allows PCs to communicate with a host computer, features an optional 3278/79 adapter or SDLC adapter attachment and coexistence with all other system extensions. \$425; entry-level version, \$185.

Finally, the **IBM Graphics Development Toolkit version 1.1** contains the virtual device interface that allows device-independent software and device-dependent drivers to communicate. New functions of version 1.1 include raster, bit map, and clipping; mouse


support; and coexistence with all other system extensions. \$495.

IBM Corporation, P.O. Box 1328, Boca Raton, FL 33429-1328; Contact the local IBM dealer, 800/426-2468

CIRCLE 302 ON READER SERVICE CARD

HARDWARE

Verticom Inc. has announced a 1,024-by-768 high-resolution controller called the **H-16**. The board emulates the IBM Enhanced Graphics Adapter, Color Graphics Adapter, and Monochrome Display Adapter and features more than 1.3MB of display memory. This memory is partitioned into two buffers for instantaneous double buffering, which allows the user to view and pan an entire object as well as a zoomed-up portion of




Verticom's H-16 high-resolution controller

that object at the same time in a split-screen format. The H-16 offers 16 displayable colors from a palette of 4,096 with four independently addressable bit planes. Under \$2,995.


Verticom Inc., 545 Weddell Drive, Sunnyvale, CA 94089; 408/747-1222

CIRCLE 309 ON READER SERVICE CARD

Quadram has announced **QuadEMS +**, a PC/XT expanded-memory board that is 100-percent software switchable between the AST/Quadram/Ashton-Tate enhanced expanded memory specification (AQE/EMS) and the Lotus/Intel/Micro-soft expanded memory specification



SURPRISE! by Maynard Electronics



Tecmar's EGA Master

(LIM/EMS). The QuadEMS+ supports 64KB and 256KB chips on the same board and can be stacked with 2MB of addressable memory. The board is also available in a multifunction version called the **QuadEMS+ I/O**, which features one bidirectional parallel port, one serial port that offers users a choice of 12 addresses, and a realtime clock/calendar with a battery backup. QuadEMS+ with 256KB, \$495; QuadEMS+ I/O with 256KB, \$545. *Quadram, One Quad Way, Norcross, GA 30093-2919; 404/923-6666*

CIRCLE 304 ON READER SERVICE CARD

SURPRISE!, a high-speed board from **Maynard Electronics**, does not use an expansion slot. It is installed into the 8088 slot of a system's motherboard to accelerate the PC by up to 2½ times the normal speed. The user can toggle SURPRISE! between fast and slow operation by pressing the Ctrl-Alt-\ combination. The software included with the board accelerates the speed of DOS. \$249. *Maynard Electronics, 460 E. Semoran Blvd., Casselberry, FL 32707; 305/331-6402*

CIRCLE 303 ON READER SERVICE CARD

A high-resolution controller card for color or monochrome graphics and text displays that is compatible with IBM's Enhanced Graphics Adapter has been announced by **Tecmar, Inc.** The **EGA Master** provides 640-by-350 resolution text and graphics in 16 colors (from a palette of 64), using the IBM Enhanced Color Display. It allows smooth scrolling and panning, and permits the production of 1,024 programmable characters. An optional serial port can be added to the board. \$395.


Tecmar also has introduced the **5251/11 Emulator Board**, a hardware/software package that enables a PC, PC/XT, or PC/AT to communicate with IBM System/3x series computers. This permits the simultaneous running of

host, printer, and PC sessions at full speed. Fully IBM compatible, Tecmar's 5251/11 Emulator Board operates with standard IBM software running on the host. The board fits into the half slot on the XT or PC Portable and incorporates surface-mount technology, custom gate arrays, and hybrid drivers for higher system reliability. \$795.

Tecmar, Inc., 6225 Cochran Road, Solon, OH 44139-3377; 216/349-0600

CIRCLE 305 ON READER SERVICE CARD

A new version of the **Smartmodem 1200B** internal modem from **Hayes Microcomputer Products, Inc.** works



A new version of the Smartmodem 1200B

in full- and half-card slots. Features include call progress monitoring, rotary and 16 DTMF or PABX dialing commands, built-in test modes, full Hayes AT command set implementation, CCITT V.22 compatibility, voice/data transmission, two phone jacks, 1200-bps and 0-to-300 bps transmission, and convenient redialing. The modem is bundled with Smartcom II software. \$549.

Hayes Microcomputer Products, Inc., P.O. Box 105203, Atlanta, GA 30348; 404/441-1617

CIRCLE 307 ON READER SERVICE CARD


A 2400-bps, autodial, half-card modem has been announced by **Anchor Automation, Inc.** The newest member of Anchor's Signalman family of modems, the **LIGHTNING** operates asynchronously

at 2400 bps with an automatic equalizer to ensure clear transmission over most telephone lines and with fallback to 1200 or 300 bps. It is bundled with Norton-Lambert's LYNC communications software. The modem includes an on-board speaker that provides audible call progress information. \$499. *Anchor Automation, Inc., 6913 Valjean Avenue, Van Nuys, CA 91406; 818/997-7758*

CIRCLE 308 ON READER SERVICE CARD

May-Craft Information Systems, Inc. has announced the availability of **Microcom's AX** line of asynchronous error-checking modems—five modems with transmission speeds up to 19.2 bps. All the modems provide Hayes (AT) and Microcom command set compatibility. New technology (including data compression) allows high-speed, error-free asynchronous communications over two wire dial-up lines. Error-free communications are provided through the Microcom Networking Protocol (MNP). All AX modems can operate in either asynchronous or synchronous mode, selected through commands or a front panel switch. Standard features include autodial, auto-answer, repeat and alternate number dial, and storage capacity for nine telephone numbers.

The **AX/1200** and **AX/2400** use MNP class 4 for error-free transmission with higher data throughput. Adaptive packet assembly transparently monitors telephone line conditions and automatically adjusts data packet size accordingly. Specially designed I/O buffers and flow control allow operation as high as 9600 bps even though the AX modem is transmitting at only 1200 or 2400 bps. The **AX/2400c** uses MNP class 5, which includes a proprietary compression technique that encodes data and reduces the number of bits transmitted, allowing text files to be sent over ordinary telephone lines at speeds as high as 4800 bps. The **AX/9612c** and **AX/**




AT-4000-i by Acknowledge

9624c use MNP class 6, which, in addition to the techniques in classes 4 and 5, provides statistical duplexing. This enables the modems to allocate line bandwidth and data traffic to achieve maximum throughput in both interactive use and file transfer. AX/1200, \$495; AX/2400, \$749; AX/2400c, \$899; AX/9612c, \$1,599; AX/9624c, \$1,795. *May-Craft Information Systems, Inc., 4312 Beltwood Parkway S, Dallas, TX 75244; 800/527-7456; in Texas, 214/392-3766*

CIRCLE 306 ON READER SERVICE CARD

Two high-capacity cartridge tape backup systems for the PC/XT and PC/AT have been announced by **Acknowledge, Inc.** Based on 3½-inch tape drive technology, the products provide 40MB of data storage per cartridge; data transfer rates exceed 3MB per minute. **Model**



A-Frame-40 by Acknowledge

AT-4000-i is an internally mounted unit that is designed specifically for the AT. **A-Frame-40** is an external system that fits on top of a system's CPU box just to the right of the monitor; thus, it takes up no desk space. AT-4000-i, \$595;

A-Frame-40, \$850; optional FCAB01 floppy-disk controller board, \$195. *Acknowledge, Inc., 100 Pennsylvania Avenue, Framingham, MA 01701; 800/533-1776; in MA, 617/620-8843*
CIRCLE 320 ON READER SERVICE CARD

AST Research, Inc. introduced the **SixPakPremium** expanded memory/multifunction board for the new PC/XT as well as the existing PC/XT, PC, and compatibles. SixPakPremium operates under the AST enhanced expanded memory specification. The board comes bundled with DESQview multitasking/windowing software and AST's SuperPak utility software. As a result, users can create RAM disks and allow for print spooling. The SixPakPremium features two serial ports (one standard, one optional), one parallel port, a battery-backed clock/calendar, and an optional game adapter port. \$595 to \$1,445, depending upon configuration. *AST Research, Inc., 2121 Alton Avenue, Irvine, CA 92714; 714/863-1333*

CIRCLE 310 ON READER SERVICE CARD

A high-performance multifunction board for use with the PC/AT that offers expanded, extended, and conventional memory, as well as two serial ports and one parallel port has been announced by **IDEAssociates, Inc.** The **IDEA Supermax/EMS** provides a memory capacity of up to 4MB and is compatible with the Lotus/Intel/Microsoft expanded memory specification. \$495 to \$2,595, depending upon configuration. *IDEAssociates, Inc., 29 Dunham Road, Billerica, MA 01821; 617/663-6878*
CIRCLE 314 ON READER SERVICE CARD

A multifunction, multidisplay board called **MEMEK** has been announced by **Boca Research, Inc.** MEMEK offers up to 2MB of expanded memory designed to conform to the Lotus/Intel/Microsoft specification. The board also provides a parallel port, a serial port, a clock/calen-

dar, and emulation of the Hercules Graphics and Plantronics color cards as well as the IBM CGA and MDA. MEMEK installation requires neither switch nor jumper settings. The product is shipped with a RAM disk and a print spooler. \$645; with 1MB RAM, \$795; additional 1MB RAM expansion board, \$345. *Boca Research, Inc., 6401 Congress Avenue, Boca Raton, FL 33431; 305/997-6227*

CIRCLE 313 ON READER SERVICE CARD

Philips Subsystems and Peripherals, Inc. has introduced a CD ROM drive with a fully implemented SCSI interface. The **CM 110** drive provides fast and



CM 110 CD-ROM by Philips Subsystems and Peripherals

virtually error-free access to 600MB of digitally encoded data on standard 120-mm (4.72-inch) compact disks. The SCSI interface board handles both error detection and correction and allows for streaming capabilities so as to maintain a data transfer rate of 150K bps. \$600 in OEM quantities.

Philips Subsystems and Peripherals, Inc., 100 E. 42nd Street, New York, NY 10017; 212/850-5011

CIRCLE 319 ON READER SERVICE CARD

Turbo Pascal and the Turbo Pascal family give you a perfectly integrated programming environment and unbeatable speed, power, and price

Turbo Pascal® is *faster* than any other Pascal compiler, and at only \$69.95, a distinctly better deal. But it offers much more than speed, power, and price.

There's also the complete Pascal family of products that's grown from 1 to 9 products in just 3 years.

Turbo Pascal is backed by a complete range of "toolboxes" that give you most of the programming tools you'll ever need.

The Turbo Pascal family is never static, but is continuously expanding, with new products like Turbo Editor Toolbox™ and Turbo GameWorks™.

The secret of software success is not merely low price, but top quality, allied with complete documentation, like our 400-page reference manual.

All of which are some of the reasons why Turbo Pascal is clearly the leader, and the recipient of awards like PC Week's "Product of the Year" and PC Magazine's "Award for Technical Excellence." And some of the reasons why Turbo Pascal has now become a *de facto* worldwide standard with more than half a million users.

Turbo Pascal has grown from a single product 3 years ago to a family of 9 today.

Success breeds success, so the Turbo Pascal family has flourished. Your choices now include:

☐ **Turbo Pascal 3.0** combines the fastest Pascal compiler with an integrated development environment.

☐ **Turbo Pascal with 8087** math co-processor support for heavy duty number-crunching, and/or Binary



- Turbo Pascal 3.0
- Turbo Pascal with the 8087 support
- Turbo Pascal with Binary Coded Decimal, (BCD)
- Turbo Pascal with 8087 and BCD
- Turbo Database Toolbox™
- Turbo Graphix Toolbox™
- Turbo Tutor®
- Turbo Editor Toolbox
- Turbo GameWorks

Coded Decimals to eliminate rounding-off errors for business applications.

☐ **Turbo Database Toolbox** is a perfect complement to Turbo Pascal. It includes a complete library of Pascal procedures that allows you to search and sort data, and build powerful database applications.

☐ **Turbo Graphix Toolbox** includes a library of graphics routines for Turbo Pascal programs. Lets even beginning programmers create high-resolution graphics with an IBM®, Hercules®, or compatible graphics adapter. Does complex business graphics, easy windowing, and stores screen images to memory.

☐ **Turbo Tutor** teaches you step by step how to use Turbo Pascal, with commented source code for all program examples on diskette.

Save \$109.70 when you choose the Turbo Jumbo Pack. 6 different Turbo Pascal products for only \$245.00!

For only \$245.00, you get Turbo Pascal 3.0 and Turbo Editor Toolbox and Turbo Tutor and Turbo Graphix Toolbox and Turbo GameWorks and Turbo Database Toolbox!

All 6 for only \$245.00, which saves you \$109.70. This limited offer is good through September 1, 1986, so act now.

NEW! Amazing value! Turbo Editor Toolbox includes MicroStar™, a full-blown editor that also does windows! Turbo Editor Toolbox not only gives you ready-to-compile source code and a 200-page manual that tells you how to integrate the editor procedures and functions into your programs, but also includes

MicroStar, a complete editor with full windowing capabilities. (You could pay \$100.00 or more for a program like MicroStar, but you get it free as part of our Turbo Editor Toolbox.) You can also use Turbo Editor (which of course integrates with Turbo Lightning™) to build your own word processor!

NEW! Turbo GameWorks gives you the games you can write, rewrite, bend and amend! Turbo GameWorks reveals the secrets of game design and the strategies. You're given source code, a 200-page manual, and the insight

needed to write and customize your own irresistible games.

Turbo GameWorks also includes ready-to-play Chess, Bridge, and Go-Moku—an ancient Japanese game that can divert you from reality for hours on end.

“Language deal of the century... Turbo Pascal
Jeff Duntemann, PC Magazine

Turbo Pascal has got to be the best value in languages on the market today

Jerry Pournelle, BYTE Magazine

This compiler, produced by Borland International, is one of the best programming tools presently available for the PC

Michael Covington, PC Tech Journal

YES! I want the best

To order by phone, or for a dealer nearest you, call (800) 255-8008 in CA call (800) 742-1133

Copies	Product	Price	Totals
—	Turbo Pascal 3.0	\$69.95	\$
—	Turbo Pascal w/8087††	\$109.90	\$
—	Turbo Pascal w/BCD††	\$109.90	\$
—	Turbo Pascal w/8087, BCD††	\$124.95	\$
—	Turbo Database Toolbox	\$54.95	\$
—	Turbo Graphix Toolbox†	\$54.95	\$
—	Turbo Tutor	\$34.95	\$
—	Turbo Editor Toolbox†	\$69.95	\$
—	Turbo GameWorks†	\$69.95	\$
—	Turbo Jumbo Pack†	\$245.00	\$

Outside USA add \$10 per copy
CA and MA res. add sales tax \$
Amount enclosed \$

Prices include shipping to all US cities.

Carefully describe your computer system:

Mine is: ☐ 8-bit ☐ 16-bit

I use: ☐ PC-DOS ☐ MS-DOS ☐ CP/M-80 ☐ CP/M-86

My computer's name and model is:

The disk size I use is: ☐ 3 1/2" ☐ 5 1/4" ☐ 8"

Payment: ☐ VISA ☐ MC ☐ Bank Draft ☐ Check

Credit card expiration date: /

Card #

**NOT COPY PROTECTED
60-DAY MONEY-BACK GUARANTEE

Name: _____

Shipping Address: _____

City: _____

State: _____ Zip: _____

Telephone: _____

CODs and purchase orders WILL NOT be accepted by Borland. Outside USA make payment by credit card or International Postal Money Order.

*Limited Time Offer until September 1, 1986.

**YES, if within 60 days of purchase this product does not perform in accordance with our claims, call our customer service department and we will gladly arrange a refund.

Minimum System Requirements:

Turbo GameWorks, Turbo Graphix Toolbox, & Turbo Editor Toolbox—128K. All other products, 128K.

†IBM PC, PCjr, AT, XT, and true compatibles.

††16-bit only.

TF6



4585 SCOTTS VALLEY DRIVE
SCOTTS VALLEY, CA 95066
(408) 438-8400 TELE: 172373

Borland products include Turbo Pascal, Turbo Prolog, Turbo Database Toolbox, Turbo Lightning, Turbo Graphix Toolbox, Turbo Tutor, Turbo GameWorks, Turbo Editor Toolbox, Word Wizard, Reflex, The Analyzer, SideKick, SideKick, The Macintosh Office Manager, Travelling SideKick, and SuperKey—all of which are trademarks or registered trademarks of Borland International, Inc. or Borland/Analytica, Inc.


Turbo Pascal and Turbo Tutor are registered trademarks, and Turbo GameWorks, Turbo Editor Toolbox, Turbo Database Toolbox, Turbo Graphix Toolbox, Turbo Lightning, and MicroStar are trademarks of Borland International. IBM is a registered trademark of International Business Machines Corp. Hercules is a trademark of Hercules Computer Tech. Copyright 1986 Borland International. 86-10360

CIRCLE NO. 253 ON READER SERVICE CARD





Banyan's Network Server



By ZyLAB Corporation

Chauffeur HT, a video display adapter from **STB Systems, Inc.**, combines three industry standards: STB's Chauffeur technology (which displays standard CGA software on IBM-compatible monochrome monitors without any drivers), Hercules monochrome graphics, and Tseng Laboratories 132-character compatibility. No preboot software or special drivers are needed to use the Chauffeur HT with standard CGA or MGA software. For monochrome monitors, the adapter converts color display to 16 shades of gray, and text is displayed in high-resolution 8-by-14 characters. Hercules-compatible software is displayed in 720-by-348 resolution. The Chauffeur HT runs all CGA and monochrome printer adapter software on standard RGB color monitors. Software compatible with the STB Graphix Plus II and Color XVI display adapters can use the Chauffeur HT's high-resolution 4- and 16-color graphics modes. The Chauffeur HT drives high-resolution 25-KHz color monitors producing 400-line displays. \$349.

STB Systems, Inc., 601 N. Glenville, Suite 125, Richardson, TX 75081; 214/234-8750

CIRCLE 311 ON READER SERVICE CARD

Three modem products have been introduced by **Codex Corporation**. The V.32 modems, **Codex 2250** and **2260**, allow 4800- and 9600-bps full-duplex data transmission over dial lines. The modems exceed recommendations established by the CCITT for V.32 high-speed dial-line transmission and provide synchronous and asynchronous communications, full ACU support, short and long haul echo cancellation, and a coded modulation scheme. The **Codex 2650** is a high-speed multipoint modem that operates at 14.4K bps, achieving 99.9 percent error-free performance. It operates at a significantly higher speed than 9600 bps without compromising data integrity. The **Codex 2321** and

2341 economy modems are designed for multipoint network operation and offer competitive performance for 4800- and 9600-bps transmission over leased lines. Codex 2250, \$2,995; 2260, \$3,495; 2650, \$6,600; 2321, \$1,500; 2341, \$1,950. *Codex Corporation, 20 Cabot Blvd., Mansfield, MA 02048-1193; 617/364-2000*

CIRCLE 318 ON READER SERVICE CARD

A new EGA-compatible monitor has been announced by **Quadram**. The **Quadchrome Enhanced Display** provides 640-by-320 pixel resolution with an IBM Enhanced Graphics Adapter (EGA). It also provides a 320-by-200 resolution Color Graphics Adapter (CGA) mode display and is equipped to switch automatically between EGA (22.0 KHz) and CGA (15.75 KHz) modes. The Quadchrome display has a switch that can be set to green and amber text to provide crisp monochrome output. It features a 13-inch, nonglare, tinted screen and an 80-character-by-25-line display with a sharp .31-mm trio dot pitch. The screen can support up to an 80-character-by-43-line display. \$795.

Quadram, One Quad Way, Norcross, GA 30093; 404/923-6666

CIRCLE 312 ON READER SERVICE CARD

SOFTWARE

DOS 3.1 and NetBIOS support are included in release 1.3 of **VINES**, a virtual networking software package from **Banyan Systems Incorporated** (which also produces a Network Server). This release includes design tools that enable programmers to develop network applications; diagnostics that operate locally or remotely for system hardware, network media, and serial communications; support for the Ungermann-Bass baseband/broadband Net/One LAN; and Interactive Systems/3M broadband LAN. Also included are timed system backup

and recovery; configurable 25th line display; improved print spooling, forms support, print queue management, and printer access control.

Banyan Systems Incorporated, 135 Flanders Road, Westboro, MA 01581; 617/898-2404

CIRCLE 323 ON READER SERVICE CARD

A new release of its full-text search software has been announced by **ZyLAB Corporation**. **ZyINDEX 2** is compatible with CD ROM devices, write-once-read-many (WORM) optical disks, popular LANs, and 26 major word processors. ZyINDEX can search text stored on CD ROMs and WORMs, enabling users to find any string in a 20MB section of the disk in seconds. Users can mark searched text for automatic saving and can retrieve updates stored on a hard disk. Features of the new release include simplified menus, color support, the removal of copy protection and configuration files, and a rewritten user's guide and tutorial. Standard \$145; Professional version, \$295; Plus version, \$695; tutorial disks, \$10; upgrade, \$35. *ZyLAB Corporation, 233 E. Erie Street, Chicago, IL 60611; 312/642-2201*

CIRCLE 324 ON READER SERVICE CARD

Storage Dimensions, Inc. has announced the availability of **SpeedStor**, a disk drive integration software package. SpeedStor breaks the DOS 32MB barrier and easily integrates from 20MB to 256MB of internal hard-disk mass storage in the PC/AT. It provides up to a 30 percent improvement in hard disk data throughput and system performance. The product features easy-to-learn menu-driven programs, as well as a formatter, diagnostics, and a partition editor. It is fully compatible with DOS and DOS 3.1 LANs. \$149.

Storage Dimensions, Inc. 14127 Capri Drive, Suite 1, Los Gatos, CA 95030; 408/370-3304

CIRCLE 325 ON READER SERVICE CARD


Reflex, The Analyst upgrades and adds the new Reflex Workshop!

Why running your business without Borland's Reflex and the new Reflex Workshop is an act of blind faith

Running a successful business isn't something you can do with your eyes shut, but no matter what business you're in, Reflex™ and the new Reflex Workshop™ give you all the tools and views to see what all the numbers look like.

Using Lotus 1-2-3® or dBASE® without Reflex is like driving at night without lights


Products such as 1-2-3 or dBASE can do the numbers for you, but you may still not get the picture—simply because they can't show you analytical graphs and pictures of your data, nor can they analyze and summarize all the information you manipulate like Reflex can.



The best just got better. Introducing Reflex 1.1 **NEW!**

The new Reflex 1.1 with extended memory support allows you to manage huge databases of up to 8 megabytes of RAM, 32,000 records, and 250 fields per record with the now-legendary "Reflex Lightning Speed." Furthermore, Reflex 1.1 with its EGA support displays 40 lines of information in its spreadsheet-style List View, compared to less than 25 lines displayed by traditional spreadsheets.

Reflex gives you five graphic ways of looking at your data, five different ways of analyzing your information.



SPECIAL OFFER!

If you already bought Reflex 1.0, get Reflex 1.1 and the Reflex Workshop for only \$59.95

Because you bought Reflex from us, you're "our kind of people." And since we're not the "take-the-money-and-run" kind of company, you can upgrade to Reflex 1.1 and the Reflex Workshop for only \$59.95. If you prefer to simply upgrade to Reflex 1.1, you can do that for only \$10.

SPECIAL OFFER!

You get Reflex 1.1 and the Reflex Workshop for only \$199.95*

Sold separately, the new Reflex Workshop is \$69.95 and Reflex is \$149.95, totaling \$219.90—but you can get them both for a limited time only, at an amazing \$199.95. So act now, rush to your nearest dealer, call us, or clip the coupon and put Reflex 1.1 and the Reflex Workshop to work for you right away!

NEW! Introducing the Reflex Workshop

Only \$69.95
A major addition to Reflex, the new Reflex Workshop gives you a wide range of analytical tools written for specific applications. You can use these tools "as is" or modify them to suit your analytical and business needs. What you have to work with right away are 25 different tools:

For Finance/Accounting:

- Business Expense Tracking
- Petty Cash Tracking
- Line of Credit Tracking & Analysis
- Accounts Receivable Tracking & Aging Analysis
- Purchase Order Entry & Analysis
- Purchase Order Tracking System
- Leasing Inventory Management
- Asset Inventory Tracking
- Cash Management Trial Balance

For Administration:

- Membership Dues Tracking and Analysis
- Mail List
- Time Management
- Appointment Scheduling
- Applicant Tracking & Inquiry System
- Facilities Planning

For Sales & Marketing:

- Sales Lead Tracking & Analysis
- Store Check Inventory Analysis
- Sales Analysis
- Trend Analysis
- Research Questionnaire Analysis

For Production and Operations:

- Manufacturing Quality Assurance Tracking
- Assembly Repair Turnaround Tracking
- Commercial Real Estate Tracking & Analysis
- Project Scheduling
- Product Cost Analysis and Control



BORLAND
INTERNATIONAL

Vive la différence

4585 SCOTTS VALLEY DRIVE
SCOTTS VALLEY, CA 95066
(408) 438-8400 TELEX: 172373

Borland products include Turbo Pascal; Turbo Prolog; Turbo Database Toolbox; Turbo Lightning; Turbo Graphics; Turbo Tutor; Turbo GameWorks; Turbo Editor; Turbo Wizard; Reflex; The Analyst; Reflex Workshop; SideKick; The Macintosh Office Manager; Traveling SideKick; and SuperKey—all of which are trademarks or registered trademarks of Borland International, Inc. or Borland Analytica, Inc.

Reflex and Reflex Workshop are trademarks of Borland Analytica, Inc. dBASE is a registered trademark of Ashton-Tate. Lotus 1-2-3 is a registered trademark of Lotus Development Corp. Above Board is a trademark of Intel Corp. RAMPage is a registered trademark of AST Research Corp. Liberty is a trademark of Quadram Corp. Hercules is a trademark of Hercules Computer Tech. PFS: File is a registered trademark of Software Publishing Corp. IBM is a registered trademark of International Business Machines Corp. Copyright 1986 Borland International BI-1052

CIRCLE NO. 254 ON READER SERVICE CARD

“ The best database around . . . at any price.

Jean Lockwood,
Computer Retail News

Everyone agrees that Reflex is the best-looking database they've ever seen.

Adam B. Green, InfoWorld

Reflex excels as an analytical tool . . . this program can become everyman's database manager.

Frank J. Derfler, PC Magazine

Borland has done it again.

Sheldon L. Richman,
Washington Post

YES! I want the best
Send me Reflex and Reflex Workshop at:

\$199.95*

To order by phone,
or for a dealer nearest you,
call (800) 255-8008
in CA call (800) 742-1133

Reflex/Workshop(s) at \$199.95* \$ _____
Reflex at \$149.95* \$ _____
Workshop at \$69.95* \$ _____
Upgrade to 1.1 and Workshop at \$59.95 \$ _____
Upgrade to 1.1 at \$10.00 \$ _____
(you must return your disks)

Outside USA add \$10 per copy
CA and MA res. add sales tax \$ _____
Amount enclosed \$ _____

Prices include shipping to all U.S. cities
†You must have an IBM or true compatible running
DOS 2.0 or later.

My computer's name and model is:

The disk size I use is: ☐ 3 1/2" ☐ 5 1/4"
Payment: ☐ VISA ☐ MC ☐ Bank Draft ☐ Check
Credit card expiration date: ____/____/____
Card # _____

NOT COPY PROTECTED
****60-DAY MONEY-BACK GUARANTEE**

Name: _____

Shipping Address: _____

City: _____

State: _____ Zip: _____

Telephone: _____

CODs and purchase orders WILL NOT be accepted by Borland.
Outside USA make payment by credit card or International Postal
Money Order.

*Limited time offer until September 1, 1986

**YES, if within 60 days of purchase this product does not
perform in accordance with our claims, call our customer service
department and we will gladly arrange a refund.


†Minimum System Requirements:

384K—Runs on IBM PC, AT, XT, and true compatibles. IBM
Color Graphics Adapter, Hercules Monochrome Graphics Card
or equivalent.

Reflex works with Intel's Above Board AT and Above Board/PC,
AST's RAMPage and RAMPage AT, Quadram's Liberty-PC and
Liberty-AT, Tecmar's 640 Plus, IBM's EGA
and 3270/PC, AT&T's 6300,
and many others.

R6





From Allen, Emerson & Franklin, Inc.



Chalcadony's disk directory utility

Allen, Emerson & Franklin, Inc. has announced **version 2** of the **GTP Development System**. GTP is an application generator that produces error-free Turbo Pascal code for screen and database systems. Version 2 features the ability to create multiple-screen applications automatically, a context-sensitive help function, a new database manager, and global search criteria. \$150.

Also available is the **GTP Professional Model**, which includes two fully integrated generators: a report generator operating from the database definitions created for screen programs; and a menu generator for bundling application programs together. \$200.
Allen, Emerson & Franklin, Inc., P.O. Box 928, Katy, TX 77492; 713/391-8570

CIRCLE 327 ON READER SERVICE CARD

A disk directory utility from **Chalcadony Software** is designed to help the user move easily through DOS and printer commands. **SCOUT** is memory resident and can be unloaded when not in use. It can move files, perform mass file copy and delete, search for files, establish default sort, perform multiple file sorts, change sort type dynamically, display directories, alter file attributes, view text files, and tag, untag, and retag files. SCOUT can format a floppy disk from within a resident program at twice the speed of DOS. \$49.95.

Chalcadony Software, 5580 La Jolla Blvd., Suite 126, La Jolla, CA 92037; 800/621-0852, ext. 468; in California, 619/483-8513

CIRCLE 328 ON READER SERVICE CARD

Signal Processing and Display Programs (SPD), a waveform processing, display and data structure manipulation package for the PC/XT or PC/AT, is available from **Tektronix, Inc.** SPD lets design and test engineers extract waveform pulse parameters automatically, and quickly convert time domain wave-

forms into the frequency domain using a fast Fourier transform. The product offers more than 190 processing functions in formats for users at every programming level. \$950.

Tektronix, Inc., P.O. Box 500, Beaverton, OR 97077; 800/426-2200; in Oregon call collect, 503/627-9000

CIRCLE 326 ON READER SERVICE CARD

A source-form version of the **Modula-2 compiler** for porting to any computer system is available from **Modula Corporation**. Written by Niklaus Wirth, the author of Modula and Pascal, the new version is faster because it is based on the single-pass principle. The package includes the source code to the compiler and a portable debugger, a copy of the third edition of *Programming in Modula-2* (Springer-Verlag, 1985), and reports documenting the structure of the compiler and debugger. \$1,000.
Modula Corporation, 1673 W. 820 North, Provo, UT 84601; 800/LILITH2; in Utah, 801/375-7400

CIRCLE 329 ON READER SERVICE CARD

Coefficient Systems Corporation has announced **VTERM III**, an enhanced version of the VTERM II integrated software package for communications between PCs and DEC VAX and PDP-11 computers. VTERM III combines VT100 terminal emulation, Kermit and multiprotocol file transfer, and asynchronous communications capability up to 19200 baud. It provides capabilities for the transfer of text and binary files with or without error correction and under local or host control. VTERM supports ASCII text file transfer, XMODEM, VTRANS7 and VTRANS8 protocols, and Kermit. \$195; upgrade from VTERM II, \$70; VTERM III with VT100 and Tektronix 4010 terminal emulation, \$249.

Coefficient Systems Corporation, 611 Broadway, Suite 426B, New York, NY 10012; 212/777-6707

CIRCLE 330 ON READER SERVICE CARD

A C language compiler called **HOT C** has been introduced by **WordTech Systems, Inc.** The basic package contains the compiler, a C tutorial, a program editor, and a symbolic debugger. The compiler features a preprocessor, a code generator, an optimizer, a macro assembler, large and small memory models, and a UNIX-compatible function library. HOT C is not copy protected. \$99.
WordTech Systems, Inc., P.O. Box 1747, 21 Altarinda Road, Orinda, CA 94563; 415/254-0900

CIRCLE 332 ON READER SERVICE CARD

A storage management utility package called **Arkive** has been announced by **Guaranteed Software**. Arkive is an automated file-tracking and archival program that is memory resident. It automatically and transparently creates and maintains a database; the user invokes a clean-up mode that scans the database and identifies obsolete files. These files are moved off the hard disk onto archive media, such as floppy disks, cartridge disks, or tape drives. \$79.95.
Guaranteed Software, 10044 South DeAnza Blvd., Cupertino, CA 95014; 800/232-7222, in California, 800/331-6223

CIRCLE 333 ON READER SERVICE CARD

Security Microsystems Consultants has announced **LOCKIT II**, a package that lets the user of a hard-disk-based PC set up password protected subdirectories. Passwords may be changed at any time, and utilities are included to make files read-only and invisible. LOCKIT II can work in conjunction with LOCKIT I, an access control device that mounts on the motherboard and prevents boot up without a user-specified password. LOCKIT II is not copy protected. LOCKIT II, \$79.95; LOCKIT I, \$189.95.

Security Microsystems Consultants, 16 Flagg Place, Suite 102, Staten Island, NY 10304; 718/667-1019


CIRCLE 343 ON READER SERVICE CARD

Step-by-step tutorial, demo programs with source code included!

Borland introduces Turbo Prolog, the natural language of Artificial Intelligence.

Prolog is probably the most powerful computer programming language ever conceived, which is why we've made it our *second* language—and "turbocharged" it to create Turbo Prolog."

Our new Turbo Prolog brings supercomputer power to your IBM® PC and introduces you step-by-step to the fascinating new world of Artificial Intelligence. And does all this for an astounding \$99.95.



Turbo Prolog is to Prolog what Turbo Pascal® is to Pascal!

Our Turbo Pascal astonished everyone who thought of Pascal as "just another language." We changed all that—and now Turbo Pascal is the de facto worldwide standard, with hundreds of

thousands of enthusiasts

and users in universities, research centers, schools, and with professional programmers, students, and hobbyists.

You can expect at least the same impact from Turbo Prolog, because while Turbo Prolog is the most revolutionary and natural programming language, it is also a complete development environment—just like Turbo Pascal.

Turbo Prolog radically alters and dramatically improves the brave new world of artificial intelligence—and invites you into that fascinating universe for a humanly intelligent \$99.95.

Even if you've never programmed before, our free tutorial will get you started right away

You'll get started right away because we have included a complete step-by-step tutorial as part of the 200-page Turbo Prolog Reference Manual. Our tutorial will take you by the hand and teach you everything you're likely to need to know about Turbo Prolog and artificial intelligence.

For example: once you've completed the tutorial, you'll be able to design your own expert systems utilizing Turbo Prolog's powerful problem-solving capabilities.

Think of Turbo Prolog as a high-speed electronic detective. First, you feed it information and teach it rules. Then Turbo Prolog "thinks" the problem through and comes up with all the reasonable answers—almost instantly.

If you think that this is amazing, you just need to remember that Turbo Prolog is a 5th-generation language—and the kind of language that 21st century computers will use routinely. In fact, you can compare Turbo Prolog to

Turbo Pascal the way you could compare Turbo Pascal to machine language.

You get the complete Turbo Prolog programming system for only \$99.95

You get a complete Turbo Prolog development system including:

- The lightning-fast Turbo Prolog incremental compiler and the interactive Turbo Prolog editor.
- The 200-page reference manual which includes the step-by-step Turbo Prolog tutorial.
- The free GeoBase™ natural query language database including commented source code on disk—ready to compile. GeoBase is a complete database designed and developed around U.S. geography. It includes cities, mountains, rivers, and highways, and comes complete with natural query language. Use GeoBase immediately "as is," or modify it to fit your own interests.

So don't delay—don't waste a second—get Turbo Prolog now. \$99.95 is an amazingly small price to pay to become an immediate authority—an instant expert on artificial intelligence! The 21st century is only one phone call away.

Turbo Prolog 1.0 Technical Specifications Programming System Features

- ✓ **Compiler:** Incremental compiler generating native in-line code and linkable object modules. The linking format is compatible with the PC-DOS linker. Large memory model support. Compiles over 8500 lines per minute on a standard IBM PC.
- ✓ **Interactive Editor:** The system includes a powerful interactive full-screen text editor. If the compiler detects an error, the editor automatically positions the cursor appropriately in the source code. At run-time, Turbo Prolog programs can call the editor, and view the running program's source code.
- ✓ **Type System:** A flexible object-oriented type system is supported.
- ✓ **Windowing Support:** The system supports both graphic and text windows.
- ✓ **Input/Output:** Full I/O facilities, including formatted I/O, streams, and random access files.
- ✓ **Numeric Ranges:** Integers: -32767 to 32767; Reals: 1E-307 to 1E+308
- ✓ **Debugging:** Complete built-in trace debugging capabilities allowing single stepping of programs.

YES!

 I want the best

Turbo Prolog at only:

\$99.95

To order by phone,

or for a dealer nearest you,

Call (800) 255-8008

in CA call (800) 742-1133.

Send me ☐ Turbo Prolog at \$ _____

Outside USA add \$10 per copy

CA and MA res. add applicable sales tax \$ _____

Amount enclosed: \$ _____

This price includes shipping to all US cities

Payment: ☐ VISA ☐ MC ☐ Bank Draft ☐ Check

Credit card expiration date: ____/____/____

Card # _____

You must have an IBM or true compatible running

DOS 2.0 or later. **

My computer's name and model is: _____

The disk size I use is: ☐ 3 1/4" ☐ 5 1/4"

NOT COPY PROTECTED

***60-DAY MONEY-BACK GUARANTEE**

Name: _____

Shipping Address: _____

City: _____

State: _____ Zip: _____

Telephone: _____

CODs and purchase orders WILL NOT be accepted by

Borland. Outside USA make payment by credit card or

International Postal Money Order.

**YES, if within 60 days of purchase this product does

not perform in accordance with our claims, please call

our customer service department and we will gladly

arrange a refund.

**** Minimum system requirements:**

IBM PC, XT, AT, PCjr,

and true compatibles

384K RAM

SU6



4585 SCOTTS VALLEY DRIVE
SCOTTS VALLEY, CA 95066
(408) 438-8400 TELEX: 172373


Other Borland Products include Turbo Pascal; Turbo Tutor; Turbo Lightning; Turbo Database Toolbox; Turbo Graphics Toolbox; Turbo Editor Toolbox; Turbo GameWorks; SuperKey; SideKick; SideKick; The Macintosh Office Manager; Reflex; The Analyst; and Traveling SideKick—all of which are registered trademarks or trademarks of Borland International, Inc. or Borland/Analytics, Inc. Turbo Prolog and GeoBase are trademarks and Turbo Pascal is a registered trademark of Borland International Inc. IBM and AT are registered trademarks of International Business Machines Corp. Copyright 1986 Borland International. BF-1045D

CIRCLE NO. 252 ON READER SERVICE CARD





APL*PLUS from STSC



Tapestry communications screen by Torus

Torus Systems has announced **version 1.4 of Tapestry**, a LAN software environment for NETBIOS-compatible network hardware. Version 1.4 offers enhanced external communications and improved compatibility with applications software. Tapestry 1.4 is required for Torus gateway products. Network manager pack, \$495; workstation pack, \$295; upgrade for registered users, \$200; for unregistered users, \$250.

Also from Torus comes **Remote Network Link (RNL)**, which provides Tapestry users remote access to their network using ordinary telephone lines and a PC with a modem. No network adapter is required. \$295.

Remote Access Gateway (RAG) version 1.4 configures a Tapestry network to support RNL users. RAG allows any number of Tapestry workstations to act as undedicated remote gateway servers. It requires an auto-answer modem for each station that is to serve as a remote gateway. \$250 per network.

Another product, **Advanced Gateway Support (AGS)**, extends the asynchronous communications capabilities of a Tapestry network to provide VT100 emulation. For Tapestry networks running on 3Com hardware, AGS supports Bridge CS devices. \$795 per network.

With **Torus 3270 SNA Gateway**, as many as 32 Tapestry users can have concurrent access to an IBM mainframe. The Gateway lets a Tapestry workstation emulate a 3274 cluster controller with a 3278 screen emulation. 8 ports, \$5,495; 16 ports, \$5,995; 32 ports, \$7,495. **Torus Systems**, 495 Seaport Court, Suite 105, Redwood City, CA 94063; 415/363-2418


CIRCLE 335 ON READER SERVICE CARD

From **Inference Corporation** comes a RISC-based version of its expert system development tool. The **Automated Reasoning Tool (ART)** will be available for the PC/RT running IBM's AIX version of UNIX. ART is ported to the

PC/RT for the development of expert system applications in aerospace, finance, and manufacturing. **Inference Corporation**, 5300 W. Century Blvd., Los Angeles, CA 90045; 213/417-7997

CIRCLE 334 ON READER SERVICE CARD

RM/COBOL with INFORMIX-ESQL/COBOL (embedded SQL for COBOL) is now available from **Ryan-McFarland Corporation**. This new capability allows RM/COBOL users to access Rela-



RM/COBOL with INFORMIX-ESQL/COBOL

tional Database System's INFORMIX-SQL relational database via SQL (structured query language) statements embedded in their COBOL programs. These programs pass through an RDS translator to convert SQL statements to COBOL prior to compilation; the translated COBOL code then is able to interface with the relational database.

Ryan-McFarland Corporation, 609 Deep Valley Drive, Rolling Hills Estates, CA 90274; 213/541-4828

CIRCLE 331 ON READER SERVICE CARD

A runtime version for **release 5.0 of APL*PLUS PC System** has been announced by **STSC, Inc.** This system for advanced applications development provides increased productivity by speeding up the development process with its concise and powerful APL language no-

tation. The runtime version is specially modified to run a single application. This modified interpreter enables developers to include enough of the APL*PLUS PC System to run their applications but not enough to allow end users to write or modify their own APL programs. Prices based on royalties. **STSC, Inc.**, 2115 E. Jefferson Street, Rockville, MD 20852; 800/592-0050, in Maryland or Canada, 301/984-5123

CIRCLE 342 ON READER SERVICE CARD

Microbench C is a C compiler from **Virtual Systems, Inc.** that produces highly-optimized code for the Intel 8086 family of microprocessors. Its runtime library provides a complete set of UNIX I/O services. The DOS version produces assembly language compatible with the Microsoft Macro Assembler. This compiler implements the Kernighan and Ritchie C language definition. \$500. **Virtual Systems Inc.**, 1500 Newell Avenue, Suite 406, Walnut Creek, CA 94596; 415/935-4944

CIRCLE 336 ON READER SERVICE CARD

SuperPATH from **Martin Scot Development Corporation** is a directory performance utilities package. SuperPATH lets the user run any program from any directory. It is resident in RAM for high-speed operation and allows the user to find files instantly. \$39.95. **Martin Scot Development Corporation**, 4515 Purdue NE, Seattle, WA 98105; 206/527-9605

CIRCLE 341 ON READER SERVICE CARD

Erratum: In the hardware section of the May 1986 Tech Releases, the amount of DOS memory accessed by **RYBS Electronics' HiPage utility software** should read 704KB.



The material that appears in Tech Releases is based on vendor-supplied information. These products have not been reviewed by the PC Tech Journal editorial staff.

Turbo Pascal® Source Code Included

Borland's new Turbo Editor Toolbox, "Best of the Year" award winner, lets you build your own word processor for only \$69.95!

Turbo Editor Toolbox™ lets you build the best of all word processors into your own word processor. All the modules, techniques, instructions, and Turbo Pascal source code are at your fingertips. You'll quickly learn how to integrate editor procedures and functions into your programs, or you can use Turbo Editor Toolbox "as is," because it has everything.

You get Turbo Pascal source code and everything you need to build your own word processor

The modules, the manual, ready-to-compile source code, and a full-featured word processor called MicroStar™, which we probably ought to sell separately because it's an excellent text editor. But anyway, you get it free as part of our new Turbo Editor Toolbox. (Maybe this is why Jerry Pournelle of BYTE magazine recently wrote that "Borland International is a public benefactor. The company continues to pour out good, well-documented products at reasonable prices.") Your free MicroStar includes a complete pull-down menu user interface which you can use "as is," or you can modify it for inclusion in your Turbo Pascal programs.

As well as MicroStar, you also get a complete editor ready to include in your programs. Windows, block commands, and memory-mapped screen routines come with it.



How to turn good stuff into great stuff—maybe even green stuff!

With your new Turbo Editor Toolbox, you can make WordStar® behave like MultiMate™. You can support windows just like Microsoft's® Word. And do it as fast as WordPerfect® does it. In other words, you can do what they should have done. You just go in there, tinker, fiddle, fool around, and come up with your own version—which will be the best word processor you've never seen before. (And if you want to sell it, go for it; we're not the kind of company that'll send bean-counters and ambulance-chasers after you for royalties.)


How to do windows without jamming your fingers back in your wallet

State-of-the-art "windowing" techniques are part of our new Turbo Editor's repertoire. Sophisticated but easy-to-learn techniques let you design your word processor to show several documents—or several parts of the same document—all at once.

Turbo Editor Toolbox lets you open the windows you want—wherever you want them—at a price that won't make you want to jump out of them.

You get a lightning-fast editor, innumerable features, and a 60-day money-back guarantee** for only \$69.95

For only \$69.95, you can build your own word processor and make it do whatever you want it to do. This already popular new program is just one more way that Borland helps you help yourself. So call us or the dealer nearest you. All the telephone numbers and ordering information are in the adjacent coupon.



Standard Turbo Editor Toolbox features include:

- ☒ Wordwrap
- ☒ UNDO last change
- ☒ Auto-indent
- ☒ Find & Find/Replace with options
- ☒ Set left and right margins
- ☒ Block mark, move and copy
- ☒ Tab, insert and overstrike modes, centering, etc.
- ☒ Multiple windows
- ☒ Multitasking
- ☒ RAM-based editor
- ☒ Paging, scrolling and text display



4585 SCOTTS VALLEY DRIVE
SCOTTS VALLEY, CA 95066
(408) 438-8400 TELEX: 172373

Borland products include Turbo Pascal; Turbo Prolog; Turbo Database Toolbox; Turbo Lightning; Turbo Graphix Toolbox; Turbo Tutor; Turbo GameWorks; Turbo Editor Toolbox; Word Wizard; Reflex; The Analyst; SideKick; SideKick; The Macintosh Office Manager; Traveling SideKick; and SuperKey—all of which are trademarks or registered trademarks of Borland International, Inc. or Borland/Analytica, Inc.

MicroStar is a trademark of Borland International, Inc. WordStar is a registered trademark of MicroPro International Corp. MultiMate is a trademark of MultiMate International Corp. Microsoft is a registered trademark of Microsoft Corp. WordPerfect is a registered trademark of Satellite Software International. Copyright 1986 Borland International 81-1055

CIRCLE NO. 255 ON READER SERVICE CARD

“The new Turbo Editor Toolbox is the Turbo Pascal source code to just about anything you ever wanted a PC-compatible text editor to do, along with a really excellent book of instructions on what text editors are and how to use the Toolbox to build a custom text editor... you can't afford to be without this.”

Jerry Pournelle, *BYTE Magazine*, discussing Turbo Editor Toolbox, to which he gave his "Best Of The Year" Award”

YES! I want the best

Rush me Turbo Editor Toolbox at:

\$69.95

To order by phone,
or for a dealer near you,
call (800) 255-8008
in CA call (800) 742-1133

Send me _____ Turbo Editor Toolboxes at \$ _____
Outside USA add \$10 per copy
CA and MA res. add sales tax \$ _____
Amount enclosed \$ _____

Prices include shipping to all U.S. cities
Payment: ☐ VISA ☐ MC ☐ Bank Draft ☐ Check
Credit card expiration date ____/____/____

Card # _____

*You must have an IBM or true compatible running DOS 2.0 or later.

My computer's name and model is: _____

The disk size I use is: ☐ 3 1/2" ☐ 5 1/4"

NOT COPY PROTECTED
****60-DAY MONEY-BACK GUARANTEE**

Name: _____

Shipping Address: _____

City: _____

State: _____ Zip: _____

Telephone: _____

CODs and purchase orders WILL NOT be accepted by Borland. Outside USA make payment by credit card or International Postal Money Order.

**YES, if within 60 days of purchase this product does not perform in accordance with our claims, please call our customer service department and we will gladly arrange a refund.

†Minimum System Requirements: 192K
Runs on IBM PC, XT, AT, PCjr, and true compatibles

TE6



THE PROGRAMMER'S SHOP™

31 Day
RISK-FREE TRIAL
on any product in this ad.

C Programmers: 7 Ways to Increase Productivity

Add Efficient MultiTasking to Your C Programs with Multi-C

Multi-C lets you create, manage, and communicate among tasks with little RAM and little processor overhead. Now you can handle multiple users, printers, communications, or just about anything else in a logical, well structured manner, without complex polling schemes or lockups in your programs.

Unlike an operating system toolkit, Multi-C is designed for ease of use in production programming, and Multi-C **cooperates** with your operating system, so functions are reliable. Existing and new programs can add Multi-C features without paying royalties. 40+ functions use 32,000 priority levels, handle interrupts, control flags, and messages and control queues.

Multi-C is lower in cost than other products of this type, and it's portable because it's written in C; use it for stand-alone systems. You can even make Multi-C the kernel of your own operating system!

Particularly good for applications in data acquisition, device control, communications, and to give the user control of application use, response, and keyboard productivity. Multi-C has all the functions you need for task scheduling, time scheduling, and inter-task communication.

Specify for use with MS C, Lattice 2.15 or 3.0, or C-86. Partial source.

Cytek MSDOS \$149

First Database Exclusively for C is also Royalty-Free. db_VISTA from RAIMA Corporation

— "If you are looking for a sophisticated C programmer's database, this is it." —

— Dave Schmitt, President, Lattice, Inc.

Designed exclusively for C, db_VISTA is a royalty-free programmer's DBMS. Take full advantage of C through ease of use, portability, and efficiency. You optimize for speed and efficient disk storage.

Multiple key records, fast B-tree indexing, virtual memory disk accessing. Tailor db_VISTA to your needs by using only those features you require. ASCII file transfer utilities make moving to db_VISTA a snap.

MSDOS, Unix, Xenix, Macintosh, Amiga. Single user Source \$459
Object \$179. Multiuser Source \$929. Object \$450

Even for Small Files: Convenient, Fast Access CBTREE — Only \$99

Why spend time writing file management code when you can use consistent, flexible, documented, professional functions? Even multiuser record locking and variable-length records are supported.

Add, delete, and update without needing to reindex. Store keys and record locations in B+ trees.

You can access any record or group of records by the value of a user specific key. Search your files from any point, forward or backward. Full, balanced b-tree support includes use of multiple keys, unlimited number and length of keys.

Use this powerful ISAM, even if you've previously done without.

Learn how to write systems for managing large files by using CBTREE source as a guide. Modify it and transfer it to another operating environment without royalties.

MSDOS \$99

Full Screen Library Plus Fundamentals THE HAMMER LIBRARY

1-2-3 menus (even multilevel), data validation including range checking, field editing, and Full Screen input make this a thorough access library. Data entry routines let you move between fields before completing screen.

But you also get DOS and BIOS access, file handling, string functions, and data handling. Plus pattern matching calls and library handling utilities.

Full source, no royalties. Data entry routines for solid interface with user. Specify MS C, Lattice, CI-C86, Desmet, MW C.

MSDOS. A lot for only \$179

Looking for the right tool for the job? Reach for THE HAMMER.

Flexible Screen Development with SECURITY CHECKING and HELP SCREENS: ZVIEW Screen Library

Use this field-sensitive tool to develop data entry screens and windows and provide run-time flexibility. Security level settings restrict inquiry or update of fields; multiple screen help display is available at screen and field level. You can also customize ZVIEW's operation and make any field characteristic change during execution.

ZVIEW gives you full control of attributes, colors, boxes, protected fields, scrolling, and more. Load screens from memory for fast response. Field support includes alpha, numeric, or alphanumeric data types, case conversion, range checking, and field comparison, and ZVIEW provides automatic data conversion to and from ASCII screen format. For Microsoft C, Lattice 3.0, and Aztec 3.2c. Supports EGA, color, and monochrome displays.

PCDOS \$219

C DYNAMO! WINDOWING: Full C Source, No Royalties POWER WINDOWS AND C FUNCTION LIBRARY

Power Windows covers all the bases; overlays, borders, 1-2-3 style or pop-up menus/help windows, zap instantly on/off screen, status lines, horizontal/vertical scrolling, color control or highlighting, word-wrap, files to windows, keyboard to windows. Powerful, easy to use, integrated error messages, thorough documentation. Supports IBM monochrome or color.

MSDOS. Only \$119

C Function Library - includes 325 fundamental functions with readable source and thorough documentation.

MSDOS. Only \$119

No matter what you have, you need these. Best value available. Highly recommended.

Fastest Interactive C Development on Earth: Instant C version 2.0

Instant C's NEW version 2.0 gives you immediate (2 secs.) compilation and execution of large (5,000+ line) programs, and the ability to link in external (commercial or your own) libraries in an interactive, Lattice 3.0 or Microsoft 3.0 compatible, interpreter-like environment with an integrated full screen editor and source level debugger.

You get full K&R standard C, fast (33 second sieve) execution speed, and debugging with source code animation, single-stepping, back-tracing, and unlimited conditional breakpoints.

Instant C now supports multiple screens and graphic devices, run-time checking of pointer and array references, and includes a new manual, expanded tutorial and reference section, and complete library source.

MSDOS \$399

Rational
Systems, Inc.

Call for a catalog, literature, advice and service you can trust

NEW HOURS

8:30 AM - 8:00 PM EST.

800-421-8006

THE PROGRAMMER'S SHOP™
128-P Rockland Street, Hanover, MA 02339
Mass: 800-442-8070 or 617-826-7531 5/86

"YOUR SERVICE IS FABULOUS!!! . . . Your information packets are so enticing; I really want 10 of them . . . Keep up the good work."

— Dana Bredemeyer
Bredemeyer Company

65

Video Function Call Fix

Using the code presented here, the BP register can be preserved when scrolling the screen even in high-level languages.

Calls to the ROM BIOS generally preserve all registers except those explicitly designated to return values, according to the IBM *Technical Reference Manual*. The video service call, INT 10H, is a notable exception: the BP register is altered any time the screen is scrolled. This can cause problems because the BP register is commonly used as a stack frame reference for subroutine linkage in high-level languages, and the video function call is an often-used service.

Programmers can avoid this problem when working in assembly language. However, programmers using compiled languages do not have control over the use of registers. Many ordinary programs are able to run successfully because the BP register is restored on return to the calling sequence. Problems are most likely to occur in a situation when direct BIOS calls are made from a high-level language—for example, when trying to scroll a window.

The source code described here (see listing 1), which is intended to fix this problem, patches the BIOS call itself. If installed as part of the system boot, this code, called VIDFIX.ASM, will correct any high-level programs that may run with occasional, unexplained crashes.

The source code shown in the listing must be assembled and linked before it can be installed. The resulting .EXE file can be converted to a .COM file using the DOS utility EXE2BIN. After the command VIDFIX is added to the AUTOEXEC.BAT file and the VIDFIX.COM file is included on the system disk, executing VIDFIX will install the program as a resident part of memory. This program substitutes for the original INT 10H call and adds the appropriate PUSH and POP. The installation code provides a test to ensure that the code is installed only once.

Apparently the problem of INT 10H was discovered after the BIOS was embedded in ROM—this is the only BIOS call for which the prologue to the source code mentions that some registers (DI, SI, and BP) are destroyed. However, the code itself clearly shows that the SI and DI registers are restored. Only the BP register is not preserved, and it was obviously an oversight not to include this register in the long list of PUSHes and POPs.



Richard Norman is a member of the faculty at the University of Michigan at Dearborn. He has a Ph.D. in communications sciences.

LISTING 1: VIDFIX.ASM

```
; VIDFIX.ASM          R. Norman          Nov. 11, 1985
; Fix BIOS Video Interrupt 10H to save BP register
; Install a resident program patch into the operating system.
;
; Script to assemble into COM file:
;   MASM VIDFIX;
;   LINK VIDFIX;
;   EXE2BIN VIDFIX.EXE VIDFIX.COM
;
; Make sure VIDFIX.COM is on boot disk and include the line
;   VIDFIX
; in AUTOEXEC.BAT
;

CSEG      SEGMENT
          ASSUME CS:CSEG

VIDFIX    PROC    FAR
          ORG     0100H
          JMP     INSTALL      ;installation skips over resident code

          ;resident data area
          OLD10   DD     ?      ;save area for original INT 10H vector
          ID      DW     'RN'   ;id code to test for re-installation

          EXEC:   ;beginning of executable resident code
          PUSH    BP
          PUSHF   ;simulate INT call
          CALL    CS:OLD10      ;old INT 10 executes STI and RETI
          POP     BP
          RET     2             ;clear old flags from stack
          ENDEXEC:            ;end of executable resident code
```

```
HELLO$    DB      0DH,0AH,'Install INT 10H fix ',0DH,0AH
          DB      'R. Norman, Nov. 11, 1985',0DH,0AH,'$'
ALREADY$  DB      0DH,0AH,'INT 10H fix already installed. Request
          DB      ignored.'
          DB      0DH,0AH,'$'

INSTALL:   ;beginning of installation code
          ASSUME DS:CSEG
          MOV     DX,OFFSET HELLO$
          MOV     AH,9
          INT     21H          ;logon
          MOV     AL,10H
          MOV     AH,35H
          INT     21H          ;get current INT 10H vector into ES:BX
          CMP     ES:[BX-2],'RN' ;if test id is present
          JE      NOINST      ; it is already present
          MOV     WORD PTR OLD10,BX
          MOV     WORD PTR OLD10+2,ES ;save current vector
          MOV     DX,OFFSET EXEC ;note, DS already has segment of EXEC
          MOV     AL,10H
          MOV     AH,25H
          INT     21H          ;reset interrupt 10H to new code
          MOV     DX,OFFSET ENDEXEC ;length of resident code
          INT     27H          ;terminate and remain resident

          NOINST:            ;here, exit without installation
          MOV     DX,OFFSET ALREADY$
          MOV     AH,9
          INT     21H          ;say it is already installed
          INT     20H          ; and terminate normally

VIDFIX    ENDP
CSEG      ENDS
END       ORIG
```


ZIM 2.5 A DBMS REVOLUTION

Have you been looking for perfect data management that you can enjoy on your own terms? Then you've probably already heard of ZIM 2.4 — the most powerful database system available. Until now. Because ZIM 2.5 is here.

ZIM 2.5 is a fourth generation application development tool which makes it possible to expand the capabilities of your micro beyond what you've ever imagined. ZIM mirrors the complexities of the real world by letting you develop as many and as varied applications as you could possibly need.

"ZIM is...a successful migration of mainframe ideas and needs to a micro. (ZIM) proves not only that the job can be done but also that it can be done well. ZIM provides a reference against which current and future data bases can be judged." James Creane, Data Based Advisor/July 1985.

Speed

ZIM breaks the speed limit — between 3 and 50 times faster than industry leaders in sorting and joining files within the data-base. ZIM's internal architecture, and the implementation of its strategy analyzer and priority-driven buffering ability, ensure that data is processed in the most efficient manner possible.

Portability

ZIM is the only database management system with 100% application portability for single-user and multi-user configurations. ZIM is available under PC-DOS, Concurrent PC-DOS, UNIX, XENIX, and QNX. Never again will you be required to re-write your applications for different operating systems environments.

Power

ZIM's high-level language lets you build user commands which implement applications without the necessity and cost of additional programming tools. ZIM's forms facility and extensive report generator permit completely menu-driven applications. Completed compiled, applications use the Runtime System, leading to fast execution, preventing unauthorized access or modifications, and decreasing cost and memory requirements.


Flexibility

ZIM gives you unprecedented simplicity and flexibility. ZIM commands parallel simple English sentences, making it easy to learn and use. Other features include automatic updates of all indexes, multi-user support, and an extensive range of validation, editing and masking facilities. ZIM's limits are only those of your hardware, operating system and imagination. And with ZIM 2.5, your database is no longer limited to a single hard disk.


"ZIM is (a) well-conceived, soundly-implemented, thoroughly professional system. Its design evidences a strong commitment to consistency and to the goal of natural nonprocedural user interaction."

Richard M. Foard, PC Tech Journal,
October 1985.

**ZIM 2.5 — DATA
MANAGEMENT AT
ITS BEST**




38 Antares Dr., Suite 1200
Nepean, Ontario, Canada
K2E 7V2
(613) 727-1397



CIRCLE NO. 219 ON READER SERVICE CARD

IN THE U.S. CALL
800-267-9972
TOLL FREE



Your for artificial intelligence software personal connection

Fundamentally new ideas don't come along very often, but when they do, they can be very rewarding. Artificial Intelligence and Expert Systems are emerging technologies that promise to revolutionize the software industry. We at Programmer's Connection are pleased to be your personal connection for these and other fine products for IBM Personal Computers and compatibles.

EXPERT EDGE by Human Edge

795 659

Powerful expert system builder for creating interactive knowledge-based programs. It has a natural language interface that makes creating an expert system advisor easy by prompting for rule-based knowledge one step at a time. There's also a special user language that allows you to use your text editor to create or modify knowledge bases. Knowledge checking examines your knowledge bases for redundancies and conflicts. It supports Bayesian statistics and probabilities and provides full control over the screen, windows, color, data formats, numeric punctuation and much more. DIF and SYLK formats are supported for easy interface to other programs' data. Resulting systems use an interactive dialog to communicate with the user providing fast responses, reasoning justification, context sensitive helps, printed reports, footnotes and much more. Requires 256K memory (512K recommended for large programs of up to 500 rules).

Expertech II by Intelligenceware

475 389

Comprehensive guide to expert system concepts and technology that provides a variety of AI tools for expert system experimentation. An on-line tutorial describes the operation of expert systems. It includes both a forward chaining and a backward chaining expert system shell implemented in each of LISP, Prolog, Pascal and dBase II. They support inexact reasoning with variables and how & why explanations. Expert system shells may be edited with a built-in rule editor. Includes source code and design documents for all eight expert system shells. The system comes with both a complete LISP interpreter and a complete Prolog interpreter. It also includes comprehensive case studies of several major expert systems and a comprehensive bibliography. Requires 256K memory.

EXSYS by EXSYS Inc.

475 339
Runtime License 600 479

Development software for creating IF-THEN-ELSE probabilistic knowledge based expert systems. It can interface with other programs and includes a built-in report generator to print expert system analyses in report format. It includes an editor program, a copy-protected runtime program, an expert system file compression utility, a utility to arrange rules for maximum speed, demonstration programs and more. The developer's Runtime License includes a copy of the runtime program without copy-protection and permission to copy and distribute an unlimited number of copies of the runtime program with no royalties. Requires 256K and uses full available memory.

GCLISP Golden Common Lisp by Gold Hill Computers

GCLISP 495 CALL
GCLISP 286 Developer 1190 CALL

Artificial intelligence development language that is a major subset of COMMON Lisp. GCLISP includes a small model interpreter, the GMACS editor, the San Marco LISP Explorer, on-line help facilities, the book LISP by Winston & Horn, the COMMON LISP Reference Manual by Guy Steele

and the GCLISP user manual. GCLISP 286 Developer also includes a large model interpreter that can access up to 15 megabytes of memory and a large model compiler that allows applications to run up to 15 times faster. Compiled code may call interpreted code and vice versa. GCLISP is copy protected and requires an IBM PC or AT or 100% compatible with at least 512K memory. GCLISP 286 Developer is not copy protected and requires an IBM AT or 100% AT compatible with at least 512K memory.

INSIGHT by Level 5 Research

INSIGHT 1 50 45
INSIGHT 2+ 485 389

Powerful expert system development tools that allow you to quickly and easily develop knowledge-based systems. Knowledge bases are written in the English-like Production Rule Language (PRL) and then streamlined into compiled code that is run by INSIGHT. This series of software is upwardly compatible to allow plenty of room for growth. INSIGHT 1 is an expert system primer designed for small systems, prototyping and job aids. It combines IF-THEN-ELSE rules and goal outlining to define knowledge that is processed with classical backward chaining reasoning. INSIGHT 2+ includes a Pascal compiler, Pascal interpreter, a dBase interface, a Turbo Pascal interface, intrinsic math functions, advanced knowledge representation and a backward and forward chaining/goal driven inference engine. Requires 512K memory.

Microsoft LISP

250 189

Advanced implementation of the LISP language that supports over 400 Common LISP commands, macros, special forms and control variables. It provides extremely fast performance and can be used to create exceptionally compact programs and data files. The system takes full advantage of up to 512K memory and features an efficient, two-pass garbage collector that performs automatic, dynamic-memory management over all data spaces. The package includes a powerful, symbolic LISP debugger that features a multi-level break-and-trace facility and an execution profiler. There are separate windows for editing and debugging. Comes with an interactive tutorial.

Q'NIAL by NIAL Systems

375 359

Nested Interactive Array Language is a very high level fifth generation programming language that combines ideas from APL, LISP and structural and functional programming. It provides the best features of present day languages in an environment suitable for rapid programming. This highly extensible language provides symbolic data handling that makes words, letters and sentences as easy to handle as numeric data. All data elements are defined as nested rectangular arrays. Data structures are displayed with boxes that clearly indicate the content and structure of arrays. Applications are designed in immediate mode and may be run in either batch or immediate mode. Includes a host interface allowing execution of DOS programs. It comes with a system editor, library of programs and graphics support.

Turbo Prolog by Borland International

100 79

Complete Prolog development system that includes a compiler, an interactive editor, a 200 page reference manual with a step-by-step tutorial and demo programs. This very fast incremental compiler compiles over 2500 lines per minute on a standard IBM PC. It generates native in-line code and object modules that are linkable with the standard DOS linker. When the compiler encounters an error, the interactive full screen text editor is invoked with the cursor placed over the offending code. It supports a flexible, object-oriented type system, graphic windowing, text windowing, and full I/O facilities including formatted I/O, streams and random access files. Integer values range from -32768 to 32767; real values range from 1E-307 to 1E+308. Complete built-in trace debugging facilities allow single stepping of programs and the ability to view the running program's source code. Includes Geobase, a free natural query language database designed and developed around U.S. geography that includes commented source code on disk. Requires 384K memory.

CALL TOLL FREE: U.S. 800-336-1166
CANADA 800-225-1166 OH 216-877-3781

 **programmer's
connection**

Turn the page for a wide selection of programmer's development tools exclusively for IBM Personal Computers and compatibles.

PROGRAMMER DEVELOPMENT TOOLS FOR THE IBM-PC/XT/AT and compatibles.

NO

Shipping Charge*

Handling Charge

Insurance Charge

Credit Card Charge

C.O.D. Charge

Purchase Order Charge

Hidden Charges

PLUS OUR NO RISK GUARANTEE

*When shipping via standard United Parcel Service.

apl language

APL*PLUS/PC System by STSC.....	595	449
APL*PLUS/PC Tools Vol 1 by STSC.....	295	239
APL*PLUS/PC Tools Vol 2 by STSC.....	85	69
APL*PLUS Spreadsheet Manager by STSC.....	195	159
APL*PLUS/UNIX System For AT Xenix by STSC.....	995	795
Btrieve ISAM File Mgr with No Royalties by SoftCraft.....	250	195
Financial/Statistical Library by STSC.....	275	219
FRESCO Business Graphics Library by Mr. APL.....	300	269
Pocket APL by STSC.....	95	79
STATGRAPHICS Statistical Graphics System by STSC.....	695	539

artificial intelligence

ExpertEASE by Human Edge.....	695	589
ExpertEDGE by Human Edge.....	795	659
Experteach Complete System by Intellware.....	475	389
EXSYS Expert System Development Software by EXSYS.....	395	339
GCLISP Golden Common LISP by Gold Hill.....	495	CALL
GCLISP 286 Developer LM Interpreter & LM Compiler.....	1190	CALL
Insight 1 AI Primer by Level Five Research.....	50	45
Insight 2+ by Level Five Research.....	485	389
Microsoft LISP Common LISP.....	250	189
Methods Smalltalk-based Prototyping by Digital.....	250	209
PLA microProlog by Programming Logic Associates.....	250	219
with APES.....	450	399
PLA Professional microProlog by Programming Logic.....	395	349
with APES.....	695	599
Prolog-86 from Solution Systems.....	95	CALL
Prolog-86 Plus from Solution Systems.....	250	CALL
QNIAL Combines APL with LISP by NIAL Systems.....	375	359
Small-X by Kaplan.....	125	99
TransLISP from Solution Systems.....	75	CALL
Turbo Prolog Compiler by Borland International.....	100	79

assemblers and debuggers

8088 Assembler w/Z-80 Translator by 2500 AD.....	100	89
Advanced Trace-86 with ASM Interpreter by Morgan.....	175	139
Codemith-86 Debugger by Visual Age.....	145	109
Cross Assemblers Over 25 Varieties from 2500 AD.....	CALL	CALL
Microsoft Macro Assembler with utilities.....	150	99
Periscope I w/Board & Switch by Data Base Decisions.....	295	249
Periscope II w/NMI Breakout Switch Only.....	145	115
Periscope II-X Software only.....	95	85
The PROFILER with Source Code by DWB Associates.....	125	95
Turbo EDITASM Fast Assembler by Speedware.....	99	84
Visible Computer: 8088 by Software Masters.....	80	65

basic language

BetterBASIC by Summit Software.....	200	165
8087 Math Support.....	99	85
Btrieve Interface.....	99	85
C Interface.....	CALL	CALL
Run-time Module.....	250	225
Microsoft QuickBASIC Compiler New version.....	99	79
Professional BASIC by Morgan Computing.....	99	79
8087 Math Support.....	50	47
True Basic from Addison-Wesley.....	150	105
Run-time Module.....	500	435

blaise products

Asynch Manager Specify for C or Pascal.....	175	139
C Tools Combination Package Both Items Below.....	175	149
C Tools.....	125	105
C Tools 2.....	100	84
Exec Program Chainer.....	95	79
Pascal Tools Combination Package Both Items Below.....	175	149
Pascal Tools.....	125	105
Pascal Tools 2.....	100	84
Turbo ASYNCH for Turbo Pascal.....	100	84
Turbo POWER TOOLS for Turbo Pascal.....	100	84
View Manager Specify for C or Pascal.....	275	209
with Source Code.....	295	239

borland products

REFLEX Data Base System.....	99	75
Turbo DATABASE TOOLBOX.....	55	38
Turbo EDITOR TOOLBOX.....	70	54
Turbo GAMEWORKS TOOLBOX.....	70	54
Turbo GRAPHIX TOOLBOX.....	55	38
Turbo LIGHTNING.....	99	75
Turbo PASCAL.....	70	49
with 8087 or BCD.....	110	77
with 8087 and BCD.....	125	84
Turbo Prolog Compiler.....	100	79
Turbo TUTOR for Turbo PASCAL.....	35	28

c compilers

C-86 Compiler.....	See Computer Innovations Section	395	289
Datalight C Compiler Small Memory Model.....		60	49
Datalight Developer's Kit with Large Memory Model.....		99	79
DeSmet C Compiler with Source Debugger.....		159	145
Eco-C Complete Development System by Ecosoft.....		125	89
Lattice C Compiler.....	See Lattice Section	500	299
Let's C Compiler by Mark Williams.....		75	69
with csd Source Level Debugger.....		150	129
Microsoft C Compiler.....		395	259
MWC-86 by Mark Williams.....	Special Price	495	289
Wizard C Compiler Includes Lint by Wizard Systems.....		450	369

c interpreters

C-terp by Gimpel Software Specify compiler interface.....		300	239
Instant C by Rational Systems.....		500	379
Interactive C by IMPACC Associates.....		249	219
Run/C by Age of Reason.....		150	99
Run/C Professional by Age of Reason.....		250	189

c utilities

Also refer to Blaise, Computer Innovations, Lattice, Microsoft, Phoenix, Polytron, SoftCraft and Xenix System V sections.

APT Application Programmer's Toolkit by Shaw American.....		395	339
Basic C Library by C Source.....		175	135
C Essentials by Essential Software.....		100	85
C-lib by vance info systems.....		195	125
C Power Packs by Software Horizons.....	CALL	CALL	
c-tree ISAM File Manager with source by FairCom.....		395	329
C Utility Library by Essential Software.....		185	139
C Windows by Syscom.....		100	89
C Wings by Syscom.....		50	45
dbVISTA Single-User DBMS by Raima.....		195	159
with Source Code.....		495	429
dbVISTA Multi-User DBMS by Raima.....		495	429
with Source Code.....		990	849
EditCheck by Everest Solutions.....		90	79
Entelekon Combo Package All 3 items below.....		200	175
C Function Library.....		130	115
C Windows.....		130	115
Superfonts for C.....		50	45
Essential Graphics No Royalties by Essential Software.....		250	219
Flash-up Windows by Software Bottling of NY.....		75	69
GraphiC Mono version 2.2 by Scientific Endeavors.....		280	219
GraphiC Color version 3.0 by Scientific Endeavors.....		350	299
The Greenleaf Functions by Greenleaf Software.....		185	135
Greenleaf Comm Library by Greenleaf Software.....		185	135
The HAMMER by OES Systems.....		195	175
MetaWINDOWS by Metagraphics.....		185	139
MetaWINDOWS/Plus by Metagraphics.....		235	199
Multi-Halo with Royalties by Media Cybernetics.....		300	219
On-line Help from Opt-Tech Data Processing.....		149	119
PANEL by Roundhill Library Source Also Available.....		295	229
PC Lint by Gimpel Software.....		139	109
Scientific Subroutine Library for C by Peerless.....		175	139
Vitamin C by Creative Programming.....		150	139
VC Screen Interactive Forms Designer.....		99	85
Zview by Data Management Consultants.....		245	199

cobol language

Micro Focus COBOL Workbench.....	4000	3599	
Micro Focus Level II COBOL.....	Special Price	1500	CALL
COMATH.....		200	169
FORMS-2.....		300	269
Level II Animator.....	Special Price	900	CALL
Level II SOURCEWRITER.....	Special Price	2000	CALL
Micro Focus Level II COBOL For Novell NetWare.....	New	2000	1799
Micro Focus Micro/SPF.....		175	159
Micro Focus Professional COBOL.....		3000	2395
Multi-user Runtime for PC Network.....	New	500	449
Microsoft COBOL.....	See Microsoft Section		
OPT-Tech Sort Also Sorts Btrieve Files.....		149	119
Realia COBOL.....		995	795
RM/COBOL by Ryan-McFarland.....		950	675
RM/COBOL 8X ANSI 85 COBOL by Ryan-McFarland.....		1250	995

computer innovations products

C-86 Optimizing Compiler.....		395	289
C to dBase.....		150	139
CI Probe Source Level Debugger.....		225	199
CI RomPac for C-86.....		195	149
Introducing C C Interpreter.....		125	105

forth language

CFORTH Native Code Application Compiler by LMI.....	New	300	239
LMI FORTH/83 Metacompiler Specify Target Processor.....	New	750	599
PC/Forth by Laboratory Microsystems.....		150	119
PC/Forth+ by Laboratory Microsystems.....		250	209
Advanced Color Graphics Support.....	New	100	79
Enhanced Graphics Support.....	New	200	159
Intel 8087 Support.....	New	100	79
Interactive Symbolic Debugger.....	New	100	79
Native Code Optimizer.....	New	200	159
PCTERM Modem Program for Smartmodem.....	New	100	79
Software Floating Point.....	New	100	79

fortran language

ACS Time Series by Alpha Computer Service.....		495	429
Btrieve ISAM File Manager.....	See SoftCraft Section		
For-Winds by Alpha Computer Service.....		90	79

fortran language continued

Forlib-Plus by Alpha Computer Service.....	70	55
Microsoft Fortran.....	350	209
MORE FORTRAN by Peerless Engineering.....	125	99
Multi-Halo with Royalties by Media Cybernetics.....	300	219
PANEL Screen Designer by Roundhill.....	295	229
PC Fortran Tools by Stat Com Systems.....	179	159
PolyFortran Tools by Polytron.....	179	139
RM/Fortran by Ryan-McFarland.....	595	395
Scientific Subroutine Library by Peerless.....	175	139
The Statistician by Alpha Computer Service.....	295	259
Strings & Things by Alpha Computer Service.....	70	55

lattice products

Lattice C Compiler.....	500	299
with Library Source Code.....	900	549
C Cross Reference Generator.....	50	39
with Source Code.....	200	159
C-Food Smorgasbord Function Library.....	150	99
with Source Code.....	300	195
C-Sprite Source Level Debugger.....	175	139
Curses Screen Manager.....	125	99
with Source Code.....	250	199
dBc dBase File Manager for C.....	250	199
with Source Code.....	500	395
LMK Make Facility.....	195	149
LSE Screen Editor.....	125	99
PPG II Compiler No Royalties.....	750	595
SecretDisk File Security.....	60	49
SideTalk Resident Communications.....	120	95
Text Mgmt Utilities (GREP,DIFF,ED,WC,Extract,Build).....	120	95
TopView Toolbasket Function Library.....	250	199
with Source Code.....	500	395
Z-80 C Cross Compiler.....	500	395
with Library Source Code.....	1000	789

microsoft products

Microsoft BASIC Interpreter for Xenix.....	350	279
Microsoft C Compiler.....	395	259
Microsoft COBOL Compiler.....	700	495
for Xenix.....	995	795
Microsoft COBOL Tools with COBOL Source Debugger.....	350	209
for Xenix.....	450	359
Microsoft Fortran Compiler.....	350	209
for Xenix.....	495	389
Microsoft LISP Common LISP.....	250	189
Microsoft Macro Assembler with utilities.....	150	99
Microsoft Mouse Bus Version.....	175	149
Microsoft Mouse Serial Version.....	195	159
Microsoft muMath Includes muSIMP.....	300	195
Microsoft Pascal Compiler.....	300	195
for Xenix.....	495	389
Microsoft QuickBASIC Compiler.....	New version	99
Microsoft Sort.....	195	149
Microsoft Windows.....	99	74
Microsoft Windows Developer's Kit.....	New	500
		CALL

other products

Dan Bricklin's Den Program by Software Garden	75	65
FASTBACK Backup Utility by 5th Generation Systems	179	159
Interactive EASYFLOW by Haventree Software	150	129
Janus/ADA C Pack by R&R Software	95	89
Janus/ADA D Pack by R&R Software	900	699
MODULA-2/86 by Logitech	CALL	CALL
SET:SCIL by System Engineering Tools	New 349	299
Source Print by Aldebaran Laboratories	New 97	89
SRMS Software Revision Mgmt System by Quilt	New 125	109

phoenix products

Authorized Dealer.....		
Pasm86 Macro Assembler.....	295	195
Plantasy Pac (Pfinish,Plix+,Plink+,Pmaker,Pmate,Ptel).....	1295	949
Pfinish Performance Analyzer.....	395	249
Plix-86 Plus Symbolic Debugger.....	395	249
PforCe Comprehensive C Function Library.....	475	319
Plink-86 Overlay Linker.....	395	249
Plink-86 Plus Enhanced Overlay Linker.....	495	389
Pmaker Program Development Manager.....	195	139
Pmate Macro Text Editor.....	225	149
Pre-C Lint Utility.....	395	249
Ptel Binary File Transfer Program.....	195	139

polytron products

Polytron C Beautifier.....	49	45
Polytron C Library I.....	99	79
Polytron PowerCom Communications.....	179	139
PolyFORTRAN Tools I.....	179	139
PolyLibrarian Library Manager.....	99	79
PolyLibrarian II Library Manager.....	149	119
PolyMake UNIX-like Make Facility.....	99	79
PolyOverlay Overlay Optimizer.....	99	79
PolyWindows Developer Kit.....	199	149
PolyWindows Products All Varieties.....	CALL	CALL
PolyXREF Complete Cross Reference Utility.....	219	179
PolyXREF Support for one language only.....	129	109
PVCS Polytron Version Control System.....	395	329
PVMFM Polytron Virtual Memory File Manager.....	199	149

softcraft products

Btrieve ISAM File Manager with No Royalties.....	250	195
Xtrieve Query Utility for Btrieve.....	195	169
Rtrieve Report Generator for Xtrieve.....	85	79
Btrieve/N for Networks.....	595	465
Xtrieve/N Query Utility for Btrieve/N.....	395	299
Rtrieve/N Report Generator for Xtrieve/N.....	175	159

text editors

Brief from Solution Systems.....	195	CALL
Epsilon Multi-tasking Emacs-like editor by Lugaru.....	195	165
FirstTime for Turbo by Spruce Technology.....	75	69
KEDIT Xedit-like editor by Mansfield Software Group.....	125	109
SPF/PC by Command Technology Corp.....	195	165
Vedit by CompuView.....	150	115
Vedit Plus by CompuView.....	225	180
XTC Text Editor with source by Wendin.....	99	84

turbo pascal utilities

Also refer to Blaise, Borland and SoftCraft sections.

ALICE Turbo Pascal Interpreter by Software Channels.....	95	85
FirstTime for Turbo by Spruce Technology.....	75	69
Flash-up Windows by Software Bottling of NY.....	75	69
Multi-Halo with Royalties by Media Cybernetics.....	300	CALL
On-line Help from Opt-Tech Data Processing.....	149	119
Screen Sculptor by Software Bottling of NY.....	125	95
Turbo EXTENDER by TurboPower Software.....	85	69
Turbo Professional by Sunny Hill Software.....	70	49
TurboPower Utilities by TurboPower Software.....	95	84
TurboRef by Gracon Services.....	50	45
TurboWINDOW by MetaGraphics.....	80	69

video training tapes

These video cassette training tapes are from The Information Factory and are an excellent alternative to expensive classroom training. Specify Beta of VHS. Price includes one student manual.

Basic Telecommunications.....	New	350	309
Computer Literacy.....		400	349
Local Area Networks.....		350	309
Programmer's Introduction to C.....		500	449

wendin products

Operating System Toolbox Build your own OS.....	99	84
PCUNIX Operating System.....	99	84
PCVMS Operating System Similar to VAX/VMS.....	99	84
XTC Text Editor with Pascal Source Code.....	99	84

xenix system v

Complete Xenix System by SCO All 3 items below.....	1295	1099
Xenix Development System.....	595	529
Xenix Operating System Specify XT or AT.....	595	529
Xenix Text Processing Package.....	195	179

xenix languages and utilities

APL*PLUS/UNIX System For AT Xenix by STSC.....	995	795
Btrieve ISAM File Manager by SoftCraft.....	595	465
c-tree ISAM File Manager with Source by FairCom.....	395	329
dbVISTA Single and Multi User versions by Raima.....	New	CALL
Informix by RDS.....	995	839
Lyrinx by SCO.....	595	489
Micro Focus Level II Compact COBOL For AT.....	New	1000
Forms-2.....	New	400
Level II ANIMATOR.....	New	600
Microsoft Languages.....	See Microsoft Section	
Networks for Xenix by SCO.....	595	529
PANEL Screen Designer for AT Xenix by Roundhill.....	595	539
RM/COBOL by Ryan-McFarland.....	New	1250
RM/FORTRAN by Ryan-McFarland.....	New	750
SCO Professional Complete Lotus clone by SCO.....	795	695

Prices are subject to change without notice.

We are open until 5 p.m. Pacific Time, (8 p.m. Eastern).

Visa and MasterCard are accepted with no surcharge applied.

Please include card expiration date when ordering by mail.

Account is charged when shipped.



CALL TOLL FREE

**800-336-1166**

U.S. OHIO 216-877-3781

**800-225-1166**


CANADA

OUR NO RISK GUARANTEE

If you are not completely satisfied with your purchase you may return it within 30 days. All returned products must meet our standards for being in new, resellable condition including all paperwork and unused registration card. Products including source code are generally excluded by the manufacturer from this guarantee. Please ask for specific details when placing your order.

programmer's connection

136 SUNNYSIDE ST.
HARTVILLE, OHIO 44632



Animation Techniques

*Better with less in a different way:
animation device drivers that bring speed
and performance to the CGA.*

MICHAEL ABRASH and DAN ILLOWSKY

Why did not any of the children in the first group think of this faster method of going across the room? It is simple. They looked at what they were given to use for materials and, they are like all of us, they wanted to use everything. But they did not need everything. They could do better with less, in a different way. —Frederik Pohl

The Gold at the Starbow's End




ILLUSTRATION • AKIO MATSUYOSHI

Like all humans, programmers sometimes substitute preconceptions, assumptions, and entrenched thought patterns for original thought. Because compilers and interpreters generally provide them with virtual environments largely unrelated to the underlying hardware, programmers implicitly make myriad assumptions about the rudimentary implementation of their programs. This, of course, is generally all to the good, as the human mind is incapable of effectively integrating all the details involved in a large program, as well as the minutia of the computer's architecture. By delegating all of the hardware considerations and

many of the software details to the compiler/interpreter designers, programmers are free to concentrate on overall program structure. This is, after all, their primary concern.

Not so with realtime drivers for microcomputers, and especially not so with drivers such as those for animation that depend for their very effect upon realtime human perception. Here speed becomes paramount, and any abstraction or delegation can lead to diminished effect due to reduced performance. Indeed, in this area even assembly language is not enough: an understanding of the hardware beneath the assembly language level is required, and

COMPUTER GRAPHIC • LINDA GOTTFRIED



something more as well. That something more is an ability to, as with the children in the quote above, "do better with less, in a different way." Even dearly held assumptions about programming techniques must be questioned, because those assumptions, while generally valid, may serve poorly for a given processor performing a given task. For realtime drivers (particularly those written for a relatively slow processor such as the 8088), the object is to generate, by any means, code that will perform precisely the task required in the fewest machine cycles.

If this is hacking, then it is hacking in the finest sense. The PC's hardware is being asked to do a task it is barely capable of doing: this requires stretching the rules that normally make life easier. Structured coding, top-down design, and all the rest are excellent practices—but only when they facilitate the task at hand. Standard programming practices do not provide optimal solutions for applications such as animation drivers, where performance must take precedence over considerations such as portability and even readability.


This article presents a series of animation drivers for the IBM Color Graphics Adapter (CGA), beginning with a conventional implementation and proceeding through a number of approaches far better suited to the IBM PC, the 8088 processor, and specific applications. For each driver, design requirements are examined, along with associated benefits and limitations. These drivers and the concepts behind them have evolved intermittently over several years of designing games and doing systems programming for the PC. Some unconventional (but highly disciplined) thinking and a deep understanding of the interaction of software and hardware went into these realtime drivers, designed to wring maximum performance from a microcomputer.

All assembly language code included here was assembled with the Microsoft Macro Assembler 4.0, and all C code was compiled with the Mark Williams C compiler 2.0.

BASIC ANIMATION

Animation is the process of repeatedly redrawing a form in successive locations rapidly enough so that it appears to move like a real object. All arcade-style video games are based on animation; however, most of those games have special hardware that performs the principal work. Because the IBM PC has no such hardware, all animation functions must be performed in software.

FIGURE 1: *Byte/Pixel Mapping for the CGA*



The four-pixels-per-byte structure provides an opportunity for animation optimization because a four-pixel horizontal motion increment is not perceived as jerky.

The basic rules of animation are few. Each time a form is redrawn in a new location, it also must be erased at the old location; otherwise, it would leave a trail of old images. The time between the disappearance of the form at the old location and its appearance at the new location should be as brief as possible, to avoid confusing the eye with either two or zero forms during the transition. Finally, all other forms present on the screen must be preserved when any given form is moved; for example, the animation of a bee moving across a background of a field of flowers must not leave a trail of erased flowers as it moves. Background preservation is perhaps the biggest problem in animation driver design.

The descriptions here assume the drivers' operation in four-color, medium-resolution graphics mode on the CGA. This permits access to display memory at any time, rather than having to wait for horizontal or vertical retrace to avoid snow, as is the case in high-resolution mode. The techniques discussed are applicable to monochrome graphics boards and to the IBM Enhanced Graphics Adapter (EGA) as well, although significant modifications would have to be made to take full advantage of the EGA's 16-color modes.

In the CGA's medium-resolution graphics mode, every byte of display memory controls four pixels, each of which is one of four colors (see figure 1, top). Each of the four pairs of bits

may select any one of three colors from the active palette (two palettes are available, either of which may be high or low intensity) or the background color (which may be any one of the PC's 16 colors)—see figure 1, bottom. If palette 1 (consisting of cyan, magenta, and white) with a black background is the current color selection, then each byte maps to the four pixels in the figure.

Each scan line has 80 bytes, or 320 pixels, across the screen. The top scan line (scan line 0) is defined by the bytes at addresses B800:0000 through B800:004F, the second (scan line 1) at addresses B800:2000 through B800:204F, the third (scan line 2) at B800:0050 through B800:009F. This mode has 200 scan lines, with the even scan lines in the lower 8KB at B800:0000 through B800:1FFF and the odd scan lines in the upper 8KB at B800:2000 through B800:3FFF. A total of 192 bytes of RAM are left unused at the end of each group of 100 scan lines (because 100 scan lines occupy 8,000 bytes and each group is given 8,192 bytes). This separation of a graphics buffer into halves by alternate scan lines is a consequence of a 7-bit register in the 6845 CRT controller chip that makes it unable to map more than 128 contiguous scan lines in memory from a single address. The display memory-to-screen mapping is diagrammed in figure 2. (For more information about the CGA, see volume 2 of the *IBM Technical Reference Options and Adapters*

manual and "The IBM Color Graphics Adapter," Thomas V. Hoffmann, *PC Tech Journal*, July/August 1983, p. 26.)

Textbooks on graphics generally build graphics drivers around a function that plots a single pixel. This approach draws a form by plotting each of the points that make up the form with a separate call to the pixel-plotting routine. The form-drawing routine must calculate the coordinates of each pixel in turn; the call to plot each point then incurs the full overhead required to calculate the display memory address at which to plot the pixel, as well as the overhead of calling and returning from the pixel-plotting routine.

This general (and very slow) approach is well suited to powerful mainframes but it is out of the question on the PC, where even the fastest driver can animate only a few dozen sizable forms simultaneously. The drivers presented here work with solid rectangular areas of the screen, modifying not single pixels but whole bytes with each display memory access. The form to be displayed is contained within the area. This approach offers the advantage of moving a predefined string of bytes constituting a rectangular form into screen memory in a single very rapid operation, with minimal calculation and processing overhead. Because these are byte-oriented rather than pixel-oriented drivers, forms must move a multiple of four pixels horizontally. In practice, this is not too serious a limitation, but a two-pixel movement increment is better. Internal animation (discussed below) can overcome this limitation.


EXCLUSIVE ORING

All of these drivers are called with the same interface: the row and column coordinates of the upper left corner of the form to be drawn and a pointer to a data structure describing the form are passed in registers BX, CX, and SI, respectively. The row coordinate is the scan line at which the top of the form is to be aligned, in the range 0 to 199, with limitations as noted for specific drivers. The column coordinate is the byte offset from the left margin of the screen at which the left edge of the form is to be aligned, in the range 0 to 79. The data structure contains the height in scan lines, the width in bytes, and the string of bytes that make up the form, as shown in figure 3.

For all of the animation drivers listed with this article, the following conventions hold:


- DS and CS must be the same.
- ES must contain B800H.

FIGURE 2: CGA Buffer Structure



Odd-numbered lines have an additional offset of 2000H into the buffer, dividing the buffer into 8,192-byte halves. The last 192 bytes of each half are not used.

FIGURE 3: Form Data Structure



The width (W) figure here is in bytes, not pixels. (Each byte describes a total of four pixels.) The total memory required for a given form is given by $(W * H) + 2$.

- BX contains the row value (0 to 199) for the top of the image.
- CX contains the byte column (0 to 79) for the left edge of the image.
- SI points to the data structure that contains the image description. The first byte is the height (h) in scan lines; the second byte is the width (w) in bytes. The bytes that follow (numbering $h * w$) contain the values to be placed in the screen memory map: the organization of h consecutive sets of w line image bytes.

Conceptually, the exclusive-OR driver is the simplest of animation drivers. It introduces the fewest complications into animation programming and is, consequently, the most widely used animation technique.

The exclusive-OR logical function yields 1 for operands that differ and 0 for operands that are identical: $1 \text{ XOR } 0 = 1$, $1 \text{ XOR } 1 = 0$, and so on. XOR has the handy property of being perfectly reversible—that is, when a program performs two identical exclusive-OR operations in succession, the second undoes the effects of the first. Practically speaking, when the program performs an exclusive OR on a form into display memory once, it draws the form, and when it does an exclusive OR on the same form at the same location a second time, it removes all traces of the form. This is true even if (between the two operations) other forms have been drawn overlapping or overwriting the first form, as long as all drawing is

done by exclusive-OR. (Figure 4 shows a flowchart of this driver.)

In short, animation that is performed using the exclusive-OR function preserves the background perfectly and allows multiple forms to intersect and move past one another without residual effects. This is an enormous convenience in programming all but the simplest animation on the PC.

Listing 1 (STANDXORASM) shows the code for the standard exclusive-OR driver. The C version of the driver, listing 2 (CXOR.C), may be helpful to some users in understanding the driver's operation. In operation, this driver first determines the base offset of the display memory bank in which the top line of the form is to be drawn. Even scan lines are in the first 8KB bank, odd scan lines in the second 8KB. The starting row is then multiplied by the screen width (which is a variable that may be modified during program execution) and added to the bank base address and the starting column to generate the offset at which the upper left corner of the form is to go.


Next, the height and width of the form are set aside, and the drawing begins. Each line is exclusive-ORed into display memory a byte at a time in the inner loop. After each line, the display memory offset is modified to point to the start of the next line, which is always in the alternate bank. This is repeated for the height of the form.

Note that this driver (and all drivers to follow) assumes that the ES register points to the display memory segment and that the DS register equals the CS register. Although these conventions can be modified easily, coding is simplified when they are observed.

Listing 3 (XORBENCH.ASM) is a sample implementation the exclusive-OR driver, and it is used as a benchmark for the drivers. This program (which should be linked to listing 1) bounces eight forms around the screen, minimizing considerations other than driver speed. For the sake of clarity, no attempts were made to optimize this benchmark program. This reflects the real world, in which optimization primarily is performed in drivers, while the calling routines are more concerned with program structure. Thus, the relative differences between the performance of the drivers themselves are somewhat greater than the results, as shown in table 1, would indicate.

The programs were run on an IBM PC with the files executed from AST's RAM-disk software on an AST MegaPlus multifunction board; a stopwatch was

FIGURE 4: XOR Driver Logic



The exclusive-OR driver that follows this algorithm is the standard against which all the improved drivers developed in this article are measured.

using for the timings. These benchmark times would vary somewhat with a different mix of forms: the more efficient drivers gain a relative advantage with larger forms. Also, because the various drivers have markedly different characteristics, listing 3 is modified slightly (as noted in the source code) to accommodate the non-exclusive-OR drivers, although all versions of the benchmark perform the same function of moving eight objects in the same patterns.

Two characteristics of exclusive-OR drivers should be noted when running listing 3. First, odd color effects can oc-

cur when forms overlap. This is an unavoidable result of two forms being exclusive-ORed into the same area of display memory at the same time. The animation screen shown in photo 1 illustrates this problem. Second, the forms flicker; but, this can be minimized in two ways. If all forms are drawn during retrace time, then no flicker will be present; unfortunately, animation will slow to a crawl because retrace time is a small fraction of total time. Alternatively, the time between erasing a figure at the old location and drawing it at the new location can be kept to an mini-

mum. For simplicity, the benchmark program does not *absolutely* minimize this transition time, but it does keep it very low. Even so, flicker is unavoidable with this type of driver.

WHY .ASM?

CXOR (listing 2) is the C implementation of the benchmark program (listing 3) and exclusive-OR driver (listing 1). DRIVECXOR.ASM (listing 4) is an assembly language subroutine that performs an exclusive-OR to bring each byte into display memory; it must be linked to the C program of listing 2. The assembly language routine, which permits access to display memory without using the C compiler's slow, large memory model, is nothing more than an exclusive-OR poke function. All of the intelligence involved in moving the form itself is written in C.

The C exclusive-OR driver called from the C version of the benchmark is 3.79 times slower than its assembly language counterpart (as shown in table 1)—too slow to be of much use, even though register variables are used and the loops are small and simple. The reasons for its slowness are many: first, only two register variables are available, so some variables must be kept in memory, making instructions longer and lengthening execution times; second, an assembly language subroutine must be called and parameters passed on the stack because this C implementation cannot access display memory directly in the small memory model; and, finally, C compilers do not use registers optimally for this particular application. For example, this driver reserves the BP register for stack addressing, but in this instance it would be better used for temporary storage of an offset. Similarly, the LOOP instruction is not available because the CX register is reserved for other purposes.

Other C compilers could ease some of these problems. Microsoft C, for example, can access display memory directly in the small memory model. But aside from the slowness problem, a more serious objection to coding animation drivers in C is that none of the techniques used by the more advanced drivers to be discussed can be used in C. Although often touted as a high-level assembly language, this is true of C only if the user is willing to accept the implementation assumptions a C compiler must make about an application in order to produce machine code. In this case, all registers and instructions of the 8088, as well as unusual program flow control structures, must be at the user's

TABLE 1: Benchmark Timings

ANIMATION DRIVER	BENCHMARK TIME	RATIO TO STANDARD DRIVER
Standard exclusive-OR driver (listings 1, 3)	42 seconds	1.00
C version of standard exclusive-OR driver (listings 2, 4)	159 seconds	3.79
Optimized exclusive-OR driver (listings 3, 5)	32 seconds	0.76
Exclusive-OR driver with in-line column code (listings 3, 6)	26 seconds	0.62
Exclusive-OR driver with full in-line code (listings 2, 7)	25 seconds	0.60
Byte-move graphics driver (listings 8, 9)	10 seconds	0.23
Byte-move driver with automatic erasure fringe (listings 8, 10)	8 seconds	0.19

The programs were run from a RAM disk on an IBM PC; a stopwatch was used for all timings. The figures for the driver implemented in C suggest that no substitute exists for assembly language when performance considerations are paramount.

complete disposal. The C language can provide none of these.

C advocates may note that the driver could be coded in assembly language and called from C. This is the point exactly: optimal realtime drivers must be written in assembly language. Accept no substitutes.

Of course, this does not mean that just any assembly language code will do. The code must, for example, make optimum use of registers and instructions. After all, if a driver written in assembly language kept all its variables on the stack, and reserved each register for a specific purpose at all times, the code might as well be written in C.

The exclusive-OR driver in listing 5 (OPTXOR.ASM) cuts benchmark time (when linked with listing 3) from 42 to 32 seconds by performing such optimizations. First, it keeps all variables in registers at all times. Second, it uses more efficient instructions, especially the LODSB string instruction. (Note that it is assumed a CLD has been executed in the calling program to cause string instructions to autoincrement the pointers they use.) Third, it does not preserve any of the general registers. Fourth, it uses a table look-up to calculate the display memory offset of the start of the row. Fifth, it does the calculation of the offset to the start of the next line of the form in display memory outside the main loop. It is always best to do work once instead of repetitively. This change also means that the program no longer has to push and pop the starting offset of each line.

The slow memory access of the PC's 8088 mandates keeping all vari-

ables in registers. Register-only operations tend to execute in 4 cycles or less, while memory-to-register and register-to-memory operations take a minimum of 10 cycles, and more commonly require 14 or more. (These times assume that the instruction has been pre-fetched; the state of the instruction prefetch queue can change them considerably, but register-only operations are still faster.) To derive maximum benefit, all general-purpose registers are used, including the BP register.

This slow memory access is also the reason registers are not preserved. Pushing and popping the seven general-purpose registers would take 182 cycles. Instead, the calling routine decides which registers need to be preserved. Two concerns result from this move. First, it increase code size, but memory is cheap, second, programmers must be alert, as bugs could result from undisciplined programming. However, because speed is paramount to this application, the code cannot be expected to compensate for the programmer.

The use of a table look-up to calculate the display memory offset of the row (by multiplying the row by the screen width in bytes) is illustrative of several key points. First, it is an example of, as author Pohl put it, doing better with less. The MUL instruction is available (and tempting) to the programmer; however, by ignoring it and restricting the driver to display memory of a fixed width (and by using a little more memory) as many as 50 to 100 cycles can be saved. If support for multiple display memory widths were needed, it would be better simply to



Inside Every PC-SHADOW™ Is a Network Solution

Increasingly, companies are taking a bottom-line approach to purchasing PCs. Everyone seems to wish that they could purchase an IBM PC with a built-in network for under \$1,000. Effectively, now you can...by combining the useability of PC-Shadow™ Workstations with the power of MultiLink Advanced™.

PC-Shadow™...More Than Just a Terminal, It's a PC-Workstation. If you know how to use an IBM PC, you already know how to use our PC-Workstation. Every key that's on an AT's keyboard is located in the same place on a PC-Shadow™.

Just like the PC, PC-Shadow™ has an easy-to-read 25 line screen which supports all graphics characters and attributes that are on the IBM Monochrome Display.

Best of all, when you attach a printer to PC-Shadow's™ auxiliary port, you're able to get complete printouts of reports and analyses...not just a "print screen."

PC-DOS Networking Power At Your Fingertips. PC-Shadow™ was designed expressly to work with MultiLink Advanced™, our software-driven, departmental networking solution. It transforms ONE IBM PC/XT or AT into the CPU of a multi-user, multi-tasking system.

Up to eight PC-Shadows™ can be connected to a single computer sharing printers, hard disks, programs, and files.

100% compatibility with LANLink™, our company-wide local area network, makes it possible for your PC-Shadow™ network to grow with you.

Net More by Spending Less. At \$695 per workstation, PC-Shadows™ represent the most cost-effective networking solution available. For complete details and the dealer nearest you, call The Software Link TODAY. VISA, MC, AMEX accepted.

PC-SHADOW™



THE SOFTWARE LINK, INC.

Developers of LANLink™ and MultiLink Advanced™


8601 Dunwoody Place, Suite 632, Atlanta, GA 30338
Telex 4996147 SWLINK

THE SOFTWARE LINK, INC./CANADA
400 Esna Park Drive, Suite 18
Toronto (Markham), Ont. L3R 3K2
CALL: 416/477-5480


CALL: 404/998-0700
Dealer Inquiries Invited

LANLink™, MultiLink Advanced™ and PC-Shadow™ are trademarks of The Software Link, Inc.
IBM PC, XT, AT & PC-DOS are trademarks of IBM Corp

CIRCLE NO. 196 ON READER SERVICE CARD

PHOTO 1: XOR Animation Driver

These unavoidable false-color effects are less annoying than accompanying form flicker (not shown here).

PHOTO 2: Byte-fringe Driver

The trailing edge of the partially moved box above is being erased by the figure's blanking fringe.

write multiple dedicated drivers. Memory is cheap, and, perhaps more importantly, general-purpose drivers are slow.

In addition, a key assumption was made in writing this driver. It was assumed that all forms start on even scan lines and are an even number of scan lines high; that is, the row coordinate that the driver is passed will always be even, and the height of the forms will always be even. Generally, at animation speeds, the human eye cannot detect single-pixel and double-pixel movement increments apart (remember also that the horizontal increment is four pixels), and the even-scan-line assumption means that the table look-up can be speeded up a little. Normally, the program might take the row coordinate, multiply it by two by shifting it left, and then use it as the index to look up the product of the multiplication by the screen width. By assuming an even scan line, however, the need for the shift is removed. This in itself is minor, although it does cut the size of the look-up table in half. This assumption also permits the assumption that form drawing always starts in the lower 8KB of display memory (that is, relative to a base of 0000H rather than 2000H), saving some testing performed in the original driver. Similarly, the assumption of an even number of scan lines per form permits two exclusive ORs in a row, saving a LOOP instruction. These assumptions also simplify other drivers.

The point is not that these assumptions must be made in designing *any* animation driver, rather that they worked for this application. Effective driver design consists largely of paring away cycles by knowing what must be kept and what can go in a particular circumstance. For example, a few more cy-

cles could be saved by storing the height of each form divided by two in the form data structure, so AL would not have to be shifted right to divide by two. But this would have resulted in only a small savings at the cost of changing all the form data structures and introducing confusion. Saving even one cycle inside the driver loops is always worthwhile because of the multiplier effect of the loops, but a few extra cycles outside the loops are not nearly as significant, and may be removed or left in at the programmer's discretion. The balance is application-dependent: when most of the forms are large, loop efficiency is paramount, but with smaller forms, the overhead outside the loops takes on added importance.

Third, a table look-up is used rather than multiplying by 80 with shifts and adds (see figure 5), even though the nominal time for the latter approach is faster. This method was chosen because the 8088 microprocessor must fetch instructions before it can execute them, and it cannot fetch them any faster than memory access speed will allow. For the PC, this means four cycles are required to fetch every instruction byte. Shifts and adds are supposed to take two and three cycles, respectively, and indeed they do, but because both are two-byte instructions, eight cycles are required to fetch them. The instruction prefetch queue for the 8088 is only four bytes long, so even under the best conditions two such instructions in sequence will deplete the queue, after which they effectively take eight cycles each. The result is that the multiply-by-80 code shown in figure 5 actually takes longer than the table look-up, even though, according to specifications, the code in this figure

should execute in 17 cycles and the table look-up should execute in 21.

(Note that considerations such as instruction queue interaction are inferences rather than specifications, learned through experience and experimentation. Short of a full knowledge of the internal state of the 8088, no method exists to determine exactly how long a particular code fragment in a given program will take to execute.)


ALTERNATIVE EXCLUSIVE-OR

The last exclusive-OR implementation began to blur the line between a straight assembly language implementation of an algorithm and an unconventional approach. That line is crossed with INLINXOR.ASM, the driver in listing 6. Here is another exclusive-OR driver, functionally identical to the driver just discussed except that the inner loop of the code that moves the form into the screen has been replaced with a call to in-line code.

The 8088 is relatively slow at memory access and branching: JMP requires 15 cycles, a conditional jump requires 16 cycles, and LOOP requires 17 cycles if a jump is made. In fact, this CPU is considerably slower at branching than a Z80 running at 4 MHz. (The 8088 is, of course, a more powerful processor by virtue of its additional registers and memory addressing modes and a much larger address space.) The use of registers wherever possible compensates for the slow memory access; in-line code will compensate for slow branching.

By calling in-line code, the program branches only twice each time a scan line of the form is drawn (once to call the routine and once to return from it) rather than once per byte (with the LOOP instruction). Because the

If you can't put a Hayes modem on every PC in your IBM network, here's the next best thing.



© 1986 Hayes Microcomputer Products, Inc.

*Manufacturer's estimated retail price.

It's new communications software from Hayes called Smartcom II® for the PC Network.

It lets you share modems. So even PC's without their own modems can communicate outside the network.

Before now, if you needed to communicate outside the network, you had to physically go to wherever the modem was. That, in turn, meant bumping the operator off his modem-equipped PC, so that you could handle your communications.

Hayes Smartcom II for the PC Network puts an end to all the delay and inconvenience. Now, when a PC needs the modem, the user is automatically connected from his own desk. So communications

capabilities are immediately available to everyone on your network, whether their PC has a modem or not.

You only buy one software package per modem. The workstation part of the software can then be duplicated for each PC on the network, at no extra cost. It's better than having a site license!

Each PC can have its own password, define its own log-on procedures, set its own macros, and use

all the other outstanding operating features of our standard Smartcom II while connecting with any of the shared modems on the network.

You get all this for only \$599*! And it's backed by Hayes, the PC communications leader.

So if you currently utilize, or are contemplating adding, IBM PC networks, you should also add Smartcom II for the PC Network. For efficient communications. Without delay.

See your authorized Hayes dealer for details. Or contact Hayes at 404/441-1617.

Hayes Microcomputer Products, Inc., P.O. Box 105203, Atlanta, Georgia 30348.

Hayes®

Say yes to the future

CIRCLE NO. 155 ON READER SERVICE CARD

FIGURE 5: *Shift/Add Multiplication by 80*

```

;
; Code fragment to multiply row value in BX by 80 and put it in DI.
;
    shl     bx,1    ;row*2
    shl     bx,1    ;row*4
    shl     bx,1    ;row*8
    shl     bx,1    ;row*16
    mov     di,bx   ;set aside row*16
    shl     bx,1    ;row*32
    shl     bx,1    ;row*64
    add     di,bx   ;row*80 = row*64 + row*16

```

These machine instructions take fewer cycles than table look-up, but the additional overhead of fetching them from memory makes their operation slower.

branch address is calculated outside the main loop, it adds little overhead—only 26 cycles. The in-line code saves 53 cycles per scan line for a 5-byte (20-pixel) wide form. The savings are relative to the size of the form; they are greatest for larger forms, which affect overall performance the most. The benchmark timings confirm that this approach improves driver performance significantly.

This is yet another example of doing more with less: The LOOP instruction is available for just such cases as the loops in an animation driver, and, by reflex, the programmer would use it, just as the chip's designers intended. It requires an act of will to examine the loop element of the driver and reject it as too slow, in favor of another, albeit less conceptually elegant, approach.

Ideally, all code that comprises the entire main loop, not just the inner loop, would be in-line code. This step is accomplished in RCINXORASM (listing 7) where the animation driver calculates an offset into in-line code based on the number of rows, and the row in-line code calls the column in-line code. This process eliminates all LOOPS associated with the main (row) loop in favor of a single calculated jump. A jump instead of a call to the row in-line code is used, thus control can return to the calling program when the row in-line code is finished (because the animation driver is then finished).

The benchmark results indicate that adding in-line code for the row loop does not greatly improve the performance of the exclusive-OR driver. This is not surprising considering that the row loop is the outer loop and is executed much less often than the inner loop. However, the concept of fully in-line code proves to be far more beneficial with the next driver.

(In-line code drivers must have enough in-line code to handle the maximum expected number of rows and columns for the largest form in the ani-

mation—a jump outside the in-line code would be disastrous.)

The calculated call to in-line code is the sort of technique that is essential to high-performance 8088 code. An obscure approach, one that is frowned upon because it involves multiple entry points to code and creates the potential for serious bugs, but it brings results—in the case of listing 7, a 68-percent faster execution of the benchmark application. The more esoteric approaches that follow further illustrate the necessity of innovative programming approaches in compensating for CPU deficiencies.

THE BYTE-MOVE DRIVER

The exclusive-OR approach offers many advantages with only a few drawbacks: an inevitable flicker when a form is moved, odd color effects when forms intersect (as the colors of the two forms are exclusive-ORed together), and a slow performance. Almost any arcade-style game for the PC will demonstrate these effects, and most of these games have only a few small, flickering forms moving at any one time. Support for dozens of figures moving simultaneously requires a different type of driver. Another close look at the architecture of the PC provides direction.

A higher-performance driver should minimize memory accesses (particularly display memory accesses because the CGA inserts wait states on 8088 accesses to display memory), reduce the instruction queue bottleneck, and keep branching to an absolute minimum. Ideally, it should perform memory accesses faster and perhaps provide a way of reducing the number of times the driver needs to be called per form movement from twice to once.

An inspection of the 8088's instruction set reveals one group—the string instructions—that offers remarkable (and very helpful) properties. For example, the MOVS instruction can move a byte from a source to a destination

and increment both pointers in 18 cycles—less time than the XOR instruction alone requires in the exclusive-OR driver. The REP prefix allows MOVS to operate repeatedly without branching. Using REP MOVS, the entire inner loop of the driver (the loop that draws a single form line) can be reduced to $9 + 17 * n$ cycles, where n is the number of form bytes on the scan line.

No string equivalent of the XOR instruction exists, so MOVS, which is the string equivalent of the MOV instruction, has to serve. The remainder of the drivers use MOVS, and, as a result, have fundamentally different properties from exclusive-OR drivers.

Listing 8 (BYTEMOV.ASM) is the byte-move equivalent of the exclusive-OR driver. It actually has two drivers, one to draw the form and one to erase it (the byte-move approach is not reversible like the exclusive-OR approach). When a form is to be moved, the main program first calls the erase routine to remove the form from the screen and then calls the draw routine to redraw it in the new location.

The erase routine uses the STOS instruction, which is faster than MOVS because it uses AL rather than memory for the source operand to clear the form from the screen. Both drivers use the in-line code, table look-up, and register optimization techniques discussed previously; however, in-line code works much more effectively with these drivers. This is the case because while the exclusive-OR drivers require two levels of in-line code, one to handle the rows and one to handle the columns in each row, the byte-move driver requires only one level, for the rows. The columns in each row are handled neatly by the REP operation of MOVS and STOS, providing the ideal solution for the innermost (column) loop—no branching and no in-line code. This also permits dispensing with the innermost loop and the return from it that was required by the exclusive-OR driver.

Another good point: the byte-move driver averts an instruction bottleneck because the 8088 holds the MOVS instruction internally through the entire REP operation. Thus, not only does the 8088 not have to keep fetching instructions during the REP operation, it also can fill up the prefetch queue. Because the number of instruction bytes between one REP MOVSB and the next in the in-line code is six and the size of the instruction prefetch queue is four, for forms that are more than one or two bytes wide the 8088 should be able to prefetch all the bytes up until the

Aztec C ... The Best C

Frees the genius in you

You've got a great idea . . .

. . . you're ready to write your programs.

You don't want to be sidetracked by all the paperwork. With Manx Aztec C and the ingenious **make** function, your creative processes won't get bogged down in program administration and housekeeping. Manx Aztec C has the most sophisticated, hardworking program administrator available to you. Once you've described your project, adding new features or enhancements is simple. You never have to concern yourself with the repetitive, tedious task of rebuilding your systems.

The development process moves quickly. Compiles, assemblies, link edits . . . all finish in record time.

Manx Aztec C is the fastest, most efficient C development system in the industry. Benchmarks show it . . . reviews commend it . . . users praise it.

You're ready to test the program. You're ahead of schedule. The Manx Aztec C Source Level Debugger shows you the exact C language statement giving you a problem. You fix the problem quickly . . . you're still ahead of schedule.

You've got some time for fine tuning. The Manx Aztec C Profiler examines your program, tells you where the slow spots are and validates your test procedure. A few changes and it's exactly what you wanted.

You've made it!

Aztec C is available for MS-DOS/PC DOS. Call for details on Macintosh, Amiga, Apple II, CP/M-80, CP/M-86, TRS-80, ROM and others.

To order, or, for information

Call Today

1-800-221-0440

**In NJ or outside the USA call
(201) 542-2121**

30-day satisfaction guarantee. Special Discounts are available to professors, students, independent developers, and on a "trade-in" basis. Site licenses.

MANX

Manx Software Systems
One Industrial Way
Eatontown, NJ 07724

" . . . a superb linker, a profiler, an assembler, and a set of development utilities are only the beginning of this package . . . performed admirably on the benchmarks, with short compile times and the best link times in this review . . . includes the most professional make utility . . . documentation is clear and complete. There is no doubt that this is a valuable and powerful programming environment." **Computer Languages Feb. '86**

" . . . execution times are very good, close to the best on most tests . . . " **PC Tech Journal Jan. '86**

" Easily one of the fastest compilers overall . . . library provides a lot of flexibility . . . generates small .EXE files." **Dr. Dobbs Journal Aug. '85**

C'Prime (Compiler, Assembler, Linker)	\$ 99.
Aztec C 86-d Developer's System	\$299.
Aztec C 86-c Commercial System	\$499.
PC ROM (8086, 68000, 8080, or 6502)	\$750.

Third Party Software for Aztec C: HALO, PHACT, C-tree, PRE-C, Windows for C, PC-lint, PANEL, Greenleaf, db Vista, C-terp, Plink-86, FirstTime, C Util Lib, and others.

NOTES

Aztec C Evaluation

FEATURES

C Compiler
Overlay Linker
Librarian
8086 Macro Assembler
Source for Library Routines
Make, grep, diff, utilities
Source level debugger and profiler
vi editor
Pos functions, UNIX, and Screen Libraries
Math, 8087/80287, and sensing Libraries
Intel Hex utility
mixed memory models
Intel object utility
detailed documentation
year of free updates

OPTIONS

ROM Support for 68000, 6502, 8080/280 Series
Cross development to Mac, Amiga, Apple,
CP/M-80 and others

Call
MANX
800-221-0440

MS is a registered TM of Microsoft, Inc., CP/M TM DRI, HALO TM Media Cybernetics, PANEL TM Roundhill Computer Systems, Ltd., PHACT TM PHACT Assoc., PRE-C, Plink-86 TM Phoenix, db Vista TM Raima Corp., C-terp, PC-lint, TM Gimpel Software, C-tree TM Faircom, Inc., Windows for C TM Creative Solutions, Apple II, Macintosh TM Apple, Inc., TRS-80 TM Radio Shack, Amiga TM Commodore Int'l.

CIRCLE NO. 208 ON READER SERVICE CARD

next REP MOVSB during the operation of the current REP MOVSB.

This driver also minimizes memory accesses—one read and one write per form byte (only one write when erasing) is an absolute minimum. The XOR instruction in the exclusive-OR driver actually performs two memory accesses, one to read the display memory byte and another to write back the modified value; worse, those two accesses are display memory accesses, and as a result are especially slow. The byte-move driver performs just one display memory access per form byte.

To this point, branching has been reduced to a minimum, and because the string instructions perform memory access as rapidly as is possible with the 8088, memory access has been optimized: in short, most of the criteria for a superior driver have been met. Listing 9 (BYTBENCH.ASM) is the benchmark program of listing 3 modified to call the byte-move `form_driver` and `erase_form_driver` routines. (Note that the code for drawing the initial forms is not required in this version of the benchmark; the byte-move erase routine unconditionally erases an area of the screen, unlike the exclusive-OR driver, which could erase only a form that already had been drawn.) With the byte-move driver of listing 8, the benchmark time is reduced to a mere 10 seconds—this speed improvement over the original exclusive-OR driver is greater than the improvement derived from converting the exclusive-OR driver from C to assembly language.

An added benefit of this driver is that no color side effects result when forms intersect. The most recently drawn form simply appears to be in front of the other form. However, if two forms overlap for an extended period of time, some flicker may become evident as each in turn is redrawn and appears to be in front.

The bad news about the byte-move driver is that it lacks the reversibility of the exclusive-OR driver. Whenever a form is moved, a blank is left where it was erased. This is not a serious problem if all forms on the screen are animated. In this case, the main program can redraw all the forms frequently, and any gaps left after form erasure will vanish quickly enough to be unnoticeable to the human eye.

One of the forms animated by the benchmark program is redrawn repeatedly at the same location. This is one way to provide a background with a byte-move driver. As long as the background area to be maintained is not too

large, redrawing it frequently like any other form is a good approach. This also makes it easy for the user to modify the background periodically by simply changing the form that is drawn. For example, a twinkling star can be drawn as a cyclic succession of several slightly different star forms.

If the picture has a static background that is not redrawn frequently, the byte-move driver introduces serious complications. Some scheme must be designed that allows intelligent redrawing of the background as each form is moved. (One such approach to solving this problem is discussed later.)

SELF-ERASURE

The byte-move driver is made even more effective with self-erasure. Actually, this driver is exactly the same as the last byte-move driver—the difference lies in its application. For this driver, each form must contain a blank fringe around it equal in size to the greatest move that the form will make. A normal application is to assume that the form moves a maximum of four pixels horizontally and two pixels vertically at any one time. (Larger moves can appear jerky, so this is a reasonable assumption.)

As long as the background area to be maintained is not too large, redrawing it frequently like any other form is a good approach.

tion.) Thus each form would have four pixel's worth of horizontal blanking and two pixel's worth of vertical blanking built into its movement.

This eliminates the need to erase a form when it is moved: the erasure is automatic. Moreover, no flicker appears because the form's erasure and redrawing are simultaneous. The end result is a graphics driver that is slightly less than two times faster than even the original byte-move driver (faster because the erasure step was eliminated, but only somewhat because the extra fringe bytes must be drawn), and which produces smooth animation.

Although this driver has the same drawbacks as any byte-move driver (and a few more of its own), it is extremely fast and looks very good. Listing 10 (BYTFRNGE.ASM) is the benchmark

program for the automatic erasure fringe driver. (The driver itself is the same as that in listing 8; in the benchmark program, the forms are changed to include the fringe and the code for drawing the initial forms and for erasing the forms is no longer needed.) The benchmark for this driver clocks in at a flicker-free 8 seconds, but this number does not tell the whole story. To see the real difference, run the original exclusive-OR benchmark of listings 1 and 3 and the byte-move benchmark of listings 8 and 10 one after the other to appreciate how much of an improvement in animation effect a high-performance driver makes.

One unfortunate characteristic of this byte-move driver is that the blank fringe around the form is visible when forms intersect. (See photo 2 for an illustration of this problem.) However, this is less distracting than exclusive-OR driver color effects and scarcely noticeable if the fringe is narrow.

The byte-move driver can be optimized further (beyond what is covered in this article). The form of the driver shown in listings 8 and 10 is still too general purpose. The entire erasure fringe must be drawn every time a form is moved; this wastes time and prevents forms from getting closer to the edge of the screen than the distance of their maximum move because the erasure fringe would go off the edge of the screen. The solution is to have four drivers, one for each direction of movement (more if diagonal moves are required). Each driver would be optimized to erase only the area vacated by the moving form. Alternatively, each form could have four versions, one for each direction of movement, and the main program could call the driver with the appropriate form for the direction of movement needed.

A BETTER BACKGROUND

The only serious problem with byte-move drivers is preserving the background. One solution introduces additional complexity to animation program design; but it maintains the speed advantages and smooth animation of byte-move drivers while allowing use of a static background.

The static background may be stored in a 16KB buffer within the program in the form in which it would be stored in display memory. Thus, the bytes for the erasure fringe would come from the background buffer, rather than being zero bytes. This could be done by the byte-move driver, or the main program could call a separate

driver to redraw the appropriate fringe from the background buffer after the form has been moved. In any case, calculation of the background source addresses would be very simple because a one-to-one mapping would be present between background buffer offsets and display memory offsets.

A buffer of 16KB may seem a lot of memory to use for a background, but this approach produces an excellent blend of speed, smooth animation, and background preservation. Besides, as mentioned above, memory is cheap (and the 8088 can address a lot of it), so it should be used to compensate for the limitations of the PC when possible.

ANIMATED DETAILS

All of the drivers discussed are limited to a movement increment of four pixels horizontally because the drivers work with a byte at a time, but this is not an inherent limitation of the drivers. The trick to pixel-aligning forms is to have three additional rotations of each form, one for each pixel alignment within the display memory byte, with the calling program passing the correct form for the desired pixel alignment to the driver. All of the rectangles drawn will still be byte-aligned, but each form will be positioned within its rectangle so that it appears at the correct pixel alignment.

A driver that supports pixel alignment via multiple form rotations also supports simple horizontal internal animation. Internal animation is a process whereby the appearance of an object changes as it moves, giving the object the appearance of being alive. For example, a creature's mouth might chomp, a rocket's exhaust might flare, and a humanoid's legs might walk.

Internal animation can be accomplished in many ways, but by far the simplest is to assign each of four internally animated versions of an object to one of the four pixel-aligned figures. Then the figure will automatically display internal animation as it moves horizontally in increments of one pixel.

For vertical motion, the calling program must cycle among the internal animation images to produce internal animation. This technique may be applied to horizontal motion as well for complex internal animation. Different forms can be sent to the driver by the main program for each direction of motion, so that, for example, a human figure will appear to walk right or left while moving horizontally and climb up or down while moving vertically.

Remember that the 8088 is considerably more efficient at accessing mem-

ory a word at a time than a byte at a time, requiring only four extra cycles per memory access for the added byte. When drawing medium- and large-sized forms, the drivers would benefit from the efficiency of word, rather than byte, operation. These byte-move drivers use byte memory accesses because for word-move drivers (using MOVSW instead of MOVSB) all forms must be a multiple of a word in width. For this application, a requirement that all forms be a multiple of eight pixels in width was too great a limitation. For exclusive-OR drivers, however, there is no compelling reason not to use word drivers for larger forms; any extra byte per row needed to pad a form to an even number of bytes can always be set to zero and thus have no effect.

For programmers working extensively with animation drivers, it is advisable to write a form editor that allows form modification on a dot-by-dot basis and then stores them to disk in the data structure required by the specific driver, preferably with pixel-aligned rotations supported as well. The program then can load the forms and use them. This is far easier than defining forms in hexadecimal with DB statements (as was the case in this article).

Most importantly, no best driver exists. Optimization of animation drivers for the IBM PC is an application-specific process.


In addition, remember that these optimizations were effected on the instruction timings and architecture of the 8088 and the IBM CGA. The 80286 has a different set of instruction timings, and its treatment would be different. The 80286 LOOP instruction, for example, takes 8 cycles, not 17.

A GOOD DRIVER

The animation drivers examined provide the prospective user a range of trade-offs among speed, ease of use, background preservation, memory requirements, and flexibility. None is perfect; but after all, the IBM PC and the CGA are far from perfect as vehicles for animation; however, it should be possible to customize one of these drivers to meet a given application.

The byte-move approach seems the only one capable of supporting good animation of multiple objects on the IBM PC. This is not to say that byte-move, or any of these drivers in particular, is the best possible route. Assembly language optimizations are elusive, and a programmer can examine a code fragment many times and keep finding ways to pare a few cycles here and there. A more important point, however, is that no best driver exists. In fact, some applications may call for using exclusive-OR and byte-move drivers at the same time, as each is best for a different part of the overall animation. Optimization of animation drivers for the PC is an application-specific process, because every cycle counts and every application lends itself best to a different animation structure. The techniques introduced here are meant as tools, not final answers, for the programmer to integrate into his applications as he deems appropriate. They are also meant to encourage the programmer to examine the 8088 architecture to find his own unconventional, but effective approaches to coding animation problems.

(One trial application called for moving hundreds of single dots simultaneously at a high speed, while animating dozens of larger forms as well. No driver could be devised to move the dots without slowing the program to a crawl. Finally, the actual display memory addresses of the dots were stored in an array, and the address of each dot was incremented by the display memory offset to its next position each time it moved; the exclusive-OR was performed directly from the stored screen offset value. Inflexible and highly application-specific, true, but it was the best answer to the application's needs.)


It is indeed possible to do better with less, in a different way. A good programmer knows how to apply standard techniques to a tough problem and produce a working solution. An exceptional programmer realizes that in such cases programming transcends mere implementation techniques, and he applies his knowledge and skills to produce a melding of software and hardware that performs the required task in the most effective way possible. In an arena where only results count, the flexibility of the human mind itself is often the final bottleneck. 

Michael Abrash is a senior software engineer for Tseng Laboratories in Pennsylvania. Dan Illowsky is president of Funstastic. Together and separately they have written video games for the IBM PC and Apple II.

THE ART OF STRIPPING...


Picture a complete system. One that provides a simple, reliable way to distribute and retrieve information. The centerpiece of this system is the Cauzin Softstrip™ reader. A state-of-the-art scanning device that's rapidly changing the shape of computer software.

You probably have seen Softstrip data strips containing software listings and data that have been published by such leading periodicals as Data Based Advisor, Mac User, // Computing, MACazine, Bar Code News, and Nibble mac. But the system doesn't stop there. Using the Softstrip technology, you can make paper work smarter for almost any application which uses computers.




INDEXES

Using computers to access reference data is becoming critical. To make it easy for subscribers to put Table of Contents data "on line," in their own PCs, Pergamon Press and Bar Code News have already started printing their indices within their publications in strips. Imagine, scanning data into your computer right from the pages of the journals you receive.



COMPATIBILITY BETWEEN COMPUTERS

Anything you can put on a magnetic disk, you can print on a data strip. So, one strip can be read by all computers. There's no need to worry about incompatible media sizes or densities. You can even use strips to transfer text or binary files between incompatible computers. For instance, Apple or Mac to a PC. Or the other way.



DATA BASE UPDATES

Whether it's chemical abstracts, price listings, catalogs, telephone data, or financial reports, regular updates for major files are a natural for Softstrip data strips. In fact, data strips can provide the means to effectively and inexpensively get important data out.



Softstrip
COMPUTER DATA STRIPS

TECH SPECS

The Reader is lightweight and portable. It comes complete with all the software and cables you should need to connect it to your PC; Apple II series; or Macintosh computer. It has its own power supply and connects to standard RS232 ports (or to the Apple //e cassette port).

ALL YOU NEED TO START MAKING YOUR OWN DATA STRIPS... besides your computer, a Softstrip reader, and STRIPPER™ (the "make-it-yourself Softstrip data strip program"):

FOR IBM PC or any 100% COMPATIBLE OWNERS

Epson RX or FX printer
Printer interface card

FOR MACINTOSH OWNERS

Apple Imagewriter I or II

FOR APPLE II OWNERS

Epson RX or FX printer, or,
Apple Imagewriter I or II, and,
Super Serial™ card (built into Apple //c), or,
Grappler™ graphics card, or,
Dumpling™ graphics card.

This data strip contains the program and instructions on moving Apple or Mac files to a PC.

ACT NOW!

Buy everything you need to read strips for only \$199.95 and you can get software to print your own strips for just \$19.95. Call to order or for the Dealer nearest you... 1-800-533-7323

CAUZIN SYSTEMS, INC.
835 SOUTH MAIN STREET
WATERBURY, CT 06706
203-573-0150

CAUZIN

Creators of the Softstrip™ Technology


```

0xff, 0xff, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x55, 0x55, 0x55, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x55, 0x55, 0x55, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x00, 0x00, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x00, 0x00, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x00, 0x00, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x00, 0x00, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x00, 0x00, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x00, 0x00, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x55, 0x55, 0x55, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0x55, 0x55, 0x55, 0x55, 0x55, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xaa, 0xff, 0xff,
0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff,
0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff,
0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff,
0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff,
0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff,
0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff, 0xff);
/* The list of forms to be used for the eight objects follows */
unsigned char *form_address[NUM_OBJECTS]
    = { f0, f1, f2, f3, f3, f2, f1, f0};

main()
{
    struct reg inregs, outregs;
    register int i, j;

/* set 320x200 graphics mode */
    inregs.r_ax = 4;
    intcall(&inregs,&outregs,0x10);
/* put forms on screen for the first time */
    j = NUM_OBJECTS - 1;
    do {
        form_driver(row[j],column[j],form_address[j]);
    } while ( j-- != 0 );
/* for # of iterations, move each object in turn */
    i = NUM_ITERATIONS - 1;
    do {
        j = NUM_OBJECTS - 1;
        do {
            form_driver(row[j],column[j],form_address[j]);
            if ( row[j] <= top_margin[j] || row[j]
                >= bottom_margin[j] )
                row_increment[j] *= -1;
            if ( column[j] <= left_margin[j] || column[j]
                >= right_margin[j] )
                column_incremnet[j] *= -1;
            row[j] += row_increment[j];
            column[j] += column_incremnet[j];
            form_driver(row[j],column[j],form_address[j]);
        } while ( j-- != 0 );
    } while ( i-- != 0 );
/* set 80x25 text mode before returning to DOS */
    inregs.r_ax = 2;
    intcall(&inregs,&outregs,0x10);
}

/* exclusive-OR driver */
form_driver(r,c,fax)
/* r and c are the row and column at which to put object.
r is the line number and can range from 0 - 199. 0 is the top line.
c is the column byte number and can range from 0 - 79; 0 leftmost.
fax is a pointer to the form to be XORed into screen memory */
int r, c;
unsigned char *fax;
{
    register int offset;
    register unsigned char *fa;
    int toffset, i, j, k;

    fa = fax;

```

```

if ( ( r & 1 ) == 0 )
    offset = ( r >> 1 ) * 80 + c;
else
    offset = ( r >> 1 ) * 80 + c + 0x2000;
i = *fa++;
j = *fa++;
do {
    toffset = offset;
    k = j;
    do {
        putbyt(*fa++,offset++);
    } while ( --k != 0 );
    if ( toffset < 0x2000 )
        offset = toffset + 0x2000;
    else
        offset = toffset - 0x1fb0;
} while ( --i != 0 );

```

LISTING 3: XORBENCH.ASM

```

;This program benchmarks exclusive-OR drivers.
;Link the XOR form_driver module to this program.
;
stack segment para stack 'STACK'
    db 512 dup(0)
stack ends
;
one segment para public 'CODE'
    assume cs:one,ds:one,es:nothing
    extrn form_driver:near
;
iteration_count dw 0
;
;Lists describing image, location, and motion of 8 objects.
;
form_address dw f0, f1, f2, f3, f3, f2, f1, f0 ;pointers to form
                                                    ; byte strings for
                                                    ; each object
highest_object_pointer equ (($-form_address)-2) ;the index for the
                                                    ; last object in
                                                    ; these lists
;
;in scan lines (0 - 198):
row dw 100,100,100,100,100,100,100,100
;in bytes (0 - 79):
column dw 32, 32, 32, 32, 32, 32, 32, 32
;in scan lines (0 - 198):
row_increment dw -2, 2, 0, -2, 0, 0, -2, 2
;in bytes (0 - 79):
column_increment dw 1, 1, 0, -1, 1, -1, 0, -1
;byte number on line (0-79):
left_margin dw 0, 0, 0, 0, 0, 0, 0, 0
;byte number on line (0-79):
right_margin dw 76, 74, 72, 70, 70, 72, 74, 76
;line number (0 - 198):
top_margin dw 0, 0, 0, 0, 0, 0, 0, 0
;line number (0 - 198):
bottom_margin dw 194,184,174,164,164,174,184,194
;
;Form byte structures, as follows:
;    byte 1: # of scan lines in forms.
;    byte 2: # of bytes per scan line of form.
;    byte 3: first byte of image, followed by rest of bytes
;             forming image, with bytes for top scan line,
;             left to right, first, second scan line next,
;             and so on.
;
f0 db 6,4
    db 0f0h,00fh,0f0h,00fh
    db 0f0h,03fh,0fch,00fh
    db 0ffh,0ffh,0ffh,0ffh
    db 0f0h,0ffh,0ffh,00fh
    db 0f0h,03fh,0fch,00fh
    db 0f0h,00fh,0f0h,00fh

```



FREE EXPANDED MEMORY BOARD!*

"Make no mistake, the PC-286 is the most awesome piece of high technology you can put in a PC..."


— BUSINESS COMPUTER SYSTEMS

"Of this month's selections, PC-286 was fastest for the spreadsheet recalculation."

— LOTUS MAGAZINE



- Fully compatible with the industry-standard Lotus/Intel/Microsoft (LIM) Expanded Memory Specification (EMS), version 3.2
- Expandable up to 8 megabytes.
- Compatible with all major productivity software such as Lotus 1-2-3, Symphony, Framework II.



• BUNDLED WITH MICROSOFT WINDOWS •

Top Board processes EMS-applications up to three times faster than any other EMS board on the IBM PC XT. Top Board is the only EMS expanded memory board with both an 8 and 16 bit data bus and can function across the 16 bit wide bus with the STD-powered PC-286 card.

Top Board frees you from the memory limits of 640K. Expand memory up to 2 MB with the confidence of LIM-compatible standards. Unleash this full potential with processor speeds up to 12 MHz when used with our PC-286 board

across the built-in, 16 bit data bus to the Top Board.

Expect performance that exceeds industry standards. Together, the PC-286 and Top Board perform beyond their individual state-of-the-art designs. Your CAD, spreadsheet, database or other software designed to utilize the EMS specification will run up to 8 times faster than an IBM PC XT with this product combination.

The Top Board is fully compatible with the Lotus/Intel/Microsoft Expanded Memory Specification. It's unique design has an efficient

and flexible paging scheme for even greater performance with EMS-compatible applications and multitasking software.

For the performance you and your PC have been waiting for, order a Top Board today. Solve your PC's problems with processing-intensive applications and improve your own personal productivity.

CALL (206) 883-8440

STD

**SEATTLE TELECOM
& DATA, INC.**
2637 151st Pl. N.E.
Redmond, WA 98052

Top Board and PC-286 are trademarks of STD. Framework is a trademark of Ashton-Tate. Lotus 1-2-3 and Symphony are trademarks of Lotus Development Corporation. IBM PC XT is a trademark of IBM Corp. Contact us regarding optional EGA graphics and multifunction daughter boards.

***Must purchase a 6 or 8 MHz expandable PC-286 board to receive a free 512K Top Board (\$549 value). Offer expires September 30, 1986.**


```

f1      db 16,6
        db 4 dup(6 dup(055h))
        db 4 dup(6 dup(0ffh))
        db 4 dup(6 dup(0aah))
        db 4 dup(6 dup(055h))
f2      db 26,8
        db 26 dup(0ffh,0aah,0aah,055h,055h,0aah,0aah,0ffh)
f3      db 36,10
        db 9 dup(10 dup(0ffh))
        db 3 dup(0ffh,0ffh,6 dup(0aah),0ffh,0ffh)
        db 3 dup(0ffh,0ffh,0aah,4 dup(055h),0aah,0ffh,0ffh)
        db 6 dup(0ffh,0ffh,0aah,055h,000h,000h,055h,0aah,0ffh,0ffh)
        db 3 dup(0ffh,0ffh,0aah,4 dup(055h),0aah,0ffh,0ffh)
        db 3 dup(0ffh,0ffh,6 dup(0aah),0ffh,0ffh)
        db 9 dup(10 dup(0ffh))

;
start   proc    far
        push    ds                ;set up for return to DOS
        sub     ax,ax             ; through the instruction at DS:0 set
        push    ax               ; up by DOS when it loads this program
        cld                     ;drivers count up

        push    cs
        pop     ds               ;DS and CS are to be the same
        mov     ax,0b800h        ;ES is to point to Color Graphics
        mov     es,ax           ; Adapter's memory buffer
        mov     ax,0004h        ;set 320x200 color mode
        int     10h             ;

;
;Start by drawing all the images at their starting locations
;
        mov     si,highest_object_pointer ;start at last object
next_initial_draw:
        push    si               ;save the object index
        mov     bx,[si+row]      ;get the line at which to put
                                ; this object
        mov     cx,[si+column]   ;get the column for this object
        mov     si,[si+form_address] ;get the address of the
                                ; object's image
        call    form_driver      ;put image to screen memory
        pop     si               ;restore the object index
        sub     si,2             ;point to next object to draw
        jns     next_initial_draw ;if not done draw next object

;
;Set number of times to move objects
;
        mov     [iteration_count],700 ;number of times to repeat
                                ; move loop

;
;For each iteration, move each object in turn by erasing it,
; moving it one increment, and drawing it at the new position.
;
next_iteration:
        mov     si,highest_object_pointer ;start at last object
;
;Move each object in turn.
;
move_next_object:
;
;Erase the object at its present position.
;
        push    si               ;exclusive-ORing an existing
        mov     bx,[si+row]      ; image with itself
        mov     cx,[si+column]   ; effectively erases it
        mov     si,[si+form_address] ;
        call    form_driver      ;
        pop     si               ;

;
;Advance the object's row and column and adjust increments
; so the object remains within its boundaries.
;
;If adding the row increment to the row would place it outside
; its margins...
;
        mov     ax,[si+row]      ;test the new line position
        add     ax,[si+row_increment] ; to see if it goes outside
        cmp     ax,[si+top_margin] ; its limit
        jb      negate_row_increment ;if outside negate increment
        cmp     ax,[si+bottom_margin] ; so that it will move towards
        jbe     test_column_increment ; its other limit
;

```

```

;...then make the row increment negative if positive and
; positive if negative.
;
negate_row_increment:
        neg     [si+row_increment] ;make it move in other direction
;
;If adding the column increment to the column would place it
; outside its margins...
;
test_column_increment:
        mov     ax,[si+column]    ;if the column for the object
        add     ax,[si+column_increment] ;would go outside its left or
        cmp     ax,[si+left_margin] ; right limits, then negate
        jb      negate_column_increment ; its increment so that it
        cmp     ax,[si+right_margin] ; will move in the opposite
        jbe     add_increments    ; direction
;
;...then make the column increment negative if positive and
; positive if negative.
;
negate_column_increment:
        neg     [si+column_increment] ;set to move in opposite
                                ; direction
;
;Add the increments to the row and column to arrive at the
; object's next position.
;
add_increments:
        mov     ax,[si+row_increment] ;calculate the next line
        add     [si+row],ax           ; position and store it
        mov     ax,[si+column_increment] ;calculate the next column
        add     [si+column],ax       ; position and store it
;
;Draw the object at the new location.
;
        push    si               ;save this object index
        mov     bx,[si+row]      ;find line and column no. at
        mov     cx,[si+column]   ; which to place the object
        mov     si,[si+form_address] ;find addr. of object's form
        call    form_driver      ;put object's image into screen
        pop     si               ;restore the object index
;
        sub     si,2             ;point to next object to move
        jns     move_next_object ; if not done jmp to move it
;
        dec     [iteration_count] ;count down number of times to
        jnz     next_iteration   ; move all the objects
;
;Reset the mode to 80x25 color text mode.
;
        mov     ax,0003h        ;before returning to DOS, set
        int     10h             ; screen to 80x25 text mode
;
;Return to DOS.
;
        ret                     ;return though instruction at
                                ; start of PSP set up by DOS

start   endp
one     ends
end     start

```



LISTING 4: DRIVECXOR.ASM

```

;Assembly language subroutine for C exclusive-OR driver,
; in format required by Mark Williams C compiler.
;Exclusive-ORs byte at color display offset.
;
; Input:
;      parm 1 - byte to exclusive-OR.
;      parm 2 - offset to exclusive-OR byte at.
;
; Output: none
;
CGROUP  GROUP  CODE
;
;Parameter layout for use in addressing the 2 parameters on the stack.
;
dyns    struc
old_bp  dw    ?

```


Nine Reasons to "Wonder"



The "Wonder" screen acts as a sophisticated instrument panel to guide even the most novice users through the intricacies of program selection and file management. Its menuing/macro functions and point and shoot management expedite the normally tedious routines of any product demonstration.

1 "Wonder" is easy to use. Many Corporate Training Centers and Independent consultants across the country use "Wonder" to soothe the initial fears and pave the way to increased productivity.

As Tim Daneliuk, Contributing Editor for PC Products wrote, *"Quite simply 1dir works flawlessly . . . 1dir is a well conceived and implemented product that is whole heartedly recommended for virtually anyone who uses their P.C. often. It provides an easy-to-use doorway into DOS and is flexible enough for novice and expert alike."*

2 "Wonder" is easy to install. Although "Wonder" can be programmed to perform countless time saving tasks, it is not unreasonable for a novice user to create a basic system in less than an hour.

3 "Wonder" helps sell systems. By expediting machine operation and routine maintenance, "Wonder" puts the focus on practical applications which is the real reason that people buy computers in the first place.

4 "Wonder" is ideally suited for the trend toward hard disk technology. "Wonder" is licensed by more hard disk manufacturers than any other program of its type, and many dealers sell "Wonder" with every hard disk system. As Corporate Training Specialist for Micro D., Mr. Don Kenny writes,

"1dir . . . provides the most logical system I've ever seen for managing hard disk files."

5 The demand for "Wonder" is on the rise. Rave reviews in PC, Infoworld, Business Software, PC Products, Compute and others have increased public awareness and established 1dir as an industry standard. In an article entitled "Taming Your Hard Disk The Easy Way" Phil Wiswell of PC concludes *" . . . 1dir does indeed spell WONDER."*

6 "Wonder" provides dealers with a healthy profit margin. "Wonder's" \$95.00 price tag maintains a delicate balance between reasonable prices for consumers and excellent profit margins of 40% and up for dealers.

7 "Wonder" gives you a perfect tool for providing additional services and creating new revenue sources. For those wishing to enter the realm of VAD or systems consultant, the unmatched versatility of "Wonder" provides many advantages. Individualized Turn Key systems can be created quickly and easily to match your clients needs.

8 "Wonder" is compatible with IBM and all its compatibles, & portables & a wide range of network systems. System requirements — IBM PC/XT/3270 PC/AT/jr or compatible; DOS 2.0 or higher; one disk drive.

9 We specialize in supporting VADs & VARs.

\$95.00

Bourbaki Inc.™

P.O. Box 2867
Boise, ID 83701



(208) 342-5849

¹PC Products, 8/85: The 1dir of DOS, Tim Daneliuk, Contributing Editor.

²Published letter to PC Week editors, 7/30/85.

³PC 12/85: Taming Your Hard Disk The Easy Way: Part 2


```

old_ds dw ?
retn dw ?
p1 dw ?
p2 dw ?
dyns ends
;
code segment byte public 'CODE'
public putbyt_
assume cs:cgroup
;
putbyt_ proc near
push ds
push bp
mov bp,sp
mov al,byte ptr [bp].p1 ;get byte to xor into display RAM
mov bx,0b800h
mov ds,bx ;point segment to color display RAM
mov bx,[bp].p2 ;get screen offset to xor byte at
xor [bx],al ;xor byte into display RAM
pop bp
pop ds
ret
putbyt_ endp
code ends
end

```

LISTING 5: OPTXOR.ASM

```

;Optimized XOR graphics driver for putting rectangular images into
; the Color/Graphics Adapter's medium-resolution memory map.
;
; Note: AX,BX,CX,DX,BP,SI,DI destroyed.
;
one segment para public 'CODE'
assume cs:one,ds:one,es:nothing
public form_driver
;
form_driver proc near
mov di,[bx+even_line_screen_offset_table] ;find offset of
; top line of image
add di,cx ;ES:DI now points to byte at which to put
; the image's upper left corner
lodsb ;get the height of the image
shr al,1 ;divide by 2 to arrive at number of even/odd
; line pairs in the image
mov ah,al ;store count in AH
lodsb ;get the width of the image in bytes
mov bl,al ;put width in BL
sub bh,bh ;make width a 16 bit value
mov bp,2000h ;calculate the amount to add after even scan
sub bp,bx ; lines are drawn to get to address of the
; next scan line
mov dx,1fb0h ;calculate amount to subtract after odd scan
add dx,bx ; lines are drawn to get to address of the
; next scan line
;
next_two_lines:
mov cx,bx ;set the number of bytes/line for the form
next_column_for_even_row:
lodsb ;get the next image byte
xor es:[di],al ;exclusive-OR it into screen memory
inc di ;point to next screen memory position
loop next_column_for_even_row ;loop for next byte
; on even line
add di,bp ;calculate address to start next line of image
mov cx,bx ;reset the number of bytes/line for an odd row
next_column_for_odd_row:
lodsb ;get the next image byte from the form
xor es:[di],al ;exclusive-OR onto screen
inc di ;advance screen memory pointer
loop next_column_for_odd_row ;loop for next byte on odd line
sub di,dx ;calculate the address to start next line
; of image--next line will be an even line
dec ah ;count down number of line pairs
jne next_two_lines ; jmp if any even/odd line pairs left
ret ; if not, return to calling program
;
;This table is used to find the offset of an even scan line in
; the memory map of the color graphics adapter in medium res mode.

```

```

;
even_line_screen_offset_table label word
x=0
rept 100 ;there are 100 even lines
dw x*50h ; each is 50h (80 decimal) long
x=x+1
endm
;
form_driver endp
one ends
end

```

LISTING 6: INLINXOR.ASM

```

;Column inline code XOR graphics driver for putting rectangular
; images into the CGA's medium-resolution memory map.
;
; Note: AX,BX,CX,DX,BP,SI,DI destroyed.
;
one segment para public 'CODE'
assume cs:one,ds:one,es:nothing
public form_driver
;
form_driver proc near
mov di,[bx+even_line_screen_offset_table] ;find offset of
; top line of image
add di,cx ;ES:DI now points to byte at which to put
; the image's upper left corner
lodsb ;get the height of the image
xor ah,ah ;make height into 16 bit value
shr ax,1 ;divide by 2 to arrive at number of even/odd
; line pairs in the image
mov cx,ax ;store count in CX
lodsb ;get the width of the image in bytes
mov bp,2000h ;calculate the amount to add after even scan
sub bp,ax ; lines are drawn to get to address of the
; next scan line
mov dx,1fb0h ;calculate amount to subtract after odd scan
add dx,ax ; lines are drawn to get to the address of
; the next scan line
mov bx,ax ;number of columns in image
shl bx,1 ;convert into word table index
mov bx,[bx+column_inline_vector_table-2]
;
;Code for calculating the memory address to start each line of the
; image, and calling the inline code which exclusive-ORs a line of the
; image into the screen
;
next_two_lines:
call bx ;BX holds address of inline columns code
add di,bp ;calculate address to start next line of image
call bx ;process image for odd scan line
sub di,dx ;calculate address to start next line of image
; the next line will be an even line
loop next_two_lines ;loop if any even/odd line pairs left
ret ; if not, return to calling program
;
;Inline code for XORing a line of the image into the screen
;
clabel macro x ;this macro is used to label the inline code
cline&x& ; entry points for number of columns to XOR
endm ;
;
x=10 ;this code can handle an image up to
; 10 bytes wide
clabel %x ;put in label for entry based on number of
; bytes in a column
lodsb ;get the next byte from the object's image
xor es:[di],al ; and XOR it with the value now at the
; screen position.
inc di ;point to next image byte in object's form
x=x-1 ;adjust label number
endm
ret ;this return is executed at the end of
; every line
;
;This table is used as an indirect address for jumping into
; the inline code for exclusive-ORing columns.
;

```


ONCE IN A LIFETIME A NEW PRODUCT APPEARS ON
THE HORIZON THAT SHINE ABOVE ALL OTHERS

THE CREATOR™

APPLICATION GENERATOR

by Advanced Development Technologies

- ★ FOURTH GENERATION PRODUCTIVITY
- ★ ELIMINATE DATABASE MANAGEMENT SYSTEMS
- ★ A COMPLETE APPLICATION
GENERATION ENVIRONMENT
- ★ DEVELOP APPLICATIONS IN LESS TIME
 - ★ REDUCE CODE REQUIREMENTS
BY 90 PERCENT
- ★ TRAPS ERRORS WITH DETAIL ANALYSIS
 - ★ MULTIPLE FILE ACCESS
WITHOUT PROGRAMING
- ★ 99 INDEXES PER DATA FILE
- ★ AUTOMATIC RECORD LOCK
 - ★ UNLIMITED FILE AND
RECORD SIZE
- ★ PRODUCES COMPLETE
DOCUMENTATION

\$99

MASTERCARD/VISA

INCLUDES:

- Internal Expression Compile
- Relational File Structure
- ISAM File Access Method
- Screen and Report Generator
- Rich Library of Functions
- Data Dictionary
- System and User Defined Variables

For Only \$99 The **CREATOR™** Lets You Develop Applications Without Being Bugged Down By A Lot Of Code. Regardless Of How Simple Or Sophisticated The Applications, Save Hundreds Of Hours Of Programing By Using This Advanced Method Of Application Development. Manages All Phases Of Program Development:

- Program Generation
- Database Defination
- Screen And Report Formation
- Multiple Levels of Menus.

A Complete Development System Available For IBM, PC, XT, and AT Requires 256K RAM Includes Unlimited Run Time

800-528-6060

EXT. 239

CHECKS AND MONEY ORDERS ACCEPTED

©THE CREATOR™ IS A TRADEMARK OF
ADVANCE DEVELOPMENT TECHNOLOGIES

2720 N. 68th St., Suite 5379

Scottsdale, Arizona 85257

602-945-1375

CIRCLE NO. 190 ON READER SERVICE CARD

IBM PC, XT, AT is a
Copyright of International
Business Machines, Inc.


```

column_inline_vector_table label word ;there is no entry point for
; 0 lines. Starting at 2
; eliminates the need to
; store a dummy entry point
; address

column_entry_address macro x ;this macro is used to
dw cline&x& ; generate the labels
endm ; corresponding to the inline
; code entry points

;
x=1
rept 10
column_entry_address %x
x=x+1
endm
;
;This table is used to find the offset of an even scan line in
; the memory map of the color graphics adapter in medium res mode.
;
even_line_screen_offset_table label word
x=0
rept 100 ;there are 100 even lines
dw x*50h ; each is 50h (80 decimal) long
x=x+1
endm
;
form_driver endp
one ends
end

```

LISTING 7: RCINXOR.ASM

```

;Full row & column inline code XOR graphics driver for putting
; rectangular images into the Color/Graphics Adapter's
; medium-resolution memory map.
;
; Note: AX,BX,CX,DX,BP,SI,DI destroyed.
;
one segment para public 'CODE'
assume cs:one,ds:one,es:nothing
public form_driver
;
form_driver proc near
mov di,[bx+even_line_screen_offset_table] ;find offset of
; top line of image
add di,cx ;ES:DI now points to byte at which to put
; the image's upper left corner
lodsb ;get the height of the image
xor ah,ah ;make height a word value for calculations
mov bx,ax ;store height in BX
lodsb ;get the width of the image in bytes
mov bp,2000h ;calculate the amount to add after even scan
sub bp,ax ; lines are drawn to get to the address of
; the next scan line
mov dx,1fb0h ;calculate amount to subtract after odd scan
add dx,ax ; lines are drawn to get to the address of
; the next scan line
mov cx,[bx+inline_height_vector_table-2] ;-2 because there
; is no 0 lines entry point
mov bx,ax ;number of columns in image
shl bx,1 ;convert into word table index
mov ax,[bx+column_inline_vector_table-2]
xchg ax,cx ;CX now holds column code &,
; AX the row code address
jmp ax ;jmp to into inline code for height
;
;This table is used to find the offset of an even scan line in
; the memory map of the color graphics adapter in medium res mode.
;
even_line_screen_offset_table label word
x=0
rept 100 ;there are 100 even lines
dw x*50h ; each is 50h (80 decimal) long
x=x+1
endm
;
;This is inline code for finding the screen address for each line
; of the image and calling the exclusive-ORing inline code.

```

```

;
label macro x ;this macro is used to label the inline code
line&x& ; entry points
endm
;
;
; inline code for rows
;
x=42 ;there will be an entry point for each even
; number of lines between 2 and 40. They will
; be labeled "line2", "line4", ... "line40"
rept 20 ;each repeat handles 2 lines; 1 even, 1 odd
x=x-2 ;calculate no. of lines for this entry point
label %x ;put in label for entry point
;
call cx ;CX holds address of inline columns code
add di,bp ;calculate address to start next line of image
call cx ;process image for odd scan line
sub di,dx ;calculate address to start next line of image
endm ; the next line will be an even line
ret
;
;Inline code for XORing a line of the image into the screen
;
clabel macro x ;this macro is used to label the inline code
cline&x& ; entry points for number of columns to XOR
endm
;
;
x=10 ;this code can handle an image up to ten bytes
rept 10 ; wide
clabel %x ;put in label for entry based on no. of bytes
; in a column
lodsb ;get the next byte from the object's image
xor es:[di],al ; and XOR it with the value now at the
; screen position.
inc di ;point to next image byte in object's form
x=x-1 ;adjust label number
endm
ret ;this return is executed at the end of
; every line
;
;This table is used as an indirect address for jumping into
; the inline code for image moving.
;
inline_height_vector_table label word ;there is no entry point for 0
; lines. Starting at 2
; eliminates the need to store
; a dummy entry point address
entry_address macro x ;this macro is used to generate
dw line&x& ; the labels corresponding to the
endm ; inline code entry points
;
x=2
rept 20
entry_address %x
x=x+2
endm
;
;This table is used as an indirect address for jumping into
; the inline code for exclusive-ORing columns.
;
column_inline_vector_table label word ;there is no entry point for
; 0 lines. Starting at 2
; eliminates a need to store
; a dummy entry point address
column_entry_address macro x ;this macro is used to generate
dw cline&x& ; the labels corresponding to the
endm ; inline code entry points
;
x=1
rept 10
column_entry_address %x
x=x+1
endm
;
;
form_driver endp
one ends
end

```


The Full-Service Source For Programming Software

Knowing software is an art in itself. It takes time and dedication. At Lifeboat, we're committed to more than just selling the best software. We know our products and support them. And we learn about you, our customers, giving you the complete solution to your programming needs.

LANGUAGES

Lattice C New 3.0 Version The best selling C Compiler has been upgraded to give you more functions and features. Lattice C 3.0 contains 200 new library functions, better code generation, support for new data types (void, enum, unsigned char, unsigned long), support for the 80186/80286 instruction set and the ability to generate in-line 8087/80287 instructions. Lattice C is the C compiler for professional developers.

RUN/C—The C Interpreter Upgraded Version Learn C the natural way with RUN/C. The user interface is similar to BASIC with easy familiar commands. The new 2.0 version of RUN/C comes with a full-screen editor and other enhancements.

RUN/C Professional New RUN/C Professional "...is the overall best choice in a C interpreter." *PC Tech Journal* (5/86). All RUN/C's capabilities plus powerful features for program development. Load your favorite object libraries with RUN/C Professional. Contains a full-screen editor and source code debugging facilities.

BetterBASIC New Version Now you can program in BASIC and use the full memory of your PC, create structured programs using functions and procedures, make your own library modules and more. Now compatible with Microsoft BASIC.

LANGUAGE UTILITIES

Periscope I & II The symbolic debugger that can debug anywhere within a program at anytime with a simple press of a button! Periscope's breakout button will interrupt infinite loops, gain freedom from a locked up keyboard or help you find out where that slow running program is spending all its time. Periscope covers every conceivable type of breakpoint, including breaks on reads and writes to ranges of memory. Source code and line numbers for popular high level languages are displayed. Periscope I additionally features a protected memory board which shields the debugger from runaway programs.

Plink86 Plus An overlay linkage editor for linking 8086/8088 object modules. Contains new features for memory caching, library allocation, file merging and overlay reloading.

Pfix86 Plus A symbolic and source level advanced debugger for programming professionals.

C-SPRITE Symbolic debugging at both source level and machine level. Monitor your program by setting breakpoints, examining registers and variables, or single-stepping through code.

EDITORS

FirsTime Speed-up program development with an easy-to-use syntax checking editor for C or Pascal. Detects syntax errors, undefined variables and mismatched type assignments. Use function key menus to generate statements or enter your code directly. Also includes a program formatter and unique program development aids. FirsTime key assignments can be reconfigured. Easy-to-learn with on-line help available.

VEDIT Plus A full-screen text editor for program development and word processing. It contains powerful features including use of macros, on-line help facility, paragraph formatting, and file comparison.

Pmate The programmer's editor with an extensive macro command language. Compile in the background while you continue to edit files.

EMACS Customizable editor including windowing, multi-tasking and special modes for C and Pascal.

FUNCTIONS

The Greenleaf Comm Library

A library of over 120 communication routines. Contains functions to create interrupt driven routines or perform direct I/O to multiple Comm Ports. Its strengths are in asynchronous communications, interrupt mode, modem control, XMODEM, XON/XOFF and flow control. Interfaces with Lattice, Microsoft, Wizard, Desmet, CI86, Aztec and Mark Williams C compilers.

PforCe New A library of 400 plus functions for interrupt driven communications, background tasks, string/table parsing, data base manipulation, DOS and BIOS functions and more. Superbly written and documented software with complete source code is included.

The Greenleaf Functions A mature library of over 200 functions. Version 3.0 offers all new indexed documentation, with an abundance of examples. Source code included.

BASIC.C Speed-up development time with this BASIC to C library. Designed for the BASIC programmer who is moving over to C. This library act as a bridge to C providing many of the capabilities of the BASIC language.

Essential C Utility Library Over 300 functions, with special attention given to screen handling, windows and business graphics. Source code is included.

GRAPHICS, WINDOWING and SCREEN DESIGN

GSS*CGI GRAPHICS New The GSS Computer Graphics Interface is designed for creating high performance graphics-based applications. GSS*CGI speeds up application development and provides compatibility with a wide range of peripherals. It's the only CGI implementation that provides true device-independence for both raster and vector graphics. Products in the GSS GRAPHICS line include: the GSS*CGI Graphics Development Toolkit, the GSS Kernel System; the GSS Plotting System; and the GSS*CGI Metafile Interpreter.

Essential Graphics New A brand new graphics library for C programmers with the emphasis placed on ease of use and portability. No royalties.

Halo Library of over 200 graphics functions, supporting all of the popular graphics boards.

Windows for Data New Provides C programmers with complete control over screen display and data entry, within an easy-to-use windowing system. Combines a comprehensive library of window functions with an integrated set of versatile data-entry functions. Features include one-step data entry, multiple data types, Lotus-style menu design, full-featured field editing, pop-up entry windows, and much more.

Panel A powerful tool for interactive screen design.

For more information on these and other products in our complete line call:

1-800-847-7078

NY: 914-332-1875

CIRCLE NO. 144 ON READER SERVICE CARD

The Full-Service Source for Programming Software.

LIFEBOAT

INTERNATIONAL SALES OFFICES

Australia:
Fagan Microprocessor Assoc
Phone: (61) 3699-9899
Canada: Scantel Systems
Phone: (416) 449-9252
England: Grey Matter, Ltd.
Phone: (44) 364-53499
Italy: Lifeboat Assoc., S.p.A.
Phone: (02) 656-841
Japan: Lifeboat Japan
Phone: (03) 293-4711
Spain: Micronet, S.A.
Phone: (34) 1-457-5056
The Netherlands:
GIGA Computer Products
Phone: (31) 10-771846
W. Germany:
MEMA Computer GmbH
Phone: (49) (069)34 72 26

Lifeboat
55 South Broadway
Tarrytown, NY 10591

The names of products listed are generally the trademarks of the sources of the products.
© 1986 Lifeboat Associates

LISTING 8: BYTEMOV.ASM

```

;Byte-move graphics driver for putting rectangular images into
; the Color/Graphics Adapter's medium-resolution memory map.
;
; Note: AX,BX,CX,DX,BP,SI,DI destroyed.
;
one segment para public 'CODE'
    assume cs:one,ds:one,es:nothing
    public form_driver,erase_form_driver
;
form_driver proc near
    mov di,[bx+even_line_screen_offset_table] ;find the
    ; offset of the top line of image
    add di,cx ;ES:DI now points to byte at which to put
    ; the image's upper left corner
    lodsb ;get the height of the image
    xor ah,ah ;make height a word value for calculations
    mov bx,ax ;store height in BX
    lodsb ;get the width of the image in bytes
    mov bp,2000h ;calculate the amount to add after even scan
    sub bp,ax ; lines are drawn to get to the address of
    ; the next scan line
    mov dx,1fb0h ;calculate the amount to subtract after odd
    add dx,ax ; scan lines are drawn to get to the address
    ; of the next scan line
    jmp [bx+inline_height_vector_table-2] ;-2 because there
    ; is no 0 lines entry point
;
;This table is used to find the offset of an even scan line in
; the memory map of the color graphics adapter in medium res mode.
;
even_line_screen_offset_table label word
x=0
    rept 100 ;there are 100 even lines
    dw x*50h ; each is 50h (80 decimal) long
x=x+1
    endm
;
;This is inline code for moving the image into the screen memory map.
;
label macro x ;this macro is used to label the inline code
eline&x&: ; entry points
    endm
;
x=42 ;there will be an entry point for each even
; number of lines between 2 and 40. They will
; be labeled "line2", "line4", ... "line40"
    rept 20
x=x-2 ;calculate no. of lines for this entry point
    label %x ;put in label for entry point
    mov cx,ax ;put width of image in bytes in CX to prepare
    rep movsb ; for repeated move string on even line
    add di,bp ;calc addr. of next line: DI + (2000h*width)
    mov cx,ax ;put width of image in bytes in CX to prepare
    rep movsb ; for repeated move string on odd line
    sub di,dx ;calc addr. of next line: DI - (1fb0h*width)
    endm
    ret
;
;This table is used as an indirect address for jumping into
; the inline code for image moving.
;
inline_height_vector_table label word ;there is no entry point for
; 0 lines. Starting at 2 eliminates
; the need to store a dummy entry
; point address
entry_address macro x ;this macro is used to generate
dw eline&x& ; the labels corresponding to the
endm ; inline code entry points
;
x=2
    rept 20
    entry_address %x
x=x+2
    endm
;
form_driver endp
;
;Byte-move graphics driver for erasing rectangular areas of

```

```

; the Color/Graphics Adapter's medium-resolution memory map.
;
; Note: AX,BX,CX,DX,BP,SI,DI destroyed.
;
erase_form_driver proc near
    mov di,[bx+even_line_screen_offset_table] ;find the
    ; offset of top line of image
    add di,cx ;ES:DI now points to byte at which to put
    ; the image's upper left corner
    lodsb ;get the height of the image
    xor ah,ah ;make height a word value for calculations
    mov bx,ax ;store height in BX
    lodsb ;get the width of the image in bytes
    mov bp,2000h ;calculate the amount to add after even scan
    sub bp,ax ; lines are drawn to get to the address of
    ; the next scan line
    mov dx,1fb0h ;calculate the amount to subtract after odd
    add dx,ax ; scan lines are drawn to get to the address
    ; of the next scan line
    mov si,ax ;save width in SI for this erase driver
    mov al,ah ;zero AL (data to blank with)
    jmp [bx+erase_height_vector_table-2] ;-2 because there is
    ; no 0 lines entry point
;
;This is inline code for erasing the image from the screen memory map.
;
label macro x ;this macro is used to label the inline code
eline&x&: ; entry points
    endm
;
x=42 ;there will be an entry point for each even
; number of lines between 2 and 40. They will
; be labeled "eline2", "eline4", ... "eline40"
    rept 20
x=x-2 ;calc number of lines for this entry point
    elabel %x ;put in label for entry point
    mov cx,si ;put width of image in bytes in CX to prepare
    rep stosb ; for repeated store string instruction
    add di,bp ;calc address of next line DI + (2000h*width)
    mov cx,si ;put width of image in bytes in CX to prepare
    rep stosb ; for repeated store string instruction
    sub di,dx ;calc address of next line DI - (1fb0h*width)
    endm
    ret
;
;This table is used as an indirect address for jumping into
; the inline code for image erasing.
;
erase_height_vector_table label word ;there is no entry point for
; 0 lines. Starting at 2
; eliminates the need to store
; a dummy entry point address
erase_entry_address macro x ;this macro is used to generate
dw eline&x& ; the labels corresponding to the
endm ; inline code entry points
;
x=2
    rept 20
    erase_entry_address %x
x=x+2
    endm
;
erase_form_driver endp
one ends
end

```

LISTING 9: BYTBENCH.ASM

```

;This program benchmarks the byte-move driver.
;Link the byte-move form_driver/erase_form_driver
; module to this program.
;
stack segment para stack 'STACK'
    db 512 dup(0)
stack ends
;
one segment para public 'CODE'
    assume cs:one,ds:one,es:nothing
    extrn form_driver:near,erase_form_driver:near

```



```

;
iteration_count dw 0
;
;Lists describing image, location, and motion of 8 objects.
;
;pointers to form byte strings for each object:
form_address dw f0, f1, f2, f3, f3, f2, f1, f0
;the index for the last object in these lists:
highest_object_pointer equ (($-form_address)-2)
row dw 100,100,100,100,100,100,100,100 ;lines (0 - 198)
column dw 32, 32, 32, 32, 32, 32, 32, 32 ;in bytes (0 - 79)
row_increment dw -2, 2, 0, -2, 0, 0, -2, 2 ;lines (0 - 198)
column_increment dw 1, 1, 0, -1, 1, -1, 0, -1 ;in bytes (0 - 79)
left_margin dw 0, 0, 0, 0, 0, 0, 0, 0 ;byte # (0-79)
right_margin dw 76, 74, 72, 70, 70, 72, 74, 76 ;byte # (0-79)
top_margin dw 0, 0, 0, 0, 0, 0, 0, 0 ;line # (0 - 198)
bottom_margin dw 194,184,174,164,164,174,184,194 ;line # (0 - 198)
;
;Form byte structures, as follows:
; byte 1: # of scan lines in forms.
; byte 2: # of bytes per scan line of form.
; byte 3: first byte of image, followed by rest of bytes forming
; image, with bytes for top scan line, left to right,
; first, second scan line next, and so on.
;
f0 db 6,4
db 0f0h,00fh,0f0h,00fh
db 0f0h,03fh,0fch,00fh
db 0ffh,0ffh,0ffh,0ffh
db 0f0h,0ffh,0ffh,00fh
db 0f0h,03fh,0fch,00fh
db 0f0h,00fh,0f0h,00fh
f1 db 16,6
db 4 dup(6 dup(055h))
db 4 dup(6 dup(0ffh))
db 4 dup(6 dup(0aah))
db 4 dup(6 dup(055h))
f2 db 26,8
db 26 dup(0ffh,0aah,0aah,055h,055h,0aah,0aah,0ffh)
f3 db 36,10
db 9 dup(10 dup(0ffh))
db 3 dup(0ffh,0ffh,6 dup(0aah),0ffh,0ffh)
db 3 dup(0ffh,0ffh,0aah,4 dup(055h),0aah,0ffh,0ffh)
db 6 dup(0ffh,0ffh,0aah,055h,000h,000h,055h,0aah,0ffh,0ffh)
db 3 dup(0ffh,0ffh,0aah,4 dup(055h),0aah,0ffh,0ffh)
db 3 dup(0ffh,0ffh,6 dup(0aah),0ffh,0ffh)
db 9 dup(10 dup(0ffh))
;
start proc far
push ds ;set up for return to DOS
sub ax,ax ; through the instruction at DS:0 set
push ax ; up by DOS when it loads this program
cld
push cs
pop ds ;DS and CS are to be the same
mov ax,0b800h ;ES is to point to Color Graphics
mov es,ax ; Adapter's memory buffer
mov ax,0004h ;set 320x200 color mode
int 10h
;
;Set number of times to move all objects
;
mov [iteration_count],700 ;times to repeat move loop
;
;For each iteration, move each object in turn by erasing it,
; moving it one increment, and drawing it at the new position.
;
next_iteration:
mov si,highest_object_pointer ;start at last object
;
;Move each object in turn.
;
move_next_object:
;
;Erase the object at its present position.
;
push si ;save object index
mov bx,[si+row] ;get line at which to start erasing
mov cx,[si+column] ;get col. at which to start erasing
;get address of form for object to erase:

```

```

mov si,[si+form_address]
call erase_form_driver ;erase a rectangular area = to the
; dimensions of the object whose
; form is pointed to in SI
pop si ;restore the object index
;
;Advance the object's row and column and adjust increments
; so the object remains within its boundaries.
;
;If adding the row increment to the row would place it outside
; its margins...
;
mov ax,[si+row] ;test the new line position
add ax,[si+row_increment] ; to see if it goes outside
cmp ax,[si+top_margin] ; its limit
jb negate_row_increment ;if outside negate the
cmp ax,[si+bottom_margin] ; increment so that it will
jbe test_column_increment ; move towards its other limit
;
;...then make the row increment negative if positive and
; positive if negative.
;
negate_row_increment:
neg [si+row_increment] ;make it move in other direction
;
;If adding the column increment to the column would place it
; outside its margins...
;
test_column_increment:
mov ax,[si+column] ;if the column for the object
add ax,[si+column_increment] ; would go outside its left
cmp ax,[si+left_margin] ; or right limits, then
jb negate_column_increment ; negate its increment so
cmp ax,[si+right_margin] ; that it will move in the
jbe add_increments ; opposite direction
;
;...then make the column increment negative if positive and
; positive if negative.
;
negate_column_increment:
neg [si+column_increment] ;set to move in opp. direction
;
;Add the increments to the row and column to arrive at the
; object's next position.
;
add_increments:
mov ax,[si+row_increment] ;calculate next line position
add [si+row],ax ; and store it
mov ax,[si+column_increment] ;calculate next col. position
add [si+column],ax ; and store it
;
;Draw the object at the new location.
;
push si ;save this object index
mov bx,[si+row] ;find line and column number
mov cx,[si+column] ; at which to place object
mov si,[si+form_address] ;find address of object's form
call form_driver ;put object's image into screen
pop si ;restore the object index
;
sub si,2 ;point to next object to move
jns move_next_object ; if not done jmp to move it
;
dec [iteration_count] ;count down number of times to
jnz next_iteration ; move all the objects
;
;Reset the mode to 80x25 color text mode.
;
mov ax,0003h ;before returning to DOS,
int 10h ; set screen to 80x25 text mode
;
;Return to DOS.
;
ret ;return though instruction at
; start of PSP set up by DOS
start endp
one ends
end start

```


LISTING 10: BYTFRNGE.ASM

```
;This program benchmarks the byte-move driver with automatic
; erasure by a blank fringe.
;Link the byte-move form_driver/erase_form_driver
; module to this program.

;
stack segment para stack 'STACK'
db 512 dup(0)
stack ends
;
one segment para public 'CODE'
assume cs:one,ds:one,es:nothing
extrn form_driver:near
;
iteration_count dw 0 ;will hold # of times to move the objects
;
;Lists describing image, location, and motion of 8 objects.
;
;pointers to form byte strings for each object:
form_address dw f0, f1, f2, f3, f4, f5, f6, f7
;the index for the last object in these lists:
highest_object_pointer equ (($-form_address)-2)
row dw 100,100,100,100,100,100,100,100 ;lines (0 - 198)
column dw 32, 32, 32, 32, 32, 32, 32, 32 ;bytes (0 - 79)
row_increment dw -2, 2, 0, -2, 0, 0, -2, 2 ;lines (0 - 198)
column_increment dw 1, 1, 0, -1, 1, -1, 0, -1 ;bytes (0 - 79)
left_margin dw 0, 0, 0, 0, 0, 0, 0, 0 ;byte # 0-79)
right_margin dw 74, 72, 70, 68, 68, 70, 72, 74 ;byte # (0-79)
top_margin dw 0, 0, 0, 0, 0, 0, 0, 0 ;line # (0 - 198)
bottom_margin dw 190,180,170,160,160,170,180,190 ;line # (0 - 198)
;
;Form byte structures, as follows:
; byte 1: # of scan lines in forms.
; byte 2: # of bytes per scan line of form.
; byte 3: first byte of image, followed by rest of bytes forming
; image, with bytes for top scan line, left to right,
; first, second scan line next, and so on.
f0 db 10,6
db 2 dup(6 dup(000h))
db 000h,0f0h,00fh,0f0h,00fh,000h
db 000h,0f0h,03fh,0fch,00fh,000h
db 000h,0ffh,0ffh,0ffh,0ffh,000h
db 000h,0f0h,0ffh,0ffh,00fh,000h
db 000h,0f0h,03fh,0fch,00fh,000h
db 000h,0f0h,00fh,0f0h,00fh,000h
f1 db 2 dup(6 dup(000h))
db 20,8
db 2 dup(8 dup(000h))
db 4 dup(000h,6 dup(055h),000h)
db 4 dup(000h,6 dup(0ffh),000h)
db 4 dup(000h,6 dup(0aah),000h)
db 4 dup(000h,6 dup(055h),000h)
db 2 dup(8 dup(000h))
f2 db 30,10
db 2 dup(10 dup(000h))
db 26 dup(000h,0ffh,0aah,0aah,055h,055h,0aah,0aah,0ffh,000h)
db 2 dup(10 dup(000h))
f3 db 40,12
db 2 dup(12 dup(000h))
db 9 dup(000h,10 dup(0ffh),000h)
db 3 dup(000h,0ffh,0ffh,6 dup(0aah),0ffh,0ffh,000h)
db 3 dup(000h,0ffh,0ffh,0aah,4 dup(055h),0aah,0ffh,0ffh,000h)
db 6 dup(000h,0ffh,0ffh,0aah,055h,0,0,055h,0aah,0ffh,0ffh,000h)
db 3 dup(000h,0ffh,0ffh,0aah,4 dup(055h),0aah,0ffh,0ffh,000h)
db 3 dup(000h,0ffh,0ffh,6 dup(0aah),0ffh,0ffh,000h)
db 9 dup(000h,10 dup(0ffh),000h)
db 2 dup(12 dup(000h))
;
start proc far
push ds ;set up for return to DOS
sub ax,ax ; through the instruction at DS:0 set
push ax ; up by DOS when it loads this program
cld ;the form driver counts up
push cs
pop ds ;DS and CS are to be the same
mov ax,0b800h ;ES is to point to Color Graphics
mov es,ax ; Adapter's memory buffer
mov ax,0004h ;set 320x200 color mode
int 10h ;
;Set number of times to move objects
```

```
;
;number of times to repeat move loop:
mov [iteration_count],700
;For each iteration, move each object in turn by moving
; it one increment and drawing it at the new position.
;
next_iteration:
mov si,highest_object_pointer ;start at last object
;Move each object in turn.
;
move_next_object:
;
;Advance the object's row and column and adjust increments
; so the object remains within its boundaries.
;If adding the row increment to the row would place it outside
; its margins...
;
mov ax,[si+row] ;test the new line position
add ax,[si+row_increment] ; to see if it goes outside
cmp ax,[si+top_margin] ; its limit
jb negate_row_increment ;if outside negate the
cmp ax,[si+bottom_margin] ; increment so that it will
jbe test_column_increment ; move towards its other limit
;
;...then make the row increment negative if positive and
; positive if negative.
negate_row_increment:
neg [si+row_increment] ;make it move in other direction
;
;If adding the column increment to the column would place it
; outside its margins...
;
test_column_increment:
mov ax,[si+column] ;if the column for the object
add ax,[si+column_increment] ; would go outside its left
cmp ax,[si+left_margin] ; or right limits, then
jb negate_column_increment ; negate its increment so
cmp ax,[si+right_margin] ; that it will move in the
jbe add_increments ; opposite direction
;
;...then make the column increment negative if positive and
; positive if negative.
negate_column_increment:
neg [si+column_increment] ;set to move in opp. direction
;
;Add the increments to the row and column to arrive at the
; object's next position.
;
add_increments:
mov ax,[si+row_increment] ;calc the next line position
add [si+row],ax ; and store it
mov ax,[si+column_increment] ;calc the next column position
add [si+column],ax ; and store it
;
;Draw the object at the new location.
push si ;save this object index
mov bx,[si+row] ;find line and column # at
mov cx,[si+column] ; which to place the object
mov si,[si+form_address] ;find the addr. of object's form
call form_driver ;put object's image into screen
pop si ;restore the object index
;
sub si,2 ;point to next object to move
jns move_next_object ; if not done jmp to move it
;
dec [iteration_count] ;count down number of times to
jnz next_iteration ; move all the objects
;
;Reset the mode to 80x25 color text mode.
mov ax,0003h ;before returning to DOS,
int 10h ; set screen to 80x25 text mode
;
;Return to DOS.
ret ;return though instruction at
; start of PSP set up by DOS
start endp
one ends
end start
```


THE PROGRAMMER'S SHOP

helps save time, money and cuts frustrations. Compare, evaluate, and find products.

RECENT DISCOVERY

PC Scheme LISP - by TI. SCHEME has special, simple, "orthogonal" syntax. Lexical scoping, block structure, call by value, and tail-recursive semantics. Compiler, EMACS-like editor, DOS. Supports debugging, graphics, windowing. PC \$ 95

AI-Expert System Dev't

Arity System - incorporate w/C. PC \$295
 Experteach - Powerful, no limit on memory size. Samples PC \$399
 EXSYS - All RAM, Probability. Why. Trees. Solid. files. popular PC \$359
 1st class - by example, interfaces \$250
 Insight 1 - Probabilities, required thresholds, menus, fast (\$79)
 Insight 2 adds backward, forward, partitions, dB2, lang., access. MS \$399
 Others: APES (\$359), Advisor (\$949), ES Construction (\$100), ESP (\$845), Expert Choice (\$449)

AI-Lisp

List Our
 GC LISP Interpreter - "Common", rich, Interactive Tutorial \$ 495 Call
 GC LISP 286 Developer - 2 to 15 meg RAM, compiler & Interp. \$1195 Call
 Microsoft MuLisp 85 \$ 250 \$199
 TLC LISP - "LISP-Machine" - like, all RAM, classes, compiler. MS \$225
 TransLISP - Good for learning MS \$ 75
 WALTZ LISP - "FRANZ LISP" like, big nums, debug, CPM-80 MS \$149
 Others: IQ LISP (\$155), BYSO (\$125),

AI-Prolog

ARTIY Standard - full, 4 Meg
 Interpreter - debug, C, ASM PC \$ 350
 COMPILER/Interpreter-EXE PC \$ 795
 With Exp Sys, Screen - KIT PC \$1250
 MicroProlog - enhanced MS \$ 229
 MProlog - Improved, Faster PC \$ 475
 Professional MicroProlog MS \$ 359
 Prolog-86 - Learn Fast MS \$ 95
 Others: Prolog-I (\$365), Prolog-2 (\$1795)

FEATURE

OBJECT-ORIENTED Programming: with High Performance METHODS Smalltalk Language

METHODS is a powerful, language-compatible subset of Smalltalk-80™ that is ideal for software prototyping, simulation, databases, advanced user interfaces, and numerous AI applications. Over 100 classes and 2000 methods — easily-customized software building-blocks for rapid, incremental development of real-world applications.

An open-ended window environment that encourages exploration while allowing recovery from any error. Extensively documented in a four-part manual that addresses the needs of everyone from beginners to experienced programmers.

Methods also offers a communications interface that includes remote UNIX™ access, an object-oriented shell for DOS programs, and much more.

AND NOW...

GRAPHIC METHODS — all of the above, converted to bit-mapped graphics, plus...
 - Logo-style graphics using class "Pen"
 - Multiple fonts
 - Form editor, for freehand drawing with the mouse
 - Bit editor, for the creation or modification of icons, fonts, and other graphic elements
 - A new debugger with the ability to inspect and change variables and resume execution
 - Supports CGA, EGA, Hercules, and AT&T Hi-Res graphic controllers. Available after June 1st.

METHODS PCDOS \$239
 GRAPHIC METHODS PCDOS \$665

Free Literature Compare Products

Evaluate products. Compare competitors. Learn about new alternatives. One free call brings information on just about any programming need. Ask for any "Packet" or Addon Packet □ AI □ ADA, Modula □ BASIC □ C □ COBOL □ Editors □ FORTH □ FORTRAN □ PASCAL □ UNIX/PC or □ Debuggers, Linkers.

Our Services:

- Programmer's Referral List
- Compare Products
- Help find a Publisher
- Evaluation Literature FREE
- BBS - 7 PM to 7 AM 617-826-4086
- Dealers Inquire
- Newsletter
- Rush Order
- Over 700 products
- National Accounts Center

C Language-Compilers

BDS C - solid value, fast CPM80 \$125
 C86 by CI - 8087, reliable MS \$299
 Consulair Mac C w/toolkit MAC \$299
 ECP C/88 MS \$ 60
 Lattice C - from Lifeboat MS \$289
 Lattice C - from Lattice MS \$339
 Mark Williams - w/debugger MS \$399
 Megamax - tight full ATARI/ST \$179
 Microsoft C 3.0 - new MS \$259
 Q/C 88 by Code Works - Compiler source, decent code, cross/native MS \$125
 Wizard C - Lattice C compatible, full sys. III, lint, fast. MS \$379

C Language-Interpreters

C-terp by Gimpel - full K & R, .OBJ and ASM, large progs. MS \$249
 INSTANT C - Source debug, Edit to Run-3 seconds MS \$399
 Interactive C by IMPACC Associates. Interpreter, editor, source, debug. PC \$225
 Introducing C - learn C fast, self paced tutorial PC \$109
 Professional Run/C - Run/C plus create add-in libraries, load/unload them. MS \$199
 Run/C - improved MS \$109

C Support-Systems

Basic C Library by C Source \$139
 dBrief, the dBASE Assistant PC \$ 95
 dBase Tools for C Tools \$ 79
 PC Graphics \$ 79
 C Sharp - well supported. Source, realtime, tasks \$600
 C ToolSet - DIFF, xref, source \$135
 Lattice Text Utilities \$105
 The HAMMER by OES Systems \$179
 SECURITY LIB - add encrypt to MSC. C86 programs. Source \$250 PC \$125

C Libraries-General

Application Programmer's Toolkit MS \$375
 Blaise C Tools 1 (\$109), C Tools 2 \$ 89
 C Food by Lattice-ask for source MS \$119
 C Power Windows by Entelekon \$119
 C Utilities by Essential - Comprehensive screen graphics, strings. Source. PC \$139
 C Worthy Library - Complete, machine independent, source MS \$295
 Entelekon C Function Library PC \$119
 Entelekon Superfonts for C PC \$ 45
 Greenleaf Functions - portable, ASM \$139
 Polytron - for Lattice, ASM source \$ 85
 Software Horizons - Pack I PC \$129

C Libraries-Communications

Asynch by Blaise \$149
 Greenleaf - full, fast \$139
 Software Horizons - pack 3 \$119

C Libraries-Files

FILES: C Index by Trio - full B + Tree, vary length field, multi compiler
 /File is object only \$ 89
 /Plus is full source \$349
 dbVISTA - full indexing, plus optional record types, pointers, Network.
 Object only - MS C, LAT, C86 \$179
 Source - Single user MS \$459
 Source - Multiuser MS \$929
 CBTREE - multiuser record locking, sequential, source, no royalties MS \$ 99

FEATURE

ASSEMBLER PROGRAMMERS: Be an Expert and Take Out the Pain with the First Assembler Interpreter/Debugger ADVANCED TRACE-86

A complete, interactive, visual Assembler Interpreter/Compiler is integrated with a powerful debugger and editor to create, debug, rewrite, and test code. Increase understanding while you watch on your screen all aspects of the main processor (8088, 8086, 80286) and floating point processor (8087, 80287).

Instructions from a full screen of disassembled code can be single-stepped or run at other speeds while you watch registers, flags, the stack, and memory. Set or suspend breakpoints by: address range, label, or conditions. Toggle to the user screen to see the effects.

Add or delete program statements or directly change memory and registers to recarve your program while debugging — don't lose your ideas by waiting to assemble. Gone too far? You can even back up your program!

On-line help and demos help you learn quickly. Directly access DOS functions or the 8087/287's math functions and quickly see exactly what results are produced.

If you spend even a few hours with assembler code, whether your own or from a compiler, you deserve to get frustrations out of your way with Advanced Trace-86.



Morgan Computing Co., Inc.

PCDOS \$149

We support MSDOS (not just compatibles), PCDOS, Xenix-86, CPM-80, Macintosh, Atari ST, and Amiga.

THE PROGRAMMER'S SHOP

provides complete information, advice, guarantees and every product for Microcomputer Programming.

**ORDER TODAY
SPECIAL PRICE**

C-TREE by Faircom - portable, stable, thorough, balanced Btree file manager with source. MSDOS List \$395
ORDER BEFORE 6/30/86 and mention this ad for a special price of \$289.
ORDER AFTER 6/30/86 for \$349.

Editors for Programming

BRIEF Programmer's Editor - undo, windows, reconfigure PC Call
C Screen with source 80/86 \$ 75
EMACS by UniPress - powerful, multifile, MLISP. Source: \$949 \$299
Epsilon - like EMACS PC \$169
FirstTime by Spruce - Improve productivity. Syntax directed for Turbo (\$69), Pascal (\$229), or C (\$239)
Kedit - like XEDIT PC \$115
Lattice Screen Editor-multiwindow, multitasking Amiga \$100 MS \$125
PMATÉ - power, multitask 80/86 \$159
VEDIT - well liked, macros, buffers CPM-80-86. MS \$119
XTC - multitasking PC \$ 85

Atari ST & Amiga

We carry full lines of Manx, Lattice, Metacompco and Prospero.

Note: All prices subject to change without notice. Mention this ad. Some prices are specials. Ask about COD and POs. All formats available. UPS surface shipping add \$3/item.

MultiLanguage Support

BTRIEVE ISAM MS \$199
CODESIFTER - Execution PRO-FILER. Spot bottlenecks. MS \$109
Dan Bricklin's Demo Program PC \$ 75
HALO Graphics- Multiple video boards, printer, rich. Animation, engineering, business.
Any MS language, Lattice, C86 PC \$249
PLINK 86 - a program-independent overlay linker to 32 levels for all MS languages. C86 and Lattice. MS \$299
Pfinish Performance Analyzer by Phoenix MS \$299
Profiler by DWB Associates MS \$ 99
PS MAKE by UniPress PC \$129
Screen Sculptor - slick, thorough, fast, BASIC, PASCAL. PC \$109
ZAP Communications - VT 100, TEK 4010 emulation, file xfer. PC \$ 85

Xenix-86 & Supporting

Basic - by Microsoft \$279
Cobol - by Microsoft \$795
Fortran - by Microsoft \$399
PANEL Screen LIB - multi-language \$539
Xenix Complete Development System \$985

RECENT DISCOVERY

Synergy - Create user interfaces. TopView-compatible multitasking operating environment offers windows, icons, pull-down menus and fonts in 12K RAM. MS \$375

Fortran & Supporting

Forlib + by Alpha - graph, comm. \$ 59
Fortran >>> C-FORTRIX C creates maintainable translations. \$995
MACFortran by Microsoft - full '77 \$229
MS Fortran \$219
No Limit - Fortran Scientific \$129
PolyFortran - xref, pp, screen \$149
Prospero - '66, reentrant \$390
RM Fortran - enhanced "IBM Ftn" \$399
Scientific Subroutines - Matrix \$149
Statistician by Alpha \$269
Strings and Things - registers, shell \$ 59

Debuggers

Advanced Trace-86 by Morgan Modify code on fly. PC \$149
CSprite - data structures PC \$139
Periscope I - own 16K PC \$269
Periscope II - symbolic. "Reset Box." 2 Screen PC \$119
Software Source by Atron-Lattice, MS C, Pascal, Windows single step, 2 screen, log file. MS \$115
w/Breakswitch \$199
Pfix-86 Plus Symbolic Debugger by Phoenix - windows PC \$289

FEATURE

EXPERT SYSTEM DEVELOPMENT: Practical, Complete, and Unlimited Features Help Smoothly Build Expert Systems with EXSYS

EXSYS, Inc. has built a stable and complete toolkit by listening to users and examining what they need. One of the first Expert System Shells for the PC, EXSYS provides the features of just about all of its combined competitors, plus the documentation and examples you will need to learn in this field.

UNLIMITED FEATURES? EXSYS supports backward chaining of IF/THEN/ELSE rules, full math support, probabilities, explanations, the ability to call external programs including spreadsheets, database managers, or custom-written front ends with data passed to and from the external program, plus the ability to handle substantial applications of up to 5,000 rules. All user input is either English text, menu selection, or algebraic expression.

The systems developed can explain why information is needed and how it will be used. The ability to "change and rerun" allows expert system modelling of problems. Written entirely in C, EXSYS provides very high speed execution and efficient memory utilization.

But if these features are not enough, use the interface to Lotus, dBASE, BASIC, C, or any other .EXE or .COM file. Already in use at over 1,000 sites with many complex and powerful expert systems developed. Several expert systems have been marketed with a low-cost runtime license. Single computer use is only \$349. Unlimited runtime distribution is available for an additional \$539.

PCDOS \$349

FEATURE

PROVE CONCEPTS, Tighten Designs, or Quickly Create Demos with DAN BRICKLIN'S DEMO PROGRAM

Focus exclusively on what the user sees and does — with complete, flexible tools for fast and tangible results.

Show simulations of keyboard input and screen content by using Dan's editor and screen building tools. "Snapshot" screens created by other programs, use a prior screen to create a new one. Draw boxes, cut and paste any screen subset, control attributes like inverse video and color. Use the graphics characters available in the text mode.

Cause screens to branch in any sequence using labels. Give the demo user control. Print-control helps put your slide show to paper or disk in a variety of formats.

PCDOS \$75

FEATURE

PROGRAMMING TEAMS: Manage and Control Source Versions Efficiently with POLYTRON Version Control System (PVCS)

Duplicated efforts and time wasted rebuilding and cataloging source can be avoided. Reliably delegate control for source AND documentation to PVCS.

Save confusion and disk space by letting PVCS maintain the complete current version plus all of the increments, decrements, and related notes needed to rebuild any version. Maintains a complete history of changes. No experience with such a system is assumed. The documentation and examples will help you learn quickly. Privilege levels control access so the administrator knows who is working on each module. Now used in PC software development environments at Hewlett-Packard, Sperry, 3-COM, ROLM, and many more. Ask about discounts for LAN and multi-keyboard access.

POLYTRON PCDOS \$369

Call for a catalog, literature, advice and service you can trust

NEW HOURS
8:30 AM - 8:00 PM EST.

800-421-8006

THE PROGRAMMER'S SHOP™

128-P Rockland Street, Hanover, MA 02339

Mass: 800-442-8070 or 617-826-7531

486

"I have been pleased with your catalog selection, the knowledge of your telephone answering staff, and the promptness of your service. I have every wish to become a continuing customer of the Programmer's Shop.

Carl C. Rollo

Diary of an

I traded my 16K machine and all those disks for Lotus® 1-2-3 and 256K. And immediately got the urge to merge. I started by merging regional statements in Maine. But before I could get to Iowa, I ran out of gas.

At 512K, I discovered what the coordinates IV169 looked like. I was so far out there it felt like I was walking on the moon. It didn't take long to find out 512K was nothing more than a walk around the block.

640K! Loads of space until I fell in love with integrated software and was back to cutting up files again. Sure, the other functions make my worksheet more persuasive, but I'm back to slugging in and out disks. Shades of 16K.



Old war stories of how you fought your way up through the memory ranks are great to remember as long as you don't have to relive them. And you don't.

Thanks to one incredible breakthrough. Above™ Board PS.

Above Board is the memory board that drove the Lotus®/Intel/Microsoft® expanded memory specification, Infoworld's 1985 Peripheral Product of the Year.

From Intel. The company that has driven more standards than all of the other chip shops put together.


Above Board PS has the parallel and serial ports, clock, print buffer, and RAM disk you'd expect from a conventional multifunction board.

But why buy a conventional board when Above Board PS can take you from 256K all the way to 1.5 megabytes in one fell swoop, without even pausing for a breath at 640K.

So you don't need to hot-wire your way to the top anymore. With Above Board PS, the split worksheet is history. The new norm is windowing, pop-ups, and

overachiever.

I'm on my way to 1.5 MB and I'm not looking back. Monster spread-sheets, killer models, Microsoft® Windows, and all kinds of pop-up utilities so I can juggle a bunch of balls at once.



RAM speed on everything—even databasing and word processing.

The second-biggest difference between Above Board PS and conventional multifunction boards is the unconventional warranty on it. Five years instead of the usual two.

Ease of installation is nothing to sneeze at either. Its software installs with as few as three keystrokes. It even intelligently customizes your memory allocation.

Above Board PS is part of a family of products

for the IBM PC, XT, AT and compatibles.

You can buy them at your favorite computer store. Or call 800-538-3373 for the names of dealers near you.

And re-write the book on overachieving.

Help for the overachiever.

intel®

CIRCLE 216 ON READER SERVICE CARD

The 5251 Connection

Several good choices are available to the user planning to integrate IBM 5251 display station emulation into a PC-based system.

GERRY KAPLAN

The original IBM 5251 display station boasts a long-term relationship with System/3x computers. Although IBM has introduced more powerful models to the System/3x line and many new terminals, the 5251 continues to set the standard. Now the PC, PC/XT, or PC/AT can deliver all the power of the 5251 terminal with little more difficulty than installing an emulation board and its attendant software.

Twin-axial 5251 emulation products from AST Research, CXI, Digital Communications Associates, IDEAssociates, Quadram Corporation (and Ampak Business Systems), and Techland Systems are reviewed here. Table 1 provides a comparison of features among the products. (Remote 5251 emulation products are used much less frequently and are not reviewed here. Also note that while the System/36 is used as the principal focus, all System/3x workstations are similar in concept.)

The 5251 terminal does not appear to function the way the regular ASCII

terminal does. The most notable difference is speed: screen updates do not "slide" down from the top of the display, they appear all at once. More attribute combinations are available on a 5251 terminal than on the PC's monochrome display, as are a few innovative capabilities, such as column separators, which appear as very thin vertical lines that fit between each set of character positions in a field. The keyboard has the IBM Selectric feel and layout.

IBM extended the family of 5251-compatible terminals with the 5291, models 1 and 2 (functionally equivalent), and the 3180-2, with advanced features. The 5292, models 1 and 2, and the 3179-2 are similar to the 5291 and 3180, but with color; the 5292-2 provides bit-mapped color graphics.

The 5291/2 models have been ergonomically redesigned, with more tilt options and a display resembling the PC's. These terminals differ from the 5251 in that they have a PC-type keyboard instead of the Selectric-type. The

3180-2 workstation, like the 5291, is ergonomically designed, and it is the only 5250-family terminal that can display 132 characters per line instead of 80. The 3179-2 color display station is similar in operation to the 3180-2, except that it cannot display 132 character lines; it can, however, display text in seven high-resolution colors. The color displays support blinking and underlining as attributes for most colors.

Both the 3179-2 and the 3180-2 have a new 123-key keyboard; other terminals have 83 keys. The new keyboard has a softer feel than the PC-type, but it retains a tactile feedback. In addition, the 3179/80 models offer features not found on the other terminals, including keystroke save/play and the ability to set terminal settings from the keyboard.

THE RIGHT CONNECTIONS

Most small systems use ASCII terminals connected through an RS-232 port on the computer or on a modem (see figure 1). Each cable accommodates one





TABLE 1: *Features Comparison*

	AST-5251/11	AST-5251/11+	BLUELYNX CXI 5251-11	PCOX/5251	IDEA 5251	QUAD5251 (PC-MINI)	SMARTALEC 5291/92
CONFIGURABILITY							
Key click	○	○	○	●	●	○	●
Cursor type	●	●	○	●	●	○	●
5251 keyboard	●	●	●	●	●	●	●
PC-5251 keyboard	●	●	○	●	●	○	●
Customizable keyboard	●	●	●	●	○	○	●
Alternate addresses	○	○	○	○	●	○	● ^a
Foreign language keyboard	●	●	○	●	●	●	○
Custom printer	●	●	●	●	●	○	●
CGA support	●	●	●	●	●	●	●
EGA support	●	●	●	●	●	●	●
DISK STORAGE							
Floppy-drive access	●	●	●	●	●	● ^b	●
Hard-drive access	●	●	●	●	●	● ^b	●
Dual-monitor support	●	●	○	○	○	○	○
Modified CONFIG.SYS	○	○	○	○	○	○	●
PRINTER SUPPORT							
Host-addressable printer	●	●	●	●	●	○	●
Emulated printers							
5224	●	●	●	●	●	○	○
5225	●	●	●	●	●	○	○
5256	●	●	○	●	●	○	●
5219	○	○	○	○	●	○	○
KEYBOARD SUPPORT							
Keyboard macros	○	○	● ^c	○	●	○	○
3180 keyboard available	○	○	●	○	○	○	○
BUNDLED SOFTWARE							
Software security	●	●	○	○	○	○	○
On-line help	●	●	○	●	●	○	●
Automatic sign-on	●	●	○	○	○	○	○
Screen snapshot	●	●	●	○	○	○	○
File-transfer software	●	●	●	●	○	○	●
Low-level programmer interface	●	●	●	● ^d	●	●	○
COMBATIBILITY							
IBM FSU	●	●	●	●	●	●	●
IBM transfer facility	○	○	●	●	●	○	●
PC support	●	●	●	●	●	○	●
MISCELLANEOUS							
Session maintained through reset	○	○	●	○	○	○	●
Full 5251 display attributes option	●	●	○	○	●	○	○
DMA	●	●	○	○	○	●	○
Dual-ported RAM	○	○	●	●	●	○	○
EVALUATIONS							
Installation	Moderate	Moderate	Easy	Easy	Very easy	Moderate	Very easy
Configurability	Moderate	Moderate	Very easy	Very easy	Very easy	Very easy	Very easy
Speed of screen refresh	Fast	Fast	Very fast	Very fast	Very fast	Fast	Moderate
SPECIFICATIONS							
Memory required (KB)	256	256	23	36	36	16 mono./ 28 color	192
Number of local sessions	1 wrksn. 4 printer	7	4	4	4	1	7
Determining cable termination or pass-through	Jumper	Jumper	Jumper	Jumper	— ^e	Dip	On splice box
● = Good ○ = Bad — = Not applicable							
^a Bidding ^b One or the other ^c Maximum six-character length							
^a Not documented ^e On rear of card							

The speed of screen refresh is dependent almost entirely on the method a board uses to refresh its display; boards that use equivalent methods (whether dual-ported RAM or DMA channel and interrupts) are, in general, equally fast.

FIGURE 1: Asynchronous Terminal/Host Connection Scheme



Each connected device (whether a terminal or a printer) requires its own communication link (through dedicated cable or modem) to the host. The cost of each link must be justified by the use of its connected device alone.

terminal: a system with 12 terminals would have 12 cables running from the CPU. The System/36 uses twin-axial cable, which is similar to the coaxial cable used for cable television except that the twin-axial cable has two center conductors (hence the "twin").

Depending on the model, a System/36 has one or more twin-axial ports. Each port can address as many as seven workstations, each with its own address (0 through 6). (Each terminal has switches that determine the logical address to which it responds.) To attach several displays to the host, a cable is run from the CPU to the first terminal, another cable is run from that terminal to the next, and so on (see figure 2.) The maximum distance a terminal can be located from the host is 5,000 feet.

The 5251-12 workstation (for distances of more than 5,000 feet) connects to a modem rather than to the host and acts as a communications controller for as many as seven twin-axial devices through four separate twin-axial ports (see figure 3). An alternative approach is to use the 5294 remote control unit, which is similar to the 5251-12, but without any terminal facilities of its own—it is simply a workstation controller with a bisynchronous port for connection to a bisynchronous modem. The 5294 supports either four (model CF1) or eight (model CF2) additional terminals. One important difference exists between the 5294 and the 5251-12 workstations: the controller microcode within the 5294 is programmable; the 5251-12 microcode is in ROM. Some System/36 applications programs, including Displaywrite/36, that modify this microcode to provide additional display attributes and screen formatting options *cannot* be run from a 5251-12.

Most ASCII terminals operate in full-duplex character mode: when a key

is pressed, its ASCII value is immediately sent to the host; the host processes the key and echoes the character back to the display. The CPU must do all the "dirty" work such as validity testing or checking for the Enter key.

The System/36 uses a different approach. A specialized processor, the *workstation controller*, handles all I/O with its terminals. Visually, the System/36 terminals appear to be functioning in half-duplex block mode. This, however, is not the case. Terminal functions that reside entirely within smart terminals, such as the 3278, are divided here between the workstation controller and the relatively dumb 525x terminal. All terminal functions are managed directly by the workstation controller.

A typical interactive application observes the following sequence when it requires input from the user. First a screen format or *panel* is displayed containing all text descriptions or prompts the user will need in order to know what to enter. Special nondisplayable markers called *attributes* are included in the format that tell the controller where each input or output field is located and what type of data is to be put in that field.

When the panel is completely displayed, the user types the data into the fields; only when all the fields have been filled in should Enter be pressed. For most block-mode terminals, the logic for this functionality is located within the terminal's ROM. On the System/36 however, this logic is in microcode that is loaded into the workstation controller's memory at IPL. Thus the terminal appears to be checking the user's input while it is being typed.


To illustrate, consider a user who begins to type alpha data into a field that is designated for numeric characters only. The instant a non-numeric

key is pressed, the terminal will freeze up and indicate that the field requires numeric input. The operator must press the Error Reset key to continue. This error checking is performed by the workstation controller, not the terminal or the main CPU. So while it appears that the terminal is sending blocks of data to the System/36 at isolated intervals, in fact, the workstation controller and the terminal are in nearly continuous two-way communications while the user is typing in data. The communications protocol is IBM proprietary.


Further, because the controller handles all terminal I/O, the main system processor (MSP) is free to concentrate on other CPU-dependent functions. It is only when Enter or a command key (discussed below) is pressed that the information in the input fields is returned to the user program.

The keyboards on System/36 terminals have 24 command keys, which are analogous to the PC's function keys. On 3179/80 terminals, all 24 are mapped onto separate keys on the keyboard, similar to the double row of program function (PF) keys on the 3278. On earlier-model terminals, the command keys are mapped onto key combinations like the Ctrl and Alt combinations on the PC. Other keys have specific labeled functions: Roll Up, Roll Down, Print, Help, and Dup. An application can indicate to the workstation controller which of these keys are valid at a given time. If the operator presses an invalid key, the terminal will freeze and display a message to that effect. Error Reset must be pressed to continue.

All 5250-family terminals have *edge indicators*—originally, five lamps on the right side of the CRT screen. They indicate the state of toggle conditions in a manner analogous to the CapsLock and NumLock lamps on an AT keyboard for

FIGURE 2: *System/36 Twin-axial Connection Scheme*

Early IBM terminals have two ports for "pass through" connection to other terminals. More recent terminals and most emulation boards have only one port and use special T-connectors to pass through or terminate the cable as required.

FIGURE 3: *5251/12 Cluster Connection Scheme*

A 5251 model 12 can act as a remote workstation controller and support a total of seven twin-axial devices attached to it. Remote operation over a non-twin-axial line is required when more than 5,000 feet separate host and terminals.

System Available, Input Inhibited, Message Waiting, Keyboard Shift, and Insert Mode. In later terminal models, the lamps were replaced by small character blocks appearing on the screen itself, appearing and disappearing according to the state of their respective toggles.

POP AND PERFORMANCE TESTING

All of the products reviewed are twin-axial 5251 display station emulators. Testing the speed of these boards is difficult. However, because the transfer rate between 52xx terminals and the host is approximately one megabaud, normal screen refreshes should be very fast. This is difficult to judge by sight, so a program called POP, that uses the 5251's capabilities heavily, was run.

When POP (for Programmer and Operator Productivity Aid) was initiated, it first was requested to display all members in the current library. This results in a full-screen formatted directory of the library. Next to each library member name is a field for a special command. (A library member is a source or object code file.) Producing a screen format is *not* a simple matter of displaying 2,000 characters of text; rather, it is a complex dialog between the

workstation controller and the terminal itself. Because so many fields and so much text are printed, the terminal must receive a large amount of commands and text from the workstation controller. Remembering that the commands and text are being transmitted at one megabaud, this is a good way to test the PC's ability to keep up with so much work. A regular 5251 terminal would have no problems accepting such a load, and the text/fields usually would glide down from the top of the screen in about one second as the panel is constructed.

Testing a terminal's speed capabilities without the attributes was done by browsing through a library member, in this case, a COBOL source member. An initial impression in browsing through a member on a 5251 is that the terminal is memory mapped. No cursor movement takes place, and the screen appears to "punch" into view each time the Roll key is pressed. Not all of these emulation boards can handle the POP library directory and member browsing tests as quickly as a true 5251.

IDEA 5251 Emulator. This IDEComm 5251 local 5250 emulation package from IDEAssociates includes a twin-axial

interface board, twin-axial cable and connectors, a diskette containing emulation software, and a typeset manual.

Hardware configuration and installation of the IDEComm board is quite easy. One particularly nice feature is its handling of cable termination: a switch on the board bracket determines whether additional workstations are attached to the cable. Both the I/O address used by the card and the memory address for video storage are set by switches. The default I/O address is 368H, but it may be set to any in the range 0300H to 03FFH. The screen buffers are ordinarily stored at E000H, but may be relocated to any 400H block boundary in the range C000H to E000H, that is, C000H, C400H, C800H, etc. The manual provides textual and graphic explanations of installation.

Configuration is menu driven and flexible. Options include key click on/off, cursor type, and keyboard layout. Up to four local sessions are available and each session can be assigned an alternate workstation address in case the desired one is not available. The emulation software requires no changes to CONFIG.SYS; instead, it loads as a resident DOS extension. Upon invocation,

the software prompts for the desired System/36 address for each of the sessions, and, in about five seconds, confirmation (or denial) is received. If a workstation address is not granted, connection to another address is attempted. Two different keyboard mappings are available: the standard 5251 layout and a modified PC/5250 layout that makes better use of the PC's special keys.

The IDEAcmm system allows one of the four sessions to be a host-addressable printer, and several printer configurations are included with the software, along with a utility to produce a customized version. Emulated printers include the 5224, 5225, 5256, and 5219. The emulator's printer driver allows for System/36 background printing on the attached PC printer. When configured as an IBM 5224 or 5225, the PC printer supports their compressed printing and graphics capabilities.

Each session is an LU (logical unit.) Switching among the LUs is accomplished with a special command key. When a printer session is requested, a special menu is displayed giving the status of the attached printer. This menu offers the indicators and switches of the emulated printer, such as System Available, Ready, Error Check, and LPI (lines per inch) and CPI (characters per inch) indicators. This screen also allows the operator to suspend host printing so that the PC may reclaim the printer for its own output. Options are available to send a form feed, a line feed, or a Reset command to the attached printer.

Configuring the printer also can be accomplished through the software. A special screen allows the specification of command strings for special 52xx printer functions. The IDEA manual includes a table of the string specifications for several popular printers.

One complete section of the appendix is devoted to the technical details of the emulation system. Although it is aimed at advanced users, it shows how to write specialized software that can bypass the IDEA emulation package and control the emulation hardware and microcode directly. Memory maps are included, as is a thorough description of how to enable/disable the hot key—note that the hot key definition (Alt-L) cannot be changed. The software also supports keyboard macros.

For screen updates, very little difference is apparent between the IDEA emulation and a 5291 terminal. The IDEA board handled the POP directory and browse tests without incident.

The edge indicators on this product have been made more understand-

able than the normal 5291 status blocks. Rather than having the common II (Input Inhibited) block on the status line, IDEAcmm uses the plain English words *No Input* instead. Perhaps the only annoying feature of this product was its emulation of the 5251's column separator. When the host requests column separators, the IDEA software represents this with the PC's character 254 (a small block). This can become distracting on screens containing many fields and using column separators.

For users who require exact duplication of the 5251's display attributes, IDEAssociates makes the IDEAcmm 5251 D Monitor Adapter, which emulates all 32 of the 5251 display attributes. This adapter replaces IBM's Monochrome Display Adapter, including the printer port, and emulates it totally when the emulator software is not in control. When that software is active, 5251 session screen displays are identical to those of the 525x terminal family. This is a clever idea and a convenience for users who will not settle for something "almost like" the 5251.

T*he IDEAcmm software is fast. For screen updates, very little difference is apparent between this emulation and a 5291 terminal.*

The IDEA emulation software is compatible with many IBM file-transfer products, including IBM FSU on the System/34/36/38, IBM Transfer Facility on the System/3638, and PC support for System/36/38. The IDEAcmm package does not use DMA channel resources; therefore, it will not conflict with hard disks or other hardware that uses that facility. In spite of this, the IDEAcmm system is extremely fast, due mainly to its use of dual-ported RAM on the emulation board (this method is also used by CXI and Techland).

The IDEAcmm emulation package and Techland's BlueLynx were the only packages that included detailed information in their manuals for problem determination. This is complemented by IDEA with a special section containing descriptions of all error messages. **CXI PCOX/5251 TWINAX Emulator.** The CXI system includes a twin-axial interface board, a cable assembly that supports

cable through via a twin-axial T-connector, a diskette containing emulation software, documentation, and file-transfer software. PCOX/5251 can emulate a 5251, models 1 and 11, the 5291, models 1 and 2, and the 5292-1 with an attached 5224, 5225, or 5256 printer. In addition to the standard functions of the 5251/5291/5292, this emulator provides features not available on real 52xx devices. It can support up to four LU devices—four simultaneous host sessions or three host sessions and one printer session. A hot key switches the user from one LU to another.

Installation of the PCOX/5251 is simple. Even so, the user must decide if the factory settings for the screen memory address and I/O port addresses will cause conflicts with existing hardware. The default factory settings were used in this review and no hardware problems arose. The default I/O address is 368H, and, like the IDEA board, this may be reconfigured to any address in the range 300H to 3FFH. The screen buffer address defaults to D000H, and may be set to any 800H block in the range C000H to F800H. Cable termination is accomplished at the board level with a special jumper. Alternatively, an external cable terminator (not included with the package) may be used to accomplish termination. The PCOX/5251 does not use a DMA channel or dedicated interrupt vectors, therefore it will not conflict with hard- or floppy-disk drives. Once the card is installed and connected to the host, the remainder of the customization is achieved through configuration software.

The program allows for the selection of device types and addresses, as well as a variety of customizing options. Key click, in addition to keyboard layout and screen handling, can be customized via an options menu. Foreign language keyboards are supported: English/U.S., English/U.K., Austrian-German, French, Italian, Norwegian, Spanish, Swedish, and French-Canadian.

The CXI emulation software is not configured for any specific printer type. Special command strings can be defined during configuration that tell the emulation software what to send the specified printer when certain 52xx printer commands are received. Both CPI and LPI printer settings are defined in this manner. Color attributes also can be modified in the event that a non-IBM color monitor is used. EBCDIC/ASCII and color translation tables are modifiable for both the display and printer.

A unique feature of this board is its ability to intercept the System/3x Print

Adding 5251 communications to your PC is simply a matter of choice:



Complication

Introducing the PC/5251 MATE™ from Emerald Technology. Your single-board solution for PC-to-System/34/36/38 communications.

The new PC/5251 MATE includes everything your PC needs for synchronous communication with the System/3X host. It's a remote 5251-12 terminal emulator, a full-featured automatic dialer and a 2400 or 4800 bps modem— all on one economical card!


No need to grapple with separate components, tangled cables, questions about compatibility. Simply plug the MATE into your IBM PC, XT, AT or compatible and follow the menu-driven configuration routine. Then plug the phone line into the card— and that's it.

You're ready to send and receive system data. MATE's easy-to-use keystroke files can even automate the entire connection process!

To support MATE's modem and autodialer, we've included an enhanced version of SSI's popular PC/5251 PLUS™ terminal emulator software. It features a "hot key" between PC and emulator mode that won't disrupt communications, and the ability to use your PC printer as a system printer.

And MATE is fully compatible with SSI's Emulator Transfer Utility™— paving the way for speedy bidirectional file transfer with the host.

Best of all, MATE is backed by extensive technical support from Emerald Technology,



or integration.

the System/3X specialists. Call today for a dealer near you and discover how the PC/5251 MATE can take the complication out of communications integration.

(206) 462-8200

The best solutions. The best support.

Emerald
Technology Group Inc.

1601 116th Ave. NE, Bellevue, WA 98004 (206) 462-8200

CIRCLE NO. 121 ON READER SERVICE CARD

key and reroute print output to either the local PC printer or a disk file, instead of the System/3x printer device. This enables the user to press System/36 Print (which in the PCOX/5251 system is mapped onto the PC's F5 key) and have the screen image recorded to the PC printer or to a PC disk file.

The CXI emulation software is similar to that of the IDEAssociates package. The CXI board response to the host is extremely quick, and it handled the POP directory test and POP browse test with no problems. During emulation, the 52xx edge indicator blocks are replaced by words: instead of SA, like many other emulators, the CXI software prints the word System.

The PCOX/5251 emulation system includes CXI's file-transfer software (PCOX/5251 File Transfer) and allows the user to extract data from System/36 databases, copy library members to and from the System/36 and PC, and store PC-originated data in System/36 files for normal processing. It also allows the PC to retrieve print files from the System/36 for printing directly at the PC. CXI also claims its product is compatible with IBM's FSU and Transfer Facility.

The CXI technical staff appears to be very familiar with the product and its operation. The company maintains a toll-free information line.

Smart Alec. This emulation package from Digital Communications Associates (DCA) was by far the easiest of the packages to install and use. Smart Alec can emulate the 5251, 5291, and 5292 color display stations, as well as the 5256 printer. The package includes the emulator board, the 5291/92 emulation software, bidirectional file-transfer software for both the PC and the host computer, and a specially designed splice box that handles the twin-axial connection. The splice box is connected to the emulator board by a short length of cable, and has two twin-axial connectors. A switch located on the box determines whether the connected PC terminates the cable or if additional workstations are present down the line.

Another important feature: this emulator does not require a dedicated DMA channel or interrupt; thus, it will not conflict with LAN hardware, hard disks, or any device requiring either of these. On many of the other boards, the user must first choose the DMA channel (hopefully one that is not in use) and the appropriate interrupt level for the board (5 or 6 depending on PC or PC/XT). The board communicates with the emulation software through eight consecutive I/O addresses in the range

228H to 22FH. No alteration of these addresses is permitted without modification of source code. (The source code is provided; however, its modification is not a simple matter.)

As many as seven sessions can be emulated, with two printer sessions, and, on color monitors, Smart Alec supports two or seven user-selectable colors. The emulator also provides System/36 edge indicators displaying the status of the host, keyboard, and display. The user can choose to have the keyboard remapped in the usual 5291/92 layout or to a more familiar PC layout. No foreign language mappings are provided. As with all of the emulator boards, Smart Alec switches between DOS and emulation via a predefined hot key. DCA includes file-transfer software for transferring files between the emulator PC and the System/34/36.

Smart Alec offers an innovative feature called *address bidding*: several PCs,

T*he CXI board can intercept the System/3x Print key and reroute output to a local printer or disk file instead of the host printer.*

each with Smart Alec installed, can share a common System/3x workstation address. Under this feature, it is not necessary for each PC to have a dedicated workstation address as with normal terminals. This system thus allows access to the host for more than seven terminals. When any given PC requests an address, it first checks to see if another terminal sharing the address is already in use. If so, the requestor is not granted the address; it then can manually request a valid address.

For example, consider seven PCs that require intermittent access to the host. Each PC can be set up to use address 3, rather than each requiring sole use of one of the System/36's seven terminal addresses. While one PC is accessing the host, the remaining six are denied access until the active terminal exits emulation.

Smart Alec uses custom silicon chips designed especially for its application, thereby reducing the board's chip population. At the heart of the Smart Alec is a customized 8X305 CPU, a high-speed, on-board processor that manages

the System/3x protocol independently of the PC's processor. The 8X305 can maintain screen buffers for seven host sessions concurrently. This enables the PC to manage all sessions as well as full stand-alone processing activities simultaneously; as a result, the emulator is not required to be resident in PC RAM at all times to maintain host connection.

This package lets the user set up the terminal emulator so that it can be resident, transient, or automatically loaded at boot time. This gives the product a great advantage over cards that rely on the PC's hardware for processing power. If the PC becomes hung and must be warm boot, the Smart Alec hardware is not affected. It remains functional, and all sessions with the host are maintained. As soon as the emulation software is reloaded into RAM, emulation can continue as if nothing had happened. This is especially helpful when the PC being used for emulation is also used for development of PC applications that are prone to hanging the system.

Although its hardware documentation is not very detailed, the Smart Alec was the easiest installation to perform. One outstanding feature of this board is that the circuit card has no switches: all configuration is accomplished at the software level. Because the card has no jumpers or switches, it simply plugs into any unused full-length slot in the PC. The documentation does include details on cable connection.

Once installed, a menu-driven program takes the user through the configuration of any of the seven devices that are to be emulated. The Smart Alec can be configured to be simply a System/36 printer and not a workstation at all. At this point in configuration, the type of connection is determined. Smart Alec provides the option of having a session connected automatically or manually. If automatic connection is specified, the requested address becomes dedicated to that workstation, and, as soon as emulation is entered, the workstation is connected to the host and available. Using manual connection, the user must request to be connected to the host at the predefined address. If that address is already in use, no connection is made (see the earlier discussion on address bidding).

When emulation is started for the first time, diagnostics are run against the hardware. One notable diagnostic feature on the board is the three LED indicators across the top. These indicators point out the location of any hardware failures that render emulation in-

AUTHORIZED

Phoenix

COMPATIBILITY

**DART - The first CAD computer
with a super high performance
AT™ Compatible.**

**System 286 - The first high
speed AT priced below the
IBM XT™.**


The ADVANCED LOGIC RESEARCH computer has been tested for IBM compatibility with PHOENIX'S compatibility test suite using the PHOENIX AT-COMPATIBLE ROM BIOS, and the PC-COMPATIBLE ROM BIOS.

WE DON'T THINK YOUR PERFORMANCE SHOULD BE LIMITED BY THE 'STANDARD'

At ALR we don't think your performance should be limited by the 'Standard'. So preoccupied are today's computer makers with meeting the 'Standard', they seem to have overlooked the opportunity to do something much more worthwhile.


Namely, the concept of improvement beyond that 'Standard' acceptable level.

Examine the DART. The first CAD computer with a super high performance AT™ Compatible. The DART system is powered by a 10 MHz 80286 cpu with support for an 8 MHz 80287 math co-processor, when compared to the IBM® AT's 6 MHz cpu and 4 MHz co-processor, the DART system will process your next CAD design in almost half the time, with DIRECT ACCESS RESPONSE TIME (DART).




*Based on the Norton Utility SI-System Information Command.

Explore the opportunity of the System 286 - The first high speed AT below the price of an IBM XT™. The low cost of this system did not reduce the performance, with the cpu speed of 8 MHz and co-processor speed of 5 MHz. This System 286 is ready to calculate spread sheets and sort data base in a flash!




LIST PRICES AS OF APRIL 1986

The concept of having enough memory is misleading. It seems yesterday's 64K of memory was enough. Today, computers require at least 512K in order to run popular programs such as Symphony™ or Framework™. The result? ALR System 286 and DART system both have four times the memory capability built into its 'motherboard' so you don't have to pay for it tomorrow.



Option I/O device? That usually implies you need it and it costs more. ALR believes a computer needs to interface with at least a printer and in most cases modems, plotters and other computers, so we design our systems to include more standard I/O.



High performance and more features usually results in a more expensive system. However, the ALR System 286 and DART system does not match the 'Standard' price and this is one category we're glad to be considered 'sub-standard'.

Let one of our sales engineers or dealers show you the ALR System 286, DART system, Turbo XT and AT Hirise IBM compatible systems that are designed to limit your cost not your standard of performance.

CIRCLE NO. 199 ON READER SERVICE CARD
ADVANCED LOGIC RESEARCH, INC.
10 CHRYSLER
IRVINE, CA 92714
(714) 581-6770
ALR IN CANADA
416-229-6477
ENGINEERING ADVANCED COMPUTERS

ALR

operative: one light indicates whether the host is available, another whether the microcode in the Smart Alec's CPU is functioning, the third indicates errors on the communications lines.

Smart Alec has predefined hot keys for switching among emulated sessions. As noted, up to seven independent sessions can run concurrently on the host. The eighth session is a special information session that provides complete status of activity occurring on the twin-axial line. This session has indicators for communication errors and system availability, and others that show the current status of Smart Alec's CPU. In essence, this eighth display provides the same information that can be obtained from the LEDs on the card.

When the user switches to a printer session, a special screen is displayed that emulates all the switches and indicators on the 5256 printer console. This is the point at which the user can switch between on-line and off-line. Form-feed and line-feed requests also can be issued from this screen.

The Smart Alec emulation software is compatible with Laguna Laboratories' Decision Link bidirectional file-transfer software, the de facto file-transfer standard in the System/36 world. Smart Alec's program supports an unusually wide variety of data formats on the host and PC; among the types of files supported are ASCII text, BASIC sequential, BASIC random, DIF spreadsheet, Lotus 1-2-3 WKS, Lotus Symphony WRK, DOS print image, California Software's Baby/34/36, and binary image. It also supports user identification and log-on password security, read-only and write-only file protection, and downloading of print files from the System/34/36/38 to the PC printer.

Smart Alec's Enhanced File Transfer software, (available as a separate product) provides additional options for security, print spooling to the host, record selection, multiple file chaining, activity logging, and automatic control of processing through a control file. It includes a host data dictionary and a data query language for the PC. Data security is also quite extensive, providing password protection of data down to the record and field level.

The only disappointing feature of Smart Alec is its speed. It was the slowest emulator tested, and during the POP tests it resembled a terminal operating at around 9600 baud. The screens simply have no punch.

In the busy marketplace of 5250 emulators, the Smart Alec is a sound choice. It is packed with useful features,

but remains sufficiently hardware-independent to work properly on any PC in the IBM family and many close compatibles. The DCA technical personnel, who can be reached via a toll-free number, were knowledgeable and helpful about the product and its operation.

Quad5251 (PC-Mini). Quadram markets the Quad5251, which is actually the Ampak Business Systems PC-Mini 5251 emulation system. ABS markets PC-Mini under its own label. The two products are identical and are reviewed as one; for simplicity's sake, the product is referred to throughout as the Quad5251.

Quad5251, which allows the PC to emulate an IBM 5251-11 display, comes packaged with a printed circuit board, a twin-axial T-connector, and a disk containing emulation software. It is bundled with IBM 5250 emulation software and documentation in the original packaging. Only one interactive host session is supported, as well as one DOS session. Emulation switches between PC and terminal mode via a hot key. The

DCA's Smart Alec is a sound choice. It is very rich in features and highly hardware-independent, disappointing only in its speed.

PC printer is not host addressable, but the PC's PrtSc key is active and anything displayed as a 5250 screen can be printed on the local printer. Keyboard mappings for English/U.S., English/U.K., Spanish, Italian, French, and German are provided. Unlike the Techland product, this package offers no software API (application program interface) in linkable object modules; however, the IBM manual documents the program interface to emulator features through BASIC and assembly language.

This product's emulation software is a modified version of the archetype IBM 5250 emulation software. Originally, the IBM package supported only a diskette-based PC; the software was later modified to support the fixed disk drive, and access to the floppy disk was rendered inoperative.

Because the card uses an interrupt and a DMA channel, switches must be configured on the card to indicate which channels and interrupts to use. The board may use interrupt levels 5 or

6 and DMA channels 2 or 3. The reviewed card was preconfigured for a PC or AT (rather than an XT), so changes were necessary. Also, DMA/interrupt selection is accomplished through dip switches, which require close attention to the instruction manual to ensure correct settings. Terminate/cable through is also set from these switches.


Once all the jumpers and switches have been properly configured, installation is quite straightforward. The system is invoked by typing EMXT (for hard-disk-based PCs) or EM5250 (for floppy-disk-based machines). Because of the board's interrupt/DMA channel configuration, screen updates are fairly fast, but they scroll down in a rather jerky fashion. Boards that incorporate dual-ported RAM display a smooth scroll. The POP test showed the Quad5251 to be considerably faster than Smart Alec but slower than IDEA, CXI, or BlueLynx.

Although no file-transfer software is packaged with the Quad5251 board, an enclosed registration card entitles the user to Laguna Labs' Decision Link. The software is shipped upon receipt of the registration card.

The ABS PC-Mini supports FSU on the System/34/36/38 and IBM's EDL (executive data link) for CMAS and MAPICS on the System/36. PC-Mini is compatible with Ampak's Mini-Print utility (not included with the basic emulation package), which offers spooled, bidirectional transfer of printer or data files between the host and PC.

The PC-Mini/Quad5251 is not especially impressive. Its limitations on use of the PC's disk resources are severe. Quadram says that a new emulation board will become available that will allow unhindered access to all PC disk resources. It also will permit more customization, as many as seven sessions, and two host addressable printers. It will emulate the 5251-11, 5291, and a subset of the 3180.

AST-5251/11 and AST-5251/11 Plus. The AST-5251/11 from AST Research is a hardware/software product that enables the PC to emulate a locally attached 5251-11. It supports the 5251 model 11, 5291 models 1 and 2, and the 5292 model 1 color display, as well as the 5256, 5224, and 5225 printers. Two versions are available: the 5251-11 can emulate one display session and four printer sessions; the 5251-11 Plus can emulate any combination of six display sessions and four printer sessions as long as the total sessions do not exceed seven. The extra logic on the 5251 Plus resides on a piggyback board—this was the heaviest and bulkiest product reviewed.



MAKE THE CONNECTION . . .

Our **Connection** systems will solve your problem of trying to read and write diskettes or tapes from almost any computer system using your PC.

The **Diskette Connection** is a hardware system that enables the IBM PC or compatible to read and write most 8 inch, 5¼ inch, or 3½ inch diskettes.

With our **File Connection** software programs you can transfer data files between most computer systems, including CP/M, DEC, Honeywell, Univac, IBM 3740, S/1, S/3, S/23, S/32, S/34, S/36, and S/38.

Our **Word and Typesetting Connection** programs use IBM standard Document Content Architecture (DCA-RFT) to transfer document files between most word processing and typesetting systems, including Compugraphic MCS, CPT, Displaywriter, OS/6, Multiset, NBI, Quadex, Xerox, and Wang.

Our **Tape Connection** system will read and write IBM or ANSI standard ½ inch 1600 BPI magnetic tape. A full size 2400 foot tape can store a 45 MByte file and be written in 6 minutes.

Since 1982, we have supplied thousands of systems to customers around the world, including IBM, NASA, AT&T, Kodak, and General Motors.

Our specialty is conversion systems and we can provide a solution to your problem. Call us today to discuss your requirements.

This ad is one of a series featuring NASA missions. For a free poster, send us your written request.

Box 1970 Flagstaff, AZ 86002
(602) 774-5187 Telex 705609

CIRCLE NO. 107 ON READER SERVICE CARD

. . . FLAGSTAFF ENGINEERING

A predefined hot-key combination provides a simple sequence to switch from one emulation session to another; a second hot key switches between DOS and an emulation session. These hot keys cannot be redefined.

Card configuration can be accomplished at the hardware or software level. A configuration program is included to aid in configuring all aspects of the card, from display type to DMA channel selection. All hardware options can be set from software, but certain options can be set only from software.

The AST card has many features. One unique capability is control of the priority levels for printer operation. In other words, the attached printer may be given a lower priority than one of the emulated sessions (thus increasing the speed of the displays during print operations). A printer table that allows each emulated printer to have its own EBCDIC-to-PC/ASCII translation table is available (and it can be customized).

The keyboard also can be completely remapped—facilitating multilingual support and customized keyboard layouts. Several mappings are provided: Austria-Germany, Belgium, Brazil, Canada, French-Canadian, Denmark-Norway, France, Finland-Sweden, Italy, Portugal, Spain, Spanish-speaking, English/U.K., English/U.S., and English/U.S.-PC. This keyboard also supports both diacritic (which allows the entry of diacritical marks as a means of generating certain non-ASCII foreign characters) and hexadecimal mode.

The AST card lets the user apply password security to the emulation software: the emulation and configuration programs and the hot-key sequences are protected from unauthorized users. File-transfer software is included with the AST package, providing bidirectional data transfer with built-in data conversion. All translation tables (EBCDIC/ASCII and color) are configurable. The emulation software supports the saving of graphics screens when session windows are opened, permitting the emulator's use on graphics applications.

Keyboard macros can be defined to add features not generally found on 5251 terminals. Automatic sign-on macros also can be defined, thus giving configured display sessions the ability to move in sequence through multiple emulation tasks upon start-up. This function is not restricted to sign-on: as many as 250 key scan codes can be sent to the host (to submit batch jobs).

One excellent feature of the AST board is its ability to store "snapshots" of the display screens. In emulation

mode, as many as 10 display screens can be saved to PC memory. These snapshots can be recalled at any point during emulation. A screen dump program also is included, which will save all snapshots to a disk file. Also unique to this emulator is its ability to use dual monitors attached to the PC. This allows two sessions to be displayed simultaneously, with switching between them using a hot-key sequence.

Installation of this board is not for the novice. The manual is large and detailed in its description of hardware and software operation. Initially it appeared necessary to change switch settings on the board itself, but a closer study of the manual reveals that anything hardware configurable is also software configurable by a user with a technical background, and the manual provides extensive software configuration details. The DMA channel is preset to 1 and may be configured to 1, 2, or 3. The interrupt level is preset to 2, and may be configured to 2, 3, 4, or 5. Eight

T*he AST card enables the user to apply password security to the emulation and configuration programs and the hot-key sequences.*

consecutive I/O addresses are required. The default range is 250H to 257H; however, this can be reconfigured to use any of the ranges beginning at 250H, 350H, 450H, or 550H.

The AST board is fast, although it did not perform as well as other boards (particularly those emulators using dual-ported RAM for screen buffers) with the POP tests. The POP library directory test went well, but browsing through a library member was not as fast as with a true 5251 terminal.

BlueLynx 5251-11. Techland Systems produces this package. Included is a full twin-axial interface board, a diskette with emulation software, and a manual. The most advanced version of the product (III), is reviewed here. The other two versions (I and II) can be upgraded to the advanced levels. Upgrading is accomplished by replacing a ROM on the board, and instructions are included for this procedure.

BlueLynx remaps the PC keyboard to emulate the IBM 5251 keyboard. A

hot key switches the user between DOS and System/3x mode. One nice feature is that the hot key is redefinable on the PC and XT; on the AT, the System Request key is used as the hot key and may not be redefined. All three versions support IBM's Virtual Disk File Transfer Utility and Decision Link's 5251-11 file-transfer utility and query program; they are fully compatible with IBM's original 5250 local emulation package. The BlueLynx products include an API that permits access to various functions of the twin-axial board through assembly language programming. These functions are invoked in a fashion similar to regular DOS function calls. All versions also support Techland's ETU (emulator transfer utility). Techland sells an IBM-style 3180 model 2 keyboard as an extra-cost option that functions with all versions of BlueLynx 5251-11.

Version I supports only one LU. Version II supports everything in version I and includes support for two LUs: both can be configured as terminals or one can be configured as a printer. Version II has background print support, allowing host print jobs to continue printing after the user has returned to DOS. In addition, virtual disk support is available for each LU, enabling the user to create virtual DOS disks on the System/36 using facilities of the host FTU.

All features of versions I and II are supported in version III, which supports as many as four LUs. Support is also available for multiple virtual disks, allowing each LU to create its own independent virtual disk. Two PC serial and/or parallel printers can be configured as host-addressable printers. This version also includes routines for support of bar code readers, ticket printers, magnetic stripe devices, light pens, pointing devices, and data gathering/production control devices.

The Techland documentation is clear and precise. Although the emulation card comes with factory settings, the manual describes how to change the switch settings if necessary. Installation is accomplished in minutes. A very thorough diagnostic section is included in the appendix; this section is further divided for ease of use (display problems, printer problems, and so on). The BlueLynx board uses dual-ported RAM rather than a DMA channel, and therefore does not require special settings for use with the hard or floppy disks. This also tends to make the installation procedure less complicated because the user need not be concerned with the details of interrupt or DMA channel assignments. The product requires one



Now...**ALICE**: The Personal Pascal™ and TurboPascal

ALICE: The Personal Pascal. For the first time, you can quickly learn to program and go on to interactively develop, debug, and run sophisticated programs... all with one complete software system. And now you can compile and run your *ALICE** programs with TurboPascal! **CUT DEVELOPMENT TIME IN HALF** *ALICE*'s fully interactive "intelligent" editor actually checks your programs for errors as you type. And *ALICE*'s exclusive debugging environment contains a dynamic variable trace facility in the heart of the execution interpreter – no matter what variables you wish to follow, *ALICE* displays their status immediately. And with *ALICE*'s split window system, you can watch your program's output and

execution at the same time... and stop it when you need to make a change. For experienced programmers, *ALICE*'s interpreter is the most advanced source-level TurboPascal debugging tool.

LEARN PASCAL WITH *ALICE* For novice users, *ALICE* makes learning fun and easy with an "intelligent" editor and over 500 menu-driven Help screens that unfold when they are needed.

NOW WITH TurboPascal EXTENSIONS

- Turbo Graphics... faster and far easier to design with *ALICE*. And advanced screen swapping makes *ALICE* the best graphics debugging system available.
- Cursor Addressing... for the first time, single-step through the Turbo spread sheet using the advanced interpreter.

- Windows, strings, support for Turbo libraries including Turtlegraphics... and more!

Develop and debug programs with *ALICE* then compile and run them with Turbo... all from within *ALICE*'s ultimate programming environment... and at the touch of a single key!

To order call: **1-800-448-3400, ext. *ALICE***
1-800-387-9018 (In Canada)

\$95.00 (Canada: \$129.00)

Demo Diskette: \$4.95 (Canada: \$5.95)

ALICE

The Personal Pascal™

Now with Turbo extensions.

SOFTWARE
CHANNELS
INC.

A Graham Software Company

ALICE: The Personal Pascal is available for IBM PCs and compatibles running MS/PC-DOS. 256K memory required.

**ALICE* refers to *ALICE: The Personal Pascal*, which is a trademark of Graham Software Corporation.

TurboPascal is a trademark of Borland International Inc. IBM is a trademark of International Business Machines Corporation.

Dealers Contact:

INGRAM SOFTWARE, SOFTEAM, SOFTWARE RESOURCE

CIRCLE NO. 157 ON READER SERVICE CARD

(713) 359-1024 (U.S.) (416) 591-9131 (Canada)

I/O address, which defaults to 0368H and may be set to any value from 0300H to 03FFH. The dual-ported RAM segment address defaults to D000H, and may be set to any value between C000H and EC00H in multiples of 400H.

Configuration of the emulation software is menu driven and very simple. Many configurations are included that have escape sequences for various printers already defined (HP Laserjet, Toshiba, Epson, etc.). For predefined configurations, the user needs only to define which addresses are desired for each of the LUs.

The emulation system includes a mapping of the PC keyboard to the 5250 keyboard layout; however, the configuration program allows for complete customization of the keyboard. Foreign language keyboards also can be configured in this manner (although none is included with the package). This product emulates the IBM 5224 and 5225 printers (the 5256 printer is also emulated because it uses a subset of the 5224/5 command set). The BlueLynx configuration program includes a special printer customization section, allowing any printer to be set up for 5224 emulation, and thereby enabling the special printing capabilities of Displaywrite/36. Techland's BlueLynx also offers a snapshot feature.

The emulation software resides in only 23KB. However, the emulator hardware and connected sessions can be used in a limited way *without* the emulator software resident and running; this use is available only through the API from a specially written applications program and does not include interactive user sessions. The application must be loaded initially and run.

Sessions with the host are initiated normally. Once sessions are initiated, the PC may be reset using the Ctrl-Alt-Del combination, which removes the emulation software from memory. However, the microcode already has been loaded into the emulator's on-board Z80 processor, which maintains the sessions even through reboot. Any programs that use the API can be loaded and run and can access the host through the sessions initiated while the emulation software was resident.

The BlueLynx 5251 emulator performed well with the POP library directory test. No lag in performance was apparent in its display of the library members. Browsing through a library member also was very fast. According to Techland, its board was produced by the same company that manufactures the IDEAssociates board and the CXI

board, both of which also performed well in execution of the POP tests. The key design feature that is shared by all three products is the use of dual-ported RAM for screen buffers.

Techland Systems maintains a toll-free number for technical assistance on the emulation package. The personnel seem very knowledgeable about the product and its operation.

A 5251 CHOICE

In the case of 5251 emulation, more is not always better. Some users might assert the importance of being able to emulate seven different sessions, but many will find three to four sufficient. Being able to access two display sessions is helpful, thereby allowing each session to be editing different files; the user simply switches between them. The primary goal of 5251 emulation is for the PC to reproduce the functions and features of that workstation terminal as closely as possible. The user who has experienced a true 5251 terminal knows the solid feel and fast response as its performance hallmarks.

A most important criterion is the speed at which the screens respond to information transmitted over the twin-axial cable. The POP test usually can identify emulators that do not perform up to standard. If a product appears to emulate a 9600-baud terminal, users should think twice before purchasing it. Screens should respond as if they were memory mapped directly into the CPU's main memory.

The three best boards, the IDEA-comm 5251, the CXI PCOX/5251, and the BlueLynx 5250 are all made by the same company and all use dual-ported RAM instead of DMA channel and interrupts. Each of these boards offers outstanding performance, yet each adds some unique features of its own.

The other products perform acceptably from a speed standpoint, with the exception of DCA's Smart Alec. Yet, although it did not perform as well in these POP tests, Smart Alec probably would perform well on some IBM compatibles that run at clock speeds faster than 4.77 MHz. Moreover, Smart Alec is most likely to work on any IBM compatible in which it is installed, because it is the only board that operates without DMA, interrupts, or dual-ported RAM. Its only contact with the microcomputer is through eight standard 8088 I/O ports. In every aspect other than speed, Smart Alec is superior.

The System/36 is IBM's chosen hub for its departmental computing strategy. Many offices that are new to departmen-

tal computing have had PCs for a long time. The 5251 emulation products reviewed here allow users to retain their investment in PC technology while tapping the power of the departmental minicomputer, at minimal cost and disruption of office routines.



AST-5251/11: \$895
AST-5251/11 Plus: \$995
AST Research
2121 Alton Avenue
Irvine, CA 92714
714/863-1333
CIRCLE 344 ON READER SERVICE CARD

BlueLynx 5251-11 I, \$795;
II, \$945; III, \$1,045
Techland Systems
25 Waterside Plaza
New York, NY 10010
212/684-7788
CIRCLE 345 ON READER SERVICE CARD

CXI PCOX/5251 TWINAX
Emulator: \$895
CXI, Inc.
3606 W. Baysboro Road
Palo Alto, CA 94303-4229
800/225-PCOX; 415/424-0700
CIRCLE 346 ON READER SERVICE CARD

IDEA 5251 Emulator: \$895
5251D Monitor Adapter Card: \$495
IDEAssociates
29 Dunham Road
Billerica, MA 01821
800/257-5027; 617/663-6878
CIRCLE 347 ON READER SERVICE CARD


PC-Mini: \$895
Ampak Business Systems, Inc.
2640 Walnut Avenue
Tustin, CA 92680
714/731-4217
CIRCLE 348 ON READER SERVICE CARD

Quad5251: \$995
Quadram Corporation
One Quad Way
Norcross, GA 30093
404/923-6666
CIRCLE 349 ON READER SERVICE CARD

Smart Alec: \$895; file-transfer software, \$1,295
Digital Communications Associates
1000 Alderman Drive
Alpharetta, GA 30201
404/442-4000
CIRCLE 350 ON READER SERVICE CARD

Gerry Kaplan has been employed by IBM Corporation since he was 16. Now 23, he is a consultant and software developer specializing in the PC line, as well as the System/36.

RAMpage AT™-The Cure for




the AT Blues.



Doc plays sax down at Al's on Wednesday nights. That's blues night at Al's. And sometimes, if you shut your eyes and listen to that sultry, wailing music, you'd swear there's more than just one, lone sax playing. Doc knows his sax...been playing the same one over thirty years. And he plays it for all it's worth.

At AST we know the IBM® PC AT. We were the first to produce and ship an AT enhancement product. Like Doc's sax, your PC AT is a remarkable instrument with great potential. But if you're not using our RAMPage AT expanded memory solution, you're not playing it for all it's worth.



A Sure Cure For The AT Blues. Our RAMPage AT with up to 2 megabytes of RAM and DESQview™ multitasking/windowing software lets your PC AT soar to its maximum potential. And lets you realize your full AT investment value.

RAMPage AT For Multitasking Power. The RAMPage AT's powerful features combined with the PC AT's speed offer fast and functional multitasking capability.

Only with RAMPage AT can you sort a database, watch on-line stock quotations, calculate a spreadsheet, print labels and write a letter using your favorite word processing package...all at the same time...on the same PC AT. And with DESQview's windows you'll view and access up to nine applications instantly. You'll work faster and avoid time-consuming workflow interruptions.

Compatibility You Can Rely On. Our Enhanced Expanded Memory Specification is simply a more powerful, fully compatible version of the Lotus®/Intel®/Microsoft® (LIM) Expanded Memory Specification (EMS). With RAMPage AT you can use *All EMS Software*.



It's even certified compatible by Lotus Development for 1-2-3® Release 2 and Symphony® 1.1.

Powerful Features. RAMPage AT offers up to two megabytes of expanded memory that can also be used as extended memory, DESQview multitasking/windowing software, SuperPak™ utilities and our two-year warranty. Additionally, AST offers several models of the RAMPage AT-Pak, an optional module featuring serial, parallel and game ports.

Play Your AT For All It's Worth With RAMPage AT. For more information call our Product Information Center (714) 863-1480. Or send the coupon to AST Research, Inc., 2121 Alton Avenue, Irvine, California 92714-4992.

RAMPage AT and SuperPak trademarks of AST Research, Inc. IBM registered trademark of International Business Machines Corp. DESQview trademark of Quarterdeck Office Systems. Lotus, 1-2-3 and Symphony registered trademarks of Lotus Development Corp. Microsoft registered trademark of Microsoft Corp. Intel registered trademark of Intel Corp. The RAMPage AT Expanded Memory Board has successfully passed compatibility testing with 1-2-3 Release 2 and with Symphony 1.1 on an IBM AT with PC-DOS 3.1. Two megabytes of memory were installed. The Lotus logo is used by permission of Lotus Development Corp.

AST

RESEARCH INC.

Copyright © AST Research, Inc., 1986. All rights reserved.

CIRCLE NO. 110 ON READER SERVICE CARD

Yes, I want the cure for the AT blues. Please send me more information about RAMPage AT.

Name

Title

Company

Address

City

State

Zip


Phone

AST Research, Inc., 2121 Alton Avenue, Irvine, CA 92714-4992.

PCTR/AT-B1



TELECAT 286



PC/AT
TELECAT 286
PC/XT

Size Performance Price

TeleVideo

AT performance at an XT price. Introducing the TeleCAT-286. \$2995. Complete.

With TeleVideo, you always settle for more.

Up till now, with a mid-range budget, you had to settle for mid-range performance. And a mid-range set of features.


But not anymore. Because now, there's the new TeleCAT-286™ from TeleVideo. An IBM AT-compatible machine that lets you settle for an entirely new concept in medium-priced PCs: more.

More Performance.

The TeleCAT-286 retails for \$2995, roughly the same as a comparably-equipped IBM XT. But the similarity ends there. Instead of starting you off with a stripped-down box, we've loaded up the TeleCAT-286 with 512K RAM. A 20MB hard disk. A 1.2MB floppy. And everything else you need. Like an Intel 80286 CPU that runs at either

28% Smaller Footprint:

What you do with the extra desk space is up to you, but as you can see here, the TeleCAT-286 gives you a lot more of it than the IBM AT.



6 or 8 MHz clock speed. There's even a high-resolution monitor for text and graphics.

To make even better use of internal space, we socketed the TeleCAT-286 for one MB of RAM, and also included serial and parallel ports on the motherboard. As a result, we can still

give you three extra expansion slots.

More Productivity.

Using our experience in building terminals and systems for 750,000 users worldwide, we've designed a machine that's the last word in ergonomics. With

LEDs On Locking Keys:

For maximum visibility, we put our LEDs right on top of the three critical locking keys, so they won't get covered up by overlays.



sculptured keycaps on a high-quality keyboard. LEDs on the three critical locking keys. And a footprint that's 28% smaller than the IBM AT's. So you get more of your desk back, too.

Find Out Even More: 1 (800) TELECAT.

There's a whole lot more we could tell you about the TeleCAT-286. But it's an even better idea

to get your hands on it. So call us at 1 (800) TELECAT, Dept. 203, and we'll tell you the nearest place you can try one.

The TeleCAT-286. Our 20MB version is \$2995; 30MB, \$3495. For high performance at a low price, don't settle for less.

 **TeleVideo®**
Settle for more.

TeleVideo Systems, Inc. 1170 Morse Avenue
Sunnyvale, California 94088-3568 • (408) 745-7760

©1986 TeleVideo Systems, Inc. IBM is a registered trademark of International Business Machines, Inc.
Screen graphics by Chartmaster ©Decision Resources, Inc.

Approaching the Optimum Pascal

The latest round of Pascal compilers has brought the language close to maturity. With few exceptions, the seven implementations reviewed here live up to Pascal's reputation for facilitating supportable, structured program design.

JEFF DUNTEMANN



BEGIN

As recently as two years ago, Pascal was still an evolving language, just breaking the bonds with its creator, Niklaus Wirth, who had designed the language to teach—and nothing more. A *PC Tech Journal* review of Pascal compilers at that time (see “Pascal Times Four,” Jeff Duntemann, July 1984, p. 58) concluded that while the products exhibited many strengths, they had an unfinished feel to them. Two of the products reviewed in 1984—Digital Research’s Pascal/MT+86 and Software Building Blocks’ SBB Pascal—have fallen into limbo or disappeared entirely. The others—IBM/Microsoft and Turbo Pascal—have been updated and are included for review here. This is a reflection of the winnowing process that has been under way in the industry at large for more than a year.

Today with a few exceptions, Pascal compilers and interpreters are mature, clean, useful products. Seven are re-

viewed: IBM Pascal, Microsoft Pascal, Mystic Pascal from Mystic Canyon Software, Professional Pascal from Microtec Research, Turbo Pascal from Borland International, UCSD Pascal from Pecan Software Systems, and Utah Pascal from Ellis Computing. IBM and Microsoft Pascal are different releases of the same underlying product and therefore have very similar features.

To be reviewed here, a Pascal compiler must meet these guidelines:

- It must run under DOS. UCSD Pascal was not reviewed in 1984 because its environment, the p-System, was its own operating system at that time; today, the p-System is a shell running over DOS, and its compiler includes an 8086 native code generator.
- It must be a fully vendor-supported product with telephone support available either free or on a subscription basis. User-supported or public-domain compilers are not included.

Pascal/MT+86 is not reviewed because DRI no longer supports it via telephone. (DRI claims it will support the product through the mail.)

- It must be intended primarily for software development rather than the teaching of Pascal. The three teaching products, Alice Pascal by Software Channels, Exploring Pascal from Ash-ton-Tate, and WATCOM Pascal, are described in the accompanying sidebar.
- It must be generally available to end users and cost no more than \$1,000. OEM-only or bundled Pascal compilers are not included.

THE PORTABILITY PROBLEM

Pascal suffers from the lack of a useful standard. While two standards exist, ANSI/IEEE 770 X3.97-1983 and ISO 7185, neither specifies a language in which commercial software can be developed. Wirth’s response to early criticisms of Pascal’s incompleteness was



END

not to improve Pascal but to present Modula-2 as an alternative. In the meantime, Pascal has been filled out to commercial usability by its implementors, each with a slightly different philosophy. It is thus the least portable of the major programming languages.

Two different kinds of portability are involved. One, which could be called *vertical portability*, is concerned with a given program source compiling identically under different Pascal compilers. As anyone who has tried to convert a complicated program from MS Pascal to Turbo Pascal will attest, vertical portability can be approached but rarely achieved. *Horizontal portability* is identical compilation across different machine environments, such as the IBM PC under DOS, an AI workstation running UNIX, or a VAX minicomputer running VMS. Horizontal portability would seem more difficult than vertical, because it must address fundamental differences between computers and operating systems, but it has actually been accomplished by clever work on the part of several vendors, most notably Pecan Software Systems.

In practice, roadblocks to Pascal portability involve both horizontal and vertical elements. The best example is in file support. Standard Pascal defines a reasonable identity to only two files, Input and Output. No facility exists for connecting a logical to a physical file; an assumption is made that when the program takes control of the machine, operating system primitives have already connected Input and Output to physical files. Logical files can be created within a program using the Rewrite command, but connecting the new logical file to a physical file is left to the operating system and cannot be done under program control.

Files cannot be opened for update in standard Pascal. A file opened for input is considered read-only; a file opened for output is cleared of all previous contents. Standard Pascal has no random file support and no way to close a file. No provision is made for trapping file system errors. Remarkably, no provision whatsoever is made for separate compilation or libraries. Variable-length string processing is another omission. Screen formatting support is absent, aside from a method of specifying a field width for the display of variables. Note that these are not merely niceties but essential elements in the creation of commercial software.

Obviously, Pascal portability cannot be achieved by close attention to an established standard, as is possible with

COBOL and FORTRAN. Extensions are required to get the job done. Pascal developers must decide how important portability will be to their applications and act accordingly. Developers whose market is solely within DOS might be interested in maintaining some measure of compatibility across several different compilers in case the vendor of their development compilers goes bankrupt or abandons the product.

Vertical portability can be approached by isolating nonstandard language functions in a separate set of procedures and functions that can be identified as a group, perhaps as a library or a source code include file. Then, in moving a program from one compiler to another, the majority of coding changes can be confined to the library or include file.

Programmers developing an application for a narrow, vertical market must try for horizontal portability as well. While IBM hardware may have an

Pascal has been filled out to commercial usability by its implementors, each with a slightly different philosophy. It is thus the least portable of the major languages.

overwhelming penetration of the overall business market, within a narrow niche the mix can be highly unpredictable, and supporting more than one operating environment may mean the difference between a product that will succeed and one that will not.

Horizontal portability is best achieved by coding in a dialect of Pascal supported by the same vendor in each desired machine environment. Microsoft Pascal is available for both DOS and XENIX, and Turbo Pascal supports DOS, CP/M-86, and CP/M-80. UCSD has made horizontal portability its trademark by supporting nearly every microcomputer in common use, as well as several minicomputers and a few mainframes (see table 1).

EVALUATION CRITERIA

At the highest level, software is evaluated by asking two questions: how well does the software achieve its own goals and how well does it satisfy the needs

of a given audience? For the purpose of this review, the audience is the professional applications developer who creates software either for sale or for internal company use. Pascal is viewed primarily as an applications language—that is, the ability of a compiler to generate device drivers is less important than its ability to handle files efficiently and numeric values accurately. Professional systems programming, on the other hand, is nearly always done in assembly language or C.

Keeping these factors in mind, this review evaluates Pascal compilers based on the following criteria.

The shape of the system. To the traditional filter-type compiler/utilities package has been added the integrated programming environment: a single program incorporating a text editor, compiler, and associated utilities, all designed to work together seamlessly in pursuit of greater programmer productivity. Mystic, Turbo, and UCSD Pascal follow this model; the others are filters.

The advantage of a filter-type compiler is that it can be called from batch mode. This is especially critical when separately compiled applications expand across many modules and the link step becomes complex. IBM, MS, and Professional Pascal work well from batch mode, but Utah Pascal, while a filter-type compiler, has a proprietary interactive linker that cannot operate from batch mode—thus giving it the worst of both worlds.

An environment must be able to switch quickly between utilities or it loses much of its advantage. UCSD Pascal suffers here, because it must load its utilities from disk (rather slowly, in fact) and run them. Mystic and Turbo Pascal are entirely RAM-resident and move among screens instantly.

Another issue is the power available from within the environment. An environment must either allow access to DOS utilities or provide reasonable power on its own. UCSD Pascal has the ability to execute p-System programs (but not DOS programs) from within the environment. Mystic and Turbo Pascal lack this ability. Hot-key invoked RAM-resident utilities, such as Software of the Future's WindowDOS, make this problem less limiting than it once was. **Generated code options.** All the compilers tested except Utah Pascal are able to generate native 8086 code. Intermediate code, the primary option of UCSD Pascal and the sole option of Utah Pascal, offers compactness and portability but requires the presence of an interpreter at runtime. If the cost of this interpreter

TABLE 1: Features Comparison

	IBM	MS	MYSTIC	PRO.	TURBO	UCSD	UTAH
VERSION	2.0	3.31	1.5B	2.5	3.01A	4.4G	4.1
PRICE	\$385.00	\$300.00	\$16.00/ \$32.00 ^a	\$595	\$69.95	\$79.95	\$39.95
COMPILER SHAPE AND OPERATION							
Compile from batch mode	●	●	○	●	○	○	●
Full screen support	○	○	○	○	●	●	○
Graphics support	○	○	○	○	●	●	○
Large memory model	○	●	○	● ^b	○	—	—
Native code generator	●	●	●	●	●	●	○
.OBJ file generator	●	●	○	●	○	○	○
Overlays	●	●	○	●	●	●	○
Produces stand-alone program files	●	●	○	●	●	○	○
Separate compilation	●	●	○	●	○	●	●
Text editor	○	○	●	○	●	●	○
NEC processor support	○	○	○	●	○	○	○
186/188 and 286 optimizations	○	○	○	●	○	○	○
NUMERIC SUPPORT							
8087 detection	●	●	○	●	○	○	○
8087 support	●	●	○	●	●	●	○
BCD math	○	●	○	○	●	●	○
BYTE type	●	●	○	○	●	○	○
Long integers	●	●	○	●	○	●	○
Unsigned integer (WORD type)	●	●	○	●	○	○	○
FILE SUPPORT							
Path support in file I/O	●	●	●	●	●	●	○
Random files	●	●	●	●	●	●	●
Open for update	●	●	●	○	●	●	●
DATA EXTENSIONS							
Conformant arrays	●	●	○	○	○	●	○
Procedural parameters	●	●	○	●	○	●	○
Variable-length strings	●	●	○	●	●	●	●
FLOW OF CONTROL							
BREAK statement	●	●	○	○	○	○	○
Concurrent processes	○	○	● ^c	○	○	●	○
CYCLE statement	●	●	○	●	○	○	○
In-line machine code	○	○	○	○	●	○	○
Interrupt procedures	○	●	○	●	○	●	○
LOW-LEVEL SYSTEM HOOKS							
Absolute memory access	●	●	○	●	●	○	●
Absolute variables	●	●	○	○	●	○	○
Command line access	●	●	—	●	●	—	○
DOS calls	●	●	○	●	●	●	●
DOS condition code return	○	●	○	●	●	●	○
Interrupt calls	●	○	●	●	●	○	○
Port I/O	●	○	○	○	●	○	●
ENVIRONMENT							
Disk space required	720KB	720KB	360KB	4MB	360KB	720KB	360KB
RAM required	256KB	256KB	256KB	512KB	64KB	128KB	128KB
Link-compatible HLLs	IBM FORTRAN	MS C, FORTRAN	None	Hi-C	None	UCSD BASIC, None FORTRAN	None
Environments supported in addition to DOS	None	XENIX 286	None	VAX/VMS, UNIX	CP/M-86, CP/M-80	— ^d	CP/M-80 ^e

● = Good ○ = Bad — = Not applicable

^a \$16 for documentation on disk; \$32 for printed documentation^b Also supports small, compact, medium, and big memory models^c Not fully implemented in this release^d Amiga, Atari ST, VAX/VMS, UNIX System IV, DEC RT-11/TSX/RX/RSTS, MSX, Stride, IBM Displaywriter, Altos, and others^e The CP/M-80 version of Utah Pascal is currently sold as Nevada Pascal

Memory model is difficult to define for interpreted products. Likewise, programming environments are not command-line driven, so command-line access is undefined for programs that are executing within an environment.

WHEN YOU NEED ACCESS TO FULL MEMORY, STRUCTURE, COMPATIBILITY WITH GW- & PC-BASICA, OR WHEN YOU NEED THE POWER AND FLEXIBILITY OF C OR PASCAL...



... You need BetterBASIC. The BetterBASIC compiler has become the standard by which other BASICs are evaluated. BetterBASIC is completely compatible with GW-BASIC and PC-BASICA when running on IBM PC's and true clones. You can load and run your existing BASIC programs in BetterBASIC. It uses standard MicroSoft syntax and gives you more than 150 additional statements such as XREF, DEFINE WINDOW, MAKE MODULE, and PROCEDURE. In benchmark comparisons, BetterBASIC is five times faster than interpreted BASIC. There is optional 8087/80287 math chip support, and an optional Runtime System to create stand-alone

EXE. files. BetterBASIC is not copy protected. Technical support is provided for all registered users.

See for yourself why Dick Aarons of *PC Magazine* said "BetterBASIC may be the best of all BASIC programming worlds" and selected BetterBASIC as "Editor's Choice" (Oct. 29, 1985).

BetterBASIC	\$199
8087/80287 Math Chip Support	\$99
Runtime System	\$250
Sample Disk with Tutorial	\$10

Ask your dealer
or call to order:

1-800-225-5800

In Canada, call 416-469-5244

Better
BASIC

BetterBASIC is a registered trademark of Summit Software Technology, Inc. IBM PC, XT, AT are registered trademarks of International Business Machines Corp. Microsoft is a registered trademark of Microsoft Corp. Tandy is a registered trademark of Tandy Corp.

CIRCLE NO. 195 ON READER SERVICE CARD

Summit Software Technology, Inc.™
106 Access Rd. Norwood, MA 02062

is high, then developing applications under the compiler in question can end up being uncompetitive.

For the native code generators, the 8086 provides several memory models, which are ways of arranging code and data relative to machine registers. The small model (as seen in Turbo Pascal) limits usable RAM and makes large applications impractical. The majority of the compilers provide some sort of large memory model allowing most or all of RAM to be used, but only Professional Pascal allows a choice of models.

Other considerations are support for the 8087 or 80287 coprocessor and a linkable object format. All compilers except Mystic and Utah Pascal support the 8087/287 in some fashion. UCSD and Utah Pascal have proprietary linkable formats available only to themselves. (UCSD Pascal will link, however, with other p-System compilers.) Only IBM, MS, and Professional Pascal support Microsoft's standard .OBJ format.

Performance. Compile speed must be considered in relation to the value of the programmer's time. Turbo Pascal was designed to optimize the development cycle for speed; no other product comes close to its speed for the writing and testing of code. On the other hand, a slow compiler must generate excellent code, with intelligent optimization and access to all available machine resources. Finally, reliability is extremely important. With the exception of Mystic Pascal, all of the compilers reviewed produce very reliable code.

Numeric support. Pascal is widely used in scientific programming, so richness of numeric support is important. To the standard integer and real types have been added unsigned integer (Word or Cardinal) types and the unsigned 8-bit integer subrange (Byte) type. Several compilers provide long (usually 32-bit) integer types, and UCSD Pascal has a variable-precision integer offering up to 36 significant figures.

The precision and range of implemented real types vary widely; attention should be paid to whether a compiler supports the IEEE standard real number formats. Some speed can be gained in real operations by implementing real numbers in fewer bytes than the widely used 8-byte IEEE real. Turbo Pascal's standard real is 6 bytes, and Microsoft offers a fast 4-byte real as an option.

Finally, business programming requires some means of expressing very large values (these days, up toward the trillions) with absolute precision. Most compilers provide binary-coded decimal (BCD) math of some sort, typi-

cally as a proprietary real number format stored as a fixed-point decimal rather than floating-point value.

File support. Pascal's standard file support is notoriously minimal. As mentioned earlier, portability of file code is difficult, and close attention must be paid to the syntactic details of file access. Some de facto standards have emerged, including the Seek procedure for random I/O, but similarities appear mostly in the broad strokes; quirks and nonstandard extensions abound.

All compilers except Professional Pascal can open a file for update—that is, for write after read. Turbo and UCSD have untyped file support for reading files as blocks of raw data. Usable applications require that file status information be communicated to the program from the operating system. Most compilers can report errors from the operating system. Only a few can report in any detail what went wrong.

Variable-length string handling. Conveniently representing text within a program is next to impossible without support for variable-length strings. UCSD Pascal set a strong and early standard

When compared to other programming languages, the quality of a typical Pascal compiler's documentation is very good indeed.

with its scheme, in which strings are arrays of characters with a leading length byte reflecting changes in the logical length of the string as various operations are performed on it. UCSD's suite of string primitives has been imitated by some compilers, including Turbo and Utah Pascal. MS and Professional Pascal implement similar string types and functions, but their syntax is significantly different. Only Mystic Pascal lacks variable-length strings.

Separate compilation. Once a program grows beyond a few thousand lines, efficient development becomes exponentially more difficult without separate compilation. The power of a separate compilation scheme can be a limiting factor in the size and complexity of an application. A scheme that is compatible with Microsoft LINK can avail itself of third-party linkable libraries that are targeted for MS Pascal.

Most compilers that support separate compilation use some variation on a system pioneered by UCSD Pascal and adopted to some extent by Wirth's Modula-2. This is the *unit* concept, in which a compiland has two source modules: an interface part giving explicitly public identifiers and calling syntax, and an implementation part containing the actual private code and data definitions. Beyond this, a good scheme should address the problem of identifier name conflicts across independent linkable libraries created in ignorance of one another. By far, the best such system is Professional Pascal's.

Overlays are often implemented as a variation of separate compilation. Units in UCSD Pascal may be loaded on demand. Turbo Pascal's overlay scheme, which is the closest the product comes to separate compilation, enables a small-model program to incorporate (at least theoretically) as much code as the disk is able to hold.

Low-level hooks. Portability was once achieved by ignoring all but the most generic features of the computer. Today's competitive market makes this impossible. Screen control, I/O-mapped peripherals, and interrupt-driven peripherals all must be controllable by a program. Allowing linking to assembly language driver subprograms minimizes the need to extend the language but leaves more work to the developer.

Turbo Pascal, lacking separate compilation, has gone to greater lengths than all the other compilers to incorporate low-level hooks in the language. UCSD Pascal provides its very complete system access in the form of linkable libraries. The other compilers typically lack system hooks much beyond a generic DOS call routine and memory access through special pointer instances.

Documentation. Compared to other languages, the quality of a typical Pascal compiler's documentation is very good. With the exception of Mystic Pascal, all the products provide indexes—and Professional Pascal's index is nothing short of spectacular. Most documentation is divided into two portions: generic information about the implementation of the language and information on running the compiler in a specific operating environment. The aim is to provide a single reference manual for any implementation of the same compiler, plus a user's guide for each separate implementation, outlining the quirks imposed upon an implementation by details of the operating environment.

MS, Professional, and UCSD Pascal get very high marks for their documen-

tation. IBM's is mediocre. Turbo Pascal's is hurt by frequent typographical errors and a somewhat confusing organization, as well as a lack of adequate examples for arcane compiler features. Utah and Mystic Pascal provide documentation that is generally insufficient.

Price and support. The price range of these Pascal compilers is considerable—from \$16 to \$695. Conventional wisdom dictates that the higher the price, the better the support. This is not necessarily the case, as shown by Borland's superior telephone support of a product costing only \$69.95.

The vendors do not charge for their baseline telephone support, but long periods on hold and frequent "I'll check and get back to you" comments can be expected from time to time. Nonetheless, current telephone support of Pascal products is enormously better than three or four years ago when it was little more than message-taking for overworked staff programmers. Microsoft has a subscription ISV (independent software vendor) support program for all its language products.

Upgrade policies vary widely from vendor to vendor, and even a single vendor's policies change from upgrade to upgrade. Microtec Research has a 12-month warranty on its disk media, but replacement disks and updates cost \$50. Microsoft updates vary in cost, depending on the quantity of materials involved. Its minimum charge is \$25. Borland has offered upgrades of the entire Turbo Pascal package (including documentation) to registered users for significantly less than list price.

Support also can include independent user groups, bulletin boards, and third-party books and tutorials. Numbers are the important factor here, with the most nonvendor support lining up behind Turbo Pascal.

CONSIDERING BENCHMARKS

Benchmarks, like statistics, should be viewed carefully in context and examined for what they do not say as much as for what they do say. A good benchmark should highlight program bottlenecks, typically tasks that are very necessary and done very frequently. The benchmark program Benchcr provides ten such tests, along with the Sieve of Eratosthenes. Listing 1 is Benchcr implemented for MS Pascal. Implementations for the other compilers are nearly identical, with most deviations occurring in file access syntax.

Listing 2 is a benchmark program called Matrix borrowed with permission from *Pascal Programs for Scientists and*

Engineers, by Alan R. Miller (Sybex, Inc. 1984). Again, it is for MS Pascal, and the others are nearly identical. Matrix multiplies two 20-by-20 arrays of real numbers ten times. Its value as a benchmark is that it does a great deal of real number arithmetic without using standard real number functions that are traditionally implemented as library routines. It should thus be a good test of in-line real number code generation.

The first benchmark in Benchcr tests screen display speed by writing 1,000 64-character strings to the screen. Most business applications spend a great deal of time painting screens. In terms of user satisfaction with the final product, this factor can be critical.

The next two tests work together: one builds a 1,000-node linked list, and the other disposes of the list. The time spent here must be weighed against whether a given compiler uses 16-bit

The price range is considerable—\$16 to \$695. Conventional wisdom dictates that the higher the price, the better the support. This is not necessarily the case.

offsets or 32-bit addresses for pointers. While 16-bit pointers are faster, they may limit the user to less heap than an application requires.

Benchcr includes two tests to measure generated code's efficiency at calling and returning from subprograms. The first test calls an integer function with a null body and without parameters and is a measure of the efficiency of instantiating a stack frame and disposing of it again. The second is a procedure call with 85 bytes of parameters. This byte count varies among compilers due to differences in implementation sizes of real numbers and pointers. The test actually measures how well the code can move parameters onto the stack; TestProc has a null body and does not use the parameters.

The next test is straightforward; it measures 10,000 evaluations of the expression, $\text{Sqrt}(\text{Sin}(\text{Ln}(3.14159)))$. Variations indicate more than just code efficiency, and may also show differences in real number size (4-, 6-, or 8-byte reals all exist), coprocessor use, and the

quality of the standard function library. Most transcendental function libraries are written in assembly language for greatest speed, but some, notably UCSD's and Utah's, are written in Pascal.

Tests are included in the Benchcr program to measure file system performance. One benchmark creates a text file and sequentially writes 1,000 64-character text lines to the file using Writeln. Another test opens the same text file and reads the 1,000 text lines back from disk via Readln.

Two tests measure the performance of binary and random file I/O. A binary file of records of 70 bytes (again, this figure varies depending on the real number size in the compiler configuration) is created, and 1,000 records are sequentially written to the file. Most compilers use Put for this purpose, but some, including Turbo and Utah Pascal, use a variant of Write. For the last test, this binary file is opened and an update-in-place is performed on each record, meaning that each record is read, modified, and written out again to the same position in the file. This operation is performed from the last record in the file to the first record, using whatever facility a compiler has available for performing random file I/O.

The Sieve of Eratosthenes is provided here largely to aid in comparing these results with previously published benchmarks in other publications. The Sieve is demonstrative of a compiler's performance in only the narrowest of terms—mainly array indexing and integer arithmetic. From time to time, rumors circulate that compilers are being written with "sieve recognizers" that identify the classic Sieve source and generate an array of primes from a table stored in the runtime library.


With some compilers, buffering can be adjusted to optimize disk performance. All benchmarks were executed with the default values for file buffering and with error trapping disabled. When the option was available, the compilers were directed to generate 8087 in-line code rather than runtime 8087 detection and emulation.

All the benchmarks were run on the same machine, an IBM PC with 640KB of RAM, 4.77-MHz 8088, 8087 coprocessor, two half-height floppy disk drives, and a single 20MB hard-disk subsystem from PC's Limited. For time testing, a subdirectory called TIMETEST was created when the hard disk was about 60-percent full. Compilers and source code files were moved into TIMETEST, timed, and erased; therefore, all of the disk-bound timings represent

A remarkable breakthrough for LANs—one that's easy to use: Tapestry

No matter what local area network hardware you choose—your next choice should be **Tapestry network operating software from Torus Systems.** Here are 6 reasons why.

1 IBM chose Tapestry, for its overseas market, and it quickly became the hottest LAN system in Europe.



This is the friendly screen that caught Big Blue's eye.

2 It's the world's easiest-to-use networking software—much simpler than Novell, 3Com, or IBM because Tapestry is managed with icons. To use it, you just point to graphic symbols: the "in-tray" to get mail, the "cabinet" to access files, and so on.

You even use icons to configure the system, so almost anyone can set up a Tapestry network—and keep it running smoothly.

3 Tapestry is the most complete LAN software money can buy.

The basic system gives you:

• Advanced electronic mail

Compose memos with the Torus text editor. Send them to any person or group on the network, just by pointing to names. Track the mail you've sent. Get messages instantly.

• Cost-effective sharing of hard disks, printers and modems


You can have up to 100 Tapestry workstation/servers and access any one of them by touching the right icon. Since all Tapestry servers are undedicated, each station is free for business as usual. You don't have to invest in specialized hardware, or sacrifice your valuable PCs.

• Advanced communications capabilities

Need information from the company mainframe or an outside service? Just point to the desired Service icon. Torus offers a family of network gateways* that automatically make the connection and speed your information through.

• And there's more!

Tapestry also provides central storage of all your applications so they too can be accessed with icons. Automatic file locking so you can safely run single-user applications not originally designed for networks. File Manager icons that let you manipulate files without using DOS commands. And a Telephone Manager that places your calls and maintains a personal electronic rolodex.



What good is a network if your people don't know how to use it? Tapestry's screens are so easy to understand, anyone can net great results without special skills or training.

4 Tapestry supports all the standards, like IBM Token-Ring,

PC Network and 3Com hardware. Like PC-DOS 3.1 and NETBIOS. So you can choose the LAN hardware that's best for you, and you won't have to worry if your software will run.**

5 Tapestry is proven and reliable.

Thousands of Tapestry stations have been installed in both large and small companies in the U.S. and around the world. Customers include: Proctor & Gamble, EDS, the White House, the IRS, Prime Computer, TRW, NBC News, Shell Oil, Exxon and Citicorp.

6 With this coupon you get a FREE Network Manager AND a money back guarantee!

Usually, Tapestry costs \$495 for your first workstation (the Network Manager) and \$295 for each additional station.† BUT NOW YOU CAN GET A TAPESTRY STARTER PACK (BOTH THE MANAGER AND THE SECOND STATION) FOR ONLY \$295!

And we're so confident you'll love Tapestry, we'll let you return it—for any reason—within 30 days of shipment and we'll gladly refund your purchase price (less \$50.00 restocking fee).

So send this coupon to us, take it to your Torus Dealer, or call in your order today, and start networking the easy way.

Name _____		
Company Name _____		
Address _____		City _____
State _____	Zip _____	Phone _____
Networking Hardware _____		
Number of Workstations in Office _____		
Subtotal		\$295!
Add \$7.00 shipping/handling		\$ _____
California residents add 6½% sales tax (\$19.18)		\$ _____
Amount enclosed		\$ _____
Payment VISA MC Check _____		
Credit Card Exp. Date _____/_____/_____		
Card # _____		

Act now: offer expires August 15, 1986.
This offer is good only in U.S. and Canada.



495 Seaport Court, Suite 105
Redwood City, CA 94063
(800) 872-5335

System Requirements: Station 1: IBM PC, XT, AT or compatible 384K, 10MB hard disk. Station 2: IBM PC, XT, AT or compatible 320K. Plus suitable networking hardware.

Notes: *ASYNCR is standard, while VT100, 3270 SNA, and Remote Access are purchased separately. **Tested applications include: dBase III Plus, MultiMate Advantage, Open Systems Accounting, Displaywrite 3, WordPerfect, MS Word, Lotus 1-2-3, AutoCAD.

†6 Station Pack—\$1495, 24 Station Pack—\$3995.

Torus and Tapestry are registered trademarks of Torus Systems, Ltd. Trademarks: 3Com—3Com Corp; IBM, Displaywrite 3 and PC-DOS—IBM Corp; MS Word—Microsoft, Inc; dBase III Plus—Ashton-Tate; 1-2-3 and Lotus—Lotus Development Corp; WordPerfect—Satellite Software International; AutoCAD—Autodesk, Inc; MultiMate Advantage—MultiMate International; Novell—Novell, Inc; Open Systems Accounting—Open Systems, Inc.

© 1986 Torus Systems, 495 Seaport Court
Redwood City, CA (415) 363-2418

TABLE 2: Benchmark Timings

	IBM No 8087	IBM With 8087	MS No 8087	MS With 8087	MYSTIC	PRO. (Small model) No 8087	With 8087
BENCHER.PAS							
Compile time	1:55.17	1:48.03	1:36.72	1:34.36	0:03.74	1:59.40	1:47.92
Code file size	36,612	28,212	42,376	42,040	7,456	29,906	23,906
Screen display	1:58.90	1:58.97	2:20.23	2:20.23	0:09.12	2:16.27	2:16.22
Build list	0:01.04	0:00.99	0:00.49	0:00.49	— ^a	0:01.48	0:01.43
Dispose of list	0:00.11	0:00.06	0:00.55	0:00.55	—	0:00.66	0:00.60
Function call	0:01.82	0:01.81	0:01.76	0:01.81	0:06.76	0:02.03	0:01.97
Procedure call	0:09.88	0:09.97	0:09.94	0:09.94	3:04.33	0:09.12	0:09.06
Transcendental functions	10:13.95	0:16.54	10:23.68	0:17.24	9:16.56	15:48.90	0:10.65
Sieve	0:11.04	0:11.10	0:10.99	0:10.99	0:35.65	0:12.14	0:12.79
Text file write	0:13.08	0:13.01	0:08.95	0:09.01	0:05.87	0:04.07	0:04.01
Text file read	0:16.03	0:15.98	0:17.30	0:17.24	— ^b	0:04.95	0:04.94
Binary file write	0:06.92	0:07.19	0:06.64	0:06.64	0:07.41	0:04.12	0:03.85
Binary file update	0:25.87	0:24.06	0:27.02	0:26.92	0:18.89	— ^c	— ^c
MATRIX.PAS							
Compile time	1:37.38	1:31.72	1:21.61	1:19.03	0:02.25	1:55.83	1:46.11
Code file size	40,626	33,906	46,294	45,782	3,696	32,882	28,178
Matrix multiply	0:21.14	0:02.31	0:21.03	0:02.53	0:13.45	0:19.01	0:02.75

^a Heap support was not implemented at review time.

^b Mystic Pascal does not support line-oriented text file read.

^c Professional Pascal does not support update-in-place with standard record oriented file primitives.

^d Timings are the same as UCSD native code.

accesses to roughly the same regions on the disk. The benchmark results are presented in table 2.

The PC's built-in timer was used whenever possible to deliver an accurate elapsed time figure for the software benchmarks. For the benchmark programs themselves, the procedure `Show_Time` was written; it does nothing more than read the current time from the system clock via DOS function 2CH and write the time to a text file. `Show_Time` resolves to a PC timer tick—1/18 of a second. The code that is to be timed is bracketed by two invocations of `Show_Time`. The difference between the two times is a reasonable representation of the time taken by the bracketed code.

For filter-type compilers (IBM, MS, Professional, and Utah) a batch file similar to the one shown in listing 3 was used to bracket the compile/link commands with two DOS `TIME` commands. The first sets the timer to 0:0:0.0; the second displays the system time when the batch file is finished, giving a fairly accurate elapsed time figure for the compile operation.

A stopwatch had to be used for two of the environment-type compilers (Turbo Pascal and UCSD Pascal). The figures shown in table 2 are averages of three identical runs on each timed operation. Mystic Pascal times itself as it compiles, with the caveat that a considerable portion of its compilation effort is done while the code is being edited.

Interpreting the benchmark timing table must be done with the knowledge that any two readings that vary by less than .12 seconds must be taken as equivalent. One timer tick occurs every .06 second, so there is a .12 second window around any event during which another event can fall with no assurance that even a single timer interval (two ticks) separates them.

Finally, keep in mind that performance differences of less than 100 percent rarely create an overwhelmingly obvious difference in response in interactive applications (see "V20 Compatibility and Performance," Ted Mirecki, April 1986, p. 78). Raw performance figures should never be the first consideration in choosing a Pascal compiler. In fact, reliability, richness of features, ease of use, and quality of documentation may be considerably more important than speed. The Pascal compilers reviewed below are examined on the basis of all these factors. The order in which the products are presented is by market niche and does not reflect any judgment as to quality.

MICROSOFT PASCAL

Many people consider Microsoft's compiler the official Pascal for the IBM PC, because IBM distributes a version under its own label. It was certainly the first Pascal to be available under DOS, and in many ways it has improved more than any other Pascal reviewed here since its first release.

This is a two-pass, filter-type, native code compiler, invoked from the DOS command line and used from within a batch file. An optional third pass produces an assembly language type object code listing. The compiler's output is native code relocatable object (.OBJ) files in the Microsoft standard format.

The compiler's first pass is its *front end*, common to all implementations of MS Pascal and producing a tokenized output file. It can be used alone to check syntactic correctness quickly without spending time generating code. The second pass is the *back-end* optimizer and code generator pass, specific to an operating environment, such as DOS on the 8088. A final step using the DOS `LINK` utility is necessary to link a compiled program to the compiler's run-time library and any previously compiled or assembled external routines. The linker produces an .EXE file that can be run from the DOS prompt.

Beginning with version 3.3, MS Pascal's memory model changed from medium to large, as Microsoft pursued its policy of high-level language integration (see "Language Integration," Product of the Month, this issue, p. 29), allowing code written in MASM-compatible assembly language, MS Pascal, MS FORTRAN, and MS C to be linked freely into the same program module. MS Pascal supports only the large model; medium is no longer available. The default heap is short (16-bit pointers), but a library supporting the long heap (32-bit

PRO. (Large model) No 8087	With 8087	TURBO No 8087	TURBO With 8087	UCSD p-code	UCSD Native	Native With 8087	Native (DOS bridge)	UTAH
2:03.74	1:53.20	0:04.64	0:04.53	0:38.87	1:42.63	1:44.32	— ^d	1:17.81
43,154	34,434	14,936	13,585	3,584	4,608	4,608	—	3,072
2:16.76	2:16.71	1:41.18	1:41.23	0:28.78	0:28.56	0:28.50	—	3:04.49
0:02.25	0:02.19	0:00.55	0:00.55	0:07.25	0:06.98	0:06.97	—	0:03.36
0:01.65	0:01.70	0:00.71	0:00.66	0:10.60	0:10.38	0:10.38	—	0:02.09
0:02.09	0:02.08	0:03.52	0:03.52	0:22.14	0:09.44	0:09.40	—	1:39.31
0:09.72	0:09.78	0:15.87	0:16.14	0:42.57	0:26.37	0:23.29	—	2:54.30
19:10.42	0:11.48	6:09.76	0:10.72	10:00.11	9:56.60	0:38.73	—	3:57:27.62
0:12.08	0:12.14	0:13.84	0:13.89	2:02.43	0:15.21	0:15.22	—	8:21.69
0:05.54	0:05.55	0:10.05	0:10.05	2:28.35	2:39.89	2:19.02	0:30.54	0:25.81
0:05.22	0:05.22	0:09.56	0:09.56	0:19.06	0:17.03	0:20.48	2:16.54	0:29.11
0:04.12	0:04.18	0:06.26	0:06.54	1:17.33	1:16.57	1:11.52	0:24.67	0:28.01
— ^c	— ^c	0:15.38	0:16.37	1:51.72	1:50.45	1:53.20	1:13.38	1:27.66
1:59.62	1:50.61	0:03.61	0:03.65	0:24.83	1:20.08	1:21.72	—	0:39.93
44,946	38,722	13,574	12,187	2,048	3,072	3,072	—	1,664
0:23.50	0:02.74	0:09.94	0:06.27	0:24.72	0:08.89	0:04.07	—	0:39.93

Compile times for the two environment products Turbo and UCSD Pascal were taken with a stopwatch; Mystic Pascal contains a built-in compiler timer. IBM, MS, Professional, and Utah Pascal were compiled from batch mode and then timed with DOS's TIME command. All code timings are from the system timer through DOS function 2CH, Get Time.

pointers) is included. Also, beginning with version 3.3, programs compiled under MS Pascal cannot be run under DOS 1.x. IBM Pascal, which still supports 1.x, should be used if such support is required of an application.

A profusion of numeric formats and types gives the programmer a great deal of control over the speed and precision of numeric operations in MS Pascal. Three different signed integer types are predeclared: Integer1, a signed 8-bit integer ranging from -127..127; Integer2 or Integer, the familiar signed integer type; and Integer4, a 32-bit signed long integer type with a range of -2,147,483,647..2,147,483,647 ($\pm 2^{31}-1$). Subranges are not allowed on Integer4, nor can it index arrays. Two unsigned integer types, Byte and Word, occupy one and two bytes, respectively. The rules of how these various types can be combined in expressions and which automatic conversions are done reflect the realities of code generation more than any intuitive plan. For example, Integer freely converts to Real in expressions when such a conversion does not violate the mathematical sense of either type, but Integer4 must be converted to Real using a library routine.

The situation for real number formats is more complicated still. The standard Pascal type Real can be expressed as either a 32- or a 64-bit IEEE format by specifying the format in a compiler command. Additionally, 4- and 8-byte reals may be mixed within a

program by explicitly declaring values as Real4 and Real8; both formats are fully compatible with one another. Real8 is the familiar IEEE 64-bit format used by the 8087. Real4 uses a 24-bit mantissa and 8-bit exponent, giving seven significant figures and a range of 10^{-38} to 10^{38} . Real constants are always expressed in the 64-bit format.

MS Pascal provides a floating-point decimal real type with 14 significant figures of absolute precision. Any value requiring 14 or fewer significant figures can be represented exactly, supporting values up to \$1 trillion to the penny. If precise representation is not required, the exponent range extends from 10^{-63} to 10^{63} . This numeric type is poorly described in the documentation.

Finally, MS Pascal offers an "alternate math package" (ALTMATH) that trades precision for speed in systems that do not include math coprocessors. ALTMATH does not support the infinite stack provided by the 8087 emulator match packages and is not well documented at all with regard to available precision or internal expression of values. It runs faster than the 8087 emulator, but not as fast as code that takes advantage of the 8087 itself.

The runtime support for reals is sophisticated enough to sense the presence of an 8087 in a system and use it if it exists or emulate it if it does not. A compiler command can force the generation of in-line 8087 code for faster operation (this is how the 8087 bench-

marks for MS Pascal were generated), but the resultant program will hang a system without an 8087.

MS Pascal supports all standard file operations as well as extended file support for physical file assignment, file closing, file deletion, and random file I/O. Files may contain up to 2 billion records (Maxint for Integer4). File error conditions may be trapped and tested without allowing runtime errors to disrupt operation of the program. The file system's only lack is an untyped file in the Turbo Pascal style, through which raw sectors may be retrieved with great speed from the disk without typing or other interpretation.

MS Pascal's file support performance is disappointing, given the product's performance in other areas. At best, it equalled or slightly exceeded Turbo Pascal in speed, falling to about half Turbo's speed for reading text files. It failed even to approach Professional Pascal's file I/O in all categories.

Conformant arrays are implemented as a *super array* extension to standard Pascal. The upper bounds of super arrays are not set at compile time. They are a "type of types" that is compatible with derived array types, the upper bounds of which are set in their declarations. Super arrays can act as subprogram formal VAR parameters, and they also can be allocated dynamically on the heap. A built-in function called Upper can be used within a subprogram to determine the upper bound

PASCAL TOOLS FOR LEARNING

I learned Pascal as I learned to swim; I bought a compiler, jumped in, and thrashed around until I was confident I would not drown. This approach has two problems: (1) it takes longer than it should, and (2) it can develop peculiar programming habits. Without a curriculum, a person rarely learns the *entire* subject. Pointers and Get/Put seemed arcane, so I ignored them, using arrays and the compiler's proprietary random file syntax instead. Years passed before I bothered to study forward declarations.

Behind most languages, and Pascal in particular, is a design philosophy in which all parts of the language play an integral part. Programming with part of Pascal is simply not as effective as with *all* of it. Three Pascal interpreters/tutorials for DOS are available to aid the learning process. **Exploring Pascal.** Exploring Pascal is a recent offering from Ashton-Tate. It consists of a sturdy 420-page book and a single unprotected diskette. While the book is handy as a ready reference and for getting started, it becomes extraneous once the learner gets caught up in the on-line tutorial.

The software is a simplified programming environment, modeled after UCSD Pascal. It implements most of standard Pascal but virtually nothing more; Niklaus Wirth would approve. From the main menu (arranged along the top of the screen, UCSD-style) the user can enter the editor, compiler, filer, or the on-line tutorial.

The compiler supports a very simple superset of the language, adding only UCSD-style, variable-length strings and random file I/O. It compiles to an intermediate code that is interpreted by the environment. An optional optimizer pass makes code files a little faster and more compact, but not enough to merit the added complication to the system.

The tutorial is classic computer-assisted instruction: screens of lecture followed by exercises. The screens are clearly and crisply written, and the exercises reinforce the material. Use of color is excellent. Some of the tutorials have animated code examples in which a reverse-video bar highlights the executing statement of a FOR loop in slow motion to explain how loops operate (see photo 1).

One irritation is that some technical terms are given odd definitions. For example, the author refers to human-readable reserved words and identifiers as *tokens*, a word most people take to mean a binary code for an identifier or reserved word after some compilation has occurred. The book also lacks an index, although the table of contents is detailed enough to serve a similar function.

The two main problems of Exploring Pascal are not really germane to its stated purpose of teaching a beginner to program in Pascal. First, a source file cannot be imported from another compiler unless the file is syntactically correct from Exploring


Pascal's point of view. The error message in such a case is abominable: "ERROR: File damaged in file: 'BENCHER.PAS'." A syntax error is not the same as a damaged file, and a beginner is bound to get very nervous when confronted with this message. Furthermore, no clue is given as to what is wrong with the incorrect file. Second, the system is rather closed-ended. It has no cursor positioning ability and no means to build one out of BIOS calls or DMA to the screen. Therefore, building anything but toy programs is impossible.

The bottom line on Exploring Pascal is that it is likely to be used only once. After a person has run through the tutorials and compiled a few demo programs, restlessness will set in, and the user will want to graduate to a "real" Pascal. Taking that first step is never easy, however, and Exploring Pascal will help the new programmer take it correctly.

WATCOM Pascal. In the same way that the University of California at San Diego spun off SoftTech Microsystems to market university-developed UCSD Pascal, so did Canada's University of Waterloo create WATCOM Systems to sell its line of language products, including its Pascal interpreter.


WATCOM Pascal is a programming environment incorporating an editor, interpreter, and debugger. The bottom line of the screen is a command line, with the remainder of the screen given to the editor and to program

PHOTO 1: *Exploring Pascal Tutorial*



The green bar moves through the code example, highlighting statements as they are executed.

PHOTO 2: *Alice Pascal Template*



The programmer replaces the blue place holders with valid program reserved words and identifiers.

execution. Source code in the editor is not explicitly compiled, but is interpreted when the Run command is given. As with BASIC, true interpretation means that syntax errors are not always found until runtime.

The editor is function-key driven and has a very intuitive design. Like Turbo Pascal, it does not correctly expand tab characters from imported code. A diagram of function key meanings is always available by pressing F10, and help screens are accessible for most of the editor's (but not the language's) features.

The interpreter extends a fairly complete implementation of standard Pascal with full screen control, strings, random file I/O, peek, poke, time and date functions, DOS calls, hooks to user-loaded machine-code routines, and a superb set of graphics routines. No bugs were discovered in either the environment or interpreted code.

The debugger allows immediate execution of complete Pascal statements, single-stepping of a program, and examination and alteration of program variables. One of the debugger's virtues is its simplicity, which makes it understandable to beginners.

This very capable software is spoiled by a terribly written tutorial. It suffers from bad writing—gramatically correct but devoid of any feeling for the big picture of Pascal. The discussion of Boolean variables and expressions gives a correct description of Pascal's Boolean type without any higher-level explanation of where the type came from nor what it is for. So it continues throughout the tutorial. A newcomer to Pascal could carry away enough details to pass a first-year computer science exam, but no true understanding of the language would gel out of this relentless and unstructured progression of facts.

Annually renewable site licenses are available that favor large educational customers, and the software includes an expiration-date scheme that renders it unusable after a certain preset date. At its undated single-copy price of \$225, WATCOM Pascal is far more costly than its power merits.

Alice Pascal. Alice Pascal, from Software Channels, is a far more ambitious product than either WATCOM or Exploring Pascal. Like WATCOM, it comes from Canada; in fact, it was created as an alternative to WATCOM Pascal for the

Canadian educational market. Like the other two interpreters, it is explicitly targeted at beginners, but it gives those beginners credit for considerable intelligence and allows for more of the inevitable curiosity about the underlying computer.

Alice is a programming environment constructed around a remarkable syntax-directed editor. The editor is both command- and menu-driven in that input may be either typed or selected from a hierarchy of pop-up menus. In editing a new program, the programmer begins not with a blank screen but with a template containing place holders for the essential parts of a Pascal program. The initial template is shown in photo 2. Words in blue are place holders, and editing a program is a process of replacing the place holders with appropriate program statements. Syntactically incorrect statements are detected immediately, highlighted in color, and explained with a detailed error message. When the user selects from a menu a program structure such as a case statement, a template for the structure appears, with more place holders waiting to be filled in. The template defines Alice's text-formatting conventions, including indentation and the number of lines between procedures and functions. Fortunately, the conventions can be modified by altering the shape of the templates used by the programmer.

Alice's templates can be filled in in two ways when writing a program. One is simply to type reserved words and identifiers into the template; the editor does its best to send the cursor to what it assumes is the desired next position. Tab and Shift-Tab move forward and backward along the template. Alternatively, nearly every item can be selected from a menu without explicitly typing it.

The syntax-directed editor is thus a tutorial of sorts, because it focuses on structure and syntax while the program is under construction, offering feedback while the program concept is fresh in the programmer's mind. The programmer can go off in one direction and the editor will follow, pointing out mistakes and the correct path in the same action.

Alice has room in memory for 1,600 lines of source code, so it can do more than teach the basics of Pas-

cal, but it cannot rise above "recreational programming." Although programs written in Alice require the Alice environment to run, Software Channels is releasing a runtime version that may be distributed free with user-written programs.

Alice offers everything present in WATCOM Pascal and is much richer than Exploring Pascal; it includes full-screen control, access to the system clock, and many other features that allow truly interesting software to be written. It has a suite of built-in debugging tools, including source animated trace, and a respectable library of utility routines. Software Channels is moving Alice toward compatibility with Turbo Pascal. Future releases will include the ability to load and run Turbo's machine code external binary libraries such as GRAPH.BIN.


The Alice Pascal tutorial has a different focus from that of WATCOM and Exploring Pascal; it teaches the use of Alice rather than Pascal itself. It has no well-defined Pascal curriculum. This is not a crippling deficiency, given the three products' emphases: WATCOM and Exploring Pascal seem slanted toward the newcomer to programming, while Alice is slanted toward a computer-literate newcomer to Pascal. The material is more complex and powerful. An Alice textbook is in production, but was not available in time to review. Once it is, Alice Pascal will serve the same market as both Exploring Pascal and WATCOM Pascal—and serve it considerably better.

—Jeff Duntemann

Alice Pascal: \$95.00
Software Channels, Inc.
212 King Street West
Toronto, Ontario M5H 1K5
416/591-9131
CIRCLE 358 ON READER SERVICE CARD


Exploring Pascal: \$39.95
Ashton-Tate Publishing Group
20101 Hamilton Avenue
Torrance, CA 90502-1319
213/329-8000
CIRCLE 359 ON READER SERVICE CARD

WATCOM Pascal: \$225.00
WATCOM Products
415 Phillips Street
Waterloo, Ontario N2L 3X2
519/886-3700
CIRCLE 360 ON READER SERVICE CARD



Interactive DOS Utility **\$49⁹⁵**

Resident program gives you instant access to many enhanced DOS functions and instant return to where you were.



* **Reduce time searching for your files and performing DOS commands.** See up to 85 files per screen page. Identify sub-directories at a glance. Get quick and easy display of contents.

* **Make your DOS commands easier to use.** Pop up windows simplify DOS operations, utilize single keystroke commands, return you instantly to where you left off.

* **Take full control of your printer.** Call up printer output window from inside any program and give necessary printer commands.

"WindowDOS quickly established itself as an indispensable part of my PC environment. I can't imagine working without it."

Paul Bonner, Reviewer, PC Week

\$49.95
Plus \$5 handling and shipping

1-800-433-5355
Texas 214 264-2626

Money orders, cashier's checks, VISA, MC, AmEx, and Corporate Purchase Orders.

Software of the Future
Box 531650 Grand Prairie, TX 75053

WindowDOS is for use with IBM PC, XT, AT and true compatibles. Requires DOS 2.0 or newer and 80 column display. Uses only 40K of memory.

PASCAL

of an actual parameter that is passed through a super type.

MS Pascal's string types are derived from the super array concept. The String type is a pure super array of characters, and the LString type is a special super record having a leading length byte in addition to a super array of characters. LString is thus quite similar to the UCSD-style string used in several of the other compilers. The suite of procedures and functions acting on LString types, however, has different names, functions, and calling syntax, making MS Pascal's string handling less portable than the other compilers.

Like Turbo Pascal, MS Pascal supports array, record, and typed set constants, although its notation for structured constants is less intuitive and readable than Turbo's.

Separate compilation can be handled two ways. *Modules*, which are compilands containing external data and subprograms, amount to a program without a program body. This is the same method used with Pascal/MT+86. The better means is via *units*, which resemble modules as used by Modula-2. A unit has a definition part called an *interface*, which contains only the declarations of the unit's contents, and an *implementation* in which the data and subprograms of the unit actually reside. With units, the hiding of details in separately compiled items is complete. MS Pascal's unit concept is nearly identical to the one in UCSD Pascal.

Separately compiled modules (but not units) can be combined into libraries using MS LIB, a librarian utility bundled with MS Pascal. LIB also facilitates updates of modules contained within the library, without having to recreate the library from scratch.

MS Pascal's suite of low-level hooks is smaller than Turbo's, but the situation for MS Pascal is less serious because a programmer can write what is lacking in assembly language for inclusion in a library. MS Pascal has no I/O port access, no facility for in-line code generation, and no software interrupt call. A DOS call primitive exists, and separate functions returning date and time values are available. The Retype facility is more general and better documented than Turbo's, and free union variant records are supported. The Origin attribute allows variables to be declared at absolute memory locations. Documentation on writing external assembly language subprograms includes complete descriptions of the stack frame and of internal data representations for all but the real types.

Documentation for MS Pascal follows the common two-volume model: a reference manual for Pascal, divorced as much as possible from any particular implementation of the language, and a separate user guide for each implementation—in this case, one for DOS and one for XENIX. From a structural and organizational standpoint, the documentation is complete and proper. It has good tables of contents, indexes, listings of error messages, and so on. The pages are not overly crowded, and the text can be easily skimmed. No typographical errors are evident.

The problem with the text is a pervasive vagueness. For example, the user's guide mentions a pair of public variables, CRCXQQ and CRDXQQ, which hold register values after a DOS call, but the manual does not give their

Beginning with version 3.3, programs compiled under MS Pascal cannot be run under DOS 1.x. IBM Pascal, which still supports 1.x, should be used if such support is required.

type. Worse, it does not say which library contains them. Similar lapses occur throughout both manuals.

The telephone support people seem to know the product extremely well. A 90-day guarantee is provided for the media. Updates vary in cost depending on how many disks are involved and whether manual page updates are included. Several good books have been written about MS Pascal, and a fair number of third-party linkable libraries also are available for it.

MS Pascal makes few concessions to beginners—it is a complex, powerful tool for developing medium to large applications. For a product of its power and complexity, however, its learning curve is surprisingly short. While its price is on the high side (compared to the very capable Turbo and UCSD Pascal), it is not beyond reach of the serious personal programmer, and for the professional programmer it provides a better balance between cost and power than Professional Pascal, which offers its only real competition.

Digital has it now.




The first open-ended multi-user software system that integrates your custom application with a full range of standard business programs.

The A-to-Z™ Integrated System for MicroVAX II™ and MicroPDP-11™. Now you can integrate any number of your custom multi-user applications with word processing, graphics, spreadsheet, data management, accounting, and thousands of VAX™ and PDP-11 programs. Same menus, commands and files with no need for a system manager.

Tell me about A-to-Z on MicroVAX™ and MicroPDP-II™ ☐ Reseller ☐ Developer
Name _____ Title _____
Company _____ Phone _____
Address _____
City _____ State _____ Zip _____

Send to: Digital Equipment Corporation, Inquiry Dept.,
NR02-1/H3, 444 Whitney Street, Northboro, MA 01532.

digital™



Perfect Windows, Powerful Data Entry, FULLY Integrated, For Effortless Data Entry Windows!

- Complete input formatting
 - Unlimited Validation
 - Full attribute control
 - Field sensitive application help system
 - Multiple virtual windows
 - Fully automatic, collision proof overlay and restore
 - Print to & scroll background windows
 - Animated window "zoom"
 - Move, grow, shrink, hide, or show any window
 - "Loop function" allows processing while awaiting input
- and much much more!*

Designed to increase your productivity and help you produce superior applications in dramatically less time! Includes 100% source, tutorial, reference manual, examples, and sample programs.

Specify Microsoft,
Lattice, Computer
Innovations, Aztec,
or Mark Williams. Ask about Unix.

\$149.⁹⁵

NOW... VCScreen !

Our new interactive screen "painter" actually lets you draw your data entry windows! Define fields, text, boxes & borders. Move them around. Change attributes. Then the touch of a button generates C source code calls to the Vitamin C routines! Now, your screen designs will be faster and more pleasing when they are created with VCScreen!

Requires Vitamin C library above. For IBM & compatibles.

\$99.95

For Orders Or Information,

(214)245-6090

Creative Programming Consultants

Box 112097 Carrollton, TX 75011-2097

Include \$3 ground, \$6 air, \$15 overnight shipping, \$25 if outside USA. Texans add 6% tax. All funds must be in U.S. dollars drawn on a U.S. bank.

PASCAL

IBM PASCAL

IBM Pascal is, in fact, a private-label packaging of Microsoft Pascal, with enough differences to warrant discussion in its own right. According to Microsoft, IBM Pascal 2.0 is a proper subset of MS Pascal 3.31, with the exception of three library routines. This discussion of IBM Pascal is limited to its differences from MS Pascal.

Whereas MS Pascal uses the large memory model, IBM Pascal uses the medium model. Assembly language modules that link with one compiler therefore will not necessarily link with the other. IBM lacks MS's integration with other Microsoft languages, including the C attribute that allows the declaration of procedures with varying numbers of parameters. IBM Pascal programs can link with object files compiled under IBM FORTRAN 2.0 (again, a variant of MS FORTRAN), but the documentation for that feature is so vague that such linkage is impractical for all but the inhumanly determined.

A set-up utility is included that automates the copying of files to working floppy or hard disks. This utility also configures the runtime library file by concatenating the user's selection of numeric and DOS version libraries with the standard runtime library into a single enormous library file. The aim is to simplify the link step, an admirable goal, but the utility insists on creating a hard-disk subdirectory called \PASCAL (or using one if it already exists) and does not allow the user to specify a subdirectory name. This feature of IBM Pascal is simply unacceptable.

IBM Pascal lacks the richness of numeric formats offered by MS Pascal. Neither MS's BCD math nor its fast alternative math package (ALTMATH) are available. IBM Pascal cannot determine at runtime whether an 8087/287 coprocessor is installed, using it if there and emulating it if not. The programmer must explicitly link a given program for one situation or the other.

Although both IBM and MS Pascal support overlays, the MS implementation is more elegant and considerably better documented. (The IBM documentation references a section on overlays that does not exist.) The IBM scheme must explicitly load overlaid code via a LOADER function. MS Pascal's scheme is handled entirely through the linker; one or more linkable object modules may be specified as an overlay file at link time. The MS compiler does not know about overlays, and identical source may be linked as overlaid or not, as desired.

IBM Pascal includes three important library routines that Microsoft Pascal does not offer: INP and OUTP, which are used to perform port I/O; and INTRP, which performs software interrupts from within Pascal code.

IBM's benchmark timings are not significantly different from Microsoft's in any area except dynamic memory management. IBM Pascal is only half as fast in building a linked list, but is several times faster than MS Pascal at disposing of the list.

One area in which IBM differs overwhelmingly from MS Pascal is documentation. Both vendors offer two separate volumes, a user's guide (IBM calls this guide *Pascal Compiler Fundamentals*) and a reference manual, but beyond that point the two have little in common. Microsoft splits its manual between describing MS Pascal and detailing its DOS or XENIX implementations, whereas IBM splits the manual between a guide organized into chapters by

LIBM Pascal has three important library routines that Microsoft does not offer: INP and OUTP, which perform port I/O; and INTRP, which performs software interrupts from within Pascal code.

topic and an alphabetical key-word reference. Throughout both manuals the configuration is assumed to be the IBM PC, PC/XT, or PC/AT.

The IBM language reference for Pascal is very well done, in the fashion of the IBM BASIC manual. All key words and compiler directives are listed alphabetically, each with its own page. Skimming for a quick brush-up on an obscure compiler feature such as ACDDRQ (arccosine for real numbers) is fast, and references are given to related topics. Additionally, a table of contents with each key word and its page number is given at the front of the volume, as well as yet another section providing functional groupings of key words together with short descriptions—for example, a list of string functions, file management routines, etc.

Although the organization of IBM's volumes is somewhat more rational

Flashy Programs.

TELEPHONE ORDER ENTRY FORM

Salesperson: _____ Ship To: _____
 Today's Date: _____ Zip: _____

Root Num	Ship Date	Ship Via	FOB Point	Terms	Order Number
_____	_____	_____	_____	_____	_____

Quantity Item Num Description

Make Your Selection
 Add Record To File
 Edit Previous Record
 Go To Previous Record
 Press F10 Exit

ABC Computer Company
 New Client Information List

Company: _____ Billing Rate: \$ _____
 Contact: _____ Telephone: () _____
 Title: _____
 Address: _____
 City: _____ State: _____ Zip: _____

Referred By: _____ New Account Y or N: _____ Auth Code: _____

ABC Computer Company
 New Client Information List

Account #: _____ Salesman: _____ Today's Date: _____

Company: _____ Billing Rate: \$ _____
 Contact: _____ Telephone: _____
 Title: _____

Enter Selection
 Edit record
 Previous record
 Next record
 Exit

State: _____ Zip: _____
 New Account Y or N: _____ Auth Code: _____

THE SOFTWARE BOTTLING COMPANY OF NEW YORK
 New Client Information List

Account #: _____ Salesman: _____ Today's Date: _____

Company: _____
 Contact: _____
 Title: _____
 Address: _____
 City: _____
 Referred By: _____
 Comments: _____
 Completion Date: _____ Invoice Sent: _____ Payment Received: _____

*** POP-UP Help Screen Number One ***
 Enter data into the fields exactly as you see it here. Do not worry about making a mistake all data is error-checked as it is entered. It is impossible to make a mistake!

ABC Bottling Company
 Job Estimation and Control Program

Enter Job Description

Job Number	Part Number	Amount Needed	Amount Available	Balance This Job
_____	_____	_____	_____	_____

Job Number: _____
 Surface Type: _____
 Size Length: _____
 Thickness: _____
 Climate: _____

Do NOT Need The Following Parts
 Enter Job Selection
 Enter Job Selection
 Previous record
 Next Record
 Exit

BILL TO: _____ SHIP TO: _____

ACCOUNT #	SHIPPED	ORDER	SHIP VIA	TERMS	DATE REC	DATE SHIP
_____	_____	_____	_____	_____	_____	_____

QUANTITY DESCRIPTION WEIGHT PRICE AMOUNT

QUANTITY DESCRIPTION WEIGHT PRICE AMOUNT

TOTAL

dBASE • Turbo Pascal • BASIC • C • COBOL • Fortran • Lotus 1-2-3...

FLASH CODE™

The most powerful program developer for dBASE II and dBASE III ever developed.

DRAW any screen design with our advanced screen editor. Use Flash Code and see how incredibly easy screen design can be.

GENERATE complete programs automatically. Based on your screen designs, Flash Code can write your whole dBASE program.

FLASH-UP WINDOWS™ Menus and Help Windows add a new dimension to your dBASE programs. Create them instantly with our window editor. Use the FlashUp™ module to have windows pop-up throughout your dBASE applications.

For dBASE II and dBASE III. \$150.

"...a truly remarkable product. Brand-new, state-of-the-art and actually fun to use. The windows make it an even more amazing product."

Cary N. Prague, Author
 "Beyond programming with dBASE III"

"Destined to replace QUICKCODE™"
 MicroNews/Views, Nov. 85

SCREEN SCULPTOR™

You can create screens in minutes...then Screen Sculptor writes the program.

Move pieces of the screen around, select colors from a menu, draw boxes and lines, paint, repeat last character in any direction. And more!

Specify variable names, data types, acceptable data ranges, pictures for edit checking, etc.

Screen Sculptor then generates an actual program source code based on your screen design. Use it as is or modify it.

For BASIC, Turbo Pascal, IBM/Microsoft Pascal. \$125.

"...so well done that you may not need to refer to the manual."

"...an exceptional product that fills a real need in the development of new programs."
 Computer Language

No Risk Demo Offer!

Here's a no-risk offer. Order now and you'll also get a full demo disk. Use the demo and the manual for 30 days. If you don't love it, return the package for a full refund.

Credit card orders call 24 hrs/day
 1(800) 824-7888, operator 268.

All other orders and inquiries call or write
 Software Bottling Co., 6600 L.I. Expwy,
 Maspeth, NY 11378. 718-458-3700.



THE
 SOFTWARE
 BOTTLING
 COMPANY
 OF NEW YORK

Requires an IBM PC, XT, PC AT or true compatible, 256K

NEW! FLASH-UP WINDOWS™

An incredibly flexible and powerful tool for Flash-Up Menus and Flash-Up Help Windows!

Every program, every application becomes more sophisticated and easier to use with Flash-Up Windows.

Use the window editor to instantly create windows. Change their size, location, color...all automatically. Specify a string of characters or control codes to send back to your application program.

The windows can be flashed-up directly by your program OR by the user with the keyboard. Windows can even call other menus or help windows.


An absolute necessity for BASIC, Turbo Pascal, C, R:BASE, COBOL, Fortran, dBASE, Lotus 1-2-3...

Introductory price. Only \$75.
 (Until 3/31/86)

CIRCLE NO. 192 ON READER SERVICE CARD

Get a Grip on Assembly Language.

The award winning Visible Computer: 8088.



The Visible Computer is a book and software combination for mastering the elusive skills of assembly language.

It's an animated simulation of the PC's microprocessor that lets you see with your own eyes how assembly language works. You'll be using it as a debugging tool for years to come.

It's a tutorial. A lot of people think the 350 page manual is the best book on assembly language ever written.

It's 45 demonstration programs you'll execute with the simulator, from simple register loads to advanced programs that manipulate interrupts and perform file I/O.

• Applies to all 86 family processors, including 80186 and 80286.

• PC Tech Journal "Product of the Month."

\$49.95

Copy Protected

\$79.95

Unprotected

The Visible Computer for IBM PC/XT/AT and true compatibles. If your dealer doesn't have it, order direct: Software Masters, 2714 Finfeather, Bryan, TX, 77801. (409) 822-9490. Please include \$3.00 shipping. Bank cards accepted.



TVC takes you inside the processor as it executes programs.

Software Masters™

PASCAL

than Microsoft's, it offers much less information. The more arcane features of the IBM compiler are covered minimally if at all. For example, IBM seems to have omitted any discussion of overlays. IBM's documentation seems consciously slanted toward a less sophisticated programmer. It says much more about the Pascal language and much less about the internal structure of the compiler and runtime libraries.

IBM Pascal is somewhat simpler than MS Pascal and leans considerably more toward applications programming. The IBM compiler has some 8086-specific library routines that MS Pascal does not, and, unlike MS Pascal, it can generate programs that operate under DOS 1.x. Aside from that, however, it is a notably less powerful product, while being significantly more expensive.

PROFESSIONAL PASCAL

Professional Pascal was conceived as an improved competitor to MS Pascal. Its designers tried to make sure that anything Microsoft's compiler could do, theirs could do faster and better.

Professional Pascal is a multipass, filter-type, native code compiler that generates Microsoft-standard .OBJ modules. It supports five different 8086 memory models: small, compact, medium, big, and large; no other implementation reviewed supports more than one. Also, it is the only Pascal reviewed that is capable of generating 80186/286- and V20/V30-specific opcodes.

As with MS Pascal, 8087 support is handled two ways: by generating in-line 8087 code or by generating calls to a library that either uses the 8087 if present or emulates it if not. The in-line code is faster, and the timings in table 2 reflect that configuration.

The system is shipped on seven diskettes. It cannot be used on a floppy-disk-based system, because the compiler program is a single .EXE file 638KB in size. Obviously, overlays have been bundled into the root program for simplicity's sake. A superb installation program reads portions of large files from multiple diskettes and reconstructs the files on the target hard disk. It also builds subdirectories for all requested memory models and puts every one of the close to 80 files where it belongs.

The system borrows concepts from both C and Ada. A very C-like macro preprocessor is included, as is C-style pointer arithmetic. From Ada comes the *pragma* jargon for compiler commands and the extraordinarily sophisticated separate compilation scheme called *packages*. Ada-style comments are sup-

ported, for which a double dash (--) begins a comment that ends with the end-of-line character.

Compile speed is slower than that of MS Pascal, and the speed differential increases with the length of the program. The compiler posts more information to the screen as it works than any other compiler. The compiler warns of loose-end conditions, such as variables declared but not used, parameters passed but not used, and variables initialized but never referenced. These can be useful reminders of procedure stubs in need of completion, leftovers from a program redesign, and so on.

The speed of produced code, on the other hand, runs from good to spectacular. It has the fastest file access times of any compiler reviewed, in all categories, and can write 1,000 binary records to disk in less than four seconds. In Sieve performance it comes in slightly ahead of Turbo Pascal and slightly behind MS Pascal—although in practical terms, it is a three-way tie. Only in heap management are Professional Pascal's timings disappointing.

Table 2 has two columns for Professional Pascal—one for small and one for large models. For comparison to MS Pascal use the large model column. The speed advantage of using the small model is slight at best, except in terms of heap speed—and a short heap is only a marginally useful creature. Note that the .EXE file sizes for Professional and MS Pascal are so close as to be essentially identical.

A rich suite of numeric types is available. All three IEEE real formats are supported: 32-, 64-, and 80-bit reals. Unsigned integers are provided as type Cardinal. Four-byte long integers are available, with a range identical to MS Pascal's Integer4. Professional Pascal has no predefined Byte type, but the compiler can optimize an integer subrange of 0..255 into a single byte of storage. The documentation is honest enough to mention that multiplying two long integers cannot be done in 8086 registers and thus is much slower than similar operations on integers or cardinals.

Variable-length string support only roughly resembles that of the other compilers. String types have a two-byte leading length specifier and may be 65,534 characters long. A package of string manipulation routines allows all standard UCSD string operations, but routine names and syntax are different.

One aspect of file support is the only serious drawback of Professional Pascal. In their very serious concern for portability, its authors have refused to

This is the Modula-2 compiler everybody's been waiting for...

NEW! TURBO PASCAL TO MODULA-2 TRANSLATOR.

Now, cross the bridge to Modula-2 with ease.

LOGITECH MODULA-2/86

This is Modula-2 at its *absolute* best. It's a fully integrated development environment that takes into account what you need as a programmer. Without leaving the Editor, you can call the compiler, linker and utilities.

With Logitech's Modula-2, you'll have the ability to edit several files at once, comparing, window to window, various code modules. You can even move from window to window compiling, linking, debugging and running.

The compiler has the kind of power and room to breathe that you really need in today's complex applications. It is as *easy* to use as Turbo Pascal, without your programs being limited to 64K of code.

At your command will be the libraries of modules that make Modula-2 a programmer's dream. It has essentially the same structure as Pascal with the major addition of a library organization of code modules that allow you to put together programs on a solid, block-by-block, foundation of proven code.

Whether you're working with a module of your own making, or one of the many in our library, you'll find the system by which each module is identified, described and stored an organizational masterpiece. And that's at the heart of Modula-2.

Underneath the sophisticated system is a Modula-2 compiler that is the result of years of development and proven use in industry. We run on the Vax*, and we run on the IBM PC. And the code is portable—from one to the other.

Best of all... you can have it right now!

Logitech Modula-2/86 Complete with Editor, Run Time System, Linker, Cursor-positioning debugger, 8087 Software Emulation, BCD module, Logitech's extended library, Utility to generate standard .EXE files, Turbo Pascal (and standard Pascal, too) to Modula-2 translator (included without charge until 8/1/86), and much, much more!

Logitech Modula-2/86 with 8087 support Even if you haven't yet gotten an 8087 co-processor, you can still use this version.

Logitech Modula-2/86 Plus For machines with 512K or more. Takes advantage of the larger memory to increase compilation speed by 50%! Supports 80186 and 80286 as well as 8086 and 8088. Includes 8087 and 80287 support, too.

Window Package Now you can build true windowing into your Modula-2/86 code with ease, too. Very powerful and very full, yet only 15K in size. Features virtual screens, color support, overlapping windows and a variety of borders.

Run Time Debugger (source level) Much more powerful than just a symbolic RTD. Display source code, data, procedure call chain and raw memory. Set break points, assign values to variables, pinpoint and identify bugs in your source. The ultimate professional's tool!

Utilities Package Features a post-mortem debugger for static debugging. If a program you've written crashes at run time, the situation is frozen, and you can pinpoint, in source, the cause of the error and the data at that moment. Also includes a disassembler, a cross reference utility and a "version" utility that allows conditional compilation.

Make Utility Automatically selects modules affected by code changes for quick and minimal re-compilation and relinking. Even figures out dependencies for you.

Library Sources Source code for our major library modules is now available—for customization or exemplification.

ROM Package If you need to produce rommable code, call our 800 number for further information on this package.

To place an order call our special toll free number

800-231-7717

in California

800-552-8885

Special offer until 8/1/86!

includes

Free! \$49.95 value Turbo Pascal translator!

Now, you can take your library with you!

\$89

Yes, I'd like to take the next logical step in programming.

Please send my copy of Logitech Modula-2/86 to the following address:

☐ VISA ☐ MasterCard ☐ Check Enclosed

Card Number _____ Expiration Date _____

Signature _____

Name _____

Address _____

City _____

State _____ Zip _____ Phone (____) _____

Here's the configuration I'd like:

☐ Logitech Modula-2/86 \$89

☐ Logitech Modula-2/86 \$129

with 8087 support

☐ Logitech Modula-2/86 Plus \$189

Please add \$6.50 for shipping

and handling.

Total enclosed \$ _____

(California residents, please add applicable sales tax)

And include the indicated items:

☐ Window Package \$49

☐ Run Time Debugger \$99

(source level)

☐ Utilities Package \$49

☐ Make Utility \$29

☐ Library Sources \$99



LOGITECH

LOGITECH, Inc.
805 Veterans Boulevard
Redwood City, California 94063
Telephone (415) 365-9852

For European pricing, please contact:

LOGITECH SA
Box 32, CH-1143 Apples, Switzerland
Telephone 41 (21) 774545

Please call our 800 line for: ☐ Information on our *VAX version ☐ Site License and University Discounts ☐ Dealer and Distributor information

CIRCLE NO. 229 ON READER SERVICE CARD

*Turbo Pascal is a registered trademark of Borland International

extend the standard by allowing an update mode for file access using standard file notation. In other words, Reset opens a file as read-only; a record read cannot be updated and rewritten to its previous position in the file. This is an essential operation in business programming, and all the other Pascals reviewed here include it. Update mode is supported when using a supplied library of character-oriented C-like file primitives, but support for record I/O must be written by the programmer under such a system.

Otherwise, file support is good, and file performance is unexcelled. Seek supports random file I/O. Close works as in the other Pascal implementations. File status is returned by a library package routine.

Professional Pascal's provisions for separate compilation are the most detailed and powerful of any Pascal reviewed. Its traditional external declaration scheme, which is similar to that supported by MS Pascal and Pascal/MT+86, is included only for compatibility with older code. The recommended

method is to form packages similar to those defined for the Ada language.

A package is much like MS and UCSD Pascal's unit. It has an interface-and-implementation part and allows internal details of exported objects to be completely hidden from the importer. Additionally, packages allow two imported objects to have the same name by specifying the object name after its package name, using *dotting* or the WITH key word from record notation. For example, programmers no longer have to worry about using two unrelated external routines, both named Strip—one to strip white space from text lines and one to strip file headers from data files; instead, one can be specified as TextTools.Strip and the other as FileTools.Strip.

Furthermore, packages allow data abstraction—that is, hiding a type's implementation details from the importers of the type. The simplest example concerns a type that is a subrange of Integer: programmers importing the type might be tempted to make assumptions based on integer properties; the subrange might be imported as a closed interval between two constants whose values are also hidden, allowing some limited work to be done with the subrange without revealing its base type. Professional Pascal also provides manual and automatic aliasing of objects with identical names in different packages across linkable boundaries, because linkers do not understand packages and cannot deal with two objects sharing the same name. Such techniques have been used in certain main-frame languages for some time.

Professional Pascal's documentation is certainly the best of any compiler reviewed here. Like the others, it is divided into two volumes: a programmer's reference, which deals with compiler operation and implementation specifics, and a language extension manual, describing Professional Pascal's extensions to standard Pascal. The documentation does not describe standard features except to contrast them with language extensions. Each extension is given a very complete description as well as a rationale describing what the extension is for and why it is included. The descriptions are wonderfully complete and concise. None of the vagueness that mars documentation for MS and UCSD Pascal is apparent. The 20-page tutorial on packages, for example, is a model of technical clarity.

The indexes for the two volumes are quite unusual; key words are indexed along with a few words of con-

NOVELL COMPATIBLE

ONE-STOP ARCnet™ LAN SOLUTIONS

Now you can get all the tools you need to build industry standard **TOKEN-PASSING** networks from one source.
InterContinental Micro.

Our networking packages let you configure any combination of nodes (PC's and compatibles, ATs, XTs, Jrs., Z-100's) to a common Fileserver in just a few minutes with our menu-driven installation program.

Active and passive hubs allow you to integrate up to 255 users on a single network with *increased* efficiency as the network grows.

In addition, our stand-alone ARCnet™ Workstation/Fileserver and complete line of S-100 Bus products (single board computers, slaves and controllers) give you and your customers even more options.

We're also compatible with other industry-leading ARCnet PC™ and S-100 products, and our PC networking boards include an optional 256K of system RAM.

All with InterContinental Micro's reputation for outstanding reliability, exceptional service, and highly competitive pricing.

Call InterContinental Micro today, or circle the bingo number below for ARCnet™ LAN solutions.

**InterContinental
Micro**

4015 Leaverton Court, Anaheim, CA
92807; Phone: (714) 630-0964
Telex: 821375 SUPPORT UD; Easylink: 62562040.

ARCnet is a trademark of Datapoint Corporation.

Call for GSA pricing.



CIRCLE NO. 117 ON READER SERVICE CARD

Read what the experts say about the PC's Limited AT.

"I have no qualms recommending this system to experienced users who need the added speed."

—Sol Libes,
Micro/Systems Journal,
January/February 1986

30 DAY
Money-Back
Guarantee




"The PC's Limited AT™ proved to be the functional equivalent to the IBM® product, only faster. Priced at roughly one-third less, it rates as one of the best bargains available."

—Winn L. Rosch,
PC Magazine,
February 25, 1986

"If price is your primary consideration, skip both AT&T® and TI® and choose this issue's best buy, the PC's Limited AT™. Check its benchmark results—you won't be sacrificing performance to save money."

—PC Magazine,
Editor's Choice,
February 25, 1986

**And if that's not enough to convince you,
now we've got a 30-day money-back guarantee.**



- One Year Limited Warranty
- 80286-based System Unit (Runs at 6MHZ. 8MHZ option included at no extra charge.)
- 1024K on Mother Board
- 1.2 Meg Floppy Drive
 - Combined Floppy/Hard Drive Controller Card
 - AT Keyboard
 - 192W Power Supply
- 2 Serials and 1 Parallel Port
 - Clock/Calendar with Battery Backup
 - Operations Manual

\$1495

I'm Michael Dell, President of PC's Limited. And I want you to know about your latest industry-leading step. We're so sure that you'll like everything about our PC's Limited AT that we're willing to offer you a 30-day money back guarantee on it. This machine, with 1024K on the Mother Board and an 8MHZ option included at no extra cost, has been a standout since we introduced it. So give us a chance to show you what it can do for your operation. With a deal like this, there's no way you can lose. (And see the opposite side of this page for information about our Turbo PC™, plus details on our guarantee.)

Michael Dell

When a PC's Limited Turbo PC is on your desk, you'll think it's a headliner too.

"... a good machine. And a heck of a buy... a fine box. One I'd happily choose over Big Blue's original... no status... beyond the status that attaches to getting twice as much for your money."

—Jim Seymour,
PC Week,
August 13, 1985

"It almost sounds unbelievable."

—MIS Week,
August 21, 1985

TOTAL SATISFACTION GUARANTEE WARRANTY

For Warranty Service: One year Limited Warranty on PC's Limited products. Contact Technical Support for a Return Authorization Number (RMA). Returns must be accompanied by your RMA, the invoice, and a brief explanation. During the Warranty Period, PC's Limited will repair or replace items at our option.

30-DAY TOTAL SATISFACTION GUARANTEE

Any item bought from PC's Limited may be returned within 30 days from the date it was shipped for a full refund of your purchase price. Returned items must be as new, not modified or damaged, with all warranty cards, manuals, and packaging intact. Returned items must be shipped prepaid and insured, and must bear a PC's Limited Credit Return Authorization (CRA) on the shipping label. Call PC's Limited's Customer Support Department for CRA. No credit issued after 30 days from date of shipment.

CONSUMER TIP

When shopping for PC products, ask our competitors about their refund policies.

"We tested a wide variety of software on the machine and everything ran well... The bottom line for anyone considering buying one of these computers would seem to be this: PC's Limited sells quality systems for extraordinarily low prices."

—PC Week,
October 29, 1985

- 16-bit 8088-2 System Unit (runs at 4.77 or 6.66MHz)
- 640K on Mother Board
- 360K Floppy Drive
- AT Keyboard
- 130W Power Supply
- Operations Manual
- One Year Limited Warranty


\$795

Microsoft GW Basic™ \$95 • IBM DOS 3.1 \$85 • 8087-2 \$149



Our Turbo PC™ has sold in large quantities since the first week we introduced it. Of course, that's not surprising, since we were the first company to break the \$800 barrier with a machine that outruns the "Big" name by a 40% speed factor. Now, we're going to extend the margin even further by offering a 30-day money back guarantee. If that sounds good, it'll look even better when one of our Turbo PC's is on your desk. So call us today. We're guaranteeing you'll like what you get.

Some quantities may be limited. PC's Limited sells equipment certified to be compliant with FCC Class B standards. Where equipment manufactured by PC's Limited has not yet received certification, PC's Limited will substitute equivalent certified equipment. All prices are subject to change without notice. We are an independent sales organization.



PC'S LIMITED™

SALES CALLS OUTSIDE TEXAS, 1-800-426-5150

SALES CALLS INSIDE TEXAS, 1-800-252-8336


1611 Headway Circle, Building 3, Austin, Texas 78754

Sales Calls from anywhere in the country, (512) 339-6962

Technical Support Calls, (512) 339-6963 Customer Service Calls, (512) 339-6964

*Limited Warranty

Telex No 9103808386 PC LTD FAX (512) 339-6721



Call for latest prices.

FREE SHIPPING

in the Continental United States via UPS Ground.

NO SURCHARGE FOR



OR




30 DAY
Money-Back
Guarantee

Floppy Disk Drive

Also available for AT™
in Gray Color.


MITSUBISHI
ELECTRONICS
Half-Height, DS/DD

\$95



PC's Limited AT Multifunction Card

- Expandable To 3 Meg (1.5 on Board/1.5 on Piggy Back Board)
- Supports 64 or 256K Rams
- Parallel Port
- Serial Port (2nd Serial Optional)



\$199


Piggy Back
w/OK Board \$59 w/OK

PC's Limited Mini I/O

- Serial Port
- Parallel Port
- Clock
- Software
- Fits In Short Slot

\$99

300/1200 Baud Hayes Compatible Modem Fits in Short Slot



\$159

64K RAM

Set of 9 chips, 200 or 150 Nanoseconds

\$10

per set


256K RAM \$29

Set of 9 chips
150 Nanoseconds

PC's Limited Monochrome Graphics Fully Hercules Compatible


\$159

- Text Mode 80 X 25
- Graphics Mode 720 X 348 Pixels
- One Parallel Printer Port



Seagate 20, 30 and 40 MEG High Speed 40 MS Access Time Hard Drives for AT™

Uses Linear
Voice Coil
Activator.



Heads park automatically
at power down.


20 MEG \$579
30 MEG \$699
40 MEG \$819

Includes Seagate Full Height Hard Disk,
Cable, and Mounting Rails.
Boots from Hard Disk. One Year Warranty.

PC's Limited PC-576 RAM Board

- Expandable to 576K
- Supports 64K or 256K RAMS
- Fits in Short Slot

\$69 w/OK



PC'S LIMITED Six Function Card

- Upgradable to 384K
- Clock/Calendar
- Includes Software
- Parallel Port
- Serial Port
- Game Port




Two Year Warranty

w/OK \$99 w/384K \$129

SOLVE YOUR POWER PROBLEM.

XT™ POWER 130W

\$99




Directly replaces power
supply in PC.™
Fully XT™ compatible.
One Year Warranty

PC'S LIMITED MONO-1 MONITOR \$169
PC'S LIMITED RGB-1 MONITOR \$459



- 12-inch screen
- Amber
- Compatible with monochrome or color graphics cards




- .31MM dot pitch
- RGB input
- 12-inch screen
- 690X240 resolution
- 16 colors

Wangtek 60 MEG Tape Backup System

- Backs up 5 Megs per minute
- Runs under MS DOS or PC DOS, Novell, Xenix
- Pulse Software Included

\$795



Tandon HD □ Western Digital Controller 20 MEG Hard Disk System for PC™

Internal \$409



Includes Tandon Hard Disk, Western Digital Controller, Cables, Manual, Software, and Mounting Hardware. Boots From Hard Disk One Year Warranty

Or add a second 20 MEG Hard Drive to your system with the PC's Limited Hard Disk Kit—Two 20 MEG Hard Disks daisy-chained together, plus a controller card—\$695.

Our Hard Disk Systems are compatible with the latest versions of the following Computers: IBM PC, IBM XT, AT&T 6300, Compaq Deskpro, Tandy 1000, Tandy 1200, PC's Limited Turbo PC, Leading Edge PC (Both Models), Sperry PC, Wyse PC, Televideo PC, Faraday Mother Boards, Corona PC, Eagle PC, ITT PC, and most other Compatibles.

PLEASE SPECIFY YOUR COMPUTER TYPE WHEN ORDERING.

WARRANTY

For Warranty Service: One Year Limited Warranty on PC's Limited products. Contact Technical Support for a Return Authorization Number (RMA). Returns must be accompanied by your RMA, the invoice, and a brief explanation. During the Warranty Period, PC's Limited will repair or replace items at our option.

30-DAY TOTAL SATISFACTION GUARANTEE
Any item bought from PC's Limited may be returned within 30 days from the date it was shipped for a full refund of your purchase price. Returned items must be as new, not modified or damaged, with all warranty cards, manuals, and packaging intact. Returned items must be shipped prepaid and insured, and must bear a PC's Limited Credit Return Authorization (CRA) on the shipping label. Call PC's Limited's Customer Support Department for CRA. No credits issued after 30 days from date of shipment.

CONSUMER TIP

When shopping for PC products, ask our competitors about their refund policies.

Ad Number A07/86



PC'S LIMITED™

SALES CALLS OUTSIDE TEXAS, 1-800-426-5150

SALES CALLS INSIDE TEXAS, 1-800-252-8336

1611 Headway Circle, Building 3, Austin, Texas 78754

Sales Calls from anywhere in the country, (512) 339-6962

Technical Support Calls, (512) 339-6963 Customer Service Calls, (512) 339-6964

Telex No 9103808386 PC LTD FAX (512) 339-6721

*Limited Warranty

Panasonic, TEAC, Mitsubishi, Intel, IBM, Hercules, Plantronics, Xebec, Seagate, Western Digital, AT&T, Compaq, Tandy, Leading Edge, Sperry, Wyse, Televideo, Faraday, Corona, Eagle, and ITT are registered trademarks of their respective companies. IBM PC, IBM XT, IBM AT, are trademarks of IBM Corporation. Leading Edge PC, Sperry PC, Wyse PC, Compaq Deskpro, Televideo PC, Corona PC, Eagle PC, AT&T 6300, Tandy 1000 and Tandy 1200 are trademarks of their respective companies.

Some quantities may be limited. PC's Limited sells equipment certified to be compliant with FCC Class B standards. All prices are subject to change without notice.

IBM MERGES WITH AT&T

**Or DEC. Or DG, HP, or Wang. Or any other computer using
BLAST Data Transfer Software.**

Quite simply, BLAST solves one of the most basic problems of information management today: getting data from one computer to another reliably. And it does so faster, more efficiently, and less expensively than any other method available.

We'd be happy to send you the details of how BLAST works. But what it all boils down to is this: BLAST breaks the incompatibility barrier between 180 different micros, minis and mainframes. Perhaps more importantly, it does so across myriads of different operating systems.

Link any number of computers.

Using BLAST, you can link any number of computers over data switches, PBXs, satellite links, LANs and packet networks. BLAST can operate over hardwired RS-232 links or through low-cost asynchronous modems.

**BLAST IS AVAILABLE FOR
180 MAJOR COMPUTERS,
INCLUDING THE FOLLOWING:**

MAINFRAMES

**IBM VM/CMS & MVS/TSO; AMDAHL
MVS/TSO**

MINIS

**DIGITAL EQUIPMENT VAX/VMS, PDP/
RSX, RT-11; WANG/VS; DATA GEN-
ERAL AOS, AOS/VS, RDOS, DOS;
HARRIS VOS; AT&T 3B2, 3B5, 3B20,
NCR TOWER/UNIX; HEWLETT PACK-
ARD 3000/MPE, 1000/RTE, 9000 UNIX;
PRIME PRIMOS**

MICROS

**AT&T 6300 & UNIX PC; UNIX SYS 5,
BSD 4.2; APPLE DOS, MACINTOSH;
MS-DOS/PC-DOS, CP/M 80, 86**

IBM® is a trademark of International Business Machines
AT&T® is a trademark of American Telephone & Telegraph

Whatever system you use, your data will transfer *100% error-free*, even through hazards like phone noise, delays and distortions.

No expensive add-on boards required.

BLAST software is specifically tailored to the computer you're using. So you won't have to purchase any additional hardware or interfaces.

You can order BLAST—or get more information—by calling us at the toll-free number below. Or, you can write to us at: Communications Research Group, 8939 Jefferson Highway, Baton Rouge, LA 70809. Telex 759985.

1-800-242-5278

BLAST®

text to clarify their meaning, with the key words themselves lined up in a single column in the center of the page. This creates an index that can be easily scanned. A full page of instructions on how to use the index is included. Furthermore, the indexes are large—21 full pages of single-spaced type for the programmer's reference.

Both compiler and generated code are robust. One peculiar bug was identified, however: the compiler chokes on a small number (about 40) of comment delimiters (curly braces or asterisks) in column 1 of the source file. Aside from the fact that Pascal is supposedly column-independent, every considerable Pascal system I have seen has hundreds of comment delimiters in column 1. The interface library source code provided with the product uses the Ada-style double-dash, rest-of-line comment delimiter almost exclusively, so this bug may be an oversight based on a developer's stylistic preferences. It shakes the user's confidence in the rest of the system, however. That, and the inability of the code to open a file of records for update are the only serious flaws in an otherwise rock-solid product.

Professional Pascal makes no concession whatsoever to simplicity. The aim is power, and power is what it delivers, damn the cost. This is at once the most expensive, best documented, most powerful, and least accessible Pascal available. It requires a great deal of study and close attention to its mountain of detail, but it is capable of handling as large and complex a project as anyone would ever be willing to undertake in Pascal.

TURBO PASCAL

A certain elemental tension exists between ease-of-use and complexity in the nature of any tool. Very powerful tools tend to be complex and require much study and practice, losing the beginner and the impatient in the process; tools with little power are branded as toys and quickly shelved. Somewhere between the two is a "Golden Mean," at which a tool can be simple enough to draw in the new and the restless, yet powerful enough to accomplish significant work. Turbo Pascal has struck closer to this ideal than any compiler reviewed; this more than anything else accounts for its incredible popularity. (Turbo Pascal was *PC Tech Journal's* Product of the Month in January 1985.)

Turbo Pascal is a programming environment, the same as Mystic and UCSD Pascal. Within the environment are a text editor screen and two menu

screens. Text editing is done in the editor, and all other tasks are done from the menus. The menus are of the traditional press-a-character-to-choose type rather than pull-down or pop-up.

The system is very compact—a single .COM file of about 40KB. All parts of the system reside in RAM at once, so no time is lost loading system utilities or overlays. Moving among the menus and the editor is usually accomplished with a single keystroke (except to leave the editor, which requires two) as are virtually all system commands.

Compilation is accomplished in one pass to native code, which can be directed to storage in RAM (for greatest speed) or to disk as a stand-alone .COM executable file. No link step is necessary; the output from the compiler is executable code. When compiling short programs to RAM, compile time is usually only a few seconds on a PC, and even less on an AT. The environment serves productivity well and is never so obtrusive as to break a critical train of thought while developing code. As with UCSD Pascal, however, errors can be

FLASH

SPEED UP YOUR COMPUTER!

NOT COPY PROTECTED

Increase the **speed** of your computer by as much as **4-8** times. Why buy a PC AT when all you may need is some **FLASH**. **FLASH** is just that, it gives disk accesses in a **FLASH**. Every PC owner can't be without **FLASH** once the powers of **FLASH** are discovered. The program is totally invisible to the user. There is nothing to learn. Make your floppies **faster** than a hard disk. Make your hard disks faster than ever before. Allows the user to have sub-directories on his floppies without the usual loss of speed. **FLASH** will also tell you just how much faster you are running than you would have been without **FLASH**. **FLASH** is handcrafted in ASSEMBLER. Upgrade your computer with **FLASH**. Batch files will **fly** like they had wings. Save wear & tear on expensive program disks.

You'll be so **amazed** with your improved performance, you will want to call us to tell us so!

"The novice and expert alike will consider **FLASH** their most valued utility."

DAVE LEE REED
President, **SOFTWARE MASTERS**

BENCHMARKS for different programs utilizing **FLASH**

	W/O FL ASH	W/FL ASH
WORD STAR	2.0	0.33
BASICA	2.7	0.40
LINKING	113.8	6.00
SORTING FILES	105.0	27.00

When **FLASH** increases your speed it generally makes you run **3-5** times faster. In favorable conditions like the ones above **FLASH** can make your PC run **6-16** times faster! PC's over the world are screaming for **FLASH**. Reach the speed of a RAM DISK, without their disadvantages. If you think you DON'T need **FLASH**, call us and tell us why!

Order Line 1-800-25-**FLASH**
Info Line 1-317-253-8088
MC, Visa, Check, C.O.D.
For: IBM PC, AT, XT, JR, or clone.

Now utilizes expanded & extended memory.

Reg. Price.....\$69.95
Limited Time.....\$49.95
add 4.00 shpg hndl
Software Masters
6223 Carrollton Ave.
Indpls., IN 46220


THE UTILITY ROOM

■ Spool-Master , ram printer spooler. Multiple copies, handles single sheets, any buffer size.	49.95	29.95
■ Buffer-Master , keyboard buffer extender from 15 to 2000 key type ahead.	29.95	24.95
■ Super-Ram-Disk , set up MULTIPLE ram disks and as MANY as you want.	49.95	24.95
■ Calc-Pad , ram resident calculator, hex octal binary and decimal. Works in ANY graphic mode. Unlimited parenthesis nesting. Many functions.	49.95	24.95
■ Sort-Merge-Copy , a super sort utility. Use it stand alone or call it from ANY language.	150.00	49.95
■ Unprotect , unprotects basic programs.	49.95	29.95
■ Data-Path , Have paths setup to find your data and overlay files. Works with ALL programs.	49.95	29.95
■ MoreHard , gain up to 10%-50% more hard disk space! ALL programs work in harmony with each other.	49.95	29.95

SUPER-ED Version 3.0

■ Do ANY DOS command or RUN ANY program from within SUPER-ED .	■ Editing commands & colors & more are fully user configurable.
■ Turbo Pascal like environment for ANY language.	■ ON-LINE language-specific user definable HELP .
■ MULTI-FILE window editing. Move & copy between file windows.	■ Full featured editor with WORD STAR like commands.
■ Extensive Find & Replace usage.	■ Fully utilizes sub-directories.
■ ON-LINE editing HELP .	■ Supports keyboard MACROS .
	Reg. Price \$59.95 Limited Time \$39.95

We believe in the highest quality software at the lowest possible price!
Turbo Pascal is a trademark of Borland Intl. Word Star is a trademark of Micro Pro Intl.



Barriers Were Made To Be Broken

If you're using Turbo Pascal, Turbo Extender is the software you need to break the 64K barrier. Now write programs as long as you need, limited only by available RAM.

LARGE CODE MODEL

Write programs using all 640K without overlays or chaining. Convert existing programs with minimal effort. Offers advanced dynamic binding or standard EXE files.

MAKE FACILITY

Offers separate compilation. No starting from scratch for source code changes.

LARGE DATA ARRAYS

Automatically manages data arrays up to 30 megabytes, as well as arrays stored in expanded memory.

ADDITIONAL TOOLS

Overlay Analyst, Disk Cache, Pascal Encryptor, Shell File Generator, and File Browser.

TURBO EXTENDER

Includes 2 DSDD disks, complete source code, 150 page printed manual. Requires Turbo Pascal 3.0 and PC DOS 2.x or 3.x. Runs on IBM PC/XT/AT and compatibles. Call for MSDOS support. \$85 COMPLETE.

ALSO AVAILABLE TURBOPOWER UTILITIES

Bruce Webster, in BYTE Magazine, February 1986, named it Product of the Month, saying "If you own Turbo Pascal, you should own TurboPower Utilities, that's all there is to it."

It offers 9 programs in all, including the Program Structure Analyzer which locates subtle coding problems the compiler fails to catch. It also produces reports that describe your code, providing cross reference and hierarchy diagrams. Also includes Execution Timer, Execution Profiler, Pretty Printer, Command Repeater, Pattern Replacer, Difference Finder, File Finder and Super Directory.

TURBOPOWER UTILITIES

Come compiled, ready to use. Includes manual, reference card, three DSDD disks, complete source code. Requires Turbo Pascal 2.0 or 3.0. \$95 with source code; \$55 executable only.

GET BOTH TURBO EXTENDER AND
TURBOPOWER UTILITIES (Source) \$149

MC/VISA CALL TOLL-FREE 7 days a week
800-538-8157 x830 (CA)
800-672-3470 x830 For PO, COD,
Dealers, Info, Brochures - call or write:



478 W. Hamilton #196
Campbell, CA 95008
(408) 378-3672 M-F
9AM-5PM PST

INTERNATIONAL REPRESENTATIVES

Switzerland: Software Haus 064-512651
Japan: Southern Pacific Ltd. 045-314-9514
Norway: Polysoft 03-825275
England: Grey Matter Ltd. 0364-53499
Australia: Videogram Communications 02-627-1261

PASCAL

detected only one at a time, which often makes the task of importing code from another not-quite-compatible compiler tedious in the extreme.

Borland's compiler breaks down into three separate products by the nature of floating-point support: Turbo Pascal, Turbo-87 Pascal, and Turbo-BCD Pascal. Each is a distinct and separately priced version of the environment, configured for a different real number format. The standard Turbo Pascal uses a proprietary six-byte real number format providing 11 significant figures and a range of 10^{-38} to 10^{38} . It cannot make use of the 8087 coprocessor. Turbo-87 uses the IEEE double-precision real number format occupying eight bytes and providing a range of 4.19×10^{-307} to 1.67×10^{308} . Code generated by Turbo-87 Pascal always uses the 8087 for real number operations and cannot be used on, nor can generated programs be run on, a machine without an 8087 or 80287. BCD support is provided by Turbo-BCD Pascal, which lacks a floating-point real type as well as certain built-in functions that make sense only in a floating-point context, such as Sin, Cos, ArcTan, Ln, Exp, and Sqrt. It operates with 18 significant digits, including four fixed decimal places.

The Turbo Pascal editor is a full-screen text editor, the command set of which is a subset of WordStar's, with a few annoying peculiarities. For example, tab characters in imported text are displayed as highlighted I characters (tab is Ctrl-I), while tabbing within the editor does not insert tab characters but instead puts spaces in the file until the cursor rests under the start of the next word in the previous line. The editor is not function-key driven, but a keyboard macro such as SuperKey can make the Turbo Editor "look" more like another editor if desired. Simple key-definition changes also can be made with a supplied installation utility.

The Turbo Pascal editor can pinpoint a compile-time error in the source code, allowing the programmer to enter the editor at or near the probable cause of the error in source. The Turbo Pascal system also uses this feature to locate the position of runtime errors located in the source file, by re-compiling code until the number of bytes of generated code equals the program counter value displayed when the runtime error occurred.

Typically, a Turbo Pascal program allocates all available free RAM to the heap, once it has set aside room for the code and data segments. The secondary menu allows code, data, and heap sizes

to be adjusted for programs compiled to .COM files. This is required by Turbo's program chaining scheme, which requires that enough code and data space be allocated in the root program to contain the largest program file to which control will be passed.

No linkable object format is available from Turbo, but a mechanism exists to declare a machine-code routine as external and read it from disk into the code segment at compile time.

Turbo supports the standard Pascal integer and an unsigned Byte type ranging from 0 to 255. It has no unsigned integer type (such as Word in MS Pascal), nor any long integer type. Lack of these two numeric types forces the use of real numbers in counting common system resources such as disk sectors, file records in large files, and available paragraphs of heap space. Counting with real numbers grinds like sand in the teeth; this deficiency detracts from Turbo's best application: the building of small to medium-sized utilities.

Long heap support uses New and Dispose, along with MemAvail and MaxAvail. (Mark and Release also are available for atavists.) Its 32-bit pointers can address all available RAM. Considering that it is a long heap, Turbo Pascal's heap support is very fast, more than twice as fast as Professional Pascal's short heap support in its small memory model. Entire text or graphics screen buffers can be stored on the heap and flashed into the video refresh buffer with the built-in Move statement.

String support is UCSD-style, an array of characters with a leading length byte. UCSD-style string primitives are built in, including Concat, Insert, Delete, Copy, Length, and Pos. Additionally, the plus symbol functions as a string concatenation operator. The complementary routines Val and Str perform numeric/string conversions.

Turbo provides an excellent suite of low-level machine hooks for DOS compatibles. Intr and MSDOS support software interrupt and DOS calls. All of memory is available through two pre-declared arrays: Mem, which treats memory as an array of Byte, and Memw, which treats it as an array of Integer. These arrays may be handled exactly as though they were user-defined, save that the array as a whole may not be referenced. Similarly, two arrays, Port and Portw, allow read and write access to all 8086 I/O ports. Turbo Pascal shares its Move, FillChar, and Sizeof routines with UCSD Pascal.

On a higher level, simple text and graphics windowing routines, CRT

mode controls, and raster and turtle graphics primitives are all provided. The graphics primitives are available as an external machine code file; all other features are built into the compiler itself. The graphics routines are not very fast and limited in many ways. The Circle routine, for example, cannot compensate for the IBM Color Graphics Adapter's asymmetrical pixels, and it produces pronounced ellipses in both of the graphics modes.

Portability is up to the programmer but is made easier by Turbo's fairly high degree of vertical portability to UCSD, Utah, and Pascal/MT+86. (UCSD is older than and served as a model for those three newer Pascals.) Aside from reasonable compatibility with UCSD Pascal, horizontal portability is limited to CP/M-80 and CP/M-86. Developers must keep in mind that a good many of Turbo's extensions, including text windowing and graphics, are limited to the DOS implementation. Turbo Pascal for the Macintosh and Amiga have been announced but not yet delivered.

Turbo Pascal's downward deviations from standard Pascal are fairly few, but two in particular are very irritating. Get and Put are not available; both text and binary file I/O are accomplished through Read and Write. Although Borland's extension of Read and Write are rational and intuitive, the change makes converting file-intensive code from another compiler far more work than it should be. Turbo Pascal also limits the use of Goto to within the current block. The rare times that a Goto is called for, typically in emergency situations when a program must cease what it is doing and do something else *now*, are not satisfied under Turbo's limitation. Page is not supported and is flagged as an error, but could easily be ignored. Packed is allowed, but is not functional. Procedural parameters are not supported, and variant records may not be allocated on the heap via New.

Turbo Pascal's documentation is a 375-page paperback book. It has too few useful examples of Turbo Pascal's more arcane features. In contrast, its index is excellent and its table of contents is good enough to be used as a second index. The simplicity of Turbo Pascal helps here. Its documentation is fairly complete without being as thick as a phone book. Although the font and general design are very legible, typographical errors have been a problem since release 1.0, and the first pass should be made with a red pen and the READ.ME file close at hand.

"...RUN/C (Professional) outclasses the other products...It is the overall best choice in a C interpreter."

Marty Franz, PC Tech Journal, May '86

You don't get to the top by just being ordinary. You have to offer more: more functions, more features, more value. Enter RUN/C Professional.

With RUN/C Professional, you can dynamically load and unload previously compiled functions, and execute these functions in real-time at compiled speed.

RUN/C Professional includes an array of source-code debugging facilities to test your modules before compiling. Trace by line ranges. Execute by function in immediate mode. Set multiple breakpoints. Read and/or change the value of a variable and continue with the execution of a program.

Along with these state-of-the-art features, RUN/C Professional comes complete with clear, thorough documentation loaded with examples and an extensive index.

See why PC Tech named RUN/C the best C interpreter on the market today. Talk with the experts at Lifeboat.

1-800-847-7078 In NY: 914-332-1875

The Full-Service Source for Programming Software.

LIFEBOAT

Lifeboat
55 South Broadway
Tarrytown, NY 10591

CIRCLE NO. 173 ON READER SERVICE CARD


PERSTOR™

Removable Hard Disk Cartridge Expansion Systems

BERNOULLI ALTERNATIVE!

- High Performance Fixed and Removable from 10 to 560 mbyte

- Internal or external mount



- The only Removable Hard Disk Cartridge Drive that attaches directly to the IBM PC-AT Controller*—internally mounted

PERSTOR™ products provide portability, storage and backup for IBM-PC, AT, XT and compatibles.

DOS, Xenix, Multi-User and Networks

Combine a removable (12MB) with another drive—removable or fixed (26MB-140MB) for a highly flexible systems solution!

SYSTEMS & SOFTWARE, INC. (602) 948-7313
7825 East Redfield Road, Scottsdale, AZ 85260

*Patent Pending Copyright 1985 Perstor® is a trademark of Systems and Software, Inc. IBM-PC, AT, XT, are registered trademarks of International Business Machines Corp.

CIRCLE NO. 231 ON READER SERVICE CARD

Support is available not only from Borland itself but from many user group SIGs and a forest of computer bulletin boards. Megabytes of public domain source code are available from user groups and BBSs, and while some of it is predictably amateurish, much of it, like the PIB utilities from Northwestern University's Phil Burns, is excellent. Turbo's third-party enhancements have exploded over the last 12 months and now comprise an industry to themselves. Bizarre but useful solutions to Turbo's lack of a linkable object format have been offered, along with many excellent source-form and external-form libraries from vendors such as Blaise Computing and Metagraphics. Several good books focusing exclusively on Turbo are available, and Borland itself publishes a detailed beginner's tutorial, called *Turbo Tutor*.

Against all of this must be weighed the 5,000-line barrier: for applications longer than 5,000 lines, Turbo Pascal becomes considerably more trouble than a compiler designed specifically for large projects, such as MS Pascal and especially, Professional Pascal. Overlays can extend the 64KB code segment limitation considerably, but Turbo Pascal overlays make an application notoriously difficult to debug. Lack of an .OBJ

format makes symbolic debugging techniques useless. Without any convenient means to break down a large application into separately compiled boxes, Turbo is not particularly appropriate for team-developed software.

On the other hand, Borland President Philippe Kahn has made it plain that these are design decisions serving an overall goal of simplicity. Within its niche, for utilities and business applications up to about 5,000 lines in size, Turbo Pascal is unexcelled.

UCSD PASCAL

When SoftTech Microsystems went bankrupt last year, a group of investors and long-time p-System users purchased the company's assets and re-released the p-System and the three UCSD languages, Pascal, FORTRAN, and BASIC, under the name Pecan Software Systems. The p-System and one language can be purchased for \$79.95—an awesome bargain for a system of this power. More languages are under development, including C and COBOL. Pecan recently bought Volition Systems and will be adding Volition's p-System-based Modula-2 compiler to the Pecan line. The new company's stated intent is to have every major language implemented as quickly as possible.

The driving force behind the p-System philosophy is horizontal portability. The p-System is actually an operating system atop an operating system and provides a common face to the programmer no matter what operating system lies beneath it. It is available for virtually all important machines and operating systems (see table 1).

The p-System reflects 1977 thinking in many ways. Disk storage is handled by defining virtual volumes on the host system disks. A virtual volume can occupy an entire floppy disk with a proprietary format, or it can be a large DOS file on a floppy or hard disk. Unlike DOS, the p-System has no FAT, and disk sectors are allocated statically. If several files are created sequentially on a volume and a few are deleted in the middle, the space they took is not returned to a free sector pool; instead, it remains as "holes" in the volume. To consolidate and reclaim the space, a "Krunch" command must be issued explicitly, which moves files around wholesale until all free space is collected at the end of the volume.

Differences in instruction sets and architectures are handled by creating a pseudomachine (p-machine) that has its own pseudoinstruction set that is the same across all p-System implementa-


More COBOL productivity...

...than you ever thought possible. Micro Focus' productivity tools are closely integrated to give you interaction, speed of response and functionality beyond your wildest dreams. You can create code fast, test it thoroughly and modify it easily. You can use your PC as a programmer workstation for mainframe applications and for creating high performance PC applications.

COBOL has evolved. Find out how this evolution can help you...

MICRO FOCUS

2465 East Bayshore Road
Palo Alto, CA 94303
Telephone: (415) 856-4161



Yes, I'm interested in the widest range of development products for PCs.

Single-user _____ Multi-user _____ PC DOS _____ Unix _____ Other _____

Programmer Workstations:

- ☐ VS COBOL Workbench
☐ Professional COBOL

Compilers:

- ☐ VS COBOL Compiler
☐ High Performance Level II COBOL
☐ Level II COBOL/ET
☐ Mac COBOL

Development Tools:

- ☐ ANIMATOR
☐ FORMS-2
☐ CO-Graphics
☐ CO-Maps
☐ CO-Math
☐ micro/SPF

Application Generator:

- ☐ Sourcewriter

Name _____

Title _____ Phone _____

Company _____

Address _____

City _____ State _____ Zip _____

Send to: Micro Focus, Inc., 2465 East Bayshore Road, Palo Alto, CA 94303

PCT 7/86

Level II COBOL, VS COBOL Workbench, ANIMATOR, FORMS-2, Professional COBOL, CO-Maps, Mac COBOL and CO-Graphics, are trademarks of Micro Focus Limited. micro/SPF is a registered trademark of Phaser Systems, Inc. Sourcewriter is a trademark of Softwright Systems Limited.

tions. This p-machine is an interpreter and exacts a perceptible but not unacceptable overhead. (There are mitigating factors for the PC; see below.) The system components are written in the p-machine's p-code, so to move the system to a new environment, only the interpreter must be rewritten.

Languages under the p-System all compile to the same p-code and follow identical calling conventions, so modules separately compiled under Pascal, BASIC, and FORTRAN (as well as upcoming new languages) can be linked interchangeably, as is possible with Microsoft's Pascal, C, and FORTRAN.

The p-System is menu-driven, with each menu a line of key words displayed at the top of the screen. Each key word may be selected by a single character. The major system components are the editor, compiler, and filer. Optional components include debugging tools and a p-assembler for creating p-code directly. As with Turbo Pascal, the programmer enters a working file name and then can move freely between editing, compiling, and running the program under development.

The UCSD compiler operates in a single pass to p-code. Some implementations, including the PC's, have a native code generator that may be invoked as a second pass. Even though native code may be produced, the files cannot stand alone; many of the built-in functions remain in p-code libraries. Nor can the interpreter and libraries be combined into a stand-alone DOS file; however, the p-System may be configured to "autostart" an application as soon as the p-System is invoked from DOS.

The native code generator pass is unique in that it can be invoked on a procedure-by-procedure basis. Integer performance improves by a factor of eight for native code over p-code, and by a factor of three for nontranscendental real operations. Native code does little for heap, screen, and file operations, so such code is best kept in the more compact p-code form.

Compiler performance falls somewhere between the disk-bound filter-type compilers of MS and Professional Pascal and the memory-resident Turbo Pascal. The compiler must be loaded from disk each time it is invoked, but the source code remains in RAM for small files. Object code is always written to a disk file. Given all that disk access, the compiler is fast, but it is slow enough to start a programmer's toe tapping, even on small projects.

Code performance holds some surprises. On the screen access bench-

mark, UCSD Pascal beat all other products except Mystic Pascal by at least a factor of three, even from p-code. The native code generator is good and puts UCSD numerics in the same league with Turbo, MS, and Professional. Where the intervening layers of the p-System make themselves felt most strongly is in file I/O. UCSD file performance lags behind Turbo, MS, and Professional by an order of magnitude.

The UCSD editor can best be described as an obtrusive nuisance and is by far the weakest part of an otherwise

strong system. It dates back to the genesis of CRT terminals and is designed to minimize the influence of slow serial terminal links and limited CRT control. In recent years editing software has moved away from strictly delimited modes to unlimited full-screen insertion and deletion, but the UCSD editor's four major modes—insert, exchange, delete, adjust—remain.

In the editor's command mode, the cursor can be moved about the file, but only commands may be entered; nothing can be typed or deleted. To delete


Programmer Essentials

"Offers many capabilities for a reasonable price"

W. Hunt, PC Tech Journal

"I highly recommend the  UTILITY LIBRARY"

D. Deloria, The C Journal



ESSENTIALS

\$100

200 functions: video, strings, keyboard, directories, files, time/date and more. Source code is 95% C. Comprehensive manual with plenty of examples. Demo programs on diskette. Upgrade to THE C UTILITY LIBRARY for \$95.

THE UTILITY LIBRARY

\$185

Thousands in use world wide. 300 functions for serious software developers. The C ESSENTIALS plus "pop-up" windows, business graphics, data entry, DOS command and program execution, polled async communications, sound and more.

ESSENTIAL GRAPHICS

\$250

Fast, powerful, and easy to use. Draw a pie or bar chart with one function. Animation (GET and PUT), filling (PAINT) and user definable patterns. IBM color, IBM EGA and Hercules supported (more soon). NO ROYALTIES. Save \$50 when purchased with above libraries.

Compatible with Microsoft Ver. 3, Lattice, Aztec, Mark Williams, CI-C86, DeSmet, and Wizard C Compilers. IBM PC/XT/AT and true compatibles.

C Compiler Packages: Microsoft C - 319, Lattice or CI-C86 compilers - \$329. Save \$40 - \$50 when purchasing compiler and library combinations. Specify C compiler and version number when ordering. Add \$4 for UPS or \$7 for UPS 2-day. NJ residents add 6% sales tax. Visa, MC, Checks, PO's.



ESSENTIAL SOFTWARE, INC

P.O. Box 1003 Maplewood, NJ 07040 914/762-6605

CIRCLE NO. 120 ON READER SERVICE CARD

Fortran Support for IBM PC/XT/AT & Compatibles

Versions Available For:

Microsoft, Supersoft, RyanMcFarland, IBM Professional, Lahev, & IBM Fortran.

Forlib-Plus \$69.95

Supports graphics, interrupt driven communication, program chaining, and file handling/ disk support. A Fortran coded subroutine is included which will plot data on the screen either in linear/linear, log/linear, linear/log, or log/log on the appropriate grid.

Strings & Things \$69.95

Supports string manipulations, command line usage, DOS call capabilities, SHELL generation and data transmission, BATCH file control, music generation, PEEKS and POKES, PORT access, and general register manipulations.

For-Winds \$89.95

Gives the Fortran programmer the capability of generating up to 255 windows on the screen. Each window can be individually scrolled, moved, sized, generated, and removed. Both color and monochrome type displays are supported. Full source code is supplied for customization.

ACS Time Series \$495.00

This is a COMPLETE time series analysis package which contains VERY HIGH SPEED FFTs, Filter generations, convolutions, transfer function calculations, auto and cross spectra calculations, Cepstrum, curve fitting algorithms, coherence calculations, and many other associated routines. The price includes FULL source code.

Fortran Scientific Subroutine Package \$295.00

There are approximately 100 Fortran subroutines included which fall under the following 12 categories:

1) Matrix storage and Operations 2) Correlation and Regression, 3) Design Analysis (ANOVA), 4) Discriminant Analysis, 5) Factor Analysis, 6) Eigen Analysis, 7) Time Series, 8) Nonparametric Statistics, 9) Distribution Functions, 10) Linear Analysis, 11) Polynomial Solutions, 12) Data Screening. Full source code is included.



Alpha Computer Service
5300 Orange Ave., Suite 108
Cypress, California 90630
(714) 828-0286

California Residents
Include 6% Sales Tax

There are NO license fees

PASCAL

text, the user must enter D, move the cursor past the text to be deleted, and then press Ctrl-C. Any text between the cursor's position on entry and exit from delete mode is deleted. Insert mode inserts text, and exchange mode types over existing text. Each mode must be exited by pressing Ctrl-C, at which time changes made take effect in the file. Control of Pascal's line indentation on existing text must be handled from adjust mode, which allows a line to be moved horizontally.

Performing any amount of editing using these modes takes two or three times the keystrokes a more modern editor requires. Fortunately, the UCSD editor is an installable program file (unlike, say, the Turbo Pascal editor) and if the p-System becomes popular again, someone could make a lot of money offering a p-System text editor that operates like the Turbo editor or Satellite Software International's P-Edit.

UCSD Pascal supports the standard Pascal integer and expresses real values in eight bytes. It has no unsigned integer or byte types. However, an intriguing variable-precision long integer type may contain up to 36 significant digits. The long integer is not a simple type and is not able to be returned by a function, act as a loop control variable, or index arrays. The limitations of the long integer type are not fully explained in the text and had to be discovered by experimentation.

Support of the 8087 is handled by installing a special version of the p-machine interpreter, the runtime library, and the native code generator. The 8087 native code generator produces a six- to eightfold improvement over p-code in real number and transcendental performance.

If UCSD Pascal's file support looks familiar, it may be because later and more familiar implementations such as Turbo and Pascal/MT+86 use it as a functional model. Seek and the IOResult function originated here. No Assign procedure is available; logical/physical file assignment is handled within Reset and Rewrite. Ordinarily, files are handled through the p-System's file manager, but if broad horizontal portability is not an overriding concern, a feature called the *DOS bridge* allows direct access to DOS files. This improves performance somewhat over p-System access (except, inexplicably, for text file reads), but sacrifices the portability that is the p-System's greatest virtue.

UCSD string support is similar to Turbo Pascal's, because UCSD set a consistent standard for Pascal strings that

Turbo followed. String variables are represented identically, as arrays of characters with a leading length byte; UCSD was the basis for all of Turbo's string primitives, except Val and the plus symbol for string concatenation.

Separate compilation is similar to MS Pascal's scheme. A separately compiled unit has both an interface and an implementation part, and, once perfected, compiled units may be gathered into libraries with an included utility. Units can serve as an overlay scheme—a unit generates a p-System code segment and may be swapped in and out of memory by the runtime memory manager. The p-System's "real" overlay scheme—called *segmentation*—is more appropriate for dividing large programs into manageable sections.

Not much in the line of debugging tools is provided with the \$79.95 package. This is an important consideration, because most DOS-based debuggers will not work under the p-System. A separate \$49.95 package contains a symbolic debugger, p-instruction disassembler, cross referencer, and toolkit for recovering data from damaged disks.

A host of library units provide frosting to the basic Pascal toolkit, including text windowing, turtle graphics, IBM display adapter low-level support, joystick, paddle, light pen, and sound support, keyboard redefinition, and system clock access. A serial communications utility is included with every implementation of UCSD Pascal to facilitate wire transfer of files between machines with incompatible media. Pecan's turtle graphics are fast and have elements of raster graphics often missing from turtle implementations. This is certainly appropriate for generating business graphics, although no graphics printer support is provided.

Like Mystic Pascal, UCSD supports concurrent processes—but UCSD's are fully implemented. To call concurrent processes multitasking is stretching the point, because no time slicing is involved. A process, once it is initiated, continues running until it is interrupted or finishes or must wait on a semaphore. Hardware interrupts and two higher-level events may suspend a process in favor of another: the PC's timer tick and a key press. Using these events and semaphores, a programmer could build a time-slice emulator in Pascal, but the overhead exacted probably would be unacceptably large. Processes are much more suitable for problems such as communications input buffering and keyboard input editing. Pecan's documentation of concurrency is insuf-

ficient—a person unfamiliar with the concept would be lost.

It is too early to judge how well Pecan will support the reborn p-System—the acid test will come when 100,000 or more units are sold and in use. The documentation will help, as it is enormous (593 pages), dense (each page is filled to the brim), and reasonably complete. Such a large tome is necessary because the p-System is complex and for most DOS users is an alien environment. A very good tutorial begins the manual and quickly gives the new user a flavor for the system in general and the editor in particular.

The manual suffers from the same disease as MS Pascal's—essential details are missing, typically in the most technical areas. One example is the lack of detail regarding variable-precision long integers, as mentioned above. Another involves concurrency; the statement is made that a process's stack must have room to evaluate expressions, but no guidelines are given on determining how much room is required. Documentation on concurrency is almost nonexistent—this is made all the worse because it is a unique and potentially valuable feature that probably goes unused for being so badly understood.

UCSD Pascal's fundamental problem is that it must drag its past along with it. Clever work could free it to some degree; the p-System could be modified to do dynamic sector allocation in the DOS fashion, rather than the older delete-and-repack model of disk management. Its editor could be replaced tomorrow with something better. These anachronisms, along with its isolation from DOS, might warn some developers away.

UCSD Pascal is, however, a special case, because the overhead of the p-System buys what no other Pascal can hope to offer: near-absolute horizontal portability to virtually every microcomputer and operating system of consequence in use today. Every copy of an application requires a copy of the environment, but various licensing arrangements are available for developers that can bring the per-copy overhead well below the \$79.95 list price.

UCSD is not a good choice for developing small utilities, because all applications must be run from the environment. Nor is it likely to compete for developers who limit their scope to IBM PCs and compatibles, where run-time fees for developer tools have all but disappeared. For the vertical market applications developer chasing a narrow niche, however, this is the only choice.

MYSTIC PASCAL

Mystic Pascal is the latest product from James R. Tyson, who wrote JRT Pascal for CP/M-80, and Utah Pascal, which is JRT Pascal converted to DOS. At the time of this review, Mystic Pascal was incomplete, lacking many features of standard Pascal and even some described in its own documentation. However, the product was on the market and met the other criteria, so it is included here. Mystic Canyon Software's target date for full support of the ISO standard was June 1.

Mystic Pascal is a programming environment with a very elegant function-key-driven design. The programmer may move between four screens, each with a distinct function: (1) text editor; (2) direct mode for executing programs and procedures and displaying the values of variables; (3) a system display that gives the current extent of stack, heap, data area, and other environment parameters, including a display of the status of concurrently executing processes; and (4) the laser display, which is not explained in the documentation but is a hex dump of the region of RAM containing the program code and data. Moving between the four screens is accomplished by a pop-up menu invoked by the F1 key. Executing system commands is done from a menu invoked by F2. Keys F7 through F10 display help screens summarizing the Pascal language and editor commands.

The compiler makes two passes to native code. The first pass creates an optimized intermediate code, which is then immediately converted to native code and stored in what is called the *laser area*. This area also stores the heap and the tokenized source file currently being edited. The laser area allocates as much RAM for itself as it needs, and it can expand to occupy all available RAM. This is fortunate, considering that all source and object code must reside in memory at one time, and neither separate compilation nor source include files is supported. An .EXE file generator for stand-alone program modules is planned but was not yet implemented at review time. Currently, code must be developed and run from within the environment.

The system compiles extraordinarily quickly, mostly because it is an incremental compiler—that is, it compiles just those portions of the source that have changed since the last compile. Only when a source file is loaded initially from disk is the entire file compiled at one time. Also, a partial compilation of a source code line happens

CopyWrite


BACKS UP IBM PC SOFTWARE

Hundreds of the most popular copy-protected programs are copied readily. CopyWrite needs no complicated parameters. It needs an IBM Personal Computer, or an XT or an AT, 128k bytes of memory, and one diskette drive. CopyWrite will run faster with more memory or another drive.

CopyWrite is revised monthly to keep up with the latest in copy-protection. You may get a new edition at any time for a \$15 trade in fee.

CopyWrite makes back up copies to protect you against accidental loss of your software. It is not for producing copies for sale or trade, or for any other use that deprives the author of payment for his work.

To order CopyWrite, send a check for \$50 U.S., or call us with your credit card. We will ship the software within a day.



Quaid Software Limited

45 Charles Street East
Third Floor
Toronto, Ontario M4Y 1S2
(416) 961-8243

Ask about ZeroDisk to run copy-protected software from a hard disk without floppies.

Instant-C™ **The Fastest** **Interpreter for C**

**Runs your programs 50
to 500 times faster than
any other C language
interpreter.**

Any C interpreter can save you compile and link time when developing your programs. But only **Instant-C** saves your time by running your program at compiled-code speed.

Fastest Development. A program that runs in one second when compiled with an optimizing compiler runs in two or three seconds with **Instant-C**. Other interpreters will run the same program in two minutes. Or even ten minutes. Don't trade slow compiling and linking for slow testing and debugging. *Only Instant-C will let you edit, test, and debug at the fastest possible speeds.*

Fastest Testing. **Instant-C** immediately executes any C expression, statement, or function call, and display the results. Learn C, or test your programs faster than ever before.

Fastest Debugging. **Instant-C** gives you the best source-level debugger for C. Single-step by source statement, or set any number of conditional breakpoints throughout your program. Errors always show the source statements involved. Once you find the problem, test the correction in seconds.

Fastest Programming. **Instant-C** can directly generate executable files, supports full K & R standard C, comes with complete library source, and works under PC-DOS, MS-DOS, or CP/M-86. *Instant-C gives you working, well-tested programs faster than any other programming tool.* Satisfaction guaranteed, or your money back in first 31 days. **Instant-C** is \$495.

Rational
Systems, Inc.

P.O. Box 480
Natick, MA 01760
(617) 653-6194

PASCAL

each time a change is made to the line and the cursor leaves the line. These line-by-line incremental compilations are so rapid that the programmer does not notice them. Because of the speedy compilation and the instantaneous transfer from one screen to another, the system is very interactive and development can move extremely quickly once the shape of the system sinks into the user's reflexes.

The missing entries under Mystic in the benchmark timings table bear explanation. The linked list timings could not be taken because implementation of pointers was not complete at the time of the review. The text file read test was not implemented because Mystic Pascal cannot read a line from a text file as a unit into an array of characters via Readln. This is in line with standard Pascal, but the alternative, reading a line one character at a time by looping and testing Eoln, is so much slower than line-by-line text file I/O that comparing the two techniques would be unfair. Every other Pascal tested supports line-by-line text file I/O into string types or character arrays. Note that the screen I/O benchmark took place in nine seconds—one-third the time of UCSD Pascal and an order of magnitude faster than any other compiler.

Compiler reliability is poor. Mystic Pascal frequently locks up the AT or aborts to the DOS command line without warning. Mystic Canyon indicated that it has never systematically tested the product on the AT. On both the PC and AT, the compiler enforces its capitalization conventions on reserved words embedded in comments. Programs without reserved words in comments seem to compile and run more reliably, especially when multiline comments are involved; the line-oriented precompiler tokenizes comments but marks the tokens as nonexecutable. Single quotes within a comment confuse the system and often cause it to crash.

Incomplete as it is, Mystic Pascal is a remarkable product in several ways. It is the first incremental Pascal compiler of which I am aware, and it is also the first to incorporate multitasking in the compiler mechanism itself. The manual describes elaborate support for coprocessors, although not all of that support was implemented at the time of this review. At \$16 for a version with the documentation on disk, it is the least expensive vendor-supported Pascal in history. Printed documentation adds another \$16 to the cost.

Mystic Pascal is not ready for serious software development at this time,

but it has some intriguing technology lurking inside. Once its support for concurrency and the ISO standard is fully implemented, it will be worth its price simply to experiment with coprocessors on a high-level language basis.

UTAH PASCAL

When Jim Tyson released his JRT Pascal for CP/M-80 in 1982, the Pascal world went wild. It cost \$29.95, far less than any other commercial Pascal compiler. More than 100,000 orders came in, swamping Tyson's one-man operation and getting him in trouble with the Federal Trade Commission for failure to ship merchandise. JRT Pascal is still available from Ellis Computing as Nevada Pascal; Utah Pascal is JRT processed through Digital Research's 8080/8086 source code conversion utility and touched up to support DOS.

Utah Pascal is a filter-type compiler that processes source code to intermediate code, which is then executed by an interpreter program. The runtime interpreter cannot be merged with the intermediate code to produce a single stand-alone program. No native code generator is available, nor is any use made of the 8087. As might be expected, Utah Pascal produces the slowest code of any compiler tested.

The Utah compiler is fairly slow and locked up the computer several times during attempts to compile code from other Pascal dialects that did not match Utah syntax in all respects. A good compiler should display a meaningful error message and exit to the operating system without locking up the machine, regardless of how confused the system might be. This tendency to lock up and glacially slow code execution are Utah Pascal's worst faults.

Separate compilation is supported by a virtual storage manager acting as a smart overlay system that loads separately compiled external code modules as needed, keeping track of what has been loaded into memory and how much RAM remains. A queue of loaded routines is kept, and when storage gets short, the oldest routines are disposed of as though they were dynamic variables, until sufficient space is reclaimed.

Optionally, the programmer may link separately compiled modules with the compiled main program to produce a single intermediate code file that loads as a unit. Only 64KB are allowed for program code (excluding the runtime interpreter), stack, and heap; thus, linking modules into a single large main program decreases available stack and heap space. By leaving separately

compiled modules on disk, a program's size is limited only by disk space, thus leaving management of the 64KB segment to the virtual storage manager. The penalty is disk access time and the possibility that bad program design could lead to disk thrashing.

Utah Pascal supports a single real number format with 14 significant digits and a range of 10^{-64} to 10^{63} . All transcendental functions (Sqrt, Sin, Cos, Arctan, Ln, and Exp) are provided in Pascal source form only. They must be compiled to intermediate code and then interpreted as externals. Evaluating the expression `Sqrt(Sin(Ln(3.14159)))` 10,000 times takes 14,248 seconds, or 1.4 seconds for *each* evaluation. The source code for the transcendental functions is uncommented and not much can be learned from it. No way is provided to link machine code routines to the runtime interpreter.

Only a short heap (16-bit pointers) is available, and it must share a single 64KB segment with intermediate code, program data, and stack. Utah Pascal therefore does not make use of RAM much beyond the 128KB point. The heap is managed by the New and Dispose commands, but MemAvail and Maxavail are not implemented.

Utah Pascal's downward deviations from standard Pascal are fairly few. Most are in file syntax. Read/Write and ReadLn/WriteLn syntax has been altered in a confusing fashion. Random file access is accomplished with a needlessly complex variant on Read and Write rather than Seek. The standard predefined type Text is not supported; text files must be declared as FILE OF Char.

Utah Pascal has a good deal in common with Turbo Pascal. Its string handling is very similar, including string primitives Concat, Copy, Delete, Insert, Length, and Pos. An interesting BASIC-style dynamic array type is available. Dynamic arrays can be redimensioned during program execution to arbitrary dimensions not known at compile time and disposed of completely when they are no longer required. One very nice extension is a Picture function that formats real numbers to a COBOL-style PICTURE specifier, similar to Form in Turbo-BCD Pascal.

Few low-level system hooks are provided. Port I/O is supported, and a pointer can be generated to any address within the program's 64KB segment using a Map function—but it cannot point to CRT buffers and BIOS data areas outside the data segment. A CP/M-style DOS call routine (which makes a short jump to offset 5 in the code segment) is

provided, but no way is given to call arbitrary software interrupts.

Utah Pascal's interpreter can be toggled into and out of line trace mode, similar to TRON and TROFF in IBM BASIC. Also available is a procedure name trace mode that prints out the name of any subprogram when that subprogram is called. The runtime interpreter displays a very useful post-mortem dump of system status values (including stack base, top of stack, bottom of heap, and intermediate code address) when a runtime error occurs.

The only coding bug discovered during testing is that write parameters in Write and Writeln statements (that is, `Write(I : 4);`) do not right-justify data values in the specified field width. The documentation is only minimally adequate; it consists of a 132-page, perfect-bound volume with few useful examples and at least one major error in the description of the Call procedure: the order of the register-load variables was given in reverse, causing unpredictable mayhem during attempts to perform different DOS calls.

Aside from providing an upgrade path to DOS from JRT or Nevada Pascal for CP/M-80, Utah Pascal does not have much to recommend it. With its design philosophy firmly rooted in the eight-bit world of 1981, this is a product whose time has long passed. It wastes the resources of the PC by ignoring most of the available RAM and by swallowing machine cycles in a ponderously slow runtime interpreter. Utah Pascal's virtual storage manager, clever as it is, is a solution for a problem that no longer exists, now that 64KB of RAM costs \$10. While the code produced seems adequately robust, the compiler crashes unpredictably when too many semantic errors are encountered.

HITTING STRIDE

The very first Pascal compilers were packaged in plastic bags. They lacked reals, records, and had no documentation to speak of. Second generation Pascal compilers such as Pascal/MT+ implemented a spottily extended standard Pascal, but came with plenty of bugs, torpid code speed, and documentation that was at best tolerable. This was the status quo two years ago.

The third generation is now with us. Current Pascal compilers not only are acceptably bug-free and incorporate highly intelligent optimization, but they also have begun to specialize by application and market segment.

MS Pascal and Professional Pascal are peers in a similar market, and

ANNOUNCING ZIPCALC FOR TURBO PASCAL™

Capability to go from screen to screen in a fraction of a second will provide your software the decisive competitive edge - ZIPCALC makes this possible for both text and numbers.

INSTANT TEXT DISPLAY

Standard Pascal "write" procedure takes several seconds to fill the screen with text data. ZIPCALC fills the screen with the same text in less than 1/10 second. Full instant windowing capability is also included.

ULTRA FAST NUMBER DISPLAY

Writing real numbers adds crucial time to convert the number to a printable string. ZIPCALC removes this time barrier by providing a 32-bit Long Integer data type that converts to a printable string 7 times faster.

HIGH SPEED COMPUTATION

The Long Integer data type is the ideal alternative to the real data type for a wide variety of financial and other applications because of its dramatic increase in computation speed. ZIPCALC provides a full assortment of procedures and functions for Long Integer arithmetic, shifts, compares, conversions to other data types, and full string conversion (decimal, dollar, hex, binary). ZIPCALC puts the power of a 32-bit processor at your fingertips in convenient Pascal callable form.

EASY TO LEARN · EASY TO USE

ZIPCALC consists of 35 highly optimized procedures and functions, most assembler coded. Tutorial User's Guide, programmed demonstrations, and many examples make ZIPCALC easy to learn and easy to use.

IBM PC & TRUE COMPATIBLES

\$45 including N.Y. sales tax & shipping

DYNAMUS
MICRO-DATA SYSTEMS, INC.

1045-T Gravel Road
Webster, N.Y. 14580
(716) 671-5866



Turbo Pascal is a registered trademark of Borland International Inc.

choosing a clear favorite is difficult. Professional Pascal costs almost three times more than MS Pascal, yet does not seem to provide three times the value. Much of Professional's added worth lies with features a casual programmer will probably not even understand, much less use. By being simpler and easier to understand and use, MS Pascal is a better value for the vast majority of medium to large applications written by a single programmer. But for team programming or for very large projects comprising dozens of independently

developed modules, Professional Pascal stands absolutely alone.


IBM Pascal is a slightly simplified earlier version of MS Pascal with inferior documentation and a higher price tag. Turbo Pascal has yielded the high end of the market to achieve a speed and elegance that the larger compilers cannot match. UCSD Pascal competes best when narrowly directed toward applications that demand broad horizontal portability, but it succeeds to a degree impossible with the other compilers. As for Utah and Mystic Pascal,

one's time has passed and the other's, perhaps, has not yet arrived.

The drawing together of the true native code compilers in the performance table suggests that the Pascal compiler art for the 8086 is reaching an optimum state. Pascal's safeguards exact a certain performance penalty—for greater speed, assembly language or C is the answer. Pascal, however, was not designed for code speed, but to facilitate supportable, structured program design. From that perspective, the state of Pascal is quite clear: the language has hit its stride.



READY FOR COMMITMENT?



Let DaTapaSS Help You Tie the Knot!

If you're ready to unite your IBM PC's and compatibles to your host system, it's time you thought about DaTapaSS.

DaTapaSS is quick and simple. No fuss, no ceremony: Just a natural union of the features you need most. Features like unattended automatic file transfers. Automatic restart and recovery of interrupted transfers. Error-free uploading and downloading of binary or ASCII files: across public networks, dial-up phone lines, and direct-connect asynchronous lines. Full access to DOS functions. VT100 emulation. Key-selectable signon sequences. Softkeys you can program from DOS or your host system. Outstanding documentation. You can even use it to transfer files between different kinds of host systems.

Best of all, you can use DaTapaSS as is, or you can work with our staff of consultants to build it into your specialized applications.

So. If you're ready to exchange deadlock for wedlock, try DaTapaSS -- and give DTSS a ring!



DTSS Incorporated

A Subsidiary of Metropolitan Life Insurance Company
Buck Road • Box 70 • Hanover, NH • 03755 • 603/643-6600

CIRCLE NO. 103 ON READER SERVICE CARD

IBM Pascal: \$385
IBM Corporation
P.O. Box 1328
Boca Raton, FL 33431
Contact the local IBM dealer,
800/447-4700
CIRCLE 351 ON READER SERVICE CARD

Microsoft Pascal: \$300
Microsoft Corporation
16011 NE 36th Way
Redmond, WA 98052-6399
800/426-9400; 206/882-8080
CIRCLE 352 ON READER SERVICE CARD

Mystic Pascal: \$32
Mystic Canyon Software
P.O. Box 1010
Pecos, NM 87552
505/757-6344
CIRCLE 353 ON READER SERVICE CARD

Professional Pascal: \$695
Microtec Research
P.O. Box 60337
Sunnyvale, CA 94088
408/733-2919
CIRCLE 354 ON READER SERVICE CARD

Turbo Pascal: \$69.95
Borland International
4585 Scotts Valley Drive
Scotts Valley, CA 95066
408/438-8400
CIRCLE 355 ON READER SERVICE CARD

UCSD Pascal
Pecan Software Systems
1410 39th Street
Brooklyn, NY 11218
800/63-PECAN; in New York,
800/45-PECAN
CIRCLE 356 ON READER SERVICE CARD

Utah Pascal
Ellis Computing, Inc.
5655 Riggings Court, Suite 10
Reno, NV 89502
702/827-3030
CIRCLE 357 ON READER SERVICE CARD

LISTING 1: BENCHER.PAS

```
($floatcalls-)
($real:8)
PROGRAM Bencher(INPUT,OUTPUT); { For MS Pascal }
```

```
CONST
  Size      = 8190;
```

```
TYPE
  String64 = PACKED ARRAY[1..64] OF CHAR;
  NodePtr  = ^Node;
  Node     = RECORD
    X,Y : Integer;
    Next : NodePtr;
  END;
  DataRec = RECORD
    CustNum : Real;
    CustName : String64;
    Current : Boolean;
  END;
```

```
VAR
  NCount : Integer;
  Root,Current : NodePtr;
  TestNode : Node;
  I,J,K : Integer;
  R,S : Real;
  TextLine : String64;
  TextFile : Text;
  ReadText : String(64);
  CustRec,NewRec : DataRec;
  CustFile : File of DataRec;
  O : Text;
```

```
FUNCTION TICS : WORD; EXTERN;
PROCEDURE TIME(VAR S : STRING); EXTERN;
```

```
PROCEDURE Show_Time(VAR OutFile : Text);
```

```
VAR
  TimeString : LSTRING(15);
BEGIN
  TimeString := ' ';
  Time(TimeString);
  Writeln(OutFile,TimeString,'.',Tics:2);
END;
```

```
FUNCTION NullFunction : Integer;
```

```
BEGIN
  NullFunction := 0;
END;
PROCEDURE TestProc(K : Integer;
  CH : Char;
  MyPtr : NodePtr;
  S : Real;
  MyNode : Node;
  Name : String64);
```

```
BEGIN
END;
FUNCTION Sieve : Integer;
```

```
VAR
  I,Prime,K,Count : Integer;
  Flags : ARRAY [0 .. Size] OF Boolean;
```

```
BEGIN
  Count := 0;
  FOR I := 0 TO SIZE DO Flags[I] := TRUE;
  FOR I := 0 TO SIZE DO
    BEGIN
      IF ( Flags[I] ) THEN
        BEGIN
          Prime := I + 1 + 3;
          K := I + Prime;
```

NOT COPY
PROTECTED!



Sybil Is an Advanced Diagnostics disk...

She can low format hard disks just like Advanced Diagnostics (IBM, Compaq, etc.) and she can do system and memory tests which provide even more information than Advanced Diagnostics does. \$245.00 cheaper than IBM's Advanced Diagnostics!

Sybil is a Disaster Recovery program...

She can recover hard disks that have been accidentally formatted, completely! The hard disk reappears in exactly the same condition prior to the format. Truly amazing!

Sybil is a Graphics Editor...

She can draw on either RGB monitors (in color) or IBM Monochrome monitors in high ASCII characters. Perfect for creating Binary Image Files. The Binary Image Files can be converted to Assembly and then linked to other languages, such as your favorite Pascal, C, or compiled BASIC program. Includes source code.

Sybil is a File Wizard...

Sybil can backup files by **date**, by **time**, or by **size**. She can find any file (or files) anywhere on your hard or floppy disks, even if you haven't the vaguest notion. She can edit file attributes with the greatest of ease, unerase files, edit sectors, and globally change time and date stamps. All her file utilities understand paths and wildcards.

Sybil is also a...

RAM Disk, Print Spooler, General Regular Expression Parser and, Advanced File Comparator.

Order Sybil Today!

**Call 800-922-3001, In Colorado,
303-444-1542**



SOPHCO

PO Box 7430
Boulder, Colorado 80306



CIRCLE NO. 176 ON READER SERVICE CARD


```

WHILE ( K <= SIZE ) DO
  BEGIN
    Flags[ K ] := FALSE;
    K := K + Prime;
  END;
  Count := Count + 1
END
END;
Sieve := Count
END; ( Sieve )

BEGIN ( Bencher MAIN )
  { Open timings file: }
  Assign(O,'TIMINGS.MS');
  Rewrite(O);
  Writeln(O,'Benchmark timings for MS Pascal V3.31: ');
  Writeln(O,' ');

  { Display 1000 64-character text lines to the screen via Writeln: }
  Write(O,'Beginning text display time test at '); Show_Time(O);
  TextLine :=
  'AAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAAA';
  FOR I := 1 TO 1000 DO Writeln(TextLine);
  Write(O,' ...done at '); Show_Time(O);

  { Create linked list of 1000 8-byte nodes: }
  Write(O,'Beginning pointer chain time test at '); Show_Time(O);
  New(Root);
  Current := Root;
  FOR I := 1 TO 1000 DO
    BEGIN
      New(Current^.Next);
      Current := Current^.Next
    END;
  Current^.Next := NIL;
  Write(O,' ...done at '); Show_Time(O);

  { Dispose of a linked list of 1000 8-byte nodes: }
  Write(O,'Beginning chain dispose time test at '); Show_Time(O);

```

```

IF Root <> NIL THEN
  BEGIN
    REPEAT
      Current := Root^.Next;
      Dispose(Root);
      Root := Current
    UNTIL Root = NIL
  END;
  Write(O,' ...done at '); Show_Time(O);

  { 30000 invocations of an integer function without parameters: }
  Write(O,'Beginning function call time test at '); Show_Time(O);
  FOR I := 1 TO 30000 DO J := NullFunction;
  Write(O,' ...done at '); Show_Time(O);

  { 30000 invocations of a proc with >80 bytes of parameters: }
  Write(O,'Beginning procedure call time test at '); Show_Time(O);
  Current := NIL; R := 17.1776;
  TextLine :=
  'George Ian Howard Philips Macdonald Randolph Skeffington Bentley';
  FOR I := 1 TO 30000 DO TestProc(42,'Q',Current,R,TestNode,TextLine);
  Write(O,' ...done at '); Show_Time(O);

  { 10000 evaluations of a complicated transcendental expression: }
  Write(O,'Beginning transcendental time test at '); Show_Time(O);
  R := 3.14159;
  FOR I := 1 TO 10000 DO S := Sqrt(Sin(Ln(R)));
  Write(O,' ...done at '); Show_Time(O);

  { 10 Iterations of the ever-popular Sieve of Eratosthenes: }
  Write(O,'Beginning Eratosthenes Sieve test at '); Show_Time(O);
  FOR J := 1 TO 10 DO NCount := Sieve;
  Write(O,' ...done at '); Show_Time(O);

  { Time text file create/1000 sequential line writes/file close: }
  Write(O,'Beginning text file write time test at '); Show_Time(O);
  Assign(TextFile,'TEXTLINE.TXT');
  Rewrite(TextFile);
  FOR I := 0 TO 999 DO Writeln(TextFile,TextLine);

```

"IF YOU'RE LEARNING C AND NOT USING ECO-C88, YOU'RE WORKING TOO HARD!"



Eco-C88 is a full C compiler for MSDOS machines. Everything you need is included in the low price of \$59.95, including a full-screen editor. Here's what some reviewers are saying about the Eco-C88 C Compiler:

"Eco-C performed well on all the benchmarks, generating code that was quite comparable to that of compilers 10 times as costly."
Christopher Skelly, Computer Language, Feb., 1986

"This compiler does handle syntax errors much better than average - no avalanche of spurious messages here."
William Hunt, PC Tech Journal, Jan., 1986

"Eco-C88 is a high-quality package... convenient to use..."
Dr. David Clark, Byte, Jan., 1986

"Eco-C is definitely a bargain... it includes both the compiler and an excellent Turbo-style editor... a useful compiler for advanced applications, and will serve far beyond the beginning phase."
Gary Entsminger, Micro Cornucopia, April-May, 1986

The compiler comes with a standard library of over 200 functions, cc and "mini-make" utilities, ANSI language enhancements (e.g., prototyping), expanded user's manual, plus much more, all for the low price of only \$59.95. Also ask about our support products!

If ordered with the compiler, the C library source code (excluding transcendental) is \$10.00 and the ISAM file handler (as published in the **C Programmer's Library**, Que Corp) in OBJ format is an additional \$15.00. Please add \$4.00 for shipping and handling. To order, call or write:


Ecosoft Inc.
6413 N. College Avenue
Indianapolis, IN 46220
(317) 255-6476 • 8:30-4:30

1-800-952-0472
(orders only)



Trademarks: Eco-C88, Microstat (Ecosoft), CP/M (Digital Research), MSDOS (Microsoft), PC-DOS (IBM), Z80 (Zilog), 8086, 8087, 8088 (Intel).

New Release 4.1



We've continually improved Microstat since it was introduced in 1978, and the latest release includes many new features you've wanted.

Interactive and Batch Processing	Data sets that can exceed memory
Expanded Data Management Subsystem with New Data Transforms	Multiple Regression (including Stepwise)
Reading data files created by other programs (e.g., Lotus)	Scatterplots (including best fit regression)
3 types of Analysis of Variance	Correlation Analysis
Time Series	12 Nonparametric tests
Crosstabs and Chi-Square	8 Probability Distributions
Factorials, Permutations, and Combinations	Descriptive Statistics
Hypothesis Tests	Easy Installation

Microstat's algorithms have been designed to prevent numeric overflow errors and yield unsurpassed accuracy. Microstat's price is \$375.00 including the user's manual and is available for the Z80, 8086, 8088 CPU's and CP/M80, CP/M86, MS-DOS, and PC-DOS. To order, call or write.



NEW \$89.95 PRICE! 30-DAY MONEY-BACK GUARANTEE

Now Everest's EditCheck brings you a PC environment platform for C source program development

EditCheck is a new kind of programmer's tool that provides an integrated C Language source code programming platform. It improves your productivity, and reduces your frustration caused by making multiple cycles between a program editor and a compiler to manually locate and eliminate syntax, semantic, and other errors in your programs.

You can think of EditCheck as a powerful editing and program checking facility that works as a front-end companion to your C compiler.

EditCheck consists of a window-oriented full screen editor, an extensive C language program checker, a file access facility, and a context sensitive on-line help facility, all united in a consistent, integrated environment platform that extensively uses a fast windowing system.

All EditCheck commands can be executed through single-keystrokes, or thru a fast pop-up menu system, or by a combination of keystrokes and menu choices. All keystroke commands can be user reassigned to any keyboard key.

Intra & Inter-module Checking While Editing

The heart of EditCheck's contribution is a powerful C language program checker which provides strong type checking from within the editing environment. The checker does a thorough evaluation of your source code and detects common errors and questionable practices, including many that most C compilers will overlook.

The checker detects unused functions, and unused function arguments. At your option, unused external variables are also reported.

It also looks for functions called with a varying number of arguments.

In addition to the standard type checking performed by most compilers, EditCheck also looks for function arguments that do not agree in type with the arguments expected by the function. It looks for enumerated variables that are assigned values of a type other than that of the variable or that are used in operations not valid for enumerated types.

EditCheck complains about illegal type casts. At your option, it reports the assignment of longs to ints, of longs to chars, and of ints to chars.

The checker always reports when pointers refer to objects of different type.

If you set the environment option on, it checks for multiple definitions when all external symbol names are truncated to six characters. The EditCheck checker looks for names that would conflict if your Linker has a specific limit on the number of characters checked.

EditCheck's check facility tests for consistency of the external and global declarations of variables, functions and function arguments across multiple program modules. It also tests for consistency of the number of arguments between a function declaration and calls to the function.

At your option, the checker will also test for redefinition of an already defined symbol.

The checker runs interactively on part or all of a source program file, or group of program files. It opens a context window on the file where the error was detected and high-

lights the token which was being parsed when the error was detected. It also opens a message window with a descriptive error message, and presents a menu of options which you can take to correct the error.

These checker menu options on errors include: Show What's Legal, Delete, Modify, Edit, Backward Expand, Continue, Abort, and Forward Expand.

The checker allows you to provide a program module list for complete checking or checking of unchecked modules. You can also check the modules in this list in batch mode if you desire.

The interactive intra-module and inter-module checking capabilities in EditCheck will save you many time consuming and aggravating trips between an editor and compiler.

Window-oriented Full Screen Editor

EditCheck's editor allows you to edit text in the current window and to copy or move text from another window to the current window. The editor supports both horizontal and vertical scrolling, and allows you to create marks and zones, move the cursor to specified objects, search and replace (case sensitive or insensitive), change case of the text, control input mode, etc.

The editor uses a file paging scheme which allows you to edit and check modules larger than your available RAM memory. Any ASCII file may be read by the editor. Files may be inserted or appended to the current window file.

The editor is both key-command driven and menu driven, or mixed usage. Key-commands are fully user reassignable.

Windows, Files, and More

The EditCheck environment is window-oriented. You may have as many windows open at the same time as you wish. Windows may overlap or be tilted, at your option. You may

switch back and forth between windows, and move or copy information between them.

The windows which you open may display different files or multiple different areas of the same file. You control the location and size of all user windows, and can save the contents of a window, hide it, bury it, close it, or show it.

Windows are also extensively used by the EditCheck system to build commands, display help, show a module list, display messages, show program context while checking, etc.

A group of environment commands are available to change the coloring of windows (with a color graphics adapter and display), set the way you are notified of errors, and redefine the meaning of keys on the keyboard.

Context Sensitive Help

Help is available to you in several ways. You may use a function key to get context sensitive help particular to where you are in the system. You may select the help index, and choose a topic of interest. You may also ask the help subsystem to search for a particular word of interest within the entire system. Display of current keyboardings is also available.

No Risk Offer

EditCheck has been available from Everest for a few months under the name H.E.L.P. (Help, Editing, Lint, Productivity) at an introductory price of \$295. We've changed the name and we've changed the deal.

EditCheck is now available at the "Borland-like" price of \$89.95, shipping included to USA locations. We offer an unconditional 30 day money-back guarantee. EditCheck is not copy protected. Product upgrades will be available to registered users for one year for \$10.00 each.

Let us take the risk, and you enjoy the productive benefits of this new class of product. Order today by mail or by phone.

EVEREST SOLUTIONS, INC.
3350 SCOTT BLVD, BLDG 58
SANTA CLARA CA 95051
408-986-8977

CIRCLE NO. 161 ON READER SERVICE CARD

NOT COPY PROTECTED

EditCheck
FROM EVEREST SOLUTIONS, INC.
TO ORDER CALL 800-621-0854 EXT. 923

\$89⁹⁵

YES, RUSH EDITCHECK TO ME.
SEND ME _____ COPIES

30-DAY
MONEY-BACK
GUARANTEE

System Requirements:
IBM PC/XT/AT/COMPATIBLES
384K RAM
2 FLEX. DISK DRIVES
OR HARD DISK
DOS 2.0 OR LATER.


THIS PRICE INCLUDES SHIPPING
TO USA LOCATIONS. ALL
FOREIGN ORDERS ADD \$10
PER PRODUCT. ADD \$5
FOR COD.

SUBTOTAL _____
CA RES. ADD \$6.30 TAX PER COPY _____
AMOUNT ENCLOSED _____
PAYMENT ☐ CHECK ☐ MONEY ORDER
☐ BANK DRAFT ☐ CO, P.O. # _____ ☐ COD/UPS

Name _____
Shipping Address _____
City _____
State _____ ZIP _____
Telephone _____

The ultimate solution
for information interchange...

The ultimate 9-track magnetic tape subsystem for the IBM-PC/XT/AT and compatibles!



Innovative
Data Technology
offers a variety of 1/2
inch 9-track magnetic tape sub-
systems for the IBM-PC/XT/AT featuring
the new "LEO" PC tape controller.

"LEO" is a state-of-the-art PC tape controller that lends itself to the most sophisticated applications including real time data acquisition, multitasking and true streaming disk back-up. "LEO" comes standard with an impressive list of features that include a dedicated microprocessor, up to 64K of RAM for buffering, high speed thruput with memory mapping I/O—no DMA channel required, ASCII to EBCDIC code conversion and external cable connectors for easy installation.

Supplied on a 5 1/4" diskette is the most comprehensive set of software drivers and utilities available. Users have a choice between an installable I/O driver with modules to "Basic" and "C" languages, or an MT-DOS device driver, which allows direct tape access under any language supported by DOS 3.1. Also included is "ANSI," a sophisticated file transfer utility, "TAP" a comprehensive disk back-up and restore utility and "TCMD" tape command, a valuable tool for inspecting tape data and format. All utilities are menu driven with help screens for user friendly operation.

IDT manufactures the complete subsystem... controller and tape drive. With a commitment to excellence, IDT staffs a complete customer service department, offering you assistance to assure top performance at all times. Contact us today for additional information.



INNOVATIVE
DATA
TECHNOLOGY

5340 Eastgate Mall • San Diego, CA 92121
(619) 587-0555 • TWX: (910) 335-1610

Western Regional Office:
10061 Talbert Ave., Suite 202
Fountain Valley, CA 92078 • (714) 968-8082

Eastern Regional Office:
One Greentree Center, Suite 201
Marlton, NJ 08053
(609) 596-4538 • TWX: (710) 833-9888

PASCAL

```
Close(TextFile);
Write(0,' ...done at '); Show_Time(0);
{ Time text file open/1000 sequential line read/file close: }
Write(0,'Beginning text file read time test at '); Show_Time(0);
Assign(TextFile,'TEXTLINE.TXT');
Reset(TextFile);
FOR I := 0 TO 999 DO ReadLn(TextFile,ReadText);
Close(TextFile);
Write(0,' ...done at '); Show_Time(0);

WITH CustRec DO { Fill the test record with reasonable data: }
BEGIN
    CustNum := 0.0;
    CustName := TextLine;
    Current := True
END;

{ Time file create/1000 sequential record writes/file close: }
Write(0,'Beginning sequential write time test at '); Show_Time(0);
Assign(CustFile,'TESTDATA.BIN');
Rewrite(CustFile);
FOR I := 0 TO 999 DO {Write(CustFile,CustRec);}
BEGIN
    CustFile^ := CustRec;
    Put(CustFile)
END;
Close(CustFile);
Write(0,' ...done at '); Show_Time(0);

{ File open/1000 random read-update-in-place operations/file close: }
Write(0,'Beginning update-in-place time test at '); Show_Time(0);
Assign(CustFile,'TESTDATA.BIN');
CustFile.Mode := DIRECT; { MS Pascal only }
Reset(CustFile);
FOR I := 999 DOWNTO 0 DO
BEGIN
    Seek(CustFile,I+1);
    Get(CustFile);
    NewRec := CustFile^;
```

TURBOCHARGE YOUR IBM WITH NUCLEUS OVERTHRUSTER THE MAXIMUM PERFORMANCE FROM YOUR IBM



Super Summer Special
\$195.00 NOW \$85.00!

\$95.00 with V-20

- At last an affordable performance upgrade for the IBM PC & XT!
- 280% Processing speed increase.*
- 100% Compatible with all software.
- Does not require an expansion slot.
- Uses existing memory.
- No software modification or pre-boot required.

*As measured with the Norton Utilities.



Nucleus Corporation
California Office
17288 Santa Barbara
Fountain Valley, CA 92708
714-841-3336

CIRCLE NO. 135 ON READER SERVICE CARD


```

NewRec.CustNum := 1;
CustFile^ := NewRec;
Seek(CustFile,1+1);
Put(CustFile);

END;
Close(CustFile);
Write(0,' ...done at '); Show_Time(0);

Close(0)
END.

```

LISTING 2: MATRIX2.PAS

```

($real:8)
($floatcalls-)
PROGRAM MATRIX(INPUT,OUTPUT); ( For MS Pascal )

(* By Alan R. Miller; modified by Jeff Duntemann *)
(* from: PASCAL PROGRAMS FOR SCIENTISTS AND ENGINEERS *)
(* (c) 1981 by Sybex, Inc. *)

CONST
  RMAX = 20;
  CMAX = 20;

TYPE
  ARY = ARRAY[1..RMAX] OF REAL;
  ARYS = ARRAY[1..CMAX] OF REAL;
  ARY2 = ARRAY[1..RMAX, 1..CMAX] OF REAL;
  ARY2S = ARRAY[1..RMAX, 1..CMAX] OF REAL;
  STRING80 = LSTRING(80);

VAR
  Y : ARY;
  G : ARYS;
  X : ARY2;
  A : ARY2S;
  NROW,NCOL : INTEGER;
  CH : CHAR;
  I : INTEGER;

```

PROLOG APPLIED!

Not Copy
Protected



The FIRST Interactive
Prolog for the IBM
and Macintosh.

PROLOG/i

A new enhanced Interactive
Prolog for MS-DOS. **\$69⁹⁵**
Upwardly compatible
with PROLOG V and V-plus.

PROLOG/m

Prolog for the Macintosh!
Edinburgh syntax. **\$99⁹⁵**
Floating point,
math functions.

THREE GREAT APPLICATIONS

READY TO RUN
NO PROGRAMMING
EXPERIENCE NECESSARY.

NFL X-pert **\$49⁹⁵**
Expert system for professional
football handicapping.

TOOLBOX **\$29⁹⁵**
Including subroutines that speed
and compress list handling,
searches, sorts, reversal algorithms.

TOYBOX **\$29⁹⁵**
A collection of games and puzzles
that make learning Prolog fun.

MIX AND MATCH FOR ADDED SAVINGS

	PROLOG/i	PROLOG/m	*SAVE*
Interpreter plus...			
Toolbox or Toybox	\$ 79.95	\$109.95	\$20
Toolbox and Toybox	99.95	129.95	30
NFL X-pert	99.95	129.95	20
NFL X-pert and Toolbox and Toybox	119.95	149.95	30
BUY ALL 4 AND SAVE \$50	129.95	159.95	50
Applications Only			
Toolbox and Toybox	\$49.95		
NFL X-pert and Toolbox or Toybox	69.95		
BUY ALL 3 AND SAVE \$20	89.95		

COMPATIBILITY
Applications fully
compatible with
Prolog compilers
and interpreters
with Edinburgh
syntax.



**CHALCEDONY
SOFTWARE, INC.**

System Requirements
PC-DOS/MS-DOS
Ver. 2.0 or later
256K RAM
512 Macintosh

5580 LA JOLLA BLVD.
SUITE 126 D
LA JOLLA, CA
92037
(619) 483-8513

PHONE ORDERS: 1-800-621-0852 EXT 468

<input type="checkbox"/> PAYMENT ENCLOSED \$ _____ <small>CA residents add 6% sales tax</small>		PROLOG/i \$69.95 PROLOG/m 99.95 <small>If you own PROLOG V or PROLOG V-plus, call for upgrade information.</small>
<input type="checkbox"/> CHARGE MY: <input type="checkbox"/> MasterCard <input type="checkbox"/> Visa		SHIPPING: \$ 5.00 U.S. 7.50 Canada 10.00 Caribbean, Hawaii Air 20.00 Overseas Air COD Orders Not Accepted 15 day check clearance
Card No. _____ Exp. Date _____		
Signature _____		
Mr./Mrs./Ms. _____ <small>(please print full name)</small>		
Address _____		
City/State/Zip _____		

OVERCOME FORTRAN | PASCAL | C LIMITATIONS WITH

\$129
NO
LICENSE
FEE

NO

LIMIT

Ver. 3.0 For:
MS FORTRAN/Pascal/C
IBM Professional
and R-M FORTRAN
SuperSoft FORTRAN

NOW SUPPORTS IBM ENHANCED GRAPHICS AND HERCULES MONOCHROME GRAPHICS

A library of over 90 Assembler routines transform FORTRAN, Pascal and C language compilers into the flexible, responsive, complete languages needed for the microcomputer environment. Hundreds of NO LIMIT owners are creating highly interactive software systems, often utilizing existing mainframe code and saving time and money in the process. Ver. 3.0 features include:

- EXTENSIVE GRAPHICS** (Get, Put, Paint, Color, Dot, Line, Box, Circle, Ellipse)
- FULL SCREEN CONTROL** (Windows, Cursor, Read/Write Screen)
- STRING MANIPULATION** (Match, Compare, Concatenate/Extract, Pack, Justify)
- KEYBOARD CONTROL** (Read Key During Execution, String Read With Edit)
- FILE MANAGEMENT** (Exist?, Rename, Delete)
- COMMUNICATIONS** (Full Interrupt Driven to 9600 Baud, Set Com Line, Send/Receive, Line/Modem Status)
- INTERRUPTS** (DOS Execution, Program Execution)
- OTHER FEATURES** (Command Line Read, DOS 3.1 Directories, Peek, Poke, Random Numbers, System Status, etc.)

And to complement NO LIMIT, the I/O PRO development system allows creation and editing of FORTRAN/Pascal/C callable screens. This word processor type system pays for itself several times over on your first project. \$261.

M | E | F Environmental Inc.
P.O. Box 26537 Austin, Texas 78755
(800) 562-9700 (512) 251-5543 (Texas)

©Trademark of Microsoft Inc., Supersoft Inc., IBM Corporation, Ryan-McFarland and Microsoft Inc., respectively.

CIRCLE NO. 133 ON READER SERVICE CARD

CIRCLE NO. 139 ON READER SERVICE CARD

**More Memory
\$199.95**



The HiCard Wins!

WHY SPEND BIG \$\$\$ ON AN EXPANDED MEMORY BOARD WHEN YOU NEED ALL NEW SOFTWARE TO USE IT?

THE HiCard

- Expands DOS to 704KB
- Installs up to 896KB Total Memory
- Supports all your application software (no upgrades required)
- RAM Disks & Spoolers install above DOS
- Works with EGA, EMS, accelerators, networks & other memory expansion

ADVANCED FEATURES

- Multiple Print Spoolers — Supports up to 3 parallel printers simultaneously while you work
- Multiple RAM Disks can be installed & sized as required

DEVELOPERS TOOL

THE DOS LIMITER/EXPANDER

- Extends DOS to 704K or limits the amount of memory DOS can access to verify that your code runs in a given size.

**COMPATIBLE WITH IBM PC/XT/AT &
COMPATIBLES RUNNING DOS 2.0 or LATER**

**BASED ON QUALITY & PERFORMANCE
THE HICARD IS UNEQUALLED!**

2 YEAR WARRANTY PARTS & LABOR

MADE IN U.S.A.

For further information see your local computer dealer or contact:



Electronics, Inc.

5721 Arapahoe Ave., Suite A
Boulder, Colorado 80303
1-800-826-8333
Wait for tone and dial 4444-000

CIRCLE NO. 141 ON READER SERVICE CARD

PASCAL

```
O : TEXT;

FUNCTION TICS : WORD; EXTERN;
PROCEDURE TIME(VAR S : STRING); EXTERN;

PROCEDURE Show_Time(VAR OutFile : Text);

VAR
    TimeString : LSTRING(15);

BEGIN
    TimeString := '      ';
    Time(TimeString);
    Writeln(OutFile, TimeString, '.', Tics:2);
END;

PROCEDURE GET_DATA(VAR X : ARY2;
                    VAR Y : ARY;
                    VAR NROW, NCOL : INTEGER);

(* Get values for NROW, NCOL, and arrays X, Y *)

VAR I, J : INTEGER;

BEGIN
    NROW:=10;
    NCOL:=10;
    FOR I:=1 TO NROW DO
        BEGIN
            X[I,1]:=1;
            FOR J:=2 TO NCOL DO
                X[I,J]:=I*X[I,J-1];
            Y[I]:=2*I
        END
    END;
    (* GET_DATA *)

PROCEDURE WRITE_DATA;

(* Print out the answers *)
```

DeSmet C

now with 32-Bit Pointer Option

C88still \$109

The editors' choice for fast compilation and execution. The **price/performance winner** in all major C benchmarks since 1983. Includes Compiler, Assembler, Binder, Librarian, Execution Profiler and Full Screen Editor. Supports both disk and memory resident Overlays. Contains both 8087 and Software floating point support. Full STDIO library.

Large Case Option.....\$50

Makes a great C Compiler even better. Adds 32-Bit Pointers to C88 so you can utilize all of your PC. Groups scalar and static data for fast access. Supports the D88 debugger.

D88\$50

Gain most of the benefits of an interpreter while losing none of the run-time speed of the C88 compiler. Display C source and variable contents during execution. Set breakpoints by function name or line number. Examine and set variables by name using C expressions.

order direct from:

C Ware Corporation

505 W. Olive, Suite 767, Sunnyvale, CA 94086 U.S.A.
(408) 720-9696 — Telex: 358185
We accept VISA, MasterCard & American Express


```

VAR I,J : INTEGER;

BEGIN
  Writeln;
  Writeln('      X          Y');
  FOR I:=1 TO NROW DO
    BEGIN
      FOR J:=1 TO NCOL DO
        WRITE(X[I,J]:9:1, ' ');
      Writeln(' ',Y[I]:9:1)
    END;
  Writeln;
  Writeln('      A          G');
  FOR I:=1 TO NCOL DO
    BEGIN
      FOR J:=1 TO NCOL DO
        WRITE(A[I,J]:10:1, ' ');
      Writeln(' ',G[I]:10:1)
    END
  END; (* WRITE_DATA *)

PROCEDURE SQUARE(X : ARY2;
                  Y : ARY;
                  VAR A : ARY2S;
                  VAR G : ARYS;
                  NROW,NCOL : INTEGER);

(* Matrix multiplication routine *)
(* A = transpose X times X *)
(* G = Y times X *)

VAR I,K,L : INTEGER;

BEGIN (* SQUARE *)
  FOR K:=1 TO NCOL DO
    BEGIN
      FOR L:=1 TO K DO
        BEGIN
          A[K,L]:=0;
          FOR I:=1 TO NROW DO
            BEGIN
              A[K,L]:=A[K,L]+X[I,L]*X[I,K];
              IF K>L THEN A[L,K]:=A[K,L]
            END
          END; (* L loop *)
        G[K]:=0;
        FOR I:=1 TO NROW DO
          G[K]:=G[K]+Y[I]*X[I,K]
        END
      END (* K loop *)
    END; (* SQUARE *)

  BEGIN (* MAIN *)
    ( Open timings file: )
    Assign(O,'MATTIME.MS');
    Rewrite(O);
    Writeln(O,'Matrix benchmark timings for Microsoft Pascal V3.31: ');
    Writeln(O,' ');

    WRITE(O,'>>>Starting matrix multiply time test at ');
    SHOW_TIME(O);
    FOR I := 1 TO 10 DO
      BEGIN
        GET_DATA(X,Y,NROW,NCOL);
        SQUARE(X,Y,A,G,NROW,NCOL);
      END;
      WRITE(O,' ...done at ');
      SHOW_TIME(O);
      CLOSE(O);
      WRITE(O,'>>>Press (CR) to display the matrix: ');
      READLN;
      WRITE_DATA
    END.


```

LISTING 3: CBENMS.BAT

```

TIME 0:0:0
PAS1 /Q BENCHER.PAS,BENCHER.OBJ,NUL,NUL
PAS2
LINK BENCHER.OBJ,BENCHMS.EXE,NUL,,PASCAL.LIB
TIME

```



It's Midnight—

Do you know where your files are?

Lost on the Disk? Tired of the search?


Say Hello to SCOUT—*The first memory-resident disk directory utility that lets you do all this:* search, view, move, delete, copy, organize, format, sort, create, and TAKE CONTROL of your directories and printer without leaving your working program. Easy-to-use windows pop-up making SCOUT's commands just a KEYSTROKE AWAY! SCOUT is perfect for hard disks and floppy systems, too. In fact, SCOUT is the only disk directory utility that can format a floppy disk from within a resident program—AT TWICE DOS SPEED!

SCOUT works like SIDEKICK—SCOUT works WITH SIDEKICK. In fact, SCOUT works with most major programs including dBase III, Lotus 1-2-3, SuperCalc 3, WordStar, WordPerfect, Turbo Pascal, Enable, and Sidekick.

CIRCLE NO. 140 ON READER SERVICE CARD

WHY SETTLE FOR LESS?

- Memory Resident
- Remove from memory without reboot
- Memory resident disk formatter
- Move to directories
- User selection of activation key
- Move files
- Mass file copy, delete
- Search for files
- Multiple file sorts
- Display directories
- Alter file attributes
- Change default directory
- Display disk space
- View text files
- Set printer control codes
- Pop-up windows
- Display directory using file masks
- Single-key commands
- Create/remove directories
- Tag, untag, and retag files
- Rename files
- Rename directories
- Cumulative file tag totals
- Edit or delete volume labels
- Print location of files found in search
- Print directory catalog
- Print listing of files in any directory
- Show CAPs and NUMLOCK status
- Display full day, date, time
- Display DOS version
- Change sort type dynamically



INTRODUCTORY OFFER

\$49⁹⁵

NO RISK OFFER
30-Day Money-Back
Guarantee if not
thoroughly satisfied.

SYSTEM REQUIREMENTS
IBM PC and compatibles
SCOUT loads in just 128K
with DOS 2.00

Supports color and mono-
chrome monitors, and
Hercules Graphic Cards



**CHALCEDONY
SOFTWARE, INC.**

5580 LA JOLLA BLVD.
SUITE 126-T
LA JOLLA, CA.
92037

PHONE ORDERS: 1-800-621-0852 EXT 468

<input type="checkbox"/> PAYMENT ENCLOSED \$ _____	SCOUT \$49.95
<input type="checkbox"/> CHARGE MY: <input type="checkbox"/> MasterCard <input type="checkbox"/> Visa	CA Residents (sales tax) 3.00
Card No. _____ Exp. Date _____	Shipping (see below) _____
Signature _____	Total _____
Name _____	SHIPPING
Address _____	\$ 5.00 US/Canada
City/State/ZIP _____	Surface
Day Phone _____	7.50 US Air
	10.00 Overseas Air
	NO COD ORDERS ACCEPTED
	DEALER INQUIRIES WELCOME—
	Special Demonstration
	Package Available

The problem with most 4GLs is they're finished before you are.

And where does that leave you?

With the final, tricky ten percent of
your application yet to write, and no 4GL

left to write it with. Sound familiar?

Introducing INFORMIX®4GL.

Never again will you have
to switch to C or COBOL to truly
customize your application.

Instead, INFORMIX-4GL pro-
vides an all encompassing syntax
for every aspect of your application
building.

So once you're programming in
INFORMIX-4GL, you never have to
leave it. And considering all it can do,
you may never want to.

Now, for instance, you can write in

just ten to twenty pages of 4GL code, applications that would take hundreds of pages with C.

That's because INFORMIX-4GL was designed from the start to be an application building language. It's built around the full implementation of ANSI Standard SQL. And features Custom Screen Generation, Custom Menu Building and a built-in Report Writer.

What's more, INFORMIX-4GL works with UNIX[™], MS[™]-DOS and Networked DOS operating systems. And, of course, it's compatible with INFORMIX-SQL—our

popular, proven DBMS. So files you build with one, you can access with the other.

For more information and our free booklet, "A 20-Minute Guide to INFORMIX-4GL," call 415/322-4100.

Or write RDS, 4100 Bohannon Drive, Menlo Park, CA 94025.

And start taking your applications to even greater heights.



RELATIONAL DATABASE SYSTEMS, INC.




Get started in AI with Gold Hill.

You know artificial intelligence is the wave of the future. Programs based on the ideas of artificial intelligence are being written today in COMMON LISP—the new LISP standard developed by researchers from universities and corporations such as Carnegie Mellon, DEC, MIT, Stanford, Symbolics and TI. LISP allows the development of programs that are intelligent, flexible, and even human-like. The problem has been that hardware needed to run LISP is expensive.

No longer. GOLDEN COMMON LISP (GC LISP) makes it possible for you to learn and use LISP on your *personal computer*. When you use GC LISP in combination with the AI examples provided, you will be able to develop such exciting applications as expert systems, natural language systems, and intelligent interfaces to complex software. The possibilities are endless. With GC LISP you can tackle problems that you could not solve before with ordinary number crunching programs. You will be able to write powerful programs that can accommodate casual computer users who want intelligible answers quickly.

Learn Quickly with GC LISP

GC LISP makes it easy for you to learn the technology of AI at your own pace. Each package includes the *San Marco LISP Explorer*®—an interactive software tutorial developed by San Marco Associates with Patrick H. Winston. This 800-frame instructional system guides you through the



GOLDEN COMMON LISP is the best selling AI language.

steps of LISP programming and makes the full range of LISP's power accessible to both novice and experienced programmers. The second edition of the classic *LISP* textbook by Winston and Horn is also included.

GC LISP comes complete with the intelligent GMACS editor (based on EMACS), full on-line documentation of all GC LISP and GMACS functions, the *Common LISP Reference Manual* by Steele, and a comprehensive user manual. In short, GOLDEN COMMON LISP comes with everything you need to program in LISP.

NEW!

The GC LISP 286 DEVELOPER

Discover programming power you never thought possible on your PC AT! GC LISP 286 DEVELOPER is a complete programming environment designed for GC LISP-based applications requiring extended memory and faster execution. The 286 DEVELOPER includes a Large Memory Interpreter capable of addressing 15 megabytes of physical memory, a Large Memory Compiler that runs applications up to 15 times faster, and a complete set of program development features including lexical and dynamic scoping. The 286 DEVELOPER is the first PC-DOS programming environment that takes full advantage of the speed and memory capacity of the IBM PC AT and compatibles, and it's now available to help you develop powerful and productive AI applications.

Order Today

For more information on Gold Hill products, please call today:

1-800-242-LISP

In Massachusetts call collect
(617) 492-2071

GC LISP requires an IBM PC, PC XT, PC AT, or IBM-compatible with a minimum of 512K and PC-DOS 2.0 or higher. GC LISP 286 DEVELOPER is non-copy protected, and requires an IBM PC AT or compatible with a minimum of 512K of base memory, 2 megabytes of extended memory, and PC-DOS 3.0 or higher.



© 1986 Gold Hill Computers

G O L D H I L L C O M P U T E R S

163 Harvard Street, Cambridge, Massachusetts 02139

GOLDEN COMMON LISP, GC LISP and GC LISP 286 DEVELOPER are trademarks of Gold Hill Computers. The San Marco LISP Explorer is a registered trademark of San Marco Associates. LISP is copyrighted by Addison-Wesley Publishing Company, Inc. The COMMON LISP Reference Manual is copyrighted by Digital Equipment Corporation. IBM PC, PC XT, PC AT, and PC DOS are trademarks of International Business Machines.

CIRCLE NO. 122 ON READER SERVICE CARD



A Better CGA

MICHAEL COVINGTON

Two hardware modifications to the CGA may improve the display on an RGB color or a composite monochrome monitor.

Top: The modification to the CGA is a simple addition of resistors. The three resistors result in 16 shades of gray.


Bottom: Jumper P3 is a pair of holes at the edge of the MC6845PIC, which is joined with wire.

This selects a thinner font.



A better picture may be possible using the IBM Color Graphics Adapter (CGA) with a composite monochrome or an RGB color monitor. Two hardware modifications presented here can help improve the functionality of the CGA. The first removes the striping effect that occurs on monochrome monitors running color programs. It allows the CGA to render its 16 colors as

distinct shades of gray. The performance of the board with an RGB monitor is unaffected. The other modification allows the user to select an alternative character set to the standard font supported by the CGA.


Although these changes may improve the quality of the CGA, an important consideration is that any alteration to the IBM hardware will void its war-

PHOTO 1: Striping Effect

When connected to a composite monochrome monitor, the unmodified CGA renders colors as patterns of stripes (shown in photo 1). This is 40-column type; 80-column type is completely illegible. The suggested modification eliminates the stripes and renders colors as different shades of gray, producing a more acceptable display (as shown in photo 2).

PHOTO 2: Modified Striping Effect**FIGURE 1: Original CGA**

The original CGA circuit board can be modified by removing R8 and adding a portion of the red, green, and blue signals. (This information is from the *IBM Technical Reference Manual*, part 1502234.)

FIGURE 2: Newer CGA

The newer version of the CGA requires only that the resistor R8 be removed to render colors as shades of gray. (This information is from the *IBM Technical Reference Manual*, volume 2, "Options and Adapters," part 6137806.)

ranty. These changes also preclude the CGA's use with televisions.

When the CGA was first introduced, televisions sometimes were used as the display for the PC. Therefore, IBM designed the CGA to accommodate televisions as well as the RGB color and composite monochrome monitors that most people use today.

SHADES OF GRAY

This support of color television, however, results in a distracting effect when a monochrome monitor is connected to the CGA. Colors are displayed as patterns of stripes (photo 1). This can make a text screen difficult to read.

The stripes exist because PCs generate *artifact color*. In American color television broadcasting, under guidelines of the National Television System Committee (NTSC), color information is transmitted on a 3.58-MHz subcarrier embedded in an otherwise ordinary black-and-white video signal. As a result, NTSC color broadcasts can be received on black-and-white television sets. PCs, however, do not actually use a 3.58-MHz subcarrier. Instead, they render colors as patterns of stripes in which the video frequencies are exact submultiples of 3.58 MHz. A television connected to a PC is fooled into responding as if the subcarrier were present.

No real color signals are transmitted—the colors are artifacts of the phase and frequency of the stripes.

IBM recently has modified the CGA in an effort to make the stripes somewhat less troublesome. The modified version includes three additional resistors, which are configured as a voltage divider that provides a proportion of the red, green, and blue color signals to the composite video output.

Several digital signals are mixed to form the composite video signal. The original CGA circuit board had a signal for the synchronization pulses, one for blanking, one for high or low intensity, and one containing various 3.58-MHz

Build your own programming powerhouse

With the Power System™ from Pecan, you can now create the ideal environment for your programming needs.

Whether you're an experienced programmer or an enthusiastic newcomer, the right program development environment is essential to creating software that effectively delivers the capabilities you need. The optimum development environment includes your choice of language compilers, an integrated system of basic programming capabilities, and a specially selected group of utilities which fulfill your own unique requirements.

Start with a full-featured development environment

With the Power System from Pecan, you start with one of four compilers: Choose Pecan's powerful and highly versatile UCSD Pascal® or build your system on our BASIC, FORTRAN-77 or Modula-2 compilers. (Additional language compilers are on the way.) With your Pecan compiler, you get a *total* program development environment which delivers a full range of integrated development capabilities, including:

- Sophisticated text editor
- Versatile print utility
- Easy-to-use file management system
- Program library manager
- Special program execution utilities
- Turtlegraphics

With other program development systems, you'd have to purchase

some or all of these capabilities separately. With the Power System from Pecan, they're standard equipment.

Add the specialized capabilities you want

Developing specialized software calls for the right tools. Pecan offers a wide selection of optional program development aids to help you write programs that work just the way you want. These tools include:

- Program debugger
- Keyed file access (KSAM)
- Automatic print spooler
- Assemblers and cross assemblers
- Speed and space optimizer

These and Pecan's many other development aids

enable you to build your own "customized" Power System, a system which is ideally suited to your individual programming needs.

Create multi-language programs

Some languages are better for certain kinds of programming than others. For this reason, the Power System lets you write part of any given program in UCSD Pascal, additional parts in BASIC, FORTRAN-77 and Modula-2. All you need is a Pecan compiler for each language you want to use. Once you've written your program, it can then be executed exactly as if you'd written it all in one language. **Only the Power System from Pecan offers you this capability.**

Run programs on virtually any mini or micro

The programs you develop through the Power System are completely *portable*. This means that a program you write on one computer can actually be run on another—even if the second computer is *not* compatible with the first. **No other program development environment gives you this kind of flexibility.**

Total programming power at a price you can afford

Build your ideal programming powerhouse today. For the incredibly low introductory price of only **\$79.95**, you get the complete Power System with its important program development capabilities, including the compiler of your choice. You can add a second Pecan compiler for just \$59.95, or select two additional compilers for only \$99.95. Once you have the Power System, you can then customize it as your programming requirements demand—with Pecan's powerful development aids.

Order the unique Power System—available exclusively from Pecan—by mail today. Or call us at 1-800-63-PECAN. You won't find a better price/performance value anywhere. And you'll never build a better program development environment—no matter what price you pay.

PECAN™

The UCSD Pascal Company
Pecan Software Systems, Inc.
1410 39th Street, Brooklyn, NY 11218
718-851-3100

THE POWER SYSTEM

The Power System from Pecan \$79.95 (for PC-DOS, MS-DOS, AMIGA, APPLE, ATARI ST, MACINTOSH, RAINBOW, TANDY, as well as most popular 8/16/32-bit systems).
Price includes 8087 support and BCD on PC/compatible.

Please send me _____ copies of the Power System for my _____ (Operating system)
_____ which runs under _____
(Name and model of computer)

Include Pecan's UCSD Pascal® ☐ Modula-2 ☐ BASIC ☐ FORTRAN-77 ☐
(Available Summer 1988) ☐ compiler.
(First compiler of your choice, included with your order. For a second compiler, add \$59.95;
for two additional compilers, add \$99.95.)

My disk size is 3 1/2" _____ 5 1/4" _____ 8" _____

Total amount (NYS add appropriate tax) _____
Payment by ☐ VISA ☐ MC ☐ US Bank Check ☐ Bank Draft
Card Number: _____ Credit Card Expiration Date: _____

Mail to: Pecan Software Systems, Inc.
1410 39th Street
Brooklyn, NY 11218
ITT Telex No. 494 8910
CompuServe Code 76703, 500

Name _____ Zip _____
Shipping Address _____ State _____
City _____ Telephone _____

Call or write for UNIX, VAX or other Power System versions—and ask about our other powerful programming development aids.
SCHOOLS: Contact us for special educational discounts.
To place an order, call toll-free, or enclose your check with this coupon. Please add \$2.50 per copy of the Power System within the U.S. Foreign orders add \$10, and make payment by bank draft payable in US dollars on US bank. New York State residents add appropriate sales tax.

UCSD Pascal
Not copy protected
60-day money-back guarantee

CREDIT CARD ORDERS
CALL TOLL-FREE
1-800-63-PECAN
(NYS) 1-800-45-PECAN

AMIGA is a trademark of Commodore Electronics LTD.
APPLE and MACINTOSH are trademarks of Apple Computer Corp.
ATARI ST is a trademark of Atari Corporation.
RAINBOW is a trademark of Digital Equipment Corporation.
TANDY is a trademark of Radio Shack.
UCSD Pascal is a registered trademark of The Regents of University of California.

PHOTO 3: RGB Monitor

```

C>dir *.bat

Volume in drive C has no
Directory of C:\

BOOTUP    BAT      791    1-
MODEM     BAT       7    12-
COLOR     BAT      29    1-
SCR       BAT     35    12-
           4 File(s)  768

```

When the jumper P3 is connected on some CGAs, the alternative typeface is very legible on an RGB monitor (photo 3). The character is a 7-high-by-5 wide single-dot font with one descender. The alternative typeface is disappointing on the composite monitor (photo 4). Removal of the jumper restores the original font.

PHOTO 4: Monochrome

```

22:17:26 C>dir *.bat

Volume in drive C has no
Directory of C:\

BOOTUP    BAT      791    1-
MODEM     BAT       7    12-
COLOR     BAT      29    1-
SCR       BAT     35    12-
           4 File(s)  768

```

PHOTO 5: Dot Pattern

```

19:58:42 C>dir *.bat

Volume in drive C has no
Directory of C:\

BOOTUP    BAT      791    1-
MODEM     BAT       7    12-
COLOR     BAT      29    1-
SCR       BAT     35    12-
           4 File(s)  768

```

Selecting the alternative font resulted in a dot pattern on an RGB monitor. This was due to a defective character generator IC on the author's CGA.

components for generating artifact color. The mixing of the signals takes place in a network of resistors that are connected to the base of transistor Q1. Figure 1 shows an excerpt from the IBM schematic for the CGA board that illustrates the original circuit.

In the newer circuit (figure 2), the blanking signal has been replaced with the red, green, and blue drive signals. As a result, the stripes appear on a gray rather than a black background, thereby increasing legibility.

While IBM now has softened the effect of the stripes, the distraction can be eliminated entirely by removing resistor R8 to block the signal that contains the 3.58-MHz components. In IBM's newer circuit board, no other changes are necessary; resistors R6, R18, and R19 translate colors into shades of gray automatically. In the older circuit board, however, three resistors must be added to construct a composite gray signal from red, green, and blue drive signals borrowed from the RGB monitor socket. (The load on the RGB outputs is negligible, and performance of RGB monitors is not affected.) The new circuitry is indicated in figure 1 by the dotted lines. Photo 2 shows the result of the modification. The values for the resistor were chosen to ensure that each combination of red, green, or blue intensities would produce a different level of gray. If any two of the chosen values had been the same, several of the gray levels produced also would have appeared the same.

The large photo featured at the beginning of this article illustrates one method of installing the new resistors. The three resistors are placed on the circuit board so that one side is con-

nected to the base of Q1, and each of the other sides is connected to the red, blue, or green signal, as appropriate. Before proceeding in this manner, however, users should examine the circuit board closely. Some early model CGAs already include places on the board for these three resistors.

In addition to eliminating the stripes, this modification corrects a problem with horizontal synchronization sometimes encountered on older CGAs. On some monitors, lines displayed in reverse video, such as the status line of an editor, pull to the left or the right relative to the other lines. This occurs because the synchronization pulse generated by IBM's circuit is too small. According to the NTSC standard, synchronization pulses should constitute 25 percent of the amplitude of the entire video signal. The modification described above enlarges the synchronization pulses of the IBM circuit so they conform to the standard size.

The rendering of colors as shades of gray is most effective when the monitor is adjusted for relatively high brightness and low contrast—the background is not pitch black, and the entire range of shades from very dark to very light is distinguishable. A few color combinations still may be difficult to read, but none is absolutely illegible (as they would be if rendered as stripes).

THE SECOND TYPEFACE

The IBM *Technical Reference Manual* states that the CGA supports two typefaces in text mode, selectable by a jumper referred to as P3. The standard typeface (a 7-by-7 double-dot font) is selected by removing the jumper. When the jumper is in place, a 7-by-5, single-

dot font with thinner vertical strokes is invoked. (See "The IBM Color Graphics Adapter," Thomas V. Hoffmann, July-August 1983, p. 26.)

The thinner typeface is slightly more legible than the standard face on RGB color monitors (photo 3). On composite monochrome monitors, however, the vertical strokes are almost too thin to see, and the entire display can end up looking like a scattering of horizontal dots and dashes (photo 4).

Only the earliest model CGAs have a jumper marked P3 installed; in its place, later CGAs contain just two "plated-through" holes in the circuit board. Installing the jumper requires the user to solder a piece of wire between the two holes in order to connect them (refer to the small photo at the beginning of the article).

Photo 5 shows an odd problem that became apparent when jumper P3 was added to the CGA—the screen was covered with dots. Examining the contents of the character generator integrated circuit revealed that two extra bits were set in the definitions of characters 0-127 in the thinner typeface.


The integrated circuit that caused the problem pictured in photo 5 had a date stamp of 8252 and a copyright date of 1981. *PC Tech Journal* was not able to establish if this is an isolated problem or whether other character generators share the defect, which is undetectable during normal use and testing. If the problem occurs, the jumper should be removed, and the user will be no worse off than before.



Michael Covington is a research associate of the Advanced Computational Methods Center at the University of Georgia.

MIDBS III[®]

ATTN:
APPLICATION
DEVELOPERS



... DELIVERS THESE ESSENTIAL FEATURES. DOES YOUR DBMS?

MDBS III is more powerful than most mainframe data base management systems... and less expensive. MDBS III was designed for serious application developers like you. Like the developers of Solomon III, the "Number One" accounting system. And all the others who demand these essential features MDBS III provides:

DATA STRUCTURING—So flexible it captures any data relationship you can imagine. So comprehensive you'll design complex data bases faster than ever.

TRUE MULTI-USER—Few DBMSs give you as many facilities to guard against haphazard concurrent data modification as MDBS III does, down to the locking of individual data records.

PERFORMANCE—MDBS III gives you fast data modification and retrieval plus extensive performance tuning facilities.

DATA INTEGRITY—MDBS III provides airtight integrity assurances... from range checking to transaction-logging to enforcement of data relationships... *all automatically.*

PHYSICAL DATA PROTECTION—You get automatic recovery from media as well as from physical data destruction.

DATA SECURITY—Protect your data using passwords, encryption, and read/write access down to the field level.

PORTABILITY—MDBS III runs on a range of mini and micro computers, including LANs, and supports a variety of host language interfaces.

SUPPORT—**mdbs** is there when you need us, with in-depth seminars, telephone support, individual consulting and contract programming to help you develop and install your applications.


Call us today at 800-323-3629 for more information; in Canada or Illinois, dial 312-303-6300. Or write **mdbs**, P.O. Box 248, Lafayette, IN 47902, TELEX 209147 ISE UR.

MIDBS III[®]
ABSOLUTE POWER

CIRCLE NO. 211 ON READER SERVICE CARD


mdbs is a registered trademark and **MDBS III** is a trademark of Micro Data Base Systems, Inc. **IMS** is a trademark of IBM; **IDMS** of Cullinet.





A Data Manager that

Synthesizes Text and Data



A sophisticated integration of text and data management and an easy user interface are hallmarks of Metafile.

V. JOSEPH BOWMAN

Introduced in 1980, the Metafile data management package is deeply rooted in the mainframe environment, and many of its features and methods of processing reflect this. Metafile Information Systems has set as the target market for its product independent developers, MIS/DP professionals, and business managers.

Among Metafile's hallmark characteristics is a sophisticated integration of text and data management. Text is handled within a program in much the same way that data are manipulated. At any given time Metafile has two active areas—one for data and the other for text. Data files have the normal structure of fields within records, while text files have an equivalent structure of words within text. The integration of these concepts allows for root commands that operate on either of the areas by the inclusion of the simple qualifier RECORD or TEXT.

In addition to the text area being under program control, it is also used for the creation of procedures, menus, and reports. Any of these can be accessed directly by specifying TEXT instead of a file name.

Metafile also provides a rich set of commands for developing end-user interfaces. The system has an interactive menu mode (called the Assistant) that uses these commands to aid the user in the manipulation of either text or data. Help is provided in the form of an incomplete command processor that automatically takes the user to the appropriate pull-down menu and allows correct completion of the command. All of these features reflect a concern for easy user interface whether in the interactive or program mode.

The Metafile package consists of two diskettes—one contains the Metafile

program, and the other is a demonstration disk. Metafile's method of copy protection is a configuration device that plugs into the COM1 port and has pass-through capabilities in case COM1 is used for communications. If the device is not present when Metafile is started, the system is automatically configured to a restricted demonstration version. Although installation of the device requires a screw driver, once it is on the computer, the user can forget about copy protection. Because a demonstration version of Metafile is available on machines without the configuration device, a developer can demonstrate an application without having to install and uninstall hardware.

Metafile has been designed to run on IBM microcomputers, but may run on systems that are not 100-percent compatible. Metafile Information Systems provides a list of hardware on which compatibilities are reported.

DATABASE DESIGN

Metafile is not a relational database system. It has no commands for joining multiple files or for linking files together for automatic repositioning. Relating files must be done under program control. Metafile allows up to five files to be active. At any given time only one of the active databases is the primary database, but access to data elements in the current record of other active files is provided by specifying the field name, or if the field name is not unique, the file name and field name, such as AUTHOR LAST_NAME. Metafile therefore is able to support a quasi-relational structure with the relation being preserved either by a program or by interactive commands.

Each Metafile data file requires at least three DOS files and sometimes as

many as five. The data are stored in .DAT files, the data description in .DES files, and the logical sequence and physical location of the records in .SSD files. The .DAT and .SSD files have the same prefix while the .DES description file may be shared between many data files. An index file (.SSI) exists if a file is keyed, and a data recovery file (.SSR) is used if the file is set for manual updating. Other temporary work files are created by Metafile as needed.

Data are stored in variable length records as ASCII characters, with fields separated by commas. The end of record is the standard ASCII end of line sequence—carriage return and line feed—and the end of file is marked with a Ctrl-Z. Double quotes are used in data storage only when a field contains characters other than a letter, digit, or decimal point. This method of storage allows data to be manipulated without concern for type. Thus, a character variable can be set equal to a numeric value without a conversion function.

In processing updates to the database, Metafile generates a new record for each one that has been changed. The first value in each record is a status byte that indicates whether this is the current value of the record. This value is used internally by Metafile; it is not displayed with the record and cannot be read or modified by the user. While creating a new record instead of overwriting the changed record causes the data file to grow even when no records are being added, it also allows for a program-controlled update procedure to guarantee data integrity and recovery of the data after a system crash.

When data files are initially described, they must be set for either automatic update, in which every change is permanently recorded in the

PHOTO 1: Field Validation Properties

```

=====
| EDITORIAL INVENTORY -- Article file
|
| Title: Fixing a Bug in Scientific Software
| Author: Connolly Phillip Day Phone
| Co-author:
|
| Booking: Volume 3 Number 1
| Date: January 1985
|
| Article Type: Category: T
| Department:
|
| Date Due:
|
| Sizes: Editorial:
| Listings:
| Total:
|
| Input pattern:
| Comment:
|
=====
|
| DATA ELEMENT PROPERTIES - (ESC) to go back
| Name..... VOLUME
| Type..... NUM
| Length..... 2
| Default.....
| Translations..... (1983,1,1984,2,1985,3,1986,4,19
| Ranges..... (1,9)
|
=====
| ACQUIRE TEXT Proc:FIGURE1 Txt: C:INPUT Data: C:ARTICLE Rec: 1 of 360

```

Extensive editing and validation criteria can be defined for each field. During data entry, pressing the Ctrl-L combination reveals the criteria for the field being entered.

PHOTO 2: Data Validation Using Menus

```

=====
| EDITORIAL INVENTORY -- Article file
|
| Title: Fixing a Bug in Scientific Software
| Author: Connolly Phillip Day Phone
| Co-author:
|
| Booking: Volume 3 Number 1
| Date:
|
| Article Type: Category:
| Department:
|
| Date Due:
|
| Sizes: Editorial:
| Listings:
| Total:
|
| Input pattern:
| Comment:
|
=====
|
| Select Category
| Product Review
| Technical Article
| Department
| Tech Notebook
|
| Payment
|
| Total:
|
=====
| Select Proc:FIGURE2 Menu: C:CATEGORY Data: C:ARTICLE Rec: 1 of 360

```

Besides offering the user choices of action, the menu can be used to ensure valid input of data. For department name, the user must select one of the four options presented.

database, or manual update, in which the data are not permanently recorded until a KEEP command is issued or the data file is closed. During an update, DISCARD causes all records changed since the last, permanent update to be reset to their previous value. This is especially useful in transaction processing and is used by many mainframe databases to guarantee that a set of related records either are all added to the database or are backed out of it.

Because all changes generate additional records, care must be taken periodically to copy a data file to itself and eliminate all old record images in addition to any records that have been deleted. Because data are stored in variable-length form—a null data item requiring only one byte for the field-separating comma—the size of files can be substantially smaller than that of a fixed-record-length file even with the multiple record images.

The data description file (.DES) contains information on the data fields, which is used by Metafile to interpret the data file and provide automatic data entry validation and output formatting for interactive update. *Item Name* can consist of up to 40 characters. *Data Type* can be character, numeric, or date. *Length* is the maximum space needed to store the variable and must include space for translations and input or output patterns. *Position* specifies the field number in a data record, which allows multiple descriptions to be given to the same data item. Input validation and output formatting of the data item then depends on the name by which the data item is referenced. (Automatic validation and output formatting are effective only during keyboard input, not

through procedural updates.) *Default value* either is a standard value or specifies required input if the value is "?". Multiple *ranges* can be declared by entering multiple paired groups. Thus, 0,5,8,9 is a valid range that allows only the values 0, 1, 2, 3, 4, 5, 8, or 9. *Translation* provides automatic checking of input for particular values and also allows translation of coded input. The sequence, Male,M,Female,F, causes only the four values specified to be accepted for entry, and if M or F is entered, all output will translate these values to either Male or Female. Finally, standard *input* and *output patterns* can be specified along with a 250-character comment. This set of field information is automatically presented when the help key (Ctrl-L) is pressed during data input, as shown in photo 1.

Arrays, which are supported for the storage of either variables or data items, do not have to be dimensioned. An array is any sequence of characters delimited by commas, spaces, or quotes. This general definition provides tremendous power in both variable and data element manipulation. Each dimension in an array is denoted by a grouping of parentheses; the only limit on the number of dimensions is the maximum supported array length of 235 characters, including element separators. Arrays provide an alternative method of processing text because each sequential element is a word.

Numeric fields have an arithmetic accuracy of 20 digits but are limited to a length of 16 in keys and in sorts. Character fields have a maximum length of 235 characters while character variables may be 250 characters long. Date fields are in the form DDMMYY or

DDMMYYYY, with dates ranging from 01JAN1776 to 31DEC9999.

Up to three keys are allowed for each file. A key must be a field, and if the key value is not unique, only the first occurrence is maintained. If the record associated with a key value is deleted, this value also is eliminated from the key file even if the value exists on another record.


Because Metafile runs on DOS 1.1 and above, it does not support path names. All files are assumed to be in the current directory on the default drive, which must also contain the Metafile program. If files reside on another drive, the drive must be specified.

APPLICATIONS LANGUAGE

The applications development language of Metafile contains the standard looping structures of WHILE, WHERE, FOR, and IF. The WHERE command can control a loop of operations to be performed on records meeting specified conditions. No standard CASE command is provided. Procedures and loops may be nested 22 deep. The maximum storage available for variables is 4,100 bytes. Variables assigned values via the SET command are global. Parameters are passed between procedures by two reserved arrays, PASSED and RETURNED, which are limited to 250 characters; the user may define as many parameters as are necessary to meet this size restriction. Parameters do not use storage as variables do; the values of the parameters are local to the procedure to which they are passed or returned.

The language is an interpreted one, and the commands of a procedure file are displayed on the status line as they are executed if STATUS is ENABLED. All

Why your next generation of products should use our 5th generation tools.



Arity's integrated family of programming tools allows you to combine software written in Arity/Prolog, the best of the fifth generation languages, with Arity SQL, the best of the fourth generation languages, and with conventional third generation languages such as C or assembly language to build your smarter application.

You can use Arity/Prolog to build expert systems using the Arity Expert Systems Development Package. Or to build natural language frontends. Or to build intelligent information management systems. Arity/Prolog lets you build advanced technology into your vertical applications package.

And more...

That's not the whole story. Arity's products are all designed to be fast, powerful, serious. Each of our products contains unexpected bonuses. Such as a one gigabyte virtual database integrated into Arity/Prolog. The most powerful of its kind on a PC.

Quality first. Then price.

In order to be the best, we had to prove it to our customers. Our tradition of quality software design is reflected in every product we sell. Quality first. Then price. And we always provide the best in customer support.

Our products are not copy protected. We do not charge royalties. We offer generous educational and quantity discounts. And we have a 30 day money back guarantee.

Try us to know that we keep our promise on commitment to quality and reliability. Try us by using our electronic bulletin board at 617-369-5622 or call us by telephone—you can reach us at 617-371-2422.

Or fill in this coupon. Whether you order today or not, let us send you full descriptions of our integrated family of Arity products.

CIRCLE NO. 136 ON READER SERVICE CARD

arity

We design and distribute high quality, serious application software for the IBM PC, XT, AT and all MS-DOS compatibles.

Please complete this form to place your order and/or request detailed information.

		Quantity	Info only
Arity/Prolog Compiler and Interpreter V4	\$795.00	_____	_____
Arity/Prolog Interpreter V4	\$350.00	_____	_____
Arity Standard Prolog	\$ 95.00	_____	_____
Arity SQL Development Package	\$295.00	_____	_____
Arity Expert System Development Package	\$295.00	_____	_____
Arity Screen Design Toolkit	\$ 49.95	_____	_____
Arity File Interchange Toolkit	\$ 49.95	_____	_____
TOTAL AMOUNT (MA residents add 5% sales tax) (These prices include shipping to all U.S. cities)		\$	_____

NAME _____

SHIPPING ADDRESS _____

CITY/STATE/ZIP _____

TELEPHONE _____

Payment: ☐ Check ☐ PO ☐ AMEX ☐ VISA ☐ MC

Card # _____ Exp. date _____

Signature _____

ARITY CORPORATION • 358 BAKER AVENUE • CONCORD, MA 01742

arity



640 x 350 16 COLOR




EGA PAINT



GEM



FLIGHT SIMULATOR




PAINT BRUSH



Auto CAD

NO MORE Low-End Graphics Adapters.

Why Settle for Less?



IBM sets the standards for Monochrome, Color/Graphics and the Enhanced Graphics Adapter. Hercules sets the Monochrome

Graphics standard. And the MegaGraph-Plus simply redefines the standard for what the Graphics Adapter is supposed to be: Monochrome text, Hercules graphics, color graphics, enhanced graphics. And most importantly . . . No software driver patches required.

Fully Compatible

You can run almost all software from your early investment. Including Flight Simulator, Pin Ball, Jet and Lotus 1-2-3 Version 1A.

And it will still run all the business software packages written for IBM Enhanced Graphics Adapter (EGA). Examples include Auto CAD, IBM Drawing Assistant, Gem Draw, Microsoft Window, Word & Chart, Lotus 1-2-3 and Symphony, Dr. Halo, PC Paint Brush, EGA-Paint and many, many more.

ATronics is dedicated to the technical excellence of computing devices. To find out more about ATronics and our super-high performance ATI-1000 & ATI 2000 AT system compatible boards call or write:

Features

	ATronics MegaGraph +	Quadram EGA +	IBM EGA	STB EGA +
Half size, fits in any slot of PC/XT/AT	✓	✓		
EGA compatible	✓	✓	✓	✓
CGA compatible	✓	(1)	(2)	(2)
MDA compatible	✓	✓	✓	✓
Chip count	24	29	86	40
Hercules compatible 720 x 348 graphics	✓	✓		
No Software Patches required	✓		✓	✓
Boot from:				
— Flight Simulator	✓			
— Pin Ball	✓			
— Jet	✓			
Runs Lotus 1-2-3 version 1A:				
— Hercules mode	✓	(1)		
— Color mode	✓	(1)		
Two Video Jacks	✓	✓	✓	
Display Memory	256K	256K	64K	256K
Light Pen connector	✓	✓	✓	✓

(1) Needs software driver patches.

(2) Compatible only to the BIOS level, but not the hardware level. Will not be compatible with most games software.



ATronics International Inc.
491 Valley Way
Milpitas, CA 95035
(408) 943-6629 TLX: 510-600-6093

MegaGraph PLUS

IBM, Hercules, Flight Simulator, Pin Ball, Jet, Lotus 1-2-3 Version 1A, Auto CAD, Gem Draw, Window, Word & Chart, Symphony, Dr. Halo, PC Paint Brush, EGA Paint, Quadram and STB EGA+ are all registered trademarks of their respective companies.

CIRCLE NO. 159 ON READER SERVICE CARD

commands in Metafile must be typed in uppercase letters. The use of lowercase letters causes syntax errors.

String manipulation is available by functions that return the left or right portion of a string. Numeric functions include logarithms, absolute values, and two functions—EVEN() and ODD()—that return TRUE if an expression is even or odd. Dates can be added or subtracted from each other and converted to various formats. In addition, special functions such as determining the end of month and adding or subtracting a specified number of months also exist. No support of 8087 math coprocessors is provided.

The interface to DOS is via a 125-line assembly program called SUBMIT, which is listed in chapter 14 of the *User's Guide* and is part of the Utilities package in the optional Timesavers series. In addition, up to 10 serially reusable .COM files can be specified in the parameter string at start-up. These files become memory resident and are directly accessible from Metafile.

Debugging tools for procedures include single-step execution. The Assistant interactive menu mode can be used to display the active context—that is, the properties of the data items of the primary data file, current values of variables, and information about active files, current display frames, and report output destination. In addition, procedures are developed in the text areas, and a selected block of code can be executed from the edit process. This feature, coupled with the ability to enter the data area with the text area still active, allows detailed investigation of the results of this execution and quick correction of any errors. Program optimization is left to the developer.

Language interfaces are limited to Metafile execution of .COM files or DOS execution of .COM, .BAT, and .EXE files using SUBMIT. Thus, direct parameter passing between Metafile and other languages is not possible except by file generation. However, using Metafile's integration of text processing and its array capabilities, creation of files for exchanging data between programs in other languages can be as straightforward as direct parameter processing, although not as efficient.

Menu screens are also generated in the text area and may contain text, data, and formulas. SELECT <menuname> invokes a menu, treating any item enclosed in brackets as a menu option. The full cursor keypad is available for movement between these options, including the PgUp, PgDn, Home, and

End keys. When the cursor is on a menu item, the option is displayed in reverse video. A menu item is selected by pressing Enter, and the result of the selection is available for program processing in the system variable OPTION.

DATA ENTRY AND UPDATE

Screens are generated in the text area. The text is typed as needed. Input and output fields are described by pressing the Attention key and then selecting the option F for fields. The field is located at the editing location on the screen being prepared. Characteristics of the field can be described, and the default descriptions for the data element can be overridden, including display formats, ranges, translations, and whether the item is required for input. This gives the developer a wide range of control over data element validity checking on a screen-by-screen basis. Because a screen is executed in the text area, it can consist of multiple pages, with the PgUp and PgDn keys used to move between the screens.

The fields are sequenced in the order that they are placed on the screen; this allows full-screen mode to be used. It also allows an output field to represent the total of several other fields, as long as the total is preceded by its elements. In addition to fields, the results of any calculable operation can be displayed.

Entry of data via input screens automatically checks for validity of input against the current description. An error will cause an error message, and the item description is available using the help key (Ctrl-L). Variables can be displayed only (no input is allowed).

Access to programs and data elements can be controlled programmatically using the built-in functions ID and _SERIAL. ID is the value of the session name specified upon the user's entry into Metafile and may be used as a password. _SERIAL is the serial number of the current operating Metafile program. Metafile also provides the SECURE command, which encrypts procedure files so that checking of these variables can be protected from modification.

Deleted records are not eliminated from the data file until the file is copied. A file that is constantly being changed should be copied to itself on a regular basis to control file size growth and to ensure speedy access to data.

Metafile's method of accessing data based on criteria and sequence is reminiscent of some mainframe data managers. Metafile uses a record qualification method that builds a pointer file of

NEW! Break the 64K Data Limit THE INSIDE TRACK 3.1



Now updated and expanded! **THE INSIDE TRACK** is a collection of advanced utilities for PC/XT/AT and compatible

programmers. Break the 64K data limit, do **WINDOWS** and much more. Most programs run on ANY MS-DOS machine. You'll receive **80+ programs**, a **comprehensive manual**, fold out reference sheet with **memory map** and **BIOS calls**. Add our assembler code to your programs with **NO ROYALTIES!** BASIC routines are compatible with Quick BASIC and IBM BASCOM2. All **Source code included!** NOT COPY PROTECTED. Some programs require DOS 2.00 or above.

THE INSIDE TRACK

shows you how to:

- Go **beyond the 64K data limit**
- Do **fast WINDOWS** in your program
- Display data up to 10 times **faster**
- **Reserve memory** for your use
- Read/write files as **fast as DOS**
- **Control** the keyboard settings
- Much, much, more... **only \$65.00**

NEW! Break the Lock with PEEKs 'N POKES 3.1 Unprotect for GW-BASIC!



PEEKs 'N POKES has been updated and expanded for DOS 3.10, Quick BASIC and IBM BASCOM2. Learn

where to **PEEK, POKE, INP and OUT**. Swap monitors, swap printers. **DOS/BIOS function calls** to use ALL of your machine's features—not what your language limits you to. Add our routines to your programs with **NO ROYALTIES**. We supply you with **60+ sample programs**, a comprehensive manual and all **BASIC source code**. NOT COPY PROTECTED. A few programs require DOS 2.00 or above.

PEEKs 'N POKES

shows you how to:

- **Unprotect IBM and MS BASIC**
- **Disable Ctrl-Break and Ctrl-C**
- Read and change the **keyboard**
- Read and change the **monitor status**
- Access **printer & RS-232 status**
- Find more **PEEKs and POKES**
- Much, much, more... **only \$45.00**

ORDER TODAY! M/C and VISA welcome. Shipping \$3.00 per order UPS or 1st class to USA/Canada. \$8.00 per item air mail outside USA/Canada. Call for upgrade info. Dealer inquiries invited.

MicroHelp, Inc.

2220 Carlyle Dr • Marietta, GA 30062
Call Toll Free: 1-800-922-3383

Tech support
and inside GA: 404-973-9272

all records meeting a criteria specified in a FIND command. These qualified records are the only ones available for access until the criteria are lifted—via another FIND command, for example. Disqualified records can be added to the qualified set using ALSO.

FIND and ALSO must make one pass of the entire data file to build the pointer file while subsequent commands work directly on only the qualified records. This makes Metafile efficient in situations requiring a single qualification and multiple passes through the qualified records, such as producing several types of reports under one criteria. However, Metafile is less effective in situations requiring multiple qualifications and a single operation such as producing the same report for different criteria. In the latter case, for each report the entire database is passed once for qualification, and then all qualified records are again processed for the report.

Metafile supports a keyed access structure for quick access to specific records. Each key must be a single data field and is automatically updated during the input process. The number of keys is limited to three. Access to keyed values is by means of the command POINT <key> = <value>. Multiple

valued keys are not supported, so only one record is accessible for a given key value. If the records are sorted by key value, the additional records corresponding to the value are accessed by using the NEXT command. If a keyed record is deleted, the key value is lost even if another record has that key value. These restrictions on keys limit Metafile's effectiveness to data files that contain only unique key values.

Physically, the records are stored in the sequence in which they are added to the data file. In order to access the data sequentially in some other order that involves multiple data item values, the file must be sorted. Because the sort is only on qualified records, it is similar to a temporary index. The records are not physically rearranged and the original sequence is restored on completion of use of the data file or on a new criteria specification. The sorting criteria can be any number of fields as long as the sort key is less than 250 characters. Fields can be sorted in either ascending or descending order.

REPORT CAPABILITIES

Metafile provides four methods of producing report output: columnar via LIST, multi-up via LAYOUT, report form text files, and programs. The destination

of the output can be the screen, printer, or the text area.

As with most Metafile commands, LIST either can be typed as a command or programmed through menu selection. LIST produces a standard columnar report with up to three levels of control break. Averages, totals, and counts are available at each break level. Outputting of duplicated values can be suppressed so that changes in field values can be easily discerned. Headings can also be specified for each field.

The LAYOUT command produces multi-up reporting that is useful in generating mailing labels. A text file is created in which the size in rows and columns is specified and fields are named within curly braces. Text also can be entered. This text file is then named in the LAYOUT function along with the number of repetitions across the page producing the multi-up report.

Report formats are produced in the same manner as the text files for labels. However, any Metafile command can be included in these reports so that looping and value assignments can be made. The result is a completely flexible reporting technique that incorporates both report painting and programming control. An example of placing command structure within a report would be the use of IF statements to produce completely different text depending on values of a particular field.

The report format is written to the printer by the PRINT command. Because reports allow for any valid Metafile command to be placed in the text, other report formats can be merged into a report by using the PRINT command within the report.

Specifications for the reports or layouts are provided by a series of commands in the text of the report format or layout. These can be Metafile commands preceded by a % character, or they can be special printing commands that control page ejection, spacing, page depth and width, forms length, indenting, number of copies, headers, footers, and printer control codes. Most of these have system variable counterparts so that values can be tested or included in the report itself.

Metafile does not provide any utility for rebuilding damaged files; nor is transaction logging available. However, the manual updating procedure provides the developer with a powerful tool for maintaining data integrity. Data integrity can be guaranteed by specifying the data file for MANUAL update and using the KEEP or DISCARD functions after integrity has been checked.

Turbo Pascal Programmers:

Turbo-Task allows any Turbo Pascal Program to run in Foreground or Background

Turbo-Task will make your program resident in memory just like Sidekick, but with one big difference: your program can also operate in background! Turbo-Task is simple to use and complete in its operation. You only add two lines to your source code. Turbo-Task takes responsibility for all multitasking duties. You specify the invoke key that will bring the program to the foreground (it will pop up just like Sidekick) and you specify a time-slice weight the program will have when operating in background. A non-zero weight will allow the program to continue operation if the user moves it to the background. It will still have full access to disk and printer. When it completes its job, (i.e. processing data on disk and printing a report), it has the option to reset its weight to zero, thus remaining dormant until the user presses its invoke key and brings it to the foreground again. Meanwhile, the user has been running other software undisturbed by this background task. Up to 16 programs can use Turbo-Task at the same time, each with its own invoke key, independent foreground window, and time-slice weight. You do not need to understand multitasking theory to use Turbo-Task. All the work is done for you. Turbo-Task does not interfere with SIDEKICK. Works with TURBO EDITOR and GAMEWORKS.

Ram-Page provides a Virtual Screen of any Size

Ram-Page takes heap space to create up to 16 pages that can be used as virtual screens. The dimensions you select are only limited by system memory. 256k of heap could be allocated to a single Page with 80 chars by 1600 lines! All of Turbo's text handling routines will operate on the Pages. Write, Writeln, Crlf, Crlf, InsLine, DelLine, Window, and Gotoxy will be redirected to work on the Page you specify. View-Page allows you to display any portion of a Page on the screen. This "view window" is automatically updated as writes are made to the Page. These windows can appear, disappear, move, and overlap. Text written to a hidden window will be there when the overlapping window disappears. Text can be moved between pages. Foreground and background attributes are maintained separately for each Page. Ram-Page also provides two new routines: InsColumn and DelColumn.

Turbo-Linker breaks the 64k Code Segment Barrier

Turbo-Linker performs two important functions: it allows your program to grow beyond 64k, and it eliminates the need to continually recompile debugged routines. Turbo-Linker will convert a set of your procedures into a module that can be loaded into the heap at run time. These procedures will operate in the heap thus freeing space in the code segment for the main program. In effect, it is using the heap for overlays, except these "overlay" module can be shared by any number of programs. Once you create a module, you never have to recompile it. You can maintain a library of modules of your frequently used procedures. There is no limit on the number of modules that can be loaded or the number of routines in any module. A loaded module can be "disposed" and a new module loaded in its place. Handles global variables. Allows calls between modules.

All these utilities—ONLY \$70

Tangent Technologies

180 North Wacker Drive • Suite 350 • Chicago, IL 60606 • (312) 263-0024
MC/VISA Requires Turbo 3.0 for PC compatibles
Turbo Pascal, Turbo Editor, Gameworks and SideKick are trademarks of Borland Intl.

METAFILE OVERVIEW

Metafile, version 8.2

Metafile Information Systems, Inc.,
401 16th Street S.E., Rochester, MN
55904; 507/289-8967

Product type. A data manager that features a rich screen and reporting command structure, a delayed data update feature to ensure data integrity, and innovative use of a text buffer not only for standard editing but also for program-controlled text processing and the creation of menus.

IBM PC environment. PC, PC/XT, PC/AT, or 100-percent compatible running DOS 1.1 or higher with two floppy disk drives, or one floppy drive and a hard disk, a monochrome or a color monitor, and one serial port. A system configured with the minimum RAM (128KB) provides restricted text, sort, and variable capabilities—320KB are required for a full capacity system.


Other environments. Metafile's design is based on IBM hardware, but the program is able to run on some nearly compatible systems. These systems require a non-IBM configuration device or the runtime version only. A list of reported compatibles can be obtained from Metafile.

Network support. Metafile supports LANs compatible with the IBM PC Network. The LAN Toolkit provides utilities for interfacing to 3Com's EtherShare, PCnet, and Novell NetWare.

Copy protection. Metafile is not software copy protected. Hardware copy protection is provided via a special configuration device that attaches to COM1. Absence of the device restricts the system to use as a limited capacity demonstration version.

Documentation. Documentation for Metafile consists of three volumes. One volume contains an *Installation Guide* (60 pages) and a *Quick Orientation Guide* (50 pages); the second contains a 14-chapter *User's Guide*; and the third contains a *Developer's Reference Guide* that details the use of all commands. Also available for \$55 is an *Advanced Technical Guide* (70 pages) that provides details on file structures and special programming features. The *User's Guide* provides examples of the systems capabilities, and the *Developer's Reference Guide* indexes each command.

User interface. Metafile provides a menu-driven mode to communicate with the user, an interactive command



mode, and a structured programming language. A command is available to create frames (windows) so only a portion of the screen is active. Another command allows a menu selection to be returned in a reserved variable.

Help facilities. If an incomplete command is entered, Metafile automatically provides completion options via pull-down menus. A status line displays pertinent information about the active data file and commands. Pressing the help key during data input provides all validation information about the data item.

File capacities. The software allows 65KB records per file (each record with a maximum length of 1,000 bytes), 250 fields per record, and a maximum of 235 bytes for each field. The maximum number of active files allowed is 5, and the maximum file size allowed is 8 million characters. One text file can be active with a maximum of 250 characters per line.

Field types and capacities. Alphanumeric: 235 characters; numeric: 20 digits (only 16 for sorting or key purposes); and date: 7 or 9 characters with a DDMMYY or DDMMYYYY format. Date values are restricted between 01JAN1776 and 31DEC9999.

Data entry. Data validity checking via the data dictionary includes default values, multiple ranges, translation of coded input, defined input format, and defined output format. Validity checking is possible only on interactive input, and validity checks can be made screen dependent.

Applications development facilities. Turn-key systems development is supported through programming. Looping control is possible using IF, WHERE, WHILE, and FOR loops; loops and procedures can be nested to 22 deep. Parameter passing to procedures is possible via PASSED() and RETURNED(). Arrays are supported for variables and data items. Screen frame

sizing, automatic menu option retrieval, and full text control, including animation and sound, are available. The text editor allows immediate execution of selected commands.

Security. Procedure files can be encrypted. Session ID (password) is available via a special variable for program checking.

Access to system facilities. Metafile provides access to external .COM files through the command line. External .BAT, .EXE, and .COM files can be accessed via an assembly language program provided in the *User's Guide*.

Query and sorting. Queries are created by qualifying records that meet a logical condition. Additional qualifications can be specified to provide additional subsets. Queries are generated either by pull-down menus or by interactive command mode. Sorting is on multiple keys in either ascending or descending order with a maximum key length of 250 characters. Sorting is not permanent and is only done on the currently qualified records.

Reporting. Columnar reports that provide totaling, averaging, and/or counts are generated with either a single command or a menu sequence. Report files can be created that allow Metafile commands to be embedded in them. Thus, complex reports are possible if looping and accumulation commands are included in the body of the report.

Utilities. Standard file handling routines erase, rename, and copy files. Text files are automatically backed up. Data entry can be set so that updating is not automatic, and the update of records is under program control.

Data compatibility. Metafile can import or export data only in SDF format.

Distribution. Metafile is distributed via a direct sales staff with offices in Chicago, IL, Minneapolis, MN, Philadelphia, PA, Rochester, MN, and Columbus, OH. More than 5,000 copies of Metafile have been sold.

Price. \$995; demo version, \$25; Lotus Interface, \$40; *Advanced Technical Guide*, \$55; Utilities, \$60; Tabulate, \$95; Metacom Communications, \$125; LAN toolkit, \$195; RUNTIME \$795; RUNTIMEplus, \$295.

Support. Telephone support, a newsletter called *Metafile INK*, classes, and an applications catalog are provided by Metafile Information Systems, Inc.

—V. Joseph Bowman

Block software theft...

with
THE BLOCK.TM
Patented protection for your profits.

Software-based security systems can be cracked too easily.

But now there's THE BLOCK,TM an inexpensive device you supply with your software and without which it will not function.

Users simply plug THE BLOCK into an external port of their PC, where it is totally transparent. However, commands you program into your software check for the presence of the device before allowing your program to run.

What's more, THE BLOCK has the added protection of a U.S. Government patent to prevent mass distribution of illegal "work-alikes."

THE BLOCK also lowers the price of security. Prices range from \$39 for single units to \$24 for quantities over 1,000.

Call for your demonstration unit today...

So give your product investment the unmatched protection of THE BLOCK. Send today for complete information and a demonstration unit—or to get it even faster, phone us at (203) 329-8870.

And block those hackers from hacking holes in your software profit plans.



Software Security, Inc., 870 High Ridge Rd., Stamford, CT 06905.

SHELF CONSCIOUS?

Now you can organize your copies of
**PC TECH
JOURNAL**

Now your magazines can be a handsome addition to your decor, well organized, and easy to find, thanks to these durable library-quality cases or binders. They're made of luxury-look leatherette over high-quality binder board. And both styles are custom-designed for this or any other magazine you save, with size, color and imprint selected by the publisher. FREE transfer foil included for marking dates and volumes.



Magazine binders

holds your issues on individual snap-in rods, combining them into one volume. \$7.95 each; 3 for \$22.50; 6 for \$42.95. Mixed titles OK for quantity prices.



Open- back cases

store your issues for individual reference. \$6.95 each; 3 for \$19.75; 6 for \$37.50. Mixed titles OK for quantity prices.



OR CALL
1-212-503-5319

PC Tech Journal

P.O. Box 5120, Philadelphia, PA 19141

Please send: ☐ Cases ☐ Binders

TITLE _____ QUANTITY _____

PC Tech Journal _____

Other: _____

☐ PAYMENT ENCLOSED \$_____ * Add \$1.00 per order for postage and handling. Outside USA add \$2.50 per unit ordered; send US funds only.

☐ CHARGE (Minimum \$10):

☐ American Express ☐ MasterCard
☐ Visa

Card No. _____ Exp. Date _____

Signature _____

Print Name _____

Address _____

City _____

State/Zip _____

*Residents of PA add 6% sales tax.

Metafile can be used with any local area network that supports DOS 3.1 function calls. Metafile does not provide any automatic locking capabilities, and the developer must provide the correct code as part of the application. Metafile directly uses the .COM files provided by LANs for locking and unlocking software. These files are indicated in the start-up statement and then are directly usable by the procedures; parameters are available through the RETURNED function if the results are returned in the standard location for parameter passing in .COM files. New images of files that may have been created by another user are obtained by issuing the command REFRESH.

END-USER FACTORS

Metafile's end-user interface, the Assistant, is menu driven and provides access to almost all functions of Metafile. The Assistant is available to the user by pressing the attention key or by partially completing a command. If the command requires field names, they are presented in list form for selection. The same is true for selecting data files or text files. The developer can customize Metafile by providing only a subset of commands to the user. This is accomplished using ELIMINATE COMMAND

<command name>, which eliminates the command from Metafile and therefore should be performed only on copies of the program.

The IBM keyboard is not used effectively in Metafile. The function keys are ignored and the special function keys of Metafile are mapped into somewhat obscure key combinations on the keyboard—for example, help (Ctrl-L), insert record (Ctrl-F), frame left (Ctrl-T), frame right (Ctrl-Y), next record (Tab), and previous record (Backspace). A function keyboard layout card and key stickers are provided to aid in the appropriate use of keys.

Metafile supports full-screen data entry. As mentioned earlier, because screens are processed in the text area they can consist of multiple pages. In the text area, the cursor key pad provides the end user with easy movement from field to field and page to page. Because input is in the order specified during the creation of the screen, the developer can place input fields in whatever sequence that is desired. The screen function also allows data substitution, so fields that are calculated based on other input fields can be displayed on the screen as long as their sequence is after the fields that are required for the calculation.

One of the special features of screen handling is that the user can define frames that provide access to only a portion of the screen. All functions that use the text area, including screens and menus, are placed in the frame as if it were a mini screen. The commands SIZE 20,10 and AT 15,5 would define the active screen area as a frame 10 rows by 20 columns with the upper left-hand corner of the frame at row 5, column 15 of the screen. Other areas of the screen are untouched, and any cursor controls operate only in this frame. This allows for multiple page instructions to be presented on a portion of a screen or to simulate a windowing menu selection scheme.

The menu option discussed earlier is accessed by the SELECT command, which has three parameter options that provide added flexibility to the menu selection. One setting allows keyed data entry in addition to the specified menu options. The second alternative allows keyed-in data that must match one of the menu options. The third choice allows only the menu options displayed to be selected and returned in the OPTION variable. This feature was used in the *PC Tech Journal* sample editorial database to make department selection by menu and also to provide correct in-

C Cross Compiler 68000/08/10/20

Now Generates:
Position Independent Code

Features:

- Full, Standard C
- Easy to Use Compiler Options
- Complete User Documentation
- Global Code Optimization
- Optional Register Allocation Via Coloring
- ROMable and Reentrant Code
- Comprehensive Royalty Free Run-time Library
- Floating Point Library Routines
- Intermix MCC68K C with ASM68K Assembly Language or Microtec PAS68K Pascal
- Optional Assembly Language Listing Intermixed with MCC68K C Source Line Number
- Symbolic Debug Capability

The Microtec MCC68K C Cross Compiler is a complete implementation of the 'C' programming language as defined in The C Programming Language by Kernighan and Ritchie with extensions.

MCC68K emits highly optimized assembly language code for the Microtec ASM68K Motorola compatible assembler.

The Microtec MCC68K package includes the compiler, relocatable macro assembler, linking loader, run-time library, and comprehensive user's guide.

Host computers include: DEC VAX, DG MV-Series, Apollo, IBM PC and PC-compatibles..

We're **Functional** and **Fast** and **Serious** about our products. We've been providing flexible and economical solutions for software developers since 1974.

Beginning with product concept, through development, quality assurance, and post-sales support - **Quality, Compatibility and Service** are the differences which set Microtec Research apart from others.

If you're a serious software developer, shopping for software development tools, call or write today for more information:

800-551-5554,
In CA call (408) 733-2919.

3930 Freedom Circle, Suite 101, Santa Clara, CA 95054
Mailing Address: P.O. Box 60337, Sunnyvale, CA 94088

MICROTEC[®]
RESEARCH

put of state abbreviations. (For a complete description of the sample application, see "Sample Application Specifications," August 1985, p. 48. The article also is available for downloading on PCTECHline.) In the former case no keyed entry was allowed (see photo 2); in the latter, keyed entry was allowed as long as it matched the menu options.

Reverse video can be switched on or off via the SHADE command; only gray on blue or blue on gray is available with color monitors. Metafile has a graphics mode, but it displays only those characters with ASCII codes less than 128; thus, it does not provide any access to the line-drawing characters.

QUERY LANGUAGE

Queries are built by qualifying records in the currently active data file. No high-level query language exists to provide query capabilities; however, the ASSIST command allows for qualifying records via the use of menu selections, thus providing field names, operators, and connectors. Once the appropriate records are qualified, these records are available for display using ITEMIZE for one record at a time, LIST for a columnar report, which may be specified through the Assistant, or by using a report form. If data must be arranged in

an order other than physical record sequence, a sort must be performed. Queries involving multiple files cannot be created directly and must be programmed, because Metafile provides no way of relating files.

Importing and exporting of data in non-Metafile files is limited to SDF format. In order to import data, the foreign SDF file must be renamed with a .DAT extension. Then a description file (.DES) is created, which has the same field names as the file to which the data are being imported. The position variable in the description of the foreign file is the fixed character position where that field name begins. Fields that are not to be converted should not be described. Because the .DES file applies to the foreign file and does not have the standard interpretation of the position variable, it must not be used with any Metafile data file.

Importation is accomplished using the following command:

CONVERT D <filename> F.

The *D* specifies that the active Metafile data file is to be the destination, and the *F* means that the source file has fixed-length records. Exporting requires the same process except that the parameter *D* is changed to *S* for source.

Changing the *F* to *V* specifies that the foreign data record is variable length. This applies only to the length of the record; the fields to be converted should be fixed length and should begin in a fixed position.

The data file to be imported must be terminated with both end-of-record and end-of-file marks. This sequence, which is not always created when an SDF file is created, is most easily accomplished using the DOS COPY command with the parameter /A specified. CONVERT also can be used to output data from one Metafile data file to another. In the process, the order of fields can be rearranged.

The use of arrays provides another method of importing data from delimited files if their maximum line length is less than 235 characters. After renaming the delimited file to a .DAT extension and adding the end-of-file mark, the user can define the associated .DES file with a single character field 235 characters long. A temporary destination Metafile data file is also defined with the same description. CONVERT is used to convert the delimited file into a Metafile data file. At this point the single field, say DATAIN, of this file contains an exact replica of the delimited file record. Because array elements in Meta-

How to get started in expert systems ...for only \$950.

Personal Consultant™ and Personal Consultant Plus software from Texas Instruments—now you have two ways to get started in expert system development and delivery on PCs. Both run on TI Professional Computers, including the Business-Pro™ computer, as well as the IBM® PC/XT™, Personal Computer AT™ and compatibles.

Personal Consultant is the low-cost, high functionality tool for the rapid prototyping and development of expert system applications. It can get you started for only \$950*.

Personal Consultant Plus is a larger, more powerful family member with extra features to handle more complex problems, priced at \$2950*.

And, if you order Personal Consultant and decide to move up to Personal Consultant Plus, you can apply

the \$950 towards the new purchase—and keep both products!

To order, or for more information, call toll-free:

1-800-527-3500

*Suggested list price.

Personal Consultant and Business-Pro are trademarks of Texas Instruments Incorporated. IBM is a registered trademark and PC/XT and Personal Computer AT are trademarks of International Business Machines Corporation.

**TEXAS
INSTRUMENTS**

Creating useful products
and services for you.

©1986 TI 261765-03


JLASER

THE LASER PRINTER SOLUTION



Dr. HALO DPE

(Desktop Publishing Edition)




Dr. HALO just became a publisher.

For the first time, users of Dr. HALO II and the JLASER card have software that lets them merge text with graphics and print instantly. No more waiting to see how your report will turn out, press a button on your mouse or keyboard and it prints instantly, just like a snapshot.

Dr. HALO DPE has all the powerful features of Dr. HALO II with some new twists for desktop publishing. Dr. HALO DPE supports the JLASER and several advanced printers, has a new coordinate display pop-up menu, and works with the new Genius VHR graphics board and monitor.

This entire, unretouched, page was created using Dr. HALO DPE and the JLASER card and printed on a Hewlett Packard LaserJet Plus. The text was originally entered in WordStar, then read into Dr. HALO DPE in the selected typefaces. The graphics were edited using the freehand drawing functions of Dr. HALO DPE. Then, using the cut and paste functions, we moved the text and graphics around on the screen until we liked what we saw. Then we printed a full 8 1/2 by 11" page.



- Easy Icon Menus
- WYSIWYG
- Virtual Page
- Complete Painting Functions
- Over 20 fonts
- Complete ASCII Text Merging
- Image and Composition
- Document Laser Printer Support
- Advanced Laser Graphics Devices
- Support for 90 Graphics Devices
- (Including IBM EGA)
- Grab and Show Program Modules
- Instant "Snapshot" Printing


For more information, or to order Dr. HALO DPE please contact
Media Cybernetics, Inc.
8484 Georgia Avenue
Suite 200
Silver Spring, MD 20910 446-HALO
(301) 495-3305 or (800) 446-HALO

Dr. HALO DPE, JLASER, Genius VHR, IBM EGA, Hewlett Packard LaserJet Plus, and Wordstar are registered trademarks of: Media Cybernetics, Inc., Tall Tree Systems Inc., Micro Display Systems, International Business Machines, Hewlett Packard Corp., and MicroPro International Corporation respectively.

When we introduced JLASER, we knew it was the ultimate solution to current laser printer limitations. Like all good things, it's catching on fast. The list of software companies that back JLASER is expanding rapidly. We are pleased to welcome this latest addition to our growing software family of JLASER supporters.

JLASER is a controller that piggybacks onto a JRAM-3 or AT-3 two megabyte memory board giving laser printers the speed and versatility they were meant to have. It plugs directly into the printer engine of the H-P Laserjet™ or other Canon-based printers. Our interface transfers bit-mapped images from RAM, bypassing the on-board print buffer and most of the control circuitry. It opens up a creative new world of graphics and multiple type font combinations, and still gives you plenty of RAM to use for programs, data, and electronic disk.

JLASER is the powerful, economical, and efficient solution to all your laser printer problems.



TALL TREE SYSTEMS

1120 San Antonio Road
Palo Alto, CA 94303
(415) 964-1980

ATTENTION C-TREE* USERS!

The Portable Application Support System provides on-line query, screen I/O, report generation, and form generation with **no sacrifice in portability!**

- Query system allows end user on-line data inquiry and ad-hoc report generation
- Source code
- Menu and data inquiry utilities
- No royalties on application programs or on executable versions of the Query System
- Uses C-tree* portability conventions
- Complete windowing capability in a portable system. Configuration files included for IBM PC, MS-DOS generic(ANSI), and Xenix systems
- Multiple window Screen I/O system
- Single/multiple line report generator
- Page oriented form generator with automatic pagination of variable length documents
- Other source code programs available. Call for information.

\$395.00

VISA/Master Charge accepted

(718) 229-4540

**KURTZBERG
COMPUTER SYSTEMS**

*C-tree is a trademark of FairCom

CIRCLE NO. 148 ON READER SERVICE CARD

**MS-DOS, UNIX, APPLE MAC, CP/M,
NETWORKS and MORE.
ONE C-tree ISAM DOES THEM ALL!**


The creator of Access Manager™ brings you the most powerful C source code, B+ Tree file handler: **c-tree™**

- multi-key ISAM and low-level B+ Tree routines
- complete C source code written to K&R standards
- single-user, network and multi-tasking capabilities
- fixed and variable record length data files
- virtually opened files accommodate limited file descriptors
- no royalties on application programs

\$395 COMPLETE

Specify diskette format:

- 5 1/4" MS-DOS
- 8" CP/M
- 3 1/2" Mac
- 8" RT-II



For VISA, MC and COD orders
call (314) 445-6833

FairCom

2606 Johnson Drive
Columbia, MO 65203

© 1985 FairCom

The following are trademarks: c-tree and the circular disk logo—FairCom; MS—Microsoft Inc.; CP/M and Access Manager—Digital Research Inc.; Unix—AT&T; Apple—Apple Computer Co.

CIRCLE NO. 119 ON READER SERVICE CARD

METAFILE

file are separated by delimiters, one of which is the comma, assignments can be made directly by setting field1 = DATAIN(1), field2 = DATAIN(2), etc.

EXISTING APPLICATIONS

Metafile offers two options for distributing applications. RUNTIME (\$795) is purchased once and may be distributed freely. RUNTIMEplus (\$295) includes some word-processing features so the end user can modify the application. One copy must be bought for each distributed copy of the application.

The only application included with the Metafile package is the demonstration suite. Because the demonstration is written in Metafile procedures, it provides some programming examples for learning Metafile.

Metafile's sister company, Metafile Applications, provides a set of applications for nonprofit organizations. Third-party applications are available, including general business packages, such as accounting and order entry, and industry-specific packages. These applications are available from Metafile Information Systems in a 128-page catalogue.

Metafile provides a series of productivity tools in its Timesavers series. The Utilities package consists of three programs. SUBMIT allows access to DOS commands from Metafile. (As mentioned earlier, an assembly language listing of this program is provided in the *User's Guide*.) DOSTIME displays the current system time and KEYLOCKS displays the status of Caps-Lock or NumLock at any specified location on the screen.

Tabulate is a Metafile procedure, supporting screens and reports for generating cross tabulations or spreadsheet summary of Metafile data. This is a sophisticated procedure that combines data from both primary and secondary data files using the KEY feature. Counts, sums, and percents are provided.

Metacom is a program that can be used to operate an intelligent modem within Metafile. It builds a database of phone numbers along with the communications protocol to be established when dialing. This program requires access to the DOS programs COMMAND, MODE, and BASICA.

The LAN Toolkit provides utilities for interfacing with PCnet, Novell NetWare, and 3Com EtherShare. The program demonstrates methods of locking and unlocking databases and records for multiuser environments.

The Timesavers series also offers two guides in addition to Metafile's standard documentation. The *Advanced*

Powerful MS-DOSTM Software.

For the IBM®-PC, XT, AT & others with generic MS-DOS/PC-DOS 2.0 or higher.

Not copy
protected!

Only **\$39⁹⁵** Each!

UTAH **COBOL**TM

Whether student, teacher or professional programmer, this is the one you've heard so much about.

- ☐ It's easy to use. Compiles 5000 statements on a 128K machine.
- ☐ 170 clear error messages, i.e. DATA-NAME IS MISSING OR MISPELLED.
- ☐ Distribute your object code programs royalty free.
- ☐ Small object code programs conserve disk space.
- ☐ Fast compile times to increase programmer productivity. Over 25 times faster than one compiler costing \$995!
- ☐ You get a diskette and 213-page manual with lots of examples and 16 complete COBOL source code programs. **\$39.95.**

Also available: COBOL Application Packages, Book 1 **\$9.95.**

UTAH **PASCAL**TM

- ☐ 14-digit precision, BCD math, no round-off errors with decimal arithmetic for business and floating point + 63 - 64 for scientific.
- ☐ A very nice TRACE style debugging.
- ☐ Arrays up to 8 dimensions and 64K strings.
- ☐ External procedures and functions with dynamic auto-loading.
- ☐ One-step compile, no assembly or link required.
- ☐ You get a 132-page manual and diskette. **\$39.95**

UTAH **PILOT**TM

- ☐ Perfect for industrial training, office training, drill and testing, virtually all programmed instruction, word puzzle games, and data entry facilitated by prompts.
- ☐ John Starkweather, Ph.D., the inventor of the PILOT language, has added a built-in full-screen text editor, and much more.
- ☐ Meets all PILOT-73 standards for full compatibility with older versions.
- ☐ You get a diskette, 125-page manual and ten useful sample programs. **\$39.95.**

Also still available for 8-bit machines with CP/M® is our world famous Nevada Software Series used by 50,000 customers in 40 countries. These include Nevada COBOL, Nevada FORTRAN, Nevada PASCAL, Nevada PILOT, Nevada BASIC and Nevada EDIT. **\$39.95** each.

Satisfaction guaranteed. If for any reason you're not completely satisfied, just return the package within 15 days in good condition, and we'll refund your money.

IBM is a registered trademark of International Business Machines Corp. CP/M is a registered trademark of Digital Research. MS is a trademark of Microsoft Corp. © 1985 Ellis Computing, Inc.

UTAH **FORTTRAN**TM

- ☐ FORTRAN IV based upon ANSI-66 standards.
- ☐ Very fast compile times and easy to use.
- ☐ IF .. THEN .. ELSE constructs.
- ☐ Chaining with blank and named common.
- ☐ Copy statement.
- ☐ ENCODE and DECODE.
- ☐ Free-format input and output.
- ☐ A very nice TRACE style debugging.
- ☐ 150 English language error messages.
- ☐ You get a diskette, and 223-page manual. **\$39.95**

UTAH **EDIT**TM

- ☐ A character-oriented full-screen video display text editor designed specifically to create COBOL, FORTRAN and PASCAL programs.
- ☐ Only requires 15K disk space so it can fit on the same disk as your compilers.
- ☐ Completely customizable tab stops, default file type, keyboard control key layout and CRT by menu selection.
- ☐ Diskette comes with easy to read 58-page manual. **\$39.95.**


UTAH **BASIC**TM

- ☐ This interpreter has a built-in full-screen editor.
- ☐ Single- and Multi-line user definable functions.
- ☐ BCD Math- no round-off errors.
- ☐ Full Matrix operations.
- ☐ You get 220-page manual and diskette. **\$39.95.**

Handling/Shipping: No shipping charge within US. Overseas add \$10 for first package, \$5 each additional. Checks must be in US Dollars, drawn on a US bank.

Utah Software requires 128K RAM and PC-DOS or MS-DOS 2.0 or higher.

HOW TO ORDER. Send check or money order to Ellis Computing, Inc. with VISA or MASTERCARD order by phone. Sorry no COD's.



Ellis Computing, Inc.
5655 Riggins Court, Suite 10
Reno, Nevada 89502
Phone (702) 827-3030

SINCE 1977



ELLIS COMPUTINGTM

THE ULTIMATE IN ACCELERATION

X3

ITS SIMPLY THE VERY BEST MULTIFUNCTION **ACCELERATOR** FOR YOUR PC, PC/XT, AND COMPATIBLES AT THE MOST **AFFORDABLE** PRICE! AND IT USES **NO EXPANSION SLOT!**

NOW SHIPPING WITH A 30 DAY MONEY BACK GUARANTEE

YOUR COMPUTER DEMANDS PRODUCTIVITY FUNCTIONS IN ORDER TO GIVE YOU ITS BEST!

PROCESSING POWER 200% TO 800%

X3 HAS UP TO 8 TIMES THE POWER OF A PC, UTILIZING BOTH A 10 MHZ SUPER 88 AND THE EXISTING CPU FOR **DUAL PROCESSING** THAT OUTRUNS 80286 MACHINES. X3 ALSO HAS A SOCKET FOR AN 8087 MATH CO-PROCESSOR (5, 8, OR 10 MHZ).

MORE RAM 200%

X3 PROVIDES FOR TWO 640 KB MEMORY SPACES. THE 640 KB ON THE X3 IS FULLY AVAILABLE FOR YOUR APPLICATION PROGRAMS, THE 640 KB IN THE PC IS RESERVED FOR I/O BUFFERING.


HIGH PERFORMANCE I/O 15,000%

WAITING FOR I/O CONSUMES THE BULK OF YOUR COMPUTER TIME. X3 REMOVES THIS BOTTLENECK WITH SUCH STANDARD FEATURES AS DISK CACHEING, RAM DISK, PRINT SPOOLING, AND ADDITIONAL KEYBOARD BUFFERING. DUAL PROCESSING AND THE ADDITIONAL RAM GIVES UP TO 150 TIMES IMPROVEMENT IN I/O RESPONSIVENESS. YOUR PC MAY HAVE TO WAIT FOR YOU!



TRAILRIDGE RESEARCH, INC.

14300 WEST 50TH AVE.
GOLDEN, CO 80401
303-441-9109



\$449

PRICE INCLUDES 128 KB OF RAM
ADDITIONAL RAM IS AVAILABLE
IN 256 KB BANKS

YOUR EXPERIENCE DEMANDS THAT YOU ACCEPT ONLY TOP QUALITY AT THE BEST PRICE!

COMPATIBILITY 100%

X3 PROTECTS YOUR SOFTWARE INVESTMENT. IT IS TOTALLY COMPATIBLE EVEN WITH COPY PROTECTED SOFTWARE AND IT WORKS WITH MOST EMS CARDS.

WARRANTY 100% — 1 YEAR

SUPPORT 100% USA

X3 IS MANUFACTURED AND SUPPORTED FROM OUR FACILITIES IN COLORADO.

SIMPLICITY

X3 INSTALLATION IS QUICK AND EASY, JUST PLUG IT IN AND TURN IT ON. DOCUMENTATION IS CLEAR TO THE NOVICE AND COMPLETE FOR THE TECHNICAL EXPERT.

REMEMBER!

X3 DOES NOT USE AN EXPANSION SLOT, IT PLUGS DIRECTLY INTO THE EXISTING 8087 SOCKET.

NO SURCHARGE FOR
VISA OR MASTERCARD
DEALER INQUIRIES INVITED

Technical Guide provides details on the structures of data and text files, arrays, and communications protocols. Another publication is *Lotus Interface*, which explains how to write SDF files using Lotus 1-2-3 and then how to import them into Metafile and vice versa.

Metafile's standard documentation comes in three volumes. The first consists of the *Installation Guide* and a *Quick Orientation Guide*. The *Installation Guide* provides a short form for experienced computer users and a long form for novices. It discusses Metafile's configuration options, capacities, requirements, and limits, and it contains trouble-shooting guides. The *Quick Orientation Guide* offers a brief demonstration of features. The presentation is made through Metafile's end-user interface and is easy to follow.

Volume 2 contains the 14-chapter *User's Guide*. Each chapter presents a particular topic that introduces a new set of reserved words. The first several chapters discuss how to get into and out of Metafile and describe how the data and text management techniques interact. Succeeding chapters provide information on file utilities, screen generation, procedures, functions and variables, menus, report formats, special applications development facilities, communications and networking, and use of non-Metafile programs. Three appendices are provided: one describes the Assistant; one lists error messages, including a description of probable cause, correcting action if any, and a rating of the seriousness of the message; and the third lists special considerations in using some of the features.

The third volume is the *Developer's Reference Guide*, which lists reserved words alphabetically and gives the purpose, syntax, explanation, restrictions, related commands, and examples. Tabs break the alphabet into six ranges, and each reserved word is clearly printed at the side of each page. This allows easy access to the commands with the "manual lexicographic search technique"—that is, thumbing through the pages.

SAMPLE APPLICATION

The development of *PC Tech Journal's* editorial inventory system highlighted many strengths and weaknesses of the Metafile product. Metafile's strengths were in the building of user interfaces such as screens and reports, while data manipulation tended to require more programming effort because of the lack of relationships and indexing.

The first stumbling block encountered was in converting the data from

the delimited format files to a Metafile structure. Because Metafile can import only from SDF files, this seemed at first to require changing the delimited files to SDF format. However, the lengths of the delimited records were less than 235 characters, so a program was written to convert the data into a single field record; then the array capabilities were used to break out each delimited field and place its value in the appropriate field of the target database. For each database this meant defining two descriptions, one for the delimited file and one for the imported Metafile equivalent. Because these descriptions contained only one field, they could all be copied once one had been defined. Data were imported into the single field IN using the CONVERT command and put into the appropriate database by treating IN as an array. For example, in the author database the command was:

SET

LAST_NAME:IN(1),FIRST_NAME:IN(2)...

Metafile defines a comma as a delimiter between array elements and strips any quotation marks, thereby mapping the elements appropriately from the delimited Metafile record.

Another alternative was to write either a dBASE or BASIC program and

rewrite the date to SDF format. In this case the description file (.DES) of the SDF file had to be set so that the position value was equivalent to the starting character of each field.

Once the files were in Metafile format, several of the advantages of the development features of Metafile using an active text area became immediately apparent. The ability to select a block of code and execute it without leaving the editor was a tremendous time saver in both developing accurate code and debugging. A second interactive development feature that was of help in screen development and report formatting was the ability to see the text with real data by pressing the evaluate key (Ctrl-E). A major annoyance in both code development and the interactive mode was that Metafile requires all commands to be written in uppercase. A portion of the debugging process was consumed in correcting "Unknown Command" errors that were the result of failure to toggle the CapsLock key on.

Arrays should be given full consideration when designing Metafile databases. In the sample application, defining the coauthor field as character with maximum length (235) allows multiple coauthors to be handled simply, as long as the total length of the coauthor

Brand New From Peter Norton A PROGRAMMER'S EDITOR

that's *lightning fast* with the *hot*
features programmers need

only
\$50


**THE NORTON
EDITOR**™

Direct from the
man who gave you
The Norton Utilities,
Inside the IBM PC,
and the *Peter Norton
Programmer's Guide*.



"This is the programmer's editor that I wished I'd had when I wrote my *Norton Utilities*. You can *program your way to glory* with *The Norton Editor*."

Peter Norton



*Easily customized, and saved
Split-screen editing
A wonderful condensed/outline display
Great for assembler, Pascal and C*

Peter Norton Computing, Inc., 2210 Wilshire Boulevard,
Santa Monica, CA 90403, 213-453-2361. Visa,
Mastercard and phone orders welcome.

The Norton Editor™ is a trademark of Peter Norton Computing, Inc. © 1986 Peter Norton Computing.

CIRCLE NO. 150 ON READER SERVICE CARD

How to develop elegant software using Basic or "C"

by Cary Harwin

A widely shared dream is the fast, easy creation of error-free code and documentation. One of the secrets of top software designers is increased productivity through the use of powerful tools. Imagine the benefits of joining this group. Here are some ways.

For Software Designers Using BASIC :

BASIC Development Tools

➤ **Screen Builder**** easily creates powerful application screens. Using your favorite word processor or the built-in full screen editor you quickly paint your screen image. Simply create and edit fields of any length, anywhere on the screen, with both full screen editing within each field and movement from field to field. Enhanced graphics presentations are encouraged using all 255 ASCII characters. With available on-line help you are quickly up and running. Then error-free BASIC is automatically generated. Now the code is ready to insert into your application program without the use of BLOAD or BSAVE. With no BIOS calls, the code is tight and efficient. The system is complete with both a subroutine library and multiple examples. For only \$59 you should be using it now.

➤ **B-Plus Tree**** is a powerful record handling subsystem. Write programs without worrying about sorting or handling of index files. Fast (access a key field in a file of 32,000 records in less than one second). Direct and sequential accessing, variable length keys, multiple non unique keys and multiple keys per record. Get first, next, last or prior key in sequence. Users are amazed at the source code's simple elegance and are delighted in the value pricing of \$59.

➤ **Help Message**** systems are a part of every modern software application. Now you can provide your users with the help they expect. Interactive, context sensitive help reduces the need for extensive manual documentation while allowing your users to become quickly operational. High performance is assured through the inclusion of a fast assembler subroutine. Overhead to your program is insignificant as your text information is turned into callable libraries. A justifiable necessity at \$49.

➤ **EZ Screen**** or Pop up Windows is an assembler routine embedded in a basic subroutine to perform screen handling and

windowing functions when called from a BASIC program. Implementing EZ lets you create modern and fast menus, windows, notepads, etc. The power and flexibility found here rivals the windowing power of the modern languages found in the industry today and a must have at only \$39.

Each of these stand alone but when used together they are truly outstanding. Prove it to yourself by trying all four.

A Pleasant Surprise - It is hard to find good, affordable software; so I've done something about it. For a limited time you can purchase all four BASIC Development Tools for only \$89. (\$206 value)

*Runs under interpretive BASICA or Microsoft Basic. Compilable under IBM, Microsoft, or QuickBASIC Compiler.

For Software Designers Using "C" :

BlackStar™ "C" Function Library*

The new generation of "C" compilers demand a full featured, high performance function library. With over 250 functions, BlackStar is "the" new standard of "C" function libraries. Created for internal development and used extensively for the past two years, BlackStar has only recently been released to outside developers. Now there is no need for you to re-invent the wheel. I believe that it has everything (&more) on your wish-list of functions.

Standard Functions:

Screen handling, strings, graphics, file I/O, directory searches, peripheral control, and extensive date/time
Supports device drivers
Utilities with source: document extract, pretty printer, greplike

Powerful New Enhancements:

Menu manager and Text windows
Microsoft Mouse support
Encryption
Table driven printer control
Table driven keyboard functions for complete keyboard control and customization

High Performance features:

Optimized (in assembler) for speed and compactness
Interrupt redirection.

Complete

Compatible with Lattice and Microsoft Compilers (Ver.3) - adaptable to others
Complete source code, demo programs and comprehensive users manual

If you are using another function library it is time to make this major upgrade.

Wow! - An outstanding value at our regular price of \$99 but a virtual steal at our limited time special of only \$79.

Amazing Offer - I promise your programming productivity will be enhanced if you use these tools. In addition, I am going to make testing them in your home or office so easy that it will be a shame if you don't take advantage of my offer. Simply order by calling our toll-free hotline. After you receive your tools, put them to work developing those challenging projects. Try them for 75 days. If you're not convinced that they are a fantastic value, simply return them and I'll refund your full purchase price. But act now and join that select group of top software designers.

ORDER HOTLINE

1-800/7-Castle

(in CA call: 213/306-3020)

Visa, MC, COD, and checks accepted.
Shipping included in U.S. and Canada. Others please add \$15. CA residents add 6% tax.

*Requires PC or MS Dos.

Trademarks: BlackStar (Sterling Castle), MS-DOS (Microsoft), IBM and PC-DOS (International Business Machines), Lattice (Lattice, Inc)

**STERLING
CASTLE**

Helping You to Solve Problems

702 Washington Street Suite 174
Marina del Rey, CA 90292

P.S. Please remember that our products are not copy protected and we charge no royalties.

CIRCLE NO. 183 ON READER SERVICE CARD

METAFILE

names is less than the maximum. The last name of the first coauthor is COAUTHOR(1,1), and the first name is COAUTHOR(1,2). The full name can be obtained by COAUTHOR(1). This produces a separating comma between the last and first names; however, a trailing comma at the end is also included and must be stripped for correct reporting. Another reason for using arrays is that Metafile requires keys to be a single field. Thus, in the Issue data file another field was defined as ISSUE_KEY with the components:

```
ISSUE_KEY(1) = VOLUME  
ISSUE_KEY(2) = NUMBER
```

Determining the deadline for an issue was found by pointing on the key ISSUE_KEY. The volume and number were automatically displayed as year and month using the translate option in the database description.

One of the sample application tasks is to develop an input screen for article information. Several functions inherent to Metafile data field definitions were used to require certain input, validate ranges, and define output formats. The menu feature, along with defining and sizing frames, was used to guarantee accuracy of the Category, Department, and State fields. The result of the sequence of commands


```
SIZE 20,10  
AT 50,8  
SHADE 1  
SELECT CATEGORY.MNU, SUPPRESS  
SET CATEGORY:OPTION
```

produces the screen shown in photo 2. The SIZE, AT, and SHADE commands set the frame size, location, and color. The SUPPRESS option causes the user to select one of the four options presented. The SET command assigns the value in the system variable OPTION, which holds the selection, to the data field. This same technique was used for the Department field.

Input of the State field used SELECT STATE.MNU, MATCH. The MATCH option allows the user either to select the desired state or type it in. If typed in, data are validated against the allowable menu options and an error returned if no match occurs. This menu was multipaged, illustrating the full use of the cursor keys in the text area.

Producing reports in the sample application met with mixed success. The first report was columnar and provided booking information on a particular magazine issue. If the data to be output had fit on a single line, LIST could have been used to supply totals, aver-

C the Advantage.



Introducing the Lattice® MS-DOS C Compiler, Version 3.

There's never been a better time to buy Lattice C. Professional programmers the world over have made Lattice C the standard compiler for serious MS-DOS programming. Now Version 3 offers even more of the features that have made our previous versions so popular. Our new compiler features include:

ANSI language constructs including, *unsigned* as a modifier, *void* data type, *enum* data type, structure assignments, structure arguments, structure returns, and argument type checking.

The compiler also incorporates improved code generation, more efficient stack overflow checking, in-line 8087 code generation, and 80186/80286 code generation.

The library contains more than 200 new functions, including: ANSI/UNIX/XENIX compatibility; extended support for MS-DOS; extended support for networking including file sharing, file locking, and I/O redirection; and flexible error handling via user traps and exits. Plus the library has also been re-engineered to produce much smaller executables.

Try the new Version 3 Compiler from Lattice. Because C-ing is believing.



Lattice, Incorporated
P.O. Box 3702
Glen Ellyn, IL 60138
312/858-7950 TWX 910-291-2190

INTERNATIONAL SALES OFFICES:

Benelux: Ines Datacom (32) 2-720-51-61
Japan: Lifeboat Inc. (03)293-4711
England: Roundhill (0672)54675
France: SFL (1)46-66-11-55
Germany: (49)7841/4500 (49)8946/13290

CIRCLE NO. 160 ON READER SERVICE CARD

PHOTO 3: Commands Embedded within Report

```

<HEADING MDY(TODAY)&" Page Booking Report "&HMT(NOW) CE
<JECT
<FOOTING "Page "APAGE CEN 75
<WHILE NOT(EOF)
{"=" REP 75)

Volume: (VOLUME) Number: (NUMBER)

TITLE AUTHOR Editorial Listing
Pages Pages
{"=" REP 75)
< SET ISS: "(VOLUME), (NUMBER)", TEP: 0, TLP: 0
< WHILE ISS EQ "(VOLUME), (NUMBER)"
< SET EP: EDITORIAL PAGES, LP: LISTING PAGES, TEP: TEP+EP, TLP: TLP+LP
< (TITLE)
{" " &AUTHOR_LAST_NAME", "&AUTHOR_FIRST_NAME LJ 50) <EP RJ 10) <LP RJ 10)
< NEXT RECORD
< END

Total Editor Pages: {TEP}
Total Listing Pages: {TLP}

REPT_1 Txt:Col 1 Line 1 Frm:Col 1 Row 1 Margin: Mode 1%
    
```

PHOTO 4: Evaluated Report Format

```

=====
Volume: 3 Number: 1

TITLE AUTHOR Editorial Listing
Pages Pages
Fixing a Bug in Scientific Software
Connolly, Phillip EP LP

Total Editor Pages: TEP
Total Listing Pages: TLP
Total Pages : 0

Grand Total for all Issues:

Total Editor Pages: GTEP
Total Listing Pages: GTLP
Total Pages : 0

REPT_1 Txt:Col 1 Line 1 Frm:Col 1 Row 1 Margin: Mode E 1%
    
```

As photo 3 shows, any Metafile command can be included in a report form so that looping and value assignments can take place. While the report is being developed in the text area, pressing Ctrl-E will display the evaluated layout as shown in photo 4.

ages, and counts. However, automatic word wrapping for a field is not provided, resulting in the truncation of data if they exceed the allowable print area. Consequently, a report form had to be generated, but it was easy because of the ability to embed Metafile commands within the report. Photo 3 shows the report format with the embedded commands as it was developed in the text area. Pressing Ctrl-E reveals the evaluated form shown in photo 4.

The next report was a label print of all authors and coauthors for a particular issue. These labels were assumed to be multi-up; therefore, a large amount of programming was required because Metafile does not have a means of relating files. First, all articles for this issue were qualified and the author and coauthor names collected and written to a temporary file. Then, all authors not in the set to be printed had to be eliminated from the Author data file

with the DISQUALIFY command. This meant one complete pass had to be made through the Author file, pointing into the temporary file and disqualifying the Author record if a match was not found. Reading the temporary file record-by-record and searching the Author file would have meant a pass through the 900-record Author file for each author in the temporary file.

The third report, which produced information on articles written by

FORTRAN PROGRAMMERS

Looking for the right PC FORTRAN language system? If you're serious about your FORTRAN programming then you should be using F77L - LAHEY FORTRAN.

"Lahey's F77L FORTRAN is the compiler of choice. It's definitely a 'Programmers FORTRAN,' with features to aid both the casual and the professional programmer. . . F77L compiled the five files in a total of 12 minutes, which was 4 times as fast as MS FORTRAN and an astounding 6 times as fast as Pro FORTRAN!" - PC Magazine

Compare the features and performance of other PC FORTRANs with F77L and you will find that F77L is clearly the superior product.

- Full Fortran 77 Standard (F77L is not a subset)
- Popular Extensions for easy porting of mini and mainframe applications
- COMPLEX*16, LOGICAL*1 and INTEGER*2
- Recursion - allocates local variables on the stack
- IEEE - Standard Floating Point
- Long variable names - 31 characters
- IMPLICIT NONE
- Fast Compile - Increases productivity
- Source On Line Debugger (Advanced features without recompiling)
- Arrays and Commons greater than 64K
- Clear and Precise English Diagnostics
- Compatibility with Popular 3rd Party Software (i.e. Lattice C)
- Easy to use manual
- Technical Support from LCS

F77L - THE PROGRAMMER'S FORTRAN

\$477.00 U.S.

System Requirements: MS-DOS or PC-DOS, 256K, math coprocessor (8087/80287)

FOR MORE INFORMATION: (702) 831-2500




Lahey Computer Systems, Inc.
P.O.Box 6091
Incline Village, NV 89450
U.S.A.

International Dealers:

England: Grey Matter Ltd., Tel: (0364) 53499
Denmark: Ravenholm Computing, Tel: (02) 887249
Australia: Computer Transitions, Tel: (03) 537-2786
Japan: Microsoftware, Inc., Tel: (03) 813-8222

SERVING THE FORTRAN COMMUNITY SINCE 1967

MS-DOS & MS FORTRAN are trademarks of Microsoft Corporation. Pro FORTRAN refers to Professional FORTRAN a trademark of International Business Machines.



Editor's Choice
- PC Magazine

authors was simple because only the Article file had to be processed.

The sample application contained a series of ad hoc queries that emphasize the record qualification method used by Metafile. Every query has two parts: record qualification and data extraction. To illustrate, the ad hoc inquiry for finding all titles in an issue consisted of

```
FIND VOLUME = 3 AND NUMBER = 4
LIST TITLE
```

The first command qualifies the records; the second performs the task.

Because Metafile commands usually return single valued quantities for variable storage, the record qualification approach makes Metafile perform quicker than expected after simple analysis of the code if the set of qualified records is small. This was illustrated in the query that requested the average payment per page. The data extraction commands after qualification were:

```
SET A:SUM(EDITORIAL_PAGES
+ LISTING_PAGES)
SET B:SUM(PAYMENT+BONUS)
WRITE B/A
```

At first glance this appears to be extremely inefficient because SUM must be issued twice. However, for the specified query, the number of qualified rec-

ords was six so that the two SUM operations directly addressed a total of only 12 records. If the query had been for all issues, the same command would have had to pass the entire database (360 records) twice. In this case a more efficient method might be to use LIST's averaging capability. However, LIST has no summary capability, so all qualifying items would be listed before the desired result could be found.

One other query illustrated this dichotomy of Metafile's strengths and weaknesses for small changes in conditions. The requirement to find all articles received past the deadline for a particular issue was straightforward; it called for pointing to the Issue file in order to find the deadline, qualifying the records in the Article database, and then extracting the information. The commands required were:

```
IN ISSUE
POINT ISSUE_KEY = "3,4,"
SET DEAD:DEADLINE
IN ARTICLE
FIND VOLUME = 3 AND NUMBER = 4
AND DATE_RECEIVED > DEAD
LIST TITLE,DATE_RECEIVED
```

If this simple query were changed to include multiple issues, such as a single volume, a small program would

have to be written. This is due to the lack of any relational capability between files in Metafile, which would prevent automatic positioning of the Issue file to the correct record.


Metafile provides easy query capabilities when working on a single file or when requiring information from a single record in another file. It also performs well when the qualified records are a small subset of the total database, because repeated queries address only the qualified records.

BENCHMARK RESULTS

The same five benchmarks that have been run on other data managers in this series were run on Metafile under the same environment. The results are shown in table 1. In relation to previously reviewed data managers, Metafile was one of the slowest on benchmark 3; it was average on benchmark 5; and performed well above average in benchmarks 2 and 4. These two benchmarks in which Metafile was one of the top tested so far used Metafile's generation of temporary pointer files.


Benchmark 1 was a special case for Metafile because the program does not have direct import capabilities for delimited formats. The benchmark was run under two programs. One used the

Three New Ways to Get More From Your PC




1. Complete Turbo Pascal

Jeff Duntemann, Technical Editor at *PC Tech Journal*, introduces programmers to the Turbo Pascal compiler and Pascal language. You'll find clear explanations of Turbo Pascal terms and commands, advice on structured programming and program design, and numerous programming examples. **\$19.95**, 480 pages.



2. dBASE III for the Programmer

by Nelson T. Dinerstein. This best-selling book shows experienced programmers how to design and develop high-quality database systems using dBASE III. It includes a primer on the dBASE III language and explains how to convert dBASE II programs and files. **\$19.95**, 320 pages.



3. Using Your IBM PC AT

by Harley Hahn. Written for new AT users, this valuable reference guide shows you how to use DOS 3.0 and 3.1, manage disks and files, use the line editor, and more. Includes a handy summary of DOS commands and error messages. **\$19.95**, 272 pages

To order, contact your local bookstore or computer store, or send the order form to **Scott, Foresman and Company, Professional Publishing Group, 1900 East Lake Avenue, Glenview, IL 60025, (312) 729-3000.**

Send me: ☐ Complete Turbo Pascal, \$19.95, 18111
☐ dBASE III for the Programmer, \$19.95, 18180
☐ Using Your IBM PC AT, \$19.95, 18262

☐ Check/Money Order ☐ MasterCard ☐ Visa
Check method of payment. Exp. Date _____

Card # _____

Signature _____

Name _____

Address _____

City _____ State _____ Zip _____

Add applicable sales tax, plus 6% of Total for U.P.S. All orders must be pre-paid.

PT-1

C & PASCAL PROGRAMMERS

Blaise Computing provides a broad range of programming tools for Pascal and C programmers, with libraries designed for serious software development. You get carefully crafted code that can be easily modified to grow with your changing needs. Our packages are shipped complete with comprehensive manuals, sample programs and source code.

C TOOLS PLUS

\$175.00

NEW! Full spectrum of general-purpose utility functions; windows that can be stacked, removed, and accept user input; interrupt service routines for resident applications; screen handling including EGA 43-line text mode support and direct screen access; string functions; and DOS file handling.

PASCAL TOOLS/TOOLS 2

\$175.00

Expanded string and screen handling; graphics routines; easy creation of program interfaces; memory management; general program control; and DOS file support.

VIEW MANAGER

\$275.00

Complete screen management; paint data entry screens; screens can be managed by your application program; block mode data entry or field-by-field control. Specify C or IBM/MS-Pascal.

ASYNCH MANAGER

\$175.00

Full featured asynchronous communications library providing interrupt driven support for the COM ports; I/O buffers up to 64K; XON/XOFF protocol; baud rates up to 9600; modem control and XMODEM file transfer. Specify C or IBM/MS-Pascal.

Turbo POWER TOOLS PLUS

\$99.95

NEW! Expanded string support; extended screen and window management including EGA support; pop-up menus; memory management; execute any program from within Turbo Pascal; interrupt service routine support allowing you to write memory resident programs; schedulable intervention code.

Turbo ASYNCH PLUS

\$99.95

Complete asynchronous communications library providing interrupt driven support for the COM ports; I/O buffers up to 64K; XON/XOFF protocol; and baud rates up to 9600.

RUNOFF

\$49.95

NEW! Text formatter written especially for programmers; flexible printer control; user-defined variables; index generation; and general macro facility. Crafted in Turbo Pascal.

EXEC

\$95.00

Program chaining executive. Chain one program from another even if the programs are in different languages. Shared data areas can be specified.

ORDER TOLL-FREE 800-227-8087!



BLAISE COMPUTING INC.

2560 Ninth Street, Suite 316 Berkeley, CA 94710 (415) 540-5441

CIRCLE NO. 114 ON READER SERVICE CARD

METAFILE

TABLE 1: Benchmark Results

BENCHMARK TASK	TIME (secs)
Add 900 records to an empty database table	
From a delimited file	444
From an SDF format file	83
Index table on two fields (7 bytes)	20
Document and tally codes from one column	103
Mass change of one column (28 rows of 900)	9
Extract selected records to create a text file	9

When compared with data managers previously reviewed in this series, Metafile performed well above average indexing and changing records, and turned out to be one of the slowest on line output of tallied codes.

array capability of Metafile discussed earlier to import the data directly from the delimited format. This required an intermediate file and then the placement of each field in each record in the target data file; thus, it had one of the worst performances of any product reviewed to date. The benchmark was rerun with the data in SDF format. Here Metafile performed well above average when compared against other data managers; however, because the other data managers were importing using delimited format and the time required to restructure the input file into SDF format is not measured, no direct conclusions can be drawn.

Benchmark 2 required creation of an index on state and zip code. This meant using SORT to create the temporary index. This does not physically sort the records, but instead builds the equivalent of an index file. This file is not updated with new information, however, and will be lost with any subsequent SORT, FIND, or discontinued use of the file.

The poor results of Benchmark 3 seem to indicate a weakness in Metafile's interaction with the screen using program commands. This test required counting the occurrence of each state code in the author file. The required information could have been easily produced using the LIST command:

LIST STATE,,,CNT,1,Y

CNT means a count on breaks is to be produced, the 1 indicates that this is the first-level break, and the Y signifies that printing of STATE should be suppressed if its value is the same as the last line. This method was substantially slower than the benchmark program, which counted while skipping through all records in state sequence. Because the LIST command was a single command that had to be parsed only once, it should have performed rapidly. However, with no summary capability, it

required printing a line to the screen for each record even though multiple occurrences of state were suppressed in printing. The actual as well as visible slowness of this operation led to the conclusion of inefficient screen handling for line output.


Benchmark 4 tested the change of the state abbreviation CO to CL. The test made use of the fact that the data were provided in state sequence as a result of benchmark 2. The LOCATE command was used to position the data to the first occurrence of STATE = "CO", and a WHILE loop changed the succeeding records.

Because exporting to delimited format is not supported in Metafile, benchmark 5 required writing a string sequence to an intermediate file in delimited format. This was then converted to a foreign file.

STRENGTHS AND WEAKNESSES

The real strength of Metafile lies in its ability to allow the developer to build sophisticated user interfaces with minimal effort. While several other data managers provide good user interfaces in the interactive mode, Metafile allows the developer to produce custom code that provides the same level of sophisticated user interface. In fact, the entire Metafile ASSIST function could be built by a developer using the Metafile command structure. Metafile provides the developer with power far beyond what many data managers currently offer, including capabilities to define frames that automatically keep all screen I/O within this frame, to allow menus to be defined and their selected option made available to the program, and to treat text as a special type of data file with equivalent manipulation.

Unfortunately, other aspects of Metafile temper these outstanding features. Some of the problems with Metafile are simple annoyances that indicate Metafile has not kept up with the evolu-



PC TECH JOURNAL— INPUT THAT'S INDISPENSABLE

As a systems builder, integrator and overall expert in the IBM-PC field, you're called on *every day* to give recommendations and advice that call for:

- substantial expenditures, and
- professional risks

You can't afford to be uninformed or misinformed. You *must* be current on everything from the ever-growing complexity of PC capabilities to communications to graphics to the latest micro to main-frame linkage information to the function and value of new products to incorporate into *your* systems.

PC TECH JOURNAL is THE magazine that can keep you at the forefront of your rapidly changing profession. It was designed with

YOU, the systems expert, in mind and it speaks to you in your language.

Just as business consults you, *you* should consult PC TECH JOURNAL. Written *for* systems experts, *by* experts.

Subscribe today and SAVE 50%.

Use the attached order card, or call

1-800-852-5200

toll free for *fast* service

12 Issues for \$23.40

24 issues for \$47.40

SAVE 50%!

Savings based on annual single-copy price of \$47.40.

**TECH
JOURNAL**

4Z379

At last! - Fast, On-screen FLOWCHARTS

And Organization Charts

Finally! An on-screen flowchart processor that knows about flowcharts and organization charts - not just another "screen draw" program that makes you do most of the work.

Interactive EasyFlow is a powerful full-screen graphics program dedicated to flowcharts and organization charts. With this program you can quickly compose charts on the screen. More important, you can easily modify charts so they are always up to date.


Features: • Text is automatically centered, character by character, within shapes as you type it • Text formatting controls allow you to over-ride the automatic formatting where desired • Lines are created by specifying the starting and ending points - the program automatically generates the route • Powerful editing facilities allow shapes and even entire rows and columns of shapes to be inserted or deleted; lines are automatically re-routed as necessary • Large chart size (up to 16 shapes wide by 16 shapes high) allows very large flowcharts and organization charts to be handled with ease • Charts can be larger than the screen - the window into the chart scrolls both horizontally and vertically as necessary • Flexible printer interface allows it to work with all

printers, not just dot matrix printers. Wide charts can be printed in strips Also works with Hewlett-Packard 7475A (and compatible) plotters • Twenty standard flowcharting shapes included • Common shapes supplied in three sizes • Extensive manual (125 pages) includes many examples • Context sensitive "help" facility provides immediate assistance at any time • Any number of titles can be placed on a chart • Commentary text blocks can be placed anywhere in the chart • Fast: written in 8088 assembler • Plus many more features than we can mention here.

Requires at least 256K memory, DOS-2 or higher and an IBM or Hercules compatible graphics card.

Order direct for only **\$149.95** + \$2.00 S&H (USA/Canada), \$10.00 (foreign). Payment by MO, check, VISA, COD or Company PO. Rush orders accepted (\$15.00 S&H; USA/Canada only). Rush orders received by noon will be delivered the next business day (to most locations).

The sample screen display shown below is typical of what you see while editing a chart. Other screen displays are provided for entering titles, changing options, getting "help" and so on.



HavenTree Software Limited
P.O. Box 1093-N
Thousand Island Park, NY 13692
(613) 544-6035 ext 48

METAFILE

tion of PC software—commands must be in uppercase, subdirectories are not supported, the current directory of the default drive must be the one that contains the Metafile program, and color is limited to blue and gray.

Likewise, Metafile's data handling capabilities have the same dichotomy of superior strengths and major weaknesses. Foremost among the strengths are array handling and text processing. These are further complemented by a series of functions that allow simple qualification and disqualification of records. On the other side, the restriction to the use of keys only for exact matches, the inability to relate different files, and the restricted import capabilities make Metafile a program that must be evaluated in terms of the specific job that is to be accomplished.

Metafile is well suited to an application requiring the use of files independently. It also performs well in environments where only single records are required from secondary data files and the access is by a single field. More sophisticated data structures can be handled in Metafile but the lack of relations makes the programming effort substantially more complicated.

Metafile Information Systems is aware of these shortcomings and has announced version 9 of the product. This version was not available for testing but should be on the market by the time this review appears. Metafile claims this version will provide the following enhancements:

- Expanded capacity will allow 2,000 characters per record, procedure nesting to 40 deep, physical data files to 16MB, and eight active data files.
- Performance improvements in the upcoming version will include the ability to change an existing record rather than creating a new record, reduced I/O time, support of duplicate key values, expansion of POINT to include <, <=, >, >=, and navigation through the records via key values.
- Requirements will be for 256KB, serial adapter, and DOS 2.1 and higher.

This new version appears to alleviate many shortcomings of the current product, especially with the increased use of keys for accessing data and the allowance for multiple occurrences. Upgrades are to be available for \$195, and version 9 is supposed to be 100-percent compatible with version 8.

V. Joseph Bowman, Ph.D., owns Bowman Associates, specializing in information resource planning. He is treasurer of PC Professionals Association of Southern California.



*I didn't know
it was a crime* They told me those copies of
programs I made for my computer
could cost the company hundreds of thousands
of dollars. Maybe even cost me my job.

Few people realize that software piracy is a Federal crime. At ADAPSO, the computer software and services industry association, we're doing everything we can to inform the public of the problem. And the penalties.

You could unknowingly put your company on the receiving end of a lawsuit by making illegal copies of software. Maybe even put yourself on the receiving end of a pink slip. And that's why ADAPSO wants you to know the facts.

Return the coupon for a brochure that explains the risks of software piracy. It's free. And it may help you keep your job.

Send this coupon or your business card for more information.
Or call us at (703) 522-5055 and ask for Marilyn.

ADAPSO, 1300 North Seventeenth Street, Arlington,
Virginia 22209

NAME	TITLE	
COMPANY		
ADDRESS		
CITY	STATE	ZIP



Software Piracy is a Federal Crime



to




the dBx™ translator

- dBx produces quality C direct from dBASE II or III programs.
- Move dBASE programs to UNIX or other machines.
- Improve program speed and reliability.
- Support multi-user/network applications.
- With power guidebook of conversion hints.
- Includes full screen handler and uses your current C database manager.
- May be used to move existing programs or help dBASE programmers learn C easily.
- For MSDOS, PCDOS, UNIX, XENIX, Macintosh, AMIGA. (Uses ANSI.SYS driver on MSDOS, CURSES under UNIX)
- Priced from \$350, also available from distributors.

dBx is a trademark of **Desktop Ai**

1720 Post Road E., Westport, CT 06880 MCIMAIL • DESKTOPAI
Phone • 203-255-3400 Telex • 6502972226MCI

CIRCLE NO. 102 ON READER SERVICE CARD



New for IBM PC/XT/AT low cost mag tape subsystem

- Fast controller—40Kbytes/second
- New MAINSTREAMER™ tape drive
- Small size, lightweight

Send for our complete drive and interface manuals so you can evaluate and compare. Only \$25 for both.

Tape systems are also available for all other RS-232-C interfaces. Call or write attn: IBEX Applications Engineer today.

IBEX

Right for the times

IBEX COMPUTER CORPORATION
20741 Marilla St., Chatsworth, CA 91311
(818) 709-8100 TWX: 910-493-2071

CIRCLE NO. 149 ON READER SERVICE CARD



ADALAB-PC™

Adds Lab Data Acquisition
To Your IBM® PC For \$655

An ideal interface for chromatography, spectrophotometry, process control, etc.

ADALAB-PC includes ① a 13-bit integrating A/D, ② a 12-bit fast A/D (up to 20 kHz, add \$275), ③ a 12-bit D/A voltage output, ④ a second 12-bit D/A (add \$55), ⑤ 32 digital I/O bits, ⑥ four 16-bit timers or counters, and ⑦ a terminator board which has a 4-channel multiplexer and convenient screw terminals (16-channel differential analog multiplexer with programmable gains from 1 to 256, add \$300).

③ ⑤ Versatile ADAPT software and manual (free with ADALAB-PC) works with BASIC, FORTRAN or PASCAL, includes self-test and data acquisition software. Supports fast DMA sampling, extended memory storage, scrolling stripchart display.

⑩ LABTECH NOTEBOOK software \$895.

① IMI is an IBM Value Added Dealer.
COMPLETE ADALAB-PC SYSTEMS at \$3595, including 256K IBM PC, 360KB disk, PC DOS 3.0, green monitor, color/graphics adapter, Epson printer with adapter & cable, ADALAB-PC, ADAPT software, plus IMI's Scientific Plotter-PC (\$95) and Curve Fitter-PC software (\$95) **FREE** with systems!

⑩ Trademark of International Business Machines Corp.



INTERACTIVE MICROWARE, INC.
P.O. Box 139, Dept. 237 Telex: 705250
State College, PA 16804 (814) 238-8294

CIRCLE NO. 209 ON READER SERVICE CARD

IMAGE ACE II™ Video Capture System



\$295.00

— complete —

- single slot card
- software disk
- complete manual
- video cable

Digitize video images from cameras, television tuners, and video recorders directly to your IBM PC display.

- No additional monitor needed
- 320 x 200 x 4 levels: B&W or pseudocolor
- Continuous, single frame, and remote acquisition modes with 1.3 second capture
- Works with IBM PC, XT, AT, or compatible with std. color/graphics adapter
- Save compressed 16K images on disk, send via modem, or print on matrix printers
- Combine images with text
- Make hard copy printouts for reports, presentations, signs, and posters
- Display captured images on almost any other PC

Applications range from production line monitoring, product inspection, machine vision, and robotics; to video telecommunications, BBS image exchanges, personnel records, and visual data bases.

Lodge Electronics

(IBM, PC, XT, and AT are trademarks of IBM Corp.)

P.O. Box 338 • Streamwood, IL 60103 • (312) 837-6553

CIRCLE NO. 125 ON READER SERVICE CARD

Reviews and Updates



XTREE
Executive Systems, Inc.



THE NIBBLER
Tachyon Systems, Inc.



MASM 4.0
Microsoft Corporation




**KSH-1 SCIENTIFIC
CALCULATOR**
K Software House

XTREE

Executive Systems, Inc.
15300 Ventura Blvd., Suite 305,
Sherman Oaks, CA 91403
818/990-3457

PRICE: \$49.95



Many DOS directory managers are available, but no single such utility has become standard equipment for the PC user. XTREE from Executive Systems may be a candidate for such status. XTREE is appealing to the beginner because it is easier to learn than DOS. Veteran users of DOS will find it useful as well—it is more powerful and better designed than COMMAND.COM.

Unlike the directory enhancer WindowDOS from Software of the Future (see Product Watch, March 1986, p. 179), XTREE is not a terminate-and-stay-resident program; while WindowDOS can be invoked from within an application, XTREE cannot. However, XTREE includes hard disk organizing commands that WindowDOS lacks, most notably a command that can be used to remove a directory.

To enter XTREE, the user executes XTREE.EXE (a file of about 43KB) from the DOS command line. The user then is able to execute other programs from inside XTREE. The manual states that

XTREE requires 192KB of RAM, but it reduces the memory available to programs executed from within it by only about 60KB. XTREE remains fully functional when working with up to 2,500 files stored in 180 subdirectories.

XTREE divides the screen into five windows. The three smaller windows identify the currently selected disk and display file and directory sizes. The largest window shows the directory structure of the specified disk in a tree structure. Each node of the tree identifies the name of a directory.

The user selects a current directory by moving a reverse-video bar through the tree with the cursor-control keys. The files window lists the files contained in the specified directory. The speed with which XTREE lists files and directories is impressive; the program responds almost instantly. This is possible because XTREE's file searches are not disk-bound—XTREE retains a copy of the current volume's directories in RAM. XTREE can limit the display to a set of files defined using ordinary DOS conventions, including the DOS wild cards (? and *). XTREE does not limit the user to directory-by-directory file searching; it features a convenient show all mode that lists all matching files, regardless of their directory.

File searching is only a minor component of XTREE's suite of abilities. The program also lets the user create, rename, and delete directories; copy, delete, and rename files; and move files between directories. In addition, the program can copy a group of files onto multiple diskettes when the size of the files exceeds 360KB.

All processes that are possible in COMMAND.COM are also possible—and more convenient—in XTREE. In addition, XTREE provides the user with features that are not found in COMMAND.COM. For example, XTREE's replacement for the TYPE command is a built-in read-only editor that supports two-directional

paging, scrolling, and ten position markers. XTREE can sort its file lists alphabetically by root or extension, by file size, or by date. An XTREE user can search subdirectories or stacks of diskettes quickly for a particular file, collect a group of scattered files and put them in one subdirectory, set and reset archive bits, and change directory names and volume labels.

The product offers several convenient methods for tagging files, then manipulating them as a group—it even can select files of a particular DOS attribute (for example, hidden or read-only). The user can assign any set of attributes to any file or remove any existing attributes from a file.


An install program can be used to customize XTREE's colors. In addition, this program allows the user to choose between a BIOS call to interrupt 10H or a direct call to the display adapter's memory. In this way, XTREE should run on machines that are IBM BIOS compatible but do not map display memory as IBM does, such as the Tandy 2000 and the TI Professional.

The XTREE program has no real bugs—only minor annoyances. It loses track of the currently marked file when it expands its file window, and it does not always restore the cursor to its original size upon exit. However, XTREE's file-copying function, unlike the DOS function, preserves the read-only attribute. (XTREE's manual does not mention this.) Also unlike DOS, XTREE does not accept a volume label that matches the label of an existing directory or file name. XTREE's EXEC function reloads COMMAND.COM for each program name typed by the user.

XTREE lacks some minor features that users might find convenient. It would be helpful, for example, to tag files of a specified date, to move a subdirectory under a different directory node, to compare files more easily than is possible with the DOS COMP com-

GROWING OLD?

...waiting
for C programs to
compile and link?



Use C-terp
the complete C interpreter
**This is the product you've been
waiting (and waiting) for!**

Increase your productivity and avoid agonizing waits. Get instant feedback of your C programs for debugging and rapid prototyping. Then use your compiler for what it does best...compiling efficient code ...slowly.

C-terp Features

- Full K&R C (no compromises)
- Complete built-in reconfigurable screen editor -- Editor source available for \$98.
- Fast -- Linking and semi-compilation are breathtakingly fast.
- Convenient -- Compiling and running are only a keystroke or two away. Errors bring you back to the editor at the trouble spot.
- Object Module Support -- Access external functions and data. We support Aztec, Microsoft 3.0, Computer Innovations, Mark Williams, Lattice 2.1x and Lattice 3.0.
- NEW: External functions can call functions being interpreted.
- Complete Multiple Module Support.
- Symbolic Debugging -- Set breakpoints, single-step, and directly execute C expressions.
- NEW: Software Paging to support those BIG jobs.
- Many more features including trace, batch mode and 8087 support.

• **Price: \$300.00 (Demo \$45.00) MC, VISA**

Price of demo includes documentation & shipping within U.S. PA residents add 6% sales tax. Specify compiler.

- C-terp runs on the IBM PC (or compatible) under DOS 2.x with a suggested minimum of 256Kb of memory. It can use all the memory available.

GIMPEL SOFTWARE

3207 Hogarth Lane • Collegeville, PA 19426
(215) 584-4261

*Trademarks: C86 (Computer Innovations), Lattice (Lattice Inc.) IBM (IBM Corp.), C-terp (Gimpel Software), Microsoft (Microsoft), Aztec (Manx)

PRODUCT WATCH

mand, to access the DOS FIND command, to see the actual disk space occupied by files (as opposed to the number of bytes they contain), to manipulate the two unused file attribute bits, and to see files and sizes in all sub-directories under a particular directory.


Much thought and practice is required before the novice is able to use all of XTREE's features routinely. However, anyone using DOS and a hard disk should find mastering this directory manager well worth the effort.

—COLE BRECHEN
CHARLES BRADFORD

THE NIBBLER

Tachyon Systems, Inc.
2725 Congress Street, Suite 2H,
San Diego, CA 92110
619/574-1666

PRICE: \$49.95



CIRCLE 361 ON READER SERVICE CARD

Billed as a programmer's toolkit, version 2.0 of The Nibbler from Tachyon Systems, Inc. offers several disk utility operations. The product's windowed screens are nicely done, and the program loads and operates quickly. On-line help messages are provided for almost every operation. Despite these amenities, however, Tachyon would do well to put this bug-ridden utility back on the drawing board.

The Nibbler's operations can be selected by pressing function keys. Tachyon notes in the manual that redefining the function keys can prevent The Nibbler from operating correctly. Utilities such as SideKick and SuperKey from Borland International or Rose-Soft's ProKey can be used with The Nibbler only after careful consideration is given to key redefinitions.

The Nibbler can display sorted disk directories, copy files, change bytes in files, recover deleted files, and collect memory and disk information into 512-

byte memory buffers that eventually are written to disk. The Nibbler also allows the user to specify track, head, and sector numbers to read and write disk sectors directly.

The Nibbler's manual, which does not include an index, lists among the product's operations the ability to label disks or to change existing labels as well as the ability to change the status of files. To accomplish these tasks, however, the user first must read the appropriate disk sector into memory, edit the appropriate bytes, and write the changed data back to disk. Despite the suggestion included in the manual, no single command is available to perform this operation, as is the case in some utility packages, including Software of the Future's WindowDOS.

Perhaps the most serious problem with this program is the File Map command, which does not work on hard disks because, according to the manual, "the layout would be difficult to clearly show." This is unfortunate because the manual's back cover states that the product can operate on a hard disk. This actually means that the program can be operated from a hard disk.

During testing, the File Map command, which showed up on the screen as the DOS Diskette Map command, caused the test machine (a 512KB PC/XT) to hang each time the command was used to view IBMBIO.COM or IBMDOS.COM. The problem occurred when running either the master disk or a direct DISKCOPY of the master. According to Tachyon, this effect is intentional—the IBMBIO.COM and IBMDOS.COM files have been emptied to ensure that these parts of the copyrighted DOS software cannot be distributed by the user. This effect is limited to these files on the master diskette and could not be duplicated with other files on other disks. Such behavior by a software product is unacceptable.

The Nibbler's editor is well written. With it the user can edit file or memory data as either hexadecimal bytes or ASCII characters. The user also can search through memory or disk data for strings. Edited bytes are redisplayed in bright underlined characters that clearly stand out on display. In addition, the user can copy memory into disk files in an attempt to recover data that have not been erased from memory.

Unfortunately, The Nibbler's other program operations are not so well designed. On a hard disk that contains many subdirectories, the program does not allow the user to step from direc-

tory to directory as is possible with the DOS CD (or CHDIR) command. Instead, the user must select the desired drive, then position a reverse-video cursor over one of the displayed subdirectories (the program always displays all of the subdirectories contained on a disk). The program completely ignores the tree-like structure of a typical hard disk organized with directories inside of other directories. After displaying a subdirectory, the user presses Escape to return to the main prompt where another drive must be selected and the cursor repositioned over the desired directory. This feature is poorly thought out and awkward.

An encrypt/decrypt operation is provided with The Nibbler to scramble and unscramble file data, thus protecting sensitive information. Only by typing the correct password can the original data be recovered. The manual states that the program does not use the Data Encryption Standard (DES), but it offers no information about the technique that actually is used.

The Nibbler can read p-System disks in UCSD Pascal format; it does not recognize, however, the other most popular p-System directory formats: Network Consulting's 800-block and Pecan Software System's 720-block configurations. When the disk drive of the review machine was reconfigured to access tracks as cylinders, The Nibbler was able to read a nonstandard Pecan-formatted 640-block disk directory. However, it still was not able to read or transfer file data. It displayed and copied several p-System files as though they contained only F6H bytes, even though the contents of those files were verifiably intact.

The Nibbler is a rather noisy program. Error messages are accompanied by a beeping sound, as is the case with a press of the Escape key.

Technical support from Tachyon is not always reliable. Phone calls to the company during the time of the review were not always answered as promptly as had been promised.


The lack of an index in the manual, the ambiguous documentation, the quirk of the distribution diskette, the inability to read popular p-System disk formats, the unnecessary beeping, and the poor technical support all detract from what was otherwise a good idea. Its well-done screens and the numerous on-line help messages are a promising start, but The Nibbler needs additional development work.

—TOM SWAN

MACRO ASSEMBLER VERSION 4.0

Microsoft Corporation
16011 N.E. 36th Way, Redmond, WA
98073-9717
800/426-9400

PRICE: \$150



CIRCLE 365 ON READER SERVICE CARD

Microsoft's latest release of its macro assembler (MASM version 4.0) is intended to be 100-percent compatible with both the IBM macro assembler version 2.0 and the Microsoft macro assembler version 3.01 (see "Same Language, New Architecture," Ted Mirecki, October 1985, p. 48). It features several new commands as well as many new

command-line options. However, it does suffer from some bugs.

MASM 4.0 has been optimized to improve performance and can assemble code two to three times faster than prior releases. MASM 3.0 assembles the 480-line program PACKDIR.ASM (see "Dipping into Directories," Ted Mirecki, February 1985, p. 67) in 20.15 seconds; MASM 4.0 assembles the same file in 7.74 seconds. This is an improvement of nearly 300 percent. (These benchmarks were run on a 6-MHz PC/AT with the assembly language program files on a RAM disk and the source file on a 360KB floppy disk.) The I/O buffers and macro text have been moved out of the symbol space, allowing the assembly of larger source files.

Another new feature of MASM version 4.0 is conditional error directives, which allow the user to check parameters, boundaries, and other assembly-time values. The directives generate an error if predefined conditions are not found to be true during the search. Several new exit codes have been added as well. These codes can be tested using the ERRORLEVEL batch command and the MAKE command.

MASM 4.0 includes a number of new command-line options:

Make your PC or AT into a COMMUNICATING WORKSTATION for only \$85

Use ZAP, the Communications System for Technical Users COMPLETE Communications for PROGRAMMING and ENGINEERING

EMULATION of graphics and smart terminals is combined with the ability to TRANSFER files reliably, CAPTURE interactive sessions, and transmit MESSAGES while also being able to swap between your mini or mainframe session and your PC application. SUSPEND a line to run a PC application. Reconfigure features to fit the communications parameters and keyboard requirements of the host computer software. Complete technical documentation helps you understand and fit ZAP to your style.

HIGHLIGHTS OF ZAP:


- Emulate TEKtronix 4010/14 and DEC VT 100, 102, 52 including variable rows and columns, windows, full graphics, and smooth scrolling.
- Reliable *file transfer* to/from any mainframes and PCs including KERMIT and XMODEM protocols plus you get a full copy of KERMIT. Transfer *speeds* ranging from 50 to 38,400 BAUD. Session control include *printer dumps* and *save to disk*.
- **MACRO and Installation files** ("scripts") controllable by you.
- EMACS, EDT and VI "Script" files are included. ZAP is also used with other popular software including graphics products like DISSPLA and SAS/GRAPH.
- **CONFIGURABLE** to communications, terminal features on the "other end"; 1, 2 stop bits; 5, 6, 7 or 8 data bits; parity of odd, even, none, mark and space; remap all keys including the numeric pad and standard keyboard, set any "virtual" screen size.
- Full PC/MSDOS access to run any command or program that will fit in your systems memory. ZAP takes less than 64K.
- 9 Comm ports are supported by ZAP. Plus full color in text and graphics make use of the IBM color, EGA cards, or Hercules Monochrome.

ONLY
\$85

**Solution
Systems™**

335-P Washington St.
Norwell, Mass. 02061
617-659-1571
800-821-2492

Full refund if
not satisfied during
first 30 days.



Advanced Communication Link™ Lets Your PC Use All The Brains It's Got

New "smart" 8-channel serial card unloads your IBM PC — or compatible — to give you more computing performance.

Using its own on-board CPU and an array of supporting components, the new ACL card relieves PCs of communication chores with mainframes, printers, modems, plotters, and remote terminals. The PC is thus free to do the "thinking" you demand of it.

In addition, the ACL Card expands your capabilities, too, with:

- Full modem "handshake" control on all 8 channels
- Flexible address decoding
- Programmable interrupts
- Expandable memory via software
- Supplied device driver
- Ability to download custom programs
- Optional data security module


All this takes up only one I/O space on your PC — and costs about the same as a "dumb" serial card.

Call for free literature that explains what your PC has been too busy to tell you.



33800 Curtis Blvd., Eastlake, OH 44094
(216) 951-5922

CIRCLE NO. 177 ON READER SERVICE CARD



IEEE 488 \$299
INCLUDING SOFTWARE

Real Time Devices' GP100 is a full capability GPIB (IEEE 488) interface for the IBM® PC that includes high-speed software for the single quantity price of \$299.

- Over 40 high and low level GPIB commands
- Fast assembly language extensions to BASIC
- DMA and interrupt capability
- Comprehensive tutorial/instruction manual
- No hidden software, cabling, or documentation charges
- Supports up to 15 devices
- FORTRAN, PASCAL, and FORTH extensions available

Even if you're not familiar with GPIB interfacing, the GP100 will have you controlling this powerful bus in no time at all, allowing you to focus on your application requirements.



So if you've been intimidated by the complexity or cost of other GPIB implementations for the IBM PC call on us to help — you'll be pleasantly surprised.

Real Time Devices, Inc.



1930 PARK FOREST AVENUE
P.O. BOX 906
STATE COLLEGE, PA 16804
(814) 234-8087

CIRCLE NO. 165 ON READER SERVICE CARD




MODULAR DATA ACQUISITION SYSTEM

We Bring Engineers, Scientists And The IBM-PC Together. Our unique high-performance modular data acquisition system allows you to purchase the configuration that exactly meets your requirements.

8-BIT A/D
SYSTEM
\$490

12-BIT A/D
SYSTEM
\$690



QUA TECH, INC.

478 E. Exchange St. Akron OH 44304
(216) 434-3154 TLX: 5101012726

CIRCLE NO. 138 ON READER SERVICE CARD

VT100/VT52 & Tektronix™ 4010/4014 Terminal Emulator

Excellent emulation and the features you want:

- use 4096 x 3120 resolution
- zoom, pan, and window plots
- high resolution printer dumps
- choose text and plot color
- transfer files with XMODEM and Kermit protocols
- scroll last 4 pages of text
- 132 column VT100 capability
- 16 User-definable keys
- capture plots and text on disk
- full or half duplex
- access to DOS commands
- all VT100 keypad commands
- command line editing
- fast direct screen access
- password security

VTEK makes your PC better than a terminal

\$150 from Scientific Endeavors

Publication Quality Graphics for Scientific and Technical Applications

GraphiC™ 3.0
in Color

- linear, log, & polar plots
- bar charts & Smith charts
- contour plots with labels
- 3-D curves, 3-D surfaces with hidden line removal
- 4 curve types, 8 markers
- 14 fonts, font editor
- multiple levels of superscripts
- 4096 x 3120 resolution
- zoom, pan, window plots
- multiple plots on a page
- high resolution printer dumps, full or half page
- plotter support in COLOR

16 color plots on EGA, Sigma, TeleVideo & Tecmar boards
Over 100 routines can be called by your C program. \$350. Demo \$8.

SOURCE INCLUDED for private use only.

For DeSmet, C-86, Aztec, Lattice, and Microsoft C compilers.


Scientific Endeavors

Route 4, Box 79; Kingston, TN 37763

(615) 376-4146

For 256k IBM and Corona PCs, DOS 2.xx,3.xx, Epson, Okidata, Toshiba, C. Itoh printers, Hewlett Packard, Houston, Sweet-P plotters, Corona Laser printer, IBM, IBM EGA, Sigma, TeleVideo, Tecmar, Hercules, Corona graphics. A compatible assembler is required.

THIS AD WAS MADE USING GraphiC™



CIRCLE NO. 187 ON READER SERVICE CARD

- **-B nn** directs the assembler to adjust its file buffer size to **nn** bytes. This is one way MASM has improved performance—by assembling with a buffer that is larger than the source file, MASM must read the source file from disk only once.
- **-C** creates a cross-reference file with the base name of the source file and the extension **.CRF**. This option allows compatibility with XENIX.
- **-L** creates an assembly listing file with the base name of the source file and the extension **.LST**. This option also is provided to allow program compatibility with XENIX.
- **-D** symbol defines a symbol that can be used during assembly as if it had been defined in the source file. The specified symbol is defined as a null-text string and can be evaluated by the **IFDEF** and **IFDEF** conditional-assembly directives.
- **-I** path sets the path by which the assembler will search for files specified with an **INCLUDE** directive. Up to ten search paths can be set. The order of the search is the order in which the paths are listed on the command line, then the current directory.
- **-N** suppresses generation of a symbol table in the listing file.
- **-P** can be used to search for impure code that can cause problems in 80286 protected virtual mode. (Code that moves data into memory using the **CS**: override prefix can cause problems in protected mode.) This option has no effect unless the **.286p** assembler directive was specified in the source file. When **-P** is in effect, error message 100 is generated if impure code is detected.
- **-T** (terse) suppresses all messages if no errors are encountered.
- **-V** (verbose) instructs MASM to display extra statistics after assembly.
- **-Z** displays the source lines that contain errors on the screen (without this option, only the error message is shown). Previous versions of MASM always displayed both the source line and the error message.

MASM 4.0 listing files now indicate the nest level of macros. Line numbers are right justified with leading zero suppression, and a time stamp and improved symbol table have been added.

- **-O** (octal) is not supported in the new release of MASM.

The new version of the macro assembler suffers from several bugs. For example, error messages sent to the console cannot be redirected to a disk

file. In addition, if users assemble to **NULLST** or **FILELST**, “%OUT” messages to the console appear as they should; however, if users assemble to **CON**, the messages are suppressed. Finally, MASM 4.0, like its predecessors, does not parse the final **END** key word correctly unless it is followed by a carriage return/line feed.

Most assemblers feature the ability to redefine instructions and directive mnemonics by macros; MASM 4.0 does not support such redefinitions.

During testing, a problem with the listing file was noticed: the assembler directive, **ASCII DB “C:\”,61 DUP (?)**, listed the source statement twice.

The format of the cross-reference utility, **CRF**, remains virtually unchanged in MASM 4.0. A date/time stamp has been added, and Microsoft claims that **CRF** now uses all available memory space, allowing production of larger cross-reference files.

LINK has two new command-line options: **/E** allows the user to pack executable files at link time, forming a smaller **.EXE** file that is able to load more quickly. During testing, a 15- to 20-percent reduction in **.EXE** file size was achieved. The second command-line option, **/H**, displays a list of linker

options. Microsoft claims that **LINK** has been optimized to make the link process faster; however, no difference was detected during testing. **LINK** also features a number of new exit codes.

The **LINK** command in MASM 4.0 still relies on **VM.TMF** for a temporary work file, even though **DOS 3.x** provides a “Create unique file” option. **LINK** is unable to realize it is running under a more recent **DOS** release and fully use the available functions.

Several new command-line options have been added to the debugger **SYMDEB**. **/K** enables the break key as an interactive breakpoint key, and **/N** enables a nonmaskable interrupt service routine. (The documentation states that, “To use nonmaskable interrupts, your system must be equipped with the proper hardware.” Proper hardware is a push-button switch that shorts I/O channel pins **B1**, which are ground, and **A1**, which are **-I/O Channel Check**.) **/S** enables screen flip and uses an additional 32KB of storage in which to preserve the screen image. **/commands** designates start-up commands executed immediately upon entering **SYMDEB**.

In addition, new **SYMDEB** commands have been added to MASM 4.0 as well. The exclamation point (!) is a

COPY II PC™ OPTION BOARD

AN ALMOST FOOLPROOF WAY TO MAKE ARCHIVAL BACKUPS OF PROTECTED SOFTWARE!

The Copy II PC Option Board is an add-in board that will give your PC the same disk duplication technology used by most disk duplication firms (who put the copy protection on software in the first place).

DUPLICATES NEARLY ALL PROTECTED DISKETTES.

The Option Board can easily backup almost all protected diskettes for the IBM PC (except those “protected” by physical disk damage), including ones software-only backup programs can’t touch. It even includes a track editor that will allow the more technically inclined to look at protection schemes and edit any data on a diskette.

The Option Board uses a full size slot in an IBM PC, XT or AT (with at least 1 360KB floppy disk drive), Heath/Zenith 150, 151, 158, Compaq Deskpro. Extra \$15 cable required for Compaq Portable, HP Vectra and Tandy 1000. Tandy 1000 requires 256K of memory.

Call 503/244-5782, M—F, 8—5:30 (West Coast time) with your   in hand. Or send a check for \$95.00 U.S. plus \$3 s/h, \$15 overseas. Please specify your computer brand when ordering so we can send you the correct cable.


\$95.00

Central Point Software, Inc.
9700 S.W. Capitol Hwy., #100
Portland, OR 97219

Central Point
Software
INCORPORATED

Backup utilities also available for the Macintosh, Apple II, Commodore 64/128 and Atari ST.

Does **YOUR** disk Look Like
THIS?



Let
H.D. Tuneup
cleanup your act!

H.D. Tuneup tunes your disk file system, making it better than new. File loads speed along like new. Directory searches are faster than new.

H.D. Tuneup reallocates all of your files to be contiguous. Each file is placed in its proper location, adjacent to it's neighbors in the directory.

Disk operations run faster when your files have been Tuned.

H.D. Tuneup relocates your sub-directories into one area of your disk, as close to the root as possible. All deleted entries are actually removed.

Your drive head moves less from directory to directory than when your disk was new. **TREE/F** will fly when listing all of your files.

H.D. Tuneup requires IBM PC/XT/AT compatibility, 196k, and DOS 2.x/3.x. Fixed disks up to 32mb may be tuned, along with any 5.25" diskette.

NOT COPY PROTECTED!


ONLY \$39.95 plus \$3.00 S/H

SofCap Inc.
P.O. Box 131
Cedar Knolls, N.J. 07927

Visa (201) 386-5876 M/C

N.J. residents add 6% sales tax.

**For the best performance
from your disk
TUNE IT UP!!**



Visa, Master Card, Checks, Money Orders, or COD only.

CIRCLE NO. 164 ON READER SERVICE CARD

PRODUCT WATCH

shell escape, used to load and run **COMMAND.COM**. If **!** is followed by a DOS command, the system executes the command, then returns automatically to **SYMDEB**. The period (.) displays source lines when debugging high-level language programs (with the exception of **MASM**). ***comment** echoes **comment** to the display. The backslash (\) (screen swap) allows the user to view the screen display of the program that is being debugged. It requires use of the **/S** option when **SYMDEB** is started. **V address** displays high-level language source lines beginning at **address**. **Z symbol value** sets the address of **symbol** to **value**.

MASM's MAKE command has been enhanced greatly and now includes macro definitions and inference rules. Macros can be nested. The form of a macro definition is **name = value**; when **\$(name)** is found in the description file, it is replaced with **value**.

Macro definitions either can be placed on the command line or embedded within the description file. When executed, **MAKE** searches the environment for **name**. For example, if the environment contains the equation **PATH=C:\SOMEPATH**, then occurrences of **\$(PATH)** in the description file are replaced with **C:\SOMEPATH**.

MAKE features several special macros: **\$***, **\$@**, and **\$\$\$**. **\$*** means to substitute the base name portion of the target (without the extension); **\$@** means to substitute the complete target name; and **\$\$\$** means to substitute the complete list of dependencies.

In **MASM 4.0**, **MAKE** also supports inference rules. An inference rule generalizes the traditional explicit **MAKE** target/dependent relationships into a rule. For example, a rule could be defined to specify that **.ASM** files be processed into **.OBJ** files by invoking **MASM** in a specified way. If a line appears in the **MAKE** file requesting that a target **.OBJ** file be produced from a dependent **.ASM** file *without* an explicit command on the subsequent line, the inference rule takes over and executes **MASM** in the specified way to produce the **.OBJ** file.

Inference rules can be placed in a file called **TOOLS.INI** on lines that are marked at the beginning with the tag **[make]**. If **MAKE** fails to find a dependency rule in the current file, it searches **TOOLS.INI** and applies any inference rules that it finds there.

MAKE includes several new command-line options. **/D** displays the last modification date of each file as the file

is scanned. **/I** ignores exit codes that are returned by programs called by the **MAKE** description files. **/N** displays the commands that would have been executed by the description file without actually executing them. **/S** is used to execute in silent mode—that is, executed lines are not displayed.

MASM 4.0 offers two new utilities. **EXEPACK** performs the same function as the new **/EXEPACK (/E) LINK** option except that **EXEPACK** works on programs that already have been linked. **EXEMOD** displays the current status of the DOS program header and allows the user to alter the initial **SP** (stack pointer) and to set the minimum and maximum allocation values.


Overall, the documentation supplied with **MASM 4.0** is impressive. However, a reference section was not included for the assembly language itself. The documentation for IBM's **MASM 2.0** is far superior in this respect. Also, at least one error message that turned up during testing (in connection with **LINK's /E** command) was not documented. Perhaps the answer is to purchase two assemblers: the Microsoft product for the programs and the IBM product for the documentation.

—GUY QUEDENS

KSH-1 SCIENTIFIC CALCULATOR

K Software House
Route 2 Box 83B1, Unionville,
TN 37180
615/294-5090

PRICE: \$49.95; 8087/80287 and non-8087/287 versions, \$59.95



CIRCLE 363 ON READER SERVICE CARD

The idea of a memory-resident programmable calculator that can insert results of complex calculations into a report or spreadsheet is attractive. **K Software House** implements this idea in the **KSH-1 Scientific Calculator**, a memory-resident program that emulates—

8080
Z80
6809

AMX

8086
8088
Now
68000

Real-Time Multitasking Executive

- No royalties
- Source code included
- Fault free operation
- Ideal for process control
- Timing control provided
- Low interrupt overhead
- Inter-task messages

Options:


- Resource Manager
- Buffer Manager
- Integer Math Library

Language Interfaces:

C Pascal
PL/M Fortran

DOS File Access:

CP/M-80
IBM PC DOS



AMX is TM of KADAK Products Ltd.
CP/M-80 is TM of Digital Research Corp.
IBM, PC DOS are TM of IBM Corp.

AMX for 8080	\$ 800 US
8086	950
6809	950
68000	1600
Manual (specify processor)	75



KADAK Products Ltd.

(604) 734-2796

Telex: 04-55670

206-1847 W. Broadway, Vancouver, B.C., Canada V6J 1Y5

CIRCLE NO. 112 ON READER SERVICE CARD



Bill Gates
(Microsoft BASIC)

"The finest pieces of software are those on which one individual has a complete sense of how it works, even though many people may be involved with the project. For that to happen you have to really love the program."

Programmers at Work

Interviews with 19 of Today's Top Programmers

Available wherever fine books are sold.

\$14.95 softcover **\$19.95** hardcover




Micro to Mainframe Connection

The Model TC-50 1/2-inch tape subsystem provides a standard medium for transmission of mainframe data base information to PC users, while maintaining mainframe isolation and data integrity. Use ODI subsystems to import data to data base programs like dBase III.

The TC-50 subsystem also provides fast back-up capability as well as a device driver and interface software for popular compilers.

The TC-50 subsystem includes tape drive controller, cables and documentation. All ODI products carry a 30 day unconditional money-back guarantee, and are warranted for one year, parts and labor.



Overland Data, Inc.

5644 Kearny Mesa Road
San Diego, CA 92111
Tel. (619) 571-5555
Telex 754923 OVERLAND

Also Available —
XENIX tape
subsystems
for the
IBM AT

TURBO PROFESSIONAL™

SERVICE INTERRUPTS

No assembly required

RESIDENT PROGRAMS

Easy, pop-up routines

EXECUTIVE PROGRAMS

Run ANY DOS program

DISK SECTOR I/O

Lowest level access

FAST TEXT WINDOWS

Virtual windowing system

KEYBOARD MACROS

Simple, powerful

LOTS OF EXAMPLES

21+ full example programs

MUCH MORE...

Over 140 routines in all

"If you never thought Turbo Pascal was a systems programming language, you've never seen Turbo Professional."

Darryl Rubin
Computer Language

For programs that move with technology—Turbo Professional—a truly professional library of subroutines.

150 page reference manual.
Full source—many example programs.

No royalties charged for applications.

Requires IBM compatible,
DOS version 2.0 or greater,
Turbo Pascal 2.0 or greater.

Turbo Professional, trademark of Sunnyhill Software
Turbo Pascal, registered trademark of Borland International

Dealer Inquiries Invited.

\$69⁹⁵ plus \$5.00 S&H

Washington residents add 7.9%
International orders add \$5.00
VISA and Mastercard accepted.

To order Toll-Free
call 1-800-367-0651

**Sunny Hill
Software**

13732 Midvale N. Ste. 206
Seattle, WA 98133
(206) 367-0650 M-F, 8-6 PDT



CIRCLE NO. 152 ON READER SERVICE CARD

CIRCLE NO. 185 ON READER SERVICE CARD

Learn and Use AI Technology In Your First Evening With PROLOG-86

NOW ONLY
\$95

A complete *Prolog Interpreter*, *Tutorial*, and set of *Sample Programs*:

☐ **Modify and write Expert Systems.**
Use the simple "Guess the animal" example on the Tutorial or use the sophisticated system for Section 318 of the US Tax Code written by one of the PROLOG-86 authors and published in the March, 1985 issue of Dr. Dobb's Journal.

☐ **Understand Natural Language**
Use the sample program that produces a dBase DISPLAY command as output.

Programming experience is not required, but a logical mind is.

Prolog-86 Plus for \$250 adds: Windowing, 8087, 640K memory access, random access files, strings support and definite clause grammar.

RECENT IMPROVEMENTS: Floating point support, MSDOS commands, on-line help, load Editor.

AVAILABILITY: All MSDOS, PCDOS systems.

☐ **Write Symbolic Math or Abstract Problem Solving Applications**

This is a complete Prolog program to convert from Fahrenheit to Centigrade: $f_to_c(C,F) :- C \text{ is } (F-32) * 5/9$. Planning programs and games are included to help you learn.

☐ **BECOME FAMILIAR WITH PROLOG IN ONE EVENING.**

ONLY
\$95

**Solution
Systems™**

335-P Washington St.
Norwell, Mass. 02061
617-659-1571
800-821-2492

Full refund if
not satisfied during
first 30 days.

CIRCLE NO. 126 ON READER SERVICE CARD

LEARN LISP

Interactively and Write Real Programs with TransLISP for Only \$75

A "COMMON LISP" compatible *Tutorial, Interpreter, Debugging, and Pretty Printer* plus a *Fast, Full Screen Editor, Samples and Help*

☐ **Start Easily and Quickly:**
A complete, modular tutorial helps you learn LISP at your own pace. An integrated, interactive environment provides all of the elements needed to enter, modify, analyze and debug programs.

☐ **Natural Language, Expert Systems and Symbolic Manipulation:**

Natural Language concepts are illustrated by a phone number retrieval program. Choose the best word processing program for you with the Expert System. Arithmetic expressions are translated to Assembler using a code generation program.

☐ **Write Realistic Programs:**
Short examples and substantial programs of about 10 pages in length help you learn by modifying, studying and using the key concepts needed to write programs of 1000 lines or more.

☐ **The "COMMON LISP" Standard:**
TransLISP includes a 300+ function subset of the "COMMON LISP" Standard. Use extras like the MSDOS interface and graphics. Or use "strict compatibility" to make programs written in TransLISP, upwardly compatible to work with other COMMON LISP systems like VAX LISP, GC/LISP or LISP Machine LISP.

Recent Improvements: 640K Memory use supports 12000 line programs.
Full 8087 and 8086 floating point included.

Runs on any MS/PCDOS System with 256K. It is not copy protected.

"The best LISP I've ever used. Three times before, I tried to learn LISP, but until now I could never break through the surface." *W.L. Whipple, User*

ONLY
\$75

**Solution
Systems™**

335-P Washington St.
Norwell, Mass. 02061
617-659-1571
800-821-2492

Full refund if
not satisfied during
first 30 days.

CIRCLE NO. 129 ON READER SERVICE CARD

with some extensions—the Hewlett-Packard HP-11C hand-held calculator.

The user presses a hot key to invoke KSH-1, which then accepts input from either the keyboard or an optional mouse (Microsoft or Mouse Systems is supported). After calculations are performed, the results can be transferred to the original application. During testing for this review, this feature worked with Lotus 1-2-3 and Satellite Software International's WordPerfect. It would not work, however, with Microsoft Word. In addition to operating KSH-1 in direct-entry mode, the user can run, store, and retrieve with the utility.

The basic flaw of KSH-1 is its awkward user interface. The design of a hand-held calculator involves compromise. Size and functionality must be weighed continually against each other. In the HP-11C, for example, most keys provide three functions, which conserves space on the calculator's keyboard but necessitates the use of two Shift keys. In choosing to emulate the HP-11C, the authors of KSH-1 are subject to these same design limitations.

The user can accept the limitations of a hand-held calculator as a fair trade-off for the compact physical size. For the PC user, physical size is not a factor—speed and user friendliness are more important considerations. KSH-1 lacks an adequate user interface.

KSH-1 is easily installed. A configuration program is run once to specify if the user desires graphics, if a color monitor is attached to the system, if a mouse will be used for input, and which hot key combination is desired. The program requires 50 to 65KB, depending upon system configuration.

The calculator can be operated with the keyboard alone or with a combination of the keyboard and a mouse. When the user is working only from the keyboard, numeric keypad cursor keys are used to move the cursor among the calculator keys. The Space Bar is used to press each calculator key. Numbers and functions also can be entered directly from the keyboard. A table that lists the key combinations for each of the functions is provided in the README.DOC file on the program diskette. This table must be kept handy because the key combinations are not recognizable. For example, the COSH function is invoked by typing f j m.

When the user is working with the keyboard/mouse combination, the mouse can be used to move the cursor; the left mouse button pushes the calculator key, while the right button pushes


The First Idea-Processor For Programmers.

FirstTime™

Has features no other editor has.

- ☐ Fast program entry through single keystroke statement generators
- ☐ Fast editing through syntax oriented cursor movements
- ☐ Dramatically reduced debugging time through immediate syntax checking.
- ☐ The error checking is thorough and includes semantics • Undefined variables, types and constants • Assignment statements with mismatched types • Errors in include files and macro expansions
- ☐ Automatic program formatter (you specify the rules)
- ☐ Split Screen editing
- ☐ Command DOS from FirstTime
- ☐ Reading a file with errors moves cursor automatically to point of error
- ☐ Unique programmer-oriented features
 - zoom command gives top-down view of program logic
 - view macro command shows expansion of a C macro in the editor
 - view/update include file allows you to view and update an include file
 - transform command allows you to transform statements to related ones
 - search for next error command

Requires MS DOS, 256k (384 recommended) & 5.25" drive



To Order Call: (201) 741-8188 or write:

SPRUCE TECHNOLOGY CORPORATION




P.O. Box 7948
Shrewsbury, NJ 07701

FirstTime for Turbo Pascal	\$ 74.95
FirstTime for dBase III	\$125.00
FirstTime for MS-Pascal	\$245.00
FirstTime for C	\$295.00

FirstTime is a trademark of Spruce Technology Corporation • MS-DOS is a trademark of Microsoft Corporation • IBM is a trademark of International Business Machines Inc • Turbo Pascal is a trademark of Borland International • dBase III is a trademark of Ashton-Tate

CIRCLE NO. 242 ON READER SERVICE CARD



Jonathan Sachs
(Lotus 1-2-3)

"The development of 1-2-3 was ten months of nothing but eating, sleeping, and working....

The rate of innovation is rather slow. There are only a few really new ideas every decade."

Programmers at Work

Interviews with 19 of Today's Top Programmers

Available wherever fine books are sold.

\$14.95 softcover **\$19.95** hardcover



PC ↔ MAINFRAME VIA 9-TRACK TAPE

For Information Interchange - Backup - Archival Storage

IBM format compatible 9-track, 1/2 inch magnetic tape is the universally accepted media for mainframes and minicomputers. Catamount offers *Low Cost, Lightweight* 9-track Tape Subsystems for the IBM-PC/XT/AT computers which allow:

- Reading tapes generated on mainframes and minicomputers.
- Writing tapes to be read on mainframes and minis.
- ASCII, EBCDIC and Binary tapes accommodated.
- 800 bpi NRZI, 1600/3200 bpi PE, and 6250 bpi GCR format systems available.
- Storage capacities up to 270 MB on a single reel.

Systems come complete with comprehensive DOS command syntax oriented software and an Installable Device Driver. For OEM applications, the tape controller is available separately.



2243 Agate Court
Simi Valley, CA 93065-1898
(805) 584-2233

CIRCLE NO. 111 ON READER SERVICE CARD

TASKVIEW™

WHY GIVE UP. . .

BATCH FILES,

I/O REDIRECTION

SIDEKICK™

DOS MENU PROGRAMS,

MOST OF YOUR RAM,

EXECUTION SPEED?

Compatible, efficient DOS multi-tasking.

We designed Taskview with efficiency in mind. During normal operation, TASKVIEW hides behind DOS, providing you with control of up to 10 concurrent or non-concurrent programs. Just the touch of a key instantly switches a program to the foreground. Included desktop utilities let you cut and paste from program to program. Simple to use and reasonably priced, no well equipped PC user should be without it.

Requires: PC/AT/Jr compatible, DOS 2.0-3.1, 256K RAM, 1 Floppy drive.

Taskview trademark of Sunnyhill Software
Sidekick registered trademark of Borland Int.

30-day money back guarantee

Dealer Inquiries Invited.

\$69⁹⁵ plus \$5.00 S&H

Washington residents add 7.9%
International orders add \$5.00
VISA and Mastercard accepted.

To order Toll-Free
call 1-800-367-0651

**Sunny Hill
Software**

13732 Midvale N. Ste. 206
Seattle, WA 98133
(206) 367-0650 M-F, 8-6 PDT



CIRCLE NO. 158 ON READER SERVICE CARD

Does your database program let you...

1. Add and delete fields from existing files without destroying files?
2. Increase or reduce field width without destroying files?
3. Avail the updated data to all user files in the system?
4. Use the existing data instead of re-entering it as original data?
5. Create hierarchy and network databases easily?
6. Keep a true database, not just manage files?

TrueDataBase does! (and much more.)

For further information contact:
Software That Really Works, Inc.
 750 E. Colorado Blvd. Ste 4
 Pasadena, Ca. 91101
(818) 798-1661

CIRCLE NO. 147 ON READER SERVICE CARD

C COMPILERS for 680X0

- ▶ Produce highly optimized code for MC68000/010 and MC68020/68881
- ▶ Complete development environment: Assembler, Linking and Downline Loaders, Runtime Libraries
- ▶ Available for Motorola, DEC, and IBM PC host computers

HOST	68000/010	68020/68881
▶ MOTOROLA/VERSA DOS—Industry's most popular optimizing C Compiler	\$1495	\$2295
▶ DEC VAX/UNIX—half the price of comparable products	\$1495	\$2995
▶ DEC VAX/VMS—yields very fast, compact MC68K code	\$1495	\$3495
▶ IBM PC/PC DOS—Turns your PC into a MC68K development station	\$ 795	\$ 995



CALL ALCYON AND ORDER NOW! Warranty, Documentation, Maintenance, and Telephone Support included.



5010 Shoreham Place • San Diego, CA 92122 • (619) 587-1155

UNIX is a trademark of AT&T • DEC, VAX, VMS are trademarks of Digital Equipment Corporation • VERSA DOS is a trademark of Motorola • IBM PC is a trademark of International Business Machines

CIRCLE NO. 106 ON READER SERVICE CARD

PRODUCT WATCH

the KSH-1 Enter key. The mouse makes KSH-1 easier to use, but the calculator responds slowly to the instructions from the mouse. Another drawback is that the mouse tends to run along rows and columns; sliding it diagonally across the calculator is more difficult.

In addition to the direct-entry mode, KSH-1 provides a mode in which users can enter and edit HP-11C programs. KSH-1 accepts programs of up to 512 steps. Users load programs by pressing the appropriate numeral and function keys. Editing a program is straightforward—users single step forward or backward through the lines of a program to make modifications. As aids to debugging, up to 20 lines of the current program can be displayed on the monitor, and users can list all or part of a program on a printer.

Although it is designed according to the format of a calculator, KSH-1 takes advantage of the improved I/O of a PC in several ways. Programs can be saved to disk and restored. A directory of all files in a subdirectory can be requested from within KSH-1, and the four stack registers can be displayed constantly on the screen.

One nice feature that KSH-1 offers over the HP-11C is the ability to perform hex, octal, and binary arithmetic. A significant drawback, however, is that only unsigned numbers are supported. KSH-1 also supports Boolean and Shift operators. The program carries out calculations to 18 decimal digits of accuracy; 17 digits can be displayed.

KSH-1 operates with memory-resident utilities, but the program interferes with the DOS 3.1 PRINT function. In addition, the mouse does not operate in the keyboard/mouse mode when the calculator is called while the system is running Microsoft Word. While the hot-key combination used to pop up the calculator is chosen by the user, the combination that exits the calculator while passing a result to the foreground process (ALT-I) is not.

KSH-1 Scientific Calculator is available in both non-8087/80287 and 8087/80287 versions. Neither is copy protected. The program is accompanied by a 93-page reference manual that describes the overall calculator structure, discusses the function of each calculator key, and explains how to enter, edit, store, retrieve, print, and run a program. Error messages are described in one appendix, a reference to each calculator key is included in another.

—JEFFERY W. WILSON



ASMLIB

Assembly Language Programming Library for the IBM PC/XT/AT or compatible DOS systems.

ASMLIB gives the Assembly Language programmer 190+ assembly functions which do -

- Graphics functions draw CIRCLES, ARCS, ELLIPSES, LINES, and plots POINTS on the Color Adapter, Enhanced Graphic Adapter, and the Herc. Monochrome Card. Functions also allow PAINTING, IMAGE SAVES and RESTORES, and SCROLLING.
- Text Windows - Up to 64 text windows may be defined, outlined, overlapped, moved, and can be grouped onto 256 logical display pages.
- Floating Point - Arithmetic and Trigonometry functions for the MS and IEEE (8087) floating point formats (both 4 and 8 byte precision), and the 8087 (80287) can be utilized automatically if installed into the target system.
- ASCII String/Numeric conversion routines provide a user interface to the math functions. ASFORMAT function allows numeric values to be formatted utilizing commas, dollar signs, left or right justified, etc. (i.e. BASIC's PRINT USING).
- Mouse Support - ASMLIB provides support for any mouse device which adheres to the MS Mouse software standard.
- Dynamic Memory support can utilize all available memory (up to 640k). Blocks of memory can be allocated, changed, moved, and killed.
- Console I/O, Disk I/O with file copy routines, Asynchronous Communications, Printer Support, ASCII String support, Sound generation, plus much more.

ASMLIB is supplied with complete MASM source code on 3 DOS diskettes along with a 215+ page reference manual.

**- ALL FOR ONLY -
\$149.00**

For ordering or info please call:

BC Associates
13073 Springdale St., Suite 134
Westminster, CA 92683
(714) 741-3015

Phone COD orders accepted - ORDER YOURS TODAY!!!

!! POWER !!

THE KSH-1 SCIENTIFIC CALCULATOR

is memory resident and provides
all the functions available on the
HP-11C PLUS MORE!

- Imports/Exports data
- Calculations to 18 digits (17 displayable)
- Graphically presented
- Stack/storage registers displayed simultaneously
- Operates in hex, binary, octal & decimal modes
- Performs boolean algebra functions
- Fully programmable; save/recall programs to disk
- May be used in graphics mode

Price: \$49.95 Standard Version
\$59.95 8087 Version (includes standard version)

Terms: \$3 S/H US, \$4 Canada, \$10 outside US/Canada
Visa, MC, money order, check
Tenn. add 7.25% sales tax



K SOFTWARE HOUSE INC.

Software, Service, Consulting
RT 2 BOX 83B1
UNIONVILLE, TN 37180
(615) 294-5090

Be 3-6 times more Productive!!! Guaranteed* For \$99⁰⁰

Demo/Prototype/Application Generator

The "Assistant" helps you develop your functional specs (Generates Screen, File, Isam, Variable and Menu Control Documentation) and then allows you to "Quickly" prototype a validation model of your system. (Which can be incorporated as part of your functional specifications.) The Assistant can then generate a super-fast Turbo Pascal Program that features advanced screen input and control, a professional control menu, the database functions of (1) Add/Edit/Delete Records (2) Search Database by any Key (3) Database Recovery programs (4) Screen/Printer Report for each of the keys. Each Key can have up to 6 fields.

Our Users Report

- "Since Fall of 85, I have generated over 300 program modules with it and find it to be just what I needed. Most all of the modules represent 5000 to 8000 lines of Pascal Code" Oner Systems.
- "By being able to produce a 21 screen and menu control demo so quickly helped me obtain the contract."
- "Speeded up my screen development by 6 times" Elexor Associates.
- "Has many of the features of the Super Mini development tools costing \$10,000." Applied Micro Systems.
- "Saved months from having to recode portions of our system." Real Green Inc.
- "We developed 3 Vertical Market Applications in the 6 months we had your system." Absolute Systems.

Also Generates "Ready to Run" Turbo Pascal Programs
(No programming needed)

Receive 6 Floppy Disks and a 200+ page manual containing:

1. **Screen Painter/Editor & Generator** • Paint menu screens using keyboard • Has variable dictionary to provide consistent edits • Date entry masks • Date & range checks • Field and/or global help screens • Box & line drawing • Error & message handler
2. **Help Screen Maker** • Different help screen for each field.
3. **Menu Editor & Generator** • Allows selection by 4 methods.
4. **Database Program Generator** • Produces "Easy to Read" code that can be easily modified by experienced developers.
5. **Resident Isam Module** - compatible with Turbo Toolbox, but saves 8K of codespace and 10K of dataspace.
6. **Resident Screen Capture Utility** which allows you to capture Text Screens from any running program.

& Much, Much More

Credit Card Orders Call: 1-800-821-9503

In Florida 1-800-342-0137

FREE FLOPPY/PROGRAM DATA BASE ORGANIZER

***RISK FREE TRIAL**
Try the demo package included
for 30 days. If not pleased
return for a full refund.

For Other Inquiries Call:
(305) 892-5686

Hawaiian Village Computer Software
1109 Penn. Ave. St. Cloud, FL 32769

Add 7.50 shipping to all U.S. Cities.
All foreign orders add 15.00
per product ordered
Systems requires: IBM PC, ST, AT or 100%
Compatible-256K, MS DOS 2.0 or higher - 80
column screen. Turbo Pascal 3.0-2 DD/DS
Disk Drives.

RS#	PRODUCT	ADVERTISER	PAGE	RS#	PRODUCT	ADVERTISER	PAGE
IBM COMPUTERS AND COMPATIBLE UNITS							
116	PC 2/286	Advanced Logic Research	Cover 3	102	DeSmet C "Vitamin C"	C-Ware Corp.	132
199	DART	Advanced Logic Research	84		dBX Translator	Creative Programming Consultants	108
179	Twin, Triad, Quad, Quad Turbo	Tech-Personal Computers	26-27	104	A to Z Software	Desktop Ai	166
182	AT Compatible	Tele-Video Systems, Inc.	92-93		ZipCalc	Digital Equipment Corp.	107
ACCESSORY CARDS				Dynamus Micro-Data Systems, Inc. 125			
110	RAMpage! AT	AST Research Inc.	90-91	120	C Utility Library	Essential Software, Inc.	121
159	Megagraph Plus	Atronics International, Inc.	146	161	EditCheck	Everest Solutions, Inc.	129
216	Above-Board PS	Intel Corp.	74-75	119	C-Tree	FairCom	154
125	Image Ace II	Lodge Electronics	166	148	C-Tree Query	Kurtzberg Computer Systems	154
135	OverThruster	Nucleus Corp.	130	173	Run C Professional	Lifeboat Associates	119
230	Hi-Res Graphics Card	Paradise Systems, Inc.	19	125	Utilities, Editors, Functions, Graphics	Lifeboat Associates	68
137	EGA Card	Paradise Systems, Inc.	6-7	146	HELP/Control	MDS Inc.	24
138	Data Acquisition	QuaTech, Inc.	170	134	Peeks-N-Pokes	MicroHelp Inc.	147
165	GPB Interface	Real Time Devices, Inc.	170	222	C Cross Compiler	Microtec Research	151
141	HI Card Memory Board	RYBS Electronics	132		Opt-Tech Sort	Opt-Tech Data Processing	4
124	Top Board	Seattle Telecom & Data	62	Opt-Tech Scroll	Opt-Tech Data Processing	4	
194	JLaser	Tall Tree Systems	153	222	Various	PC Brand	183
197	JRam 3	Tall Tree Systems	Cover 2		Various	PC Brand	184-185
186	X-3 Multifunction	Trail Ridge Associates, Inc.	156	180	UCSD Pascal	Pecan Software Systems, Inc.	139
MASS STORAGE HARDWARE				150	Norton Editor	Peter Norton Utilities	157
111	9 Track Tape Systems	Catamount Corp.	175	168	The Visible Computer	Software Masters	110
202	Expansion Chassis	I-Bus-Systems	21	127	Window DOS	Software of the Future, Inc.	106
149	Mag Tape Subsystem	IBEX Computer Corp.	166	147	True Data Base	Software That Really Works	176
108	LEO	Innovative Data Technology	130	130	ZAP	Solution Systems	169
185	TC-50 and TC-PC	Overland Data, Inc.	173	123	BRIEF	Solution Systems	14
231	Perstor	Systems & Software	119	242	Firsttime	Spruce Technology	175
ALTERNATE INPUT DEVICES				183	C Function Library	Sterling Castle	158
156	Softstrip System	Cauzin Systems, Inc.	60	183	Basic Prog. Tools	Sterling Castle	158
215	Periscope	Data Base Decisions	5	152	Turbo Professional	Sunny Hill Software	173
201	B-Trieve	SoftCraft, Inc.	2	206	Turbo-Task	Tangent Technologies	148
133	IO Pro	MEF Environmental	131	192	Flashcode, Screen Sculptor, Flash-up Windows	The Software Bottling Co. of NY	109
DATA ACQUISITION				193	Turbo Extender	Turbo Power Software	118
209	ADALAB-PC	Interactive Microwave	166	115	Windows for C	Vermont Creative Software	18
INTEGRATED CIRCUITS				SOFTWARE UTILITIES			
213	Copy II PC	Central Point Software	171	247	1 dir	Bourbaki, Inc.	64
133	No Limit	MEF Environmental Inc.	131	140	SCOUT	Chalcedony Software	133
MONITORS				164	CopyWrite	Quaid Software Limited	123
196	Monitors/Terminals	The Software Link	52		HD Tune-up	SoftCap Inc.	172
SECURITY DEVICES				163	"FLASH"	Software Masters	117
189	The Block	Software Security	150	176	"Sybil"	SOPHCO	127
COMMUNICATIONS HARDWARE				158	Taskview	Sunny Hill Software	175
121	PC MATE	Emerald Technology Group	82	101	Fortran Support for IBM PC, XT, AT	Alpha Computer Services	122
155	SmartCOM II	Hayes Microcomputer Products	54	GRAPHIC SOFTWARE			
177	Stargate OC8000	Stargate Technologies	170	218	Pro Design II	American Small Business Computers	22
COMMUNICATIONS				113	Flowchart	Haven Tree Software Limited	164
103	BLAST	Communications Research Group	126	187	GraphiC	Scientific Endeavors	170
167	DaTapaSS Remote	DTSS, Inc.	126	DATA BASE MANAGEMENT SOFTWARE			
SOFTWARE FOR PROFESSIONALS				118	Dataflex	Data Access Corp.	20
101	Fortran Support for IBM, PC, XT, AT	Alpha Computer Service	122	211	MDBS III	Micro Data Base Systems Inc.	141
156	Softstrip System	Cauzin Systems, Inc.	60	143	INFORMIX-SQL	Relational Data Base Systems	134-135
LANGUAGES				219	ZIM	Zanthe Information, Inc.	42
136	Prolog Compiler	Arity Corporation	145	ARTIFICIAL INTELLIGENCE			
105	Clarion	Barrington Systems Inc.	12-13	107	Personal Consultant	Texas Instruments	152
252	Turbo Prolog	Borland International	37		CONVERSION SYSTEMS		
254	Reflex	Borland International	35	239	Conversion System	Flagstaff Engineering	86
253	Turbo Pascal Family	Borland International	33	OPERATING SYSTEMS			
139	PROLOG/i	Chalcedony Software	131	112	Real Time Multi	Kadak Products Ltd.	173
131	"Ecosoft C"	Ecosoft, Inc.	128	239	QNX	Quantum Software Systems, Inc.	1
170	Utah Software	Ellis Computing	155	MICROPROCESSORS			
122	C-terp	Gimpel Software	168	142	PC Turbo 286E	Orchid Technology	11
	LISP	Gold Hill Computers Inc.	136	NETWORKING PRODUCTS			
128	F77L Lahey Fortran	Lahey Computer Systems	160	117	ACRnet	Intercontinental Micro Systems	112
160	"Lattice C"	Lattice, Inc.	159	154	COBOL	Micro Focus Ltd.	120
229	Modula 286	LOGITECH, Inc.	111	184	Tapestry	TORUS Systems, Inc.	101
208	Aztec C	Manx Software Systems	56	MULTIUSER SYSTEMS			
132	mbp COBOL	mbp Software & Sys. Tech., Inc.	16	179	Twin, Triad, Quad, Quad Turbo	Tech-Personal Computers	26-27
181	Instant C	Rational Systems, Inc.	124	LITERATURE			
157	ALICE/Personal Pascal	Software Channels, Inc.	88	153	Newsletter	Microsoft Corp.	28
129	LISP-86	Solution Systems	174		Bill Gates	Microsoft Press	173
126	PROLOG-86	Solution Systems	174	Jonathan Sachs	Microsoft Press	175	
195	Better BASIC	Summit Software Technology, Inc.	98	Computer Books	Scott, Foresman & Co.	161	
PROGRAMMER'S TOOLS				MAIL ORDER			
190	The CREATOR	Advanced Development Tech.	66	145	Mail Order	Floppy Disk Services, Inc.	186
106	C68	Alcyon Corp.	176		8087 Boards	MicroWay	182
200	The PC-AT Compiler	Alslys, Inc.	17	Mail Order	PC's Limited	115	
203	PC PROBE	Atron	8	Mail Order	PC's Limited	112-113	
249	Software SOURCE PROBE	Atron	23	Mail Order	Programmers Connection	43-45	
114	Blaise Computing Programming Tools	Blaise Computing, Inc.	162	Mail Order	Programmers Shop	72	
255	Turbo Editor	Borland International	35	Mail Order	The Programmers Shop	73	

NEED IT FAST? WANT TO KNOW MORE? DON'T HAVE TIME TO SHOP AROUND? INTRODUCING...

If you're like most system professionals you're up-to-date about the products in the PC marketplace. You're aware of brand and model differences, are informed about connectivity and compatibility problems, and you shop for competitive prices and fast service.

You're also probably among the many PC TECH JOURNAL readers who purchase by mail. That's why we're starting THE MART—PC TECH JOURNAL'S First Class Mail-Order Section.

Starting this month, and every month hereafter, you'll find the products you're looking for advertised in THE MART—and you'll benefit from the fast service and helpful support that identifies PC TECH JOURNAL advertisers.

If you're ready for First Class service, you're ready for THE MART.

THE MART

FIRST CLASS MAIL ORDER SECTION!

AST ADVANTAGE W/128K	\$365
VIDO 7 VEGA EGA	\$425
GENOA SPECTRUM	\$295
FORTE PJ	\$875
INTERNAL HARD DISKS FOR THE AT*	
SEAGATE USED BY IBM	
PRIAM 40 MB	\$1195
PRIAM 60 MB	\$1395
RODIME 20 MB	\$595
RODIME 32 MB	\$695
CORE 20 MB "F"	\$1195
CORE 30 MB "F"	\$1395
CORE 40 MB	\$1795
CORE 56 MB	\$2595
CORE 72 MB	\$3295

UNlock ALBUM "A"	
\$49.95 (Plus \$4 ship/handling Foreign orders \$10)	
• LOTUS 1-2-3™ (1.A, 1.A*, 2.0)	
• dBASE III™ (1.0, 1.1, 1.2 & PLUS)	
• FRAMEWORK™ (1.0, 1.1, II)	
• SYSTAT™ (1.3 & 2.0)	
• SPOTLIGHT™ (1.0 & 1.1)	
• GRAPHWRITER™ (4.3 & 4.31)	
• REALIA COBOL™ (1.2, 2.0)	

128K 1/2 HT. (38 MS)
e reflects quantity purchase

"HOT" NEW PRODUCT

128K 1/2 HT. (25 MS)

128K F. HT. (25 MS)

128K F. HT. (25 MS)

★ **AMERICA'S
LOWEST PRICES**
★
ARE EVEN LOWER NOW!!!

IBM XT 256K/1 Dr./20 MB	2250
IBM XT 256K/1 Dr./30 MB	2299
IBM AT 512K/20 MB	3895
IBM AT 512K/30 MB	3995
Compaq Desk Pro-1 128K/1 Dr.	1699
Compaq Portable 256K/2 Dr.	1650
AST 6 PAK w/384 K/Advantage	259/369
MCI MSC w/384K	175
Samsung/PGS Max 12	109/169
Princeton HX 12/E	435/535
Hercules Color Card/Monochrome graphic	150/299
Hayes 1200B w/SW	349
US Robotics Courier 2400	419

★ **SPECIALS** ★
10 MR Hard Disk

389
479
559
895
775
379
360/499
539
575/675

INTRODUCING

4CaST/2™ Complete
Forecasting
System

For marketing, planning, financial
and forecasting professionals:

- Easy to use menus with on-screen help facilities
- Most often used forecasting methods
- Popular spreadsheet interfaces
- Outstanding color graphics
- Fast RAM-based program
- Thoroughly tested and numerically accurate
- Exponential smoothing
- Step-wise and robust capabilities
- Macro language for applications
- Full documentation

Only: \$350 Demo D

4CaST/2X includes a fa

version of the Census X-

Only: \$595 Demo D

Both versions run on IBM PC XT AT

and compatibles. These programs are not

"Top Sellers Series"
UNlock DISK "NO. 101"
\$14.95 (Plus \$4 ship/handling Foreign orders \$9)

LOTUS 1-2-3™

(1.A, 1.A*, 2.0)

"Top Seller Series"

UNlocks individual

best selling programs

at a special low price!

HIGH PERFORMANCE IBM-AT SPEED

the industry's recognized leader in High Performance Speed
have performed extensive research and developed unmatched
field. Our products offer the COMPLETE solution.

XCELX™—Switch from five frequencies including the standard
12MHz. Uses reliable frequency synthesis to allow compatibility
with all IBM ATs including the TYPE 2 and Model 239

Mil-Spec Crystals—The famous Ariel crystals. Choose from
16-17-18-19-20-21-22-23-24 MHz.

FAST 80286-10—Micro-processor for 20-24 MHz speeds


FAST RAM—For System Board 128K 120 & 100 NS

FAST RAM—For expansion board 256K 120 & 100 NS

A MEGABYTE FOR DOS!

MicroWay is the world's leading retailer of 8087s and high performance PC upgrades. We stock a complete selection of 8087s that run from 5 to 12 MHz. All of our coprocessors are shipped with a diagnostic disk and the best warranty in the business - one year! We also offer daughterboards for socketless computers (NEC PC) and 287Turbo which increases the clock speed of the 80287 from 4 to 10 MHz. Our NUMBER SMASHER/ECM™ runs at 12 MHz with a megabyte of RAM and achieves a throughput of .1 megaflops with 87BASIC/INLINE, Intel Fortran, or Microsoft Fortran. Software reviewers consistently cite MicroWay software and 8087 expertise as the best in the industry! Our customers frequently write to thank us for recommending the correct software and hardware to meet their specific needs. They also thank us for our same-day shipping! In addition to our own products which support the 8087 and 80287, we stock the largest supply of specialized software available. For more information call us at

617-746-7341



MicroWay® 8087 Support

For the IBM PC, PC XT, PC AT and Compatibles.

87SFL™ MicroWay's Scientific Function Library contains 170 scientific and engineering functions. Callable from most 8087 compatible compilers ... First Language **\$250**; Additional **\$100**.

A2D-160™ MicroWay's Data Acquisition Board performs 160,000 12 bit Analog to Digital conversions per second! Includes software drivers. The fastest 12 bit A to D board available. For the IBM PC XT and compatibles. **\$1295**

MATRIXPAK™ manages a **MEGABYTE!** Written in assembly language, our runtime package accurately manipulates large matrices at very fast speeds. Includes matrix inversion and the solution of simultaneous linear equations. Callable from RM or MS Fortran, MS Assembler, or 87BASIC/INLINE. each **\$99**

87FFT™ Written in assembly language, performs Forward and Inverse FFTs on real and complex arrays which occupy up to 512 Kbytes of RAM. Also does convolutions, auto correlations, hamming, complex vector multiplication, and complex to radial conversions. Callable from most 8087 compatible compilers. **\$200**

87FFT-2™ performs two-dimensional FFTs. Ideal for image processing. Requires 87FFT **\$100**

MICROWAY UDI runs RTOS or RMX compilers under DOS. **\$300**

FASTBREAK™ employs the 8087 to increase the speed of Lotus 1-2-3™ Version 1A or 1A* by up to 36:1. **\$79**

FASTPAK™ includes FASTBREAK software and a 5 MHz 8087 chip. **\$179**

87Verify™ For users who have to be absolutely sure of their results! This background task periodically performs an 8087 accuracy and stress test. **\$49**

INTEL ABOVE BOARD **CALL**
JRAM, AST, MAYNARD **CALL**
RM, IBM, MS Fortran **CALL**

MegaPage™ Our Intel-Lotus EMS memory card. The only EMS board which comes with two megabytes of cool-running, low power drain CMOS RAM installed. Includes RAM disk, print spooler, disk cache, and EMS drivers. For the IBM PC, XT and compatibles. **\$549**

MegaPage AT/ECC™ EMS card for the PC AT and compatibles includes Error Correction Circuitry. With ECC, 11 RAM chips cover 256K so the user never encounters RAM errors. With 1 megabyte CMOS **\$799**; with 3 megabytes CMOS **\$1295**. Optional serial/parallel daughterboard. **\$95**.

DFixer™ Our disk utility which thoroughly checks PC or AT hard disks for bad sectors and updates the MS DOS file allocation table accordingly. Solves the AT hard disk problem! ... **\$149**

DOptimizer™ Optimizes the way your hard disk or floppy stores its files. Speeds up accesses by recombining fragmented files. **\$49**

DCache™ Our disk caching software speeds up your I/O by storing repetitively used tracks in memory. The amount of memory used can be selected in 64 Kbyte banks. **\$49**

87MACRO/DEBUG™ Contains all the pieces needed for writing 8087/80287 assembly code & MicroWay's 87DEBUG debugger **\$199**

OBJ→ASM™ A multipass object module translator and disassembler. Produces assembly language listings which include public symbols, external symbols and labels commented with cross references. Ideal for patching object modules for which source is not available. **\$200**

87BASIC™ includes patches to the IBM BASIC or MS Quick BASIC Compiler for USER TRANS-PARENT 8087 support. Provides super fast performance for all numeric operations including trigonometrics, transcendentals, addition, subtraction, multiplication, and division. each **\$150**

87BASIC/INLINE™ converts the output of the IBM BASIC Compiler into optimized 8087 inline code which executes up to seven times faster than 87BASIC. Supports separately compiled inline subroutines which are located in their own segments and can contain up to 64 Kbytes of code. This allows programs greater than 128K! Requires the IBM BASIC Compiler Version 1 and a Macro Assembler. Includes 87BASIC ... **\$200**

In London, please phone 223-7762

NUMBER SMASHER/ECM™ THE FASTEST ACCELERATOR CARD AVAILABLE

gives you 12 MHz speed in two modes: 704K or one megabyte of "Extended Conventional Memory." MEGASWITCH MMU and MegaDOS software make it possible to run DOS applications with up to 1015K using PC compilers, AutoCAD and Lotus 1-2-3. Does not require EMS software. Totally compatible from **\$599** to **\$1098**
Optional 8087-12 **\$295**

8087 UPGRADES

All MicroWay 8087s include a one year warranty, complete MicroWay Test Program and accurate installation instructions.

8087 5 MHz **\$109**
For the IBM PC, XT and compatibles

8087-2 8 MHz **\$149**
For Wang, AT&T, DeskPro, NEC, Leading Edge.

80287-3 5 MHz **\$179**
For the IBM PC AT and 286 compatibles.

80287-6 6 MHz **\$229**
For 8 MHz AT compatibles.

80287-8 8 MHz **\$295**
For the 8 MHz 80286 accelerator cards.

NEC V20, V30 **\$16, \$30**

64K RAM Set 150ns **\$10**

256K RAM Set 150ns **\$34**

256K RAM Set 120ns **\$39**

128K RAM Set PC AT **\$49**

287Turbo™ 10 MHz If you own an AT, Deskpro 286 or AT compatible, this is the card you need to get reasonable numeric performance. It plugs into your 80287 socket and includes a specially driven 10 MHz 80287. The card comes in three configurations. The IBM AT version includes a hardware RESET button **\$450**

287Turbo 8 MHz **\$369**

87/88Turbo™ is a stubby card which includes a clock calendar and a speed controller which changes the speed of your motherboard from 4.77 to 7.4 MHz. Its use requires your PC to have a socketed 8284. Typical speed increase is 1.6 to 2.0. The card overcomes slow hardware by slowing up only when such devices are accessed and running at full speed otherwise **\$149**
Optional 8087-2 **\$149**

286TurboCache™ This new MicroWay accelerator uses 8K of cache memory and 80286/80287 processors to provide an average speed increase of 3:1 for most programs. Call for specifications and benchmarks **\$595**

Call for our complete catalog of software which supports the 8087.

MicroWay P.O. Box 79
Kingston, Mass.
02364 USA
(617) 746-7341

PC BRAND: CAREFULLY CHOSEN PROGRAMMER TOOLS

BRIEF Is Anything But. A Whopper of an Editor

With a name that belies its thoroughness, Brief™ has every feature you've ever contemplated for your editor-in-chief. Text, from keyboard or files, is housed in multiple buffers, and scrolled through one or more windows you open, close, resize. A text buffer may be called to different windows to view two areas at once. A change in one changes both. Text blocks may be marked for printing, writing to files, movement to scrap buffers for cut and paste into other buffers, or deletion, with as many "undo" levels as you want.

To find and fix, Brief has text search abilities rivaling "grep", with wildcards for matching, indifference to intervening characters, acceptance of character ranges, even multiple choice of patterns and their replacements.

If you use Lattice, C86™, or Wizard, and have 320k, you can compile your C program without ever leaving Brief. It finds the lines with errors, and marches you through the text for repairs.

Parts of Brief were written with its own Lisp-like macro language which has structure, 32-character variable names, conditional execution, loops, and you can actually read it! Nothing like the hieroglyphs we've seen elsewhere. Bulletin board and public domain disks with macros. Disk of contest-winning macros comes free with your purchase! "Simply the best text editor you can buy", Dvorak *Infoworld*. (Needs 192k.)

Ask for: List: PC Brand:
U0690 \$195 \$250

MULTI-HALO Multi-Board Graphics Library

The premier graphics library that got the ball rolling for PC-based graphics and has grown so omnipotent that it supports over 25 graphics boards — including IBM's EGA and Nr. 9 Revolution's hi-res series — and has a multitude of mouse and printer drivers. All that in each box. Separate C versions for Lattice, M'soft, Aztec, C186. What does Multi-Halo do? Just about anything. A full "paint" was written using it. Wonderful value for single license. Costly royalties though for redistribution. Specify: S0315 & Language. List: \$250. We: \$199.

dbc Lattice Library Maintains dBASE Compatible Files With the Power and Speed of C

dbc™ links C to dBASE. It creates and maintains files and their indexes which exactly replicate dBASE file design. So dBASE can read and update them. And the reverse. dbc can use any files created by dBASE. Now C and dBASE can operate on the same data bases interchangeably.

That opens up the widespread culture of dBASE installations to exploitation by C programmers. You can tap that market, avoid the resident dBASE language, and gain all the advantages of C with this single product.

dbc's functions parallel all dBASE's file handling commands, many decomposed to give closer control. The manual

WINDOWS for C/WINDOWS for DATA Give Your Program a Clearer Outlook

FREE DEMO!

Windows for C™ is a library of over 65 functions to add the pizzazz and practicality of window partitioning to your application. Unlimited windows, each defined in a C structure for easy reference throughout your program, can be made either to pop up or permanently overwrite the screen. Routines will scroll and highlight lists with arrow keys, will read and scroll ASCII files vertically and horizontally in windows, and even write to memory-loaded files off the screen.

Logical treatment of video attributes permits unchanged programs to run on color or monochrome. Colors of windows are set individually.

All functions are in separate modules; only those used are linked. Only buffers holding on-screen or temporarily obscured windows occupy RAM; others released dynamically. TopView™ compatible. Best overall rating and fastest display in Bill Hunt's *7/85 Tech Journal* review of five windowing products.

Windows for Data comprises all of Windows for C but takes in data through the windows as well. At the high level a single function lets you specify prompt string, field length, data type, screen location, picture, target variable, then sets lesser functions scurrying to get and process a user's input — any of which functions are available directly. There are utilities to get system date and time, mess with strings, create your own field masks.

Field options can require entry, prevent entry, permit insert or overtype, beeping on invalid or overflow keystrokes, and attachment of field-specific help messages and functions you want called to display

messages or validate entries. And you decide which keys will clear a field, jump to the next or prior, quit, etc. Options diverse enough that a set of "fields" can be made to behave like a Lotus™ menu.

Many compilers. Free demo.

Specify Compiler: List: PC Brand:
T0100 Windows for C \$195 \$169
T0150 Windows for Data \$295 \$259

C-WORTHY LIBRARY Fits Out Applications with Shipshape Interface

FREE DEMO!

Many libraries launch flotillas of functions for small crafting — re-working of strings, positioning the cursor, etc. C-Worthy, by contrast, is a formidable battle wagon for major C engagements.

The C-Worthy Library™ wraps an entire user interface around your application. Its full power can be summoned by only a few high level calls. Sound exaggerated? A single function call can set up a complete text editor in a screen window.

- High level calls pop menus and scrollable choice lists to the screen, restoring the background when dismissed, and branching to the chosen activity in your application. A full function set handles doubly-linked lists defined by C structures.
- Windowing facilities open porches of up to screen size for viewing virtual screens larger than the physical screen.
- Full context-sensitive help screen management takes over this chore. Keyboard entry routines look for the help key on their own and interrupt with pageable text win-

dows explaining what to do next.

- Full error message interface sends error codes and the functions which return them to C-Worthy which counsels user; you get to remove all that error-checking clutter from your core program.

Your application is nested in these powerful emissaries to the outside world. C-Worthy's imaginative architecture then makes heavy use of C's pointers to functions to find its way into your application to act upon the user's request.

Separate utilities maintain help and error message text and lists in files. This text segregation means applications can readily translate into foreign languages without reprogramming — doubly so because C-Worthy display routines automatically resize for text length.

Where the high level interface does not suit you, the low level routines are available as decomposed functions. All machine dependency such as key mapping is housed in interchangeable overlays loaded alongside the application at run-time; C-Worthy applications can thus run on a mix of PC and MS-DOS machines without recompilation.

C-Worthy hands you a consistent and intuitive interface and a revolutionary design approach. Novell found it "played a key role and accelerated development" in making its NetWare™ utilities easier for users. "You owe it to yourselves to take a look." Binary. Lattice. Others coming. Ingenious demo: call for it.

Ask for: List: PC Brand:
T0500 \$295 \$269
T0550 Novell Network \$495 \$449

CURSES Unix Style Screen Management

Curses from Lattice™ manages the screen of the PC like Unix™ curses. Library of 84 functions and macros parallels Unix with matching parameter lists. So your Unix program will feel at home when you move it to the PC, and programs created on the PC will be Unix compatible. Keeps any number of screen images in memory, full or partial size. Supports color, all four memory models. Vast function set to get characters, wrap lines, scroll, blank lines, highlight, etc. Carefully follows Unix curses terminal orientation by re-painting physical screen only on your refresh command.

Ask for: L0850. List: \$125. Here: \$99. With Source: L0860, \$250 / \$199.

C-TREE B-Tree File Manager, Source Code, No Royalties!

C-tree™ has been around since 1979. (It became Digital Research's Access Manager™.) That means seasoned, sturdy code which hasn't cracked under the weight of prolonged and widespread use. C-tree comes in C source code, revealing all you've ever wanted to know about how b-trees are written. Provided you bind it into your binary application, you can re-

distribute C-tree without royalties.

C-tree's design splits nodes to allow any number of users to access an index file simultaneously even when updates are in progress. So multi-user configurations and adaptation to networks are possible. You must write record-locking routines, as they are compiler and operating system dependent, but shows how.

Thanks to source code which does not deviate from the K&R standard, C-tree can travel. Tests in many environments prove that C-tree gives your application a ticket to anywhere.

C-tree permits any number of keys for a data file, supports duplicate keys, variable record length files, multiple key indexes in a single file, etc., etc. — it's a comprehensive product with everything you'd expect. Intelligently designed, too. Both high level ISAM routines which minimize coding by handling all details of an activity; as well as decomposed step-by-step functions you can access directly. Either way C-tree maintains optimal index structures which will find the record you seek amongst a million ten-byte keys in no more than five disk seeks.

Ask for: List: PC Brand:
F0660 \$395 \$329

How Quick? We stock everything you see here — and then some. Which means you can get it right away.

Looking for Something? We carry — or can get — many more products. Just ask.

For Orders, Literature, or Catalogs, Call Us at...
800 PC-BRAND

That's (800) 722-7263. In NY State call (212) 242-3600
PC Brand, 150 5th Ave., New York, N.Y. 10011-4311
Telex: 667962 (SOFT COMM NYK)

© 1986 PC BRAND
Prices, terms, and specifications subject to change without notice.

SAVE \$5
Just tell us
this code
J7

TODAY'S TOP QUALITY AIDS TO PROGRAMMING PRODUCTIVITY

PRE-C

Thorough "Lint"-like Analysis Now on the PC

Unix users have always had "lint" to thoroughly clean programs before they disappear into a compiler.

Pre-C™ looks larger than "lint". It finds problems your compiler won't. Problems that a debugger will have trouble figuring out. Even problems which will cause trouble with other compilers.

Pre-C finds all the syntactical tripwires that will blow out a compiler and much subtler problems: code which will never be accessed, casts with suspect conversions, variables declared as external but never used, functions never called, machine-dependent expressions which inhibit portability, obsolete usage.

But the big service of "lint" is this: Compilers work with one module at a time. They know nothing of other modules which only meet up at link time. Pre-C looks at all segments of your program at once and reports to you any inconsistencies of inter-module references like conflicting data type declarations; parameter lists in calls which disagree with the functions themselves in number or data type.

Pre-C uses the Unix System III compiler standard to guarantee maximum portability anywhere in the C world. Plentiful command line options relax such rigor during early coding when work is incomplete.

Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for:	List:	PC Brand:
P0590	\$395	\$295

BTRIEVE

Queen-B File Manager Abdicates Royalties

This queen of b-tree file managers was unapproachable to programmers for whom royalties would ruin profit margins.

PLINK86 & PLUS

Dynamic Cache Overlays Maximize Memory Use

Plink86™ long the overlord of overlay linkers, now has a Plus version. As a linker Plink can be used with any compiled language which delivers Microsoft/Intel format object files. It yields automatic symbol tables and more memory maps than DOS LINK, but its overlay power has won its reputation as a miracle worker. Plink86 shoe-horns large programs into small memory by binding into your compiled program an overlay manager which knows how to swap modules of large linked programs between disk and shared memory space. Plink86's straightforward overlay description language allows you to describe your overlay hierarchy in a structure permitting up to 4,095 overlays stacked 32 deep.

So if your program needs large chunks of memory, you no longer forego sales to folks who have less. But if you've assumed 128k, and they have 640k, Plink86-Plus™ knows to use extra memory as cache for overlays — at full speed compared to disk swapping. It also can automatically restore a displaced overlay to which a subsequently called overlay must return, and assign library modules to either a program's root segment or overlay areas.

Plink, the programmer's choice even when CP/M™ was the poobah of

	List	PC
Code: Product:	Price:	Brand:
S0500 Plink86	\$395	\$289
S0499 Plink86 Plus	\$495	\$359

DAN BRICKLIN'S DEMO PROGRAM

Slide Show Your Latest Greatest Idea

INDISPENSABLE!

When the inventor of the electronic spreadsheet called with a new program, we sat straight up in our chair. VisiCalc™ was for businessmen, but Dan's latest is for us programmers.

Ever had trouble putting a program idea into words? Programs are screens! Words don't work. The answer? Show your program as a procession of screens.

Dan's new program makes it easy. It creates slide shows that imitate a program's screens and sequential activity. Create a screen — a snapshot of your planned product as it runs. Anything goes: words, borders, box rules, inverse and underlining of monochrome, foreground and background color on the CGA and EGA. Press a key and make a copy of this "slide", change it a little, by a single character perhaps, to show the next instant of run-time, then copy the slide forward again. Create a whole slide show of your program in action. It will seem like the program itself is running.

Each screen is in 80x23 character mode, not bit-mapped graphics. All 250 characters and attributes are available from scrollable lists which pop to the screen. All commands are layered in Lotus-style pop-up menus, with frequent choices mapped to the function keys as well.

Screen areas can be blocked for cut and paste or filled with color or characters, even made to blink. Slides of off-appearing segments can be made for overlaying on other slides, and any slide may have several overlays assigned to it. Slides can be shuffled, deleted... many quick tools to save time, disk space.

Slides can proceed at time intervals or in response to keystrokes, and depending on a user's response, you can tell the program

to branch anywhere in the slide sequence to create innumerable paths through your show.

Don't make your ideas struggle through coding to get to the screen. Dan's Demo is invaluable to prototype the program you are about to write, to position all the labels, choose the color decor, smooth out the keystroke interface before it gets etched in code. Or load the "capture" utility above the operating system, snapshot the screens of any running program, and load an instant slide show into Dan's program. Makes tutorials a snap.

Dan's Demo has blossomed throughout Lotus™, we hear. "Lotus [was] my major test site", says Bricklin.

Each purchase entitles you to redistribute fifty copies of the slide projector program along with your show. Plain manual, no binder, to keep the price low because Dan thinks everyone should have one (he's right). You'll wish he had Demo then and left VisiCalc for now. (Needs 256k).

Ask for:	List:	PC Brand:
N0100	\$75	\$69

GREENLEAF LIBRARIES

FUNCTIONS

New 3.0 has 225 functions in both C and assembler source as well as library format. We have versions for Lattice, Microsoft, C86, Mark Wms. New emphasis on tighter functional groupings to minimize excess baggage of functions loaded whether used or not. Manual's 250 pages now help select functions, as do demos and bulletin board. 32 DOS extensions: file and directory manipulation for 2.0 and 1.1. 23 Screen Functions: Select mode, page, monochrome or color, palette; cursor shape, positioning; clearing and scrolling; pixel get and put; read light pen. 60 String Functions: Manipulation of strings, including center and justify; efficient list operations which add, delete, and sort pointers to strings for top speed. 80 Graphic & Printing Functions: Primitives to access all graphics; typeface, formatting, and forms control. Plus keyboard status and function key assignment, time and date algorithms, read registers, memory size, peek and poke.

Ask for:	List:	PC Brand:
S0770	\$185	\$139

COMMUNICATIONS

Want your application to communicate with other users or remote data bases? Now you can build asynchronous communications right into your C programs! Over 60 functions and demo programs in both C and assembler source code set up an interrupt driven scheme with separate transmit and receive ring buffers (characters are simultaneously loaded at one end and transmitted from the other, or vice versa) for an arbitrary number of ports. Interrupt control means you can download a record, then halt the incoming stream to file it, display it, let the user tamper with it, send it back up line. It all happens within the context of your program. Goodbye separate communications software.

The Greenleaf Comm Library supports ASCII or binary, any parity, any word length, 8250 UARTs, all four Lattice C memory models, Hayes 300,1200,1200B and other modems.

Its 80-page manual has examples of each function and guides you through asynchronous communications.

Ask for:	List:	PC Brand:
S0750	\$185	\$139

BASTOC

OPTIMIZES!

Translates BASIC Programs Into C

For a trifling price, BASTOC™ will move truckloads of BASIC code over to C. It is a translator which takes in Microsoft Extended or CBASIC and emits pure Kernighan & Ritchie C for the Lattice compiler. It will optionally convert your program into a single monolithic C function or will decompose it into separate functions, one for each GOSUB label.

Version 2.0 adds optimization, with dramatic reductions in execution time. It converts to C integers those numeric variables it finds in BASIC programs which really do not need floating point. It eliminates unreachable code. Where BASIC uses full assignment statements to increment and decrement counter, BASTOC converts to C's compact form, nested in other statements. Strings are dynamically allocated in the target program, ridding your application of BASIC's catatonic halts for garbage collection.

BASTOC will try to create structure of even the most convoluted BASIC code, and writes any indigestible statement into the C output as a comment accompanied by an explanation of the problem. Also, you can optionally tell BASTOC to insert BASIC source lines into the C target as comments, a dandy way to learn the differences between the languages.

Specify:	List:	PC Brand:
S0375 & Which BASIC	\$495	\$399

PANEL

Feature-Laden Screen Design Tool

The newest version of this premier programming tool lets you layer your screen designs with up to ten overlapping images, making it easy to background a screen with pop-up lists, help boxes, and alternate sets of input fields.

Writing your own screenware is a good way to blow completion dates and profits. Panel™ works with you interactively to set up foolproof screen displays and data entry forms rapidly. It tests your form to prove that it (and test data) behave correctly, then converts the finished work into C source code for incorporation into your application. Compile with Lattice or Microsoft.

Wonderfully diverse attributes may be selected for any field — size, data type, color, of course, but also conversion of input to upper case; clearance of existing data when new entry is started; masks for standard formats (eg, dates, phone numbers); a choice of styles for numeric fields; phrases which fill in when their first letter is typed; multiple-choice lists from which to choose a field fill-in by cursoring a highlighted bar. Fields may be multi-lined (eg, name and address as one field) and scrolled if larger than the screen space allotted them.

Panel builds in a user interface for keystroke movement within and between fields, and supplies extensive validation routines for checking user field entries — in source code, so you can tack on your own unique variants. Screen designs may be dynamically loaded from file, or compiled into a program, and version 6 has optimized code to quicken display speed.

The whole package is wrapped in a monitor and keyboard customization package to tailor your application for other equipment. Panel. A superior productivity tool now bigger than ever.

Ask for:	List:	PC Brand:
S0400	\$295	\$229

PRICED TO SAVE YOU MONEY, SHIPPED FAST ANYWHERE. NEW LOWER PRICES!

RUN/C PROFESSIONAL VERSION

Interpreter Now Accesses Binary Libraries

RUN/C was an innovator for converting inaccessible compiled C to an interpreted language as easy to grab hold of as BASIC. Great for learning, but a problem remained for pros: An interpreter expects nothing but source code, and that put the vast resource of professional binary libraries off limits.

No longer: RUN/C Professional™ has the tools dynamically to load and unload multiple binary function libraries while in its interpreter. Your code can now reach for functions in the commercial C libraries like C-Food Smorgasbord™ - opposite—potentially any library compiled with Lattice's large model. How? The manual shows how to develop the interface to a library, using the Lattice compiler (a must!). How about your own archive of functions? No reason why not.

The RUN/C Interpreter

The interpreting engine lies at the heart of both the improved original RUN/C and the new Professional version. Its creators had the inspiration to make once formidable C behave on screen much like PC BASIC with a full-screen editor like WordStar®. Just create a program and RUN it. If it stumbles, LIST it, EDIT it, add lines, delete lines, RUN it again, fix it again. Use familiar commands like LOAD, MERGE, SAVE, FILES, even TRON and TRACE, and a free profiler.

RUN/C is ideal for rapid program development. Put up code at high speed, tinker and re-arrange, try out things devil-may-care, and let RUN/C find your typos and malaprops.

RUN/C has a treasury of functions built into the interpreter—over 100 paralleling the most used functions found in standard compiler libraries. So when and if the time comes to compile, your source code will find counterparts.

There are lots more features—system interrupts, a shell command to invoke any operating system command without leaving RUN/C, even the ability to load a preferred editor in parallel and switch back and forth.

RUN/C Standard Version

Straight RUN/C has all above but the Loadable Libraries™ docking module. It utilizes source code only, whether created by its own editor, or from any ASCII file, such as programs you've already written, or commercial libraries which supply source code.

It makes a splendid teacher. The manual has not just instructions how to use RUN/C, but its 500-plus pages provide a thorough-going demonstration of the C language itself. Every feature, of C or RUN/C, is accorded its

own micro-chapter. Over 100 of these chapters are devoted to RUN/C's built-in functions, and every one lists a sample program showing how it is used. The programs are also on the disks. So as you read them in the manual, you can run them on the screen. (Needs 180k-256k recommended.)

RUN/C Professional

RUN/C Pro has every feature of RUN/C regular plus the binary library link-up and an extra level of debugging aids. They are ingeniously installed behind a built-in function, so you can call for debugging conditionally. The called function paints a menu of debugging tools to choose from, including immediate mode to display variables, single-step tracing, and changing of variables.

RUN/C Professional can tackle projects of any size. Use it as a creative front end to feed a continuous stream of source code into compiled modules. Only the source work in progress is still interpreted; the finished modules will whiz by at object speeds. It will change how you work. (320k minimum and 512k recommended to fit libraries.)

RUN/C: quite a run for your money.

Ask for:	List	PC
\$0910 RUN/C Classic	\$120	\$109
\$0950 RUN/C Pro	\$250	\$185

The GSS GRAPHICS SYSTEM

Leave the Driving to GSS

ANSI CGI STANDARD!

GSS™ has reconfigured two components of its comprehensive graphics tools to conform with the more advanced ANSI Computer Graphics Interface (CGI) standard.

At the heart of the system is now the Development Toolkit which contains all language interfaces and device drivers for keyboards, mice, joysticks, tablets, printers, plotters, cameras, and more. Drivers now house all management of vector graphics (plotters) and bitmaps used by raster input devices (scanners) to insulate completely the application program from concern for device idiosyncrasy. No one else has implemented CGI that way. It means programming remains generic; just switch drivers and the same program will drive a different device, including intelligent controllers which do not want micro instructions.

GSS Kernel™ conforms to level 2b of ANSI's Graphical Kernel System (GKS) and contains all its needed drivers and language bindings. Kernel has macro level tools to draw and color an object, store the sequential instructions, and recreate the object on its own, as well as segment it, transform it, etc., all the while returning data on attribute settings, system and device status. So powerful, a single command may represent several score lower level statements.

Plotting has the equivalent GKS tools for graph and chart generation and their cap-

LATTICE C VERSION 3.0

Major Upgrades to the Best Selling C Compiler

Lattice has labored and come forth with the long-awaited Version 3.0 of its top-rated compiler. A long list of enhancements, adoption of the ANSI draft standard, documentation rivaled by few, and add-on libraries matched by none in sheer quantity restore Lattice C™ to its leadership role as the C compiler to beat.

Lattice now embraces key UNIX™ enhancements which have entered the language since Kernighan & Ritchie: void functions returning no value, enumerated data types to assign stepped values to variables, the ability to pass data between structures by assignment statements. And 3.0 adopts checking of external function arguments by data type as proposed by ANSI to kill bug swarms when modules join up at link time.

The greatly expanded libraries, now comprising 325 functions(!), enable the file sharing and record locking provisions of DOS 3.1, provide a full complement of transcendental, and a host of utilities to mimic the UNIX and XENIX™ environments.

Lattice now delivers smaller .EXE files, curing one past complaint, boasts very fast link times and a more efficient aliasing algorithm.

The compiler now defaults to the ANSI proposed standard when you need a strict mistress, but command line options tolerate straying. New options generate code to use 80186 and 80286 features, and the

8087 is of course sensed and utilized if aboard.

Lattice has enjoyed pre-eminence so long that developers have created far more tools to marry into Lattice C than any other compiler. Programmers now have an enormous resource of libraries and utilities to use with Lattice to speed their work. William Hunt, in his exhaustive analysis of 12 compilers in the 1/86 issue of the *PC Tech Journal* awards Lattice the only "very good" rating for add-on library availability. He sums up with this all-around accolade: "a fine product to consider for the production of important applications."

Ask for:	List:	PC Brand:
\$0100	\$500	\$CALL

BETTER BASIC

New Version Compatible with Microsoft BASICs

This hearty implementation provides a real alternative to technical languages like C. It melds the most useful features of C, Pascal, and Modula 2 into BASIC, while retaining the familiarity of a language already known to millions. And now Version 2.0 is 100% compatible with Microsoft's GW™ BASIC and IBM BASICA including graphics, sound, and assembly language calls. Just load old programs and run. Save and they are converted to BetterBASIC.

It's big: BetterBASIC's hugely expanded features require 192k; your programs can go all the way to the PC's full 640k. It's comfy: Behaves like Microsoft BASIC at the interactive level, with a full-screen editor, direct statement execution, and always poised to RUN. It's fast: BB is an incremental compiler—unlike with interpreters each statement is checked and compiled just once. The Sieve benchmark runs six times faster than with Microsoft.

BetterBASIC* has C-like structures for reference to entire records so say goodbye to FIELD, MKIS, CVD, LSET, etc. It has "procedures" summoned by name unlike GOSUBs. Lots more features: built-in linker for compiled modules; trace; debugging breakpoints; cross-reference command; 32k strings; DOS and BIOS calls and interrupts; recursion.

Ask for:	List	PC	Ask for:	List	PC
GS010 CGI Dvlpmt Toolkit	\$395	\$339	SI200 BetterBASIC	\$195	\$169
GS020 Kernel System	\$495	\$419	SI201 Run-time Module	\$250	\$239
GS030 Plotting System	\$295	\$249	SI202 8087 Interface	\$ 99	\$ 89
GS040 Metafile Interpreter	\$250	\$209	SI205 Btrieve Interface	\$ 99	\$ 89

Need terms? On-the-spot credit to most public companies, government, educational, medical institutions.

Why Us? A few thousand words later, you gotta admit, we go to great lengths to know programmer tools.

For Orders, Literature, or Catalogs, Call Us at...

800 PC-BRAND

That's (800) 722-7263. In NY State call (212) 242-3600

PC Brand, 150 5th Ave., New York, N.Y. 10011-4311

Telex: 667962 (SOFT COMM NYK)

© 1986 PC BRAND

Prices, terms, and specifications subject to change without notice.

SAVE \$5
Just tell us
this code
J7

OUTSIDE U.S.

The dollar is weaker. In your currency, our prices are lower than ever. PC BRAND ships anywhere. We'll prepare the export documents and ship to you or your agent by air freight, courier, or air parcel post. Pay by credit card or wire funds (see "Terms" below).

TERMS AND CONDITIONS OF SALE

Licenses: Each price is for a license to use a product on a single computer and does not constitute its ownership. We will require for you about site licenses. Except as otherwise indicated or where * follows the Product Code, products may be used to create programs for distribution without royalty payments or additional licenses, provided said programs do not substantially replicate the products themselves.

Compatibility: PC BRAND's standard products are designed to operate with the IBM® PC, XT or AT under PC-DOS and require no more than 128k of RAM unless indicated. Non IBM machines using MS-DOS: contact manufacturer about precise differences so we can advise.

Returns: See box page one. Defective parts will be replaced. Please call for authorization to return a product for refund.


Payment: We honor MasterCard, Visa, American Express (no surcharge), checks in advance, or funds wired to PC Brand, c/o Chemical Bank, 126 East 86 St., New York, Account 034-016058. COD (U.S. only) for cash, money order, certified check (no fee). NY State, add sales tax. Purchase orders accepted from larger corporations and institutions at our discretion if you agree to net 30 days plus 2% a month late penalty thereafter.

Shipping & Handling: U.S.: UPS Surface: 1st product \$6, each add'l \$3. UPS 2nd Day Air: 1st product \$10, each add'l \$4.50. UPS Next Day Air or Federal Express 1-2 Day Air: 1st product \$18, each add'l \$6. FedEx Next Day 10 AM: 1st product \$28, each add'l \$7. International: Charges vary by destination and carrier. \$10 per shipping container for export forms. Air parcel post at your risk beyond collected insurable amount.

COMPUTING POWER

FROM FLOPPY DISK SERVICES

XT-turbo systems




PRICES AND SPECS SUBJECT TO CHANGE WITHOUT NOTICE.

Floppy Disk Services has been supplying storage systems to the hobby and professional computer community for 7 years now. You can buy with confidence from a supplier that is in for the long haul. Whether you need advice or technical help, our staff is here to serve you.

The 'Service' in Floppy Disk Services stands for the confidence you'll have in dealing with us. We do not make you wait when a problem comes up. We will be there to help, and more importantly support and guide you. In the unlikely event we cannot answer your questions, a staff member will return a call to you in a timely and professional manner with the answer.

Warranty is a term that sometimes is taken for granted. At Floppy Disk Services, we support one of the strongest warranty policies in the business. Our policy is to replace any equipment found to be defective in any way during the warranty period. It's as simple as that! No waiting for the merchandise to be sent back to the factory. If we find a problem, (other than abuse), we simply ship a new unit back to you.

The XT-clone system pictured above is our Super System VII XT clone. It contains a turbo processor, a 20mb hard disk formatted RLL to 31mb, 640K RAM, two 360K floppies, 1 AT 1.2 mb drive, mono amber monitor, par port, ser port, clock and AT type keyboard! You might expect to pay thousands for this system, but Floppy Disk Services, inc. will supply it ready to run with a 1 year warranty. Call for latest quotes on your custom system needs...



Complete line of drive enclosures


800-223-0306

CALL FOR FREE CATALOG

Dealer Inquiries Invited



39 Everett Dr., Bldg. D Lawrenceville, NJ 08648
(609) 799-4440



READER SERVICE NUMBER	ADVERTISER	PAGE	READER SERVICE NUMBER	ADVERTISER	PAGE	READER SERVICE NUMBER	ADVERTISER	PAGE
110	AST Research, Inc.	90-91	113	HavenTree Software Limited	164	220	Programmer's Shop	40
190	Advanced Development Technologies	66	*	Hawaiian Village Computer Software, Inc.	177	162	Programmer's Shop	72
116	Advanced Logic Research	Cover 3	155	Hayes Microcomputer Products, Inc.	54	151	Programmer's Shop	73
199	Advanced Logic Research	84	149	IBEX Computer Corp.	166	138	Qua Tech, Inc.	170
106	Alcyon Corp.	176	202	I-Bus Systems	21	*	Quaid Software Limited	123
101	Alpha Computer Service	122	108	Innovative Data Technology	130	239	Quantum Software Systems	1
200	Alslys	17	216	Intel Corp.	74-75	141	RYBS Electronics	132
218	American Small Business Computers	22	209	Interactive Microwave	166	181	Rational Systems, Inc.	124
136	Arity Corporation	145	117	Intercontinental Micro Systems	112	165	Real Time Devices, Inc.	170
203	Atron	8	*	K Software House	177	143	Relational Database Systems, Inc.	134-135
249	Atron	23	112	KADAK Products Ltd	173	187	Scientific Endeavors	170
159	Atronics	146	148	Kurtzberg Computer Systems	154	153	Scott, Foresman and Co.	161
*	BC Associates	177	128	Lahey Computer Systems, Inc.	160	124	Seattle Telecom & Data, Inc.	62
105	Barrington Systems, Inc.	12-13	160	Lattice, Inc.	159	164	SofCap, Inc.	172
114	Blaise Computing	162	144	Lifeboat Associates	68	201	SoftCraft	2
253	Borland International	33	173	Lifeboat Associates	119	192	Software Bottling Co. of NY	109
254	Borland International	35	125	Lodge Electronics	166	157	Software Channels	88
252	Borland International	37	229	LOGITECH, Inc.	111	127	Software of the Future	106
255	Borland International	39	132	mbp Software and Systems Technology, Inc.	16	196	Software Link, Inc.	52
247	Bourbaki, Inc.	64	146	MDS, Inc.	24	168	Software Masters	110
*	C-Ware Corporation	132	133	MEF Environmental	131	163	Software Masters	117
111	Catamount Corp.	175	208	Manx Software	56	189	Software Security	150
156	Cauzin Systems, Inc.	60	205	Mark Williams Company	25	147	Software That Really Works	176
213	Central Point Software	171	211	Micro Data Base Systems, Inc.	141	123	Solution Systems	14
139	Chalcedony Software	131	154	Micro Focus, Inc.	120	130	Solution Systems	169
140	Chalcedony Software	133	134	MicroHelp, Inc.	147	126	Solution Systems	174
245	Communications Research Group	116	*	Microsoft	28	129	Solution Systems	174
*	Creative Programming Consultants	108	*	Microsoft Press	173	176	SOPHCO	127
103	DTSS, Inc.	126	*	Microsoft Press	175	242	Spruce Technology Corp.	175
118	Data Access Corp.	20	167	Microstuf	Cover 4	177	Stargate Technologies, Inc.	170
215	Data Base Decisions	5	*	Microtec Research	151	183	Sterling Castle	158
102	Desktop A.i.	166	*	MicroWay	182	195	Summit Software Technology, Inc.	98
*	Digital Equipment	107	135	Nucleus Corp.	130	152	Sunny Hill Software	173
104	Dynamus Micro-Data Systems	125	222	Opt-Tech Data Processing	4	158	Sunny Hill Software	175
131	Ecosoft	128	142	Orchid Technology	11	231	Systems & Software	119
170	Ellis Computing	155	185	Overland Data, Inc.	173	194	Tall Tree Systems	153
121	Emerald Technology Group	82	*	PC Brand	183-185	197	Tall Tree Systems	Cover 2
120	Essential Software	121	145	PC's Limited	113-115	206	Tangent Technologies	148
161	Everest Solutions, Inc.	129	230	Paradise Systems	19	179	Tech PC	26-27
119	FairCom	154	137	Paradise Systems	6-7	182	TeleVideo	92-93
107	Flagstaff Engineering	86	180	Pecan Software	139	*	Texas Instruments	152
*	Floppy Disk Services	186	150	Peter Norton	157	184	TORUS Systems, Inc.	101
*	Gimpel Software	168	175	Programmer's Connection	43-45	186	Trailridge Research, Inc.	156
*	Glenco Engineering, Inc.	195				193	TurboPower Software	118
122	Gold Hill Computers, Inc.	136				115	Vermont Creative Software	18
						219	Zanthe Information, Inc.	42

TECH BOOK

ACCESSORIES/SUPPLIES

•• SOFTWARE PUBLISHING ••

GDS offers a wide variety of services that will help get your software to the market. Address your needs with GDS.

- IBM style cloth/vinyl 3-ring binders/slips
- Labels, sleeves, disk pages ...
- Disk duplication with 100% verification
- Bulk diskettes
- Shrink wrapping and assembly
- Quick turnaround

A well-packaged product can make the difference in making a sale. Call us NOW. VISA/MC Glenco Development Systems
3920 North Ridge Avenue
Arlington Heights, IL 60004
(312) 392-2492

BAR CODING

BAR CODE READERS

- IBM PC/XT, AT, AT&T 6300 & 6300 PLUS keyboard models or RS-232 interface
- NO programming. Reads dot matrix
- Auto-recognition and single code decoding
- Reads Code 39, UPC A/E, Codabar & 12 of 5
- \$635 list, units in stock, 2 year warranty
- Bar code printing software, call for info:



PERCON, Inc.
2190 W. 11th
Eugene, OR 97402
(503) 344-1189

BUSINESS OPPORTUNITIES

INCORPORATE!

- *Save Taxes!
- *Protect Your assets!
- *Free Booklet!
- *Free Forms!
- *Save \$—Do It Yourself!
- *No Legal Fees!

WRITE OR CALL TOLL-FREE TODAY!
HARVARD BUSINESS SERVICES, INC.
3151 Summerset Rd.
Wilmington, DE 19810
800-345-CORP

RATES AND INFORMATION

Standard listings consist of a bold lead line (25 characters maximum); 7 lines of body copy (45 characters per line); 4 lines for company name, address and telephone number. \$140 per insertion—3 issue minimum. Additional charge for extra lines and company logos. Prepayment and frequency discounts available. American Express, MasterCard, Visa accepted. Copy subject to publishers approval. Send typewritten or printed copy, reproducible logo art (if applicable) and remittance to Kathryn Cumberlander, Classified Sales Manager, Ziff-Davis Publishing Company, One Park Avenue, New York, NY 10016. For additional information, assistance, or to place an order by phone, call collect (212) 503-5115.

Personal Computer Owners CAN EARN \$1,000 TO \$5,000

monthly selling simple services performed by their computer. Work at home-in spare time. Get free list of 100 best services to offer. Write: C.I.L.B.Q.
PO Box 60369
San Diego, CA 92106-8369

HARDWARE/ADD-ON BOARDS

SPEECH SYNTHESIS

SynPhonix: TRUE Unlimited Speech Synthesizer for IBM-PC/XT/AT/jr & compatibles. This low power short card includes an SSI263 speech chip, amplifier and speaker. Software includes Text-to-Speech, Phonetic Editor, Talking Clock & demos. Can be programmed with BASIC and other languages. Prices start below \$200.

SynPhonix

Electronic Speech Articulator

Artic Technologies
1311 N. Main St.
Clawson, MI 48017
(313) 435-4222

RS-232/RS-422 Communications

Versatile communications and I/O boards.
—Four port RS-232 with DOS drivers\$349
—RS-422/485-serial interface\$149
—RS-232/422 with 24 parallel I/O\$199
—RS-422 synchronous with DMA\$299
—Delivery from stock
—Custom designs available

adams

Adams Incorporated
P.O. Box 17525
Greenville, SC 29606
(803) 297-9630

NEW!!! FOR THE OLD 64K PC

PC MultiPak MAX 576K Multifunction Card. Expand your old 64K IBM to 640K. Includes 576K memory, parallel port, serial port, clock, ram-disk & ramspool software, 2 year warranty. \$449 with 576K installed. Trade in discounts available for your current memory card Mfg. in USA. For more information call or write
Indigo Data Systems, Inc.
P.O. Box 57888
Webster, TX 77598
(713) 488-8186

FIXED DISK BIOS/BOOT

FIXT boots from most popular Hard Disks—DA-VONG, TECMAR, IOMEGA, GT LAKES, etc. Adds XT-like BIOS interface to your disk for PC. Security, multiple volumes, removable media support optional. No-slot plug-in installation. Specify controller and computer with order. \$80-\$95. Add \$3 shpg., CA tax.



GOLDEN BOW SYSTEMS
2870 Fifth Avenue
Suite 201
San Diego, CA 92103
(619) 298-9349

ACQUIRE DATA WITH YOUR PC

*16 to 64 differential A-D, up to 8 D-A
*24 to 48 digital I/O, 24 event counters
*Processor and 8 to 40K RAM on board
*Floating-pt processing, Battery backup
*Linearization, 4 selectable gain ranges
*Menu-driven software. Programmable.
*Systems start at \$895, 1 year guarantee
WESTERN TELECOMPUTING
202 E. Kagy Bozeman, MT 59715
(406) 586-1511, or touch-tone, toll-free
1-800-423-0587, then 328 222.

Z80 Co-processors

For PC and PC/AT. From \$199.50. Clock speeds to 9 Mhz. Run CP/M-80 software fast. Develop microprocessor software with our remote debugger kernel. Also run Intel ISIS software tools. We have Z80 processors for VAX and PDP-11 too.
Decmatron
2065 Martin Ave #110
Santa Clara, CA 95050
(408) 980-1678

HARDWARE/DISK DRIVES

8 INCH DISKETTE SYSTEM

Read, write and format diskettes from IBM mainframes, minicomputers, data entry equipment, etc. Complete easy to use software handles EBCDIC conversion. Can read and write CP/M 8-inch diskettes (many formats). You also can use 8-inch drives for PC DOS files; 1200 KB per diskette! \$1295 complete.
MicroTech Exports
223 Forest Avenue
Palo Alto, CA 94301
(415) 324-9114

HARDWARE/PERIPHERALS

SCSI-PC HOST ADAPTER

Plug & play installation for SCSI Optical/Hard disk and tape peripherals. Wide selection of SCSI peripherals selectable by manufacturer and model No. via menu window. Absolutely NO driver software need be written by the user. Price is \$149. for board, SCSI bios prom and floppy based configuration data.

Advanced Storage Concepts, Inc.
9660 Hillcroft #325
Houston, TX 77096
1-800-423-9175 (713) 729-6388

640K YOUR MOTHERBOARD!!

Put 640K of RAM on Your Motherboard! NO SLOT! NO ADD-ON BOARDS!—NO SOLDERING! Complete w/ALL Hardware, Memory Chips and Instructions. Easy PLUG-IN Installation. Avail for: IBM XT, IBM Portable, COMPAQ & COMPAQ PLUS Portables. Only \$144.95 + \$5 S/H, Specify computer when ordering. Dir. inquiries invited. CK/MO/VISA/MC

J S & J Software
1281 S. King St. Suite 6A
Honolulu, Hawaii 96814
24/hr Orders: (800) 821-5226 ext. 435

TURBO START YOUR PC!!!

FOR IBM PC'S ONLY!! The PC-INMATE, a Firmware ROM Module for the IBM-PC!!! Features: BOOT within 10 SECONDS!!! BREAK the 640K BARRIER!! Access up to 704K of RAM!!! (Lotus, DOS, etc.) SCREEN RELIEF—protects your monitor, and MORE!! Easily PLUGS IN—NO SLOT! Only \$49.95 + \$3 S/H. Dir. inquiries accepted CK/MO/VISA/MC.

JS&J Software
1281 S. King St. Suite 6A
Honolulu, HI 96814
24 hr Orders Only: (800) 821-5226 ext. 435

IBM PC/XT/AT SPEEDUP

*OVERTRUSTER: Boots the performance of PC and XT by 280%! 100% software compatible, is switchable between 4.77 and 7.38Mhz. \$195.

*SPEEDSWITCHER: This is an economical 6 speed switch (4-11Mhz) for AT's. \$89

*XCILEX: Automatic 5 speed switch (6-12Mhz) This unit will switch on the fly and works with ALL IBM AT's including the new Models with speed limiting Rom Bios. \$149.

DATA MANAGEMENT SYSTEMS, INC.
1525 Hickory St.
Salina, KS 67401
ORDER HOTLINE (913) 823-6440

CP/M & 1.2Mb AT ON PC

With MULTI-DISK and UniForm-PC use 3.5, 5.25, and 8-inch single and double density CP/M format as DOS diskettes on your IBM PC or XT. Many MS-DOS formats also supported including IBM AT 1.2 Mb, HP-150 and Data General 1. Over 200 formats. Both MULTI-DISK and UniForm-PC for \$225. Disk drives & adapter cable also available.

P S Engineering
P.O. Box 51068
San Jose, CA 95151-5068
1-800-367-2398; 1-800-423-7171 in CA

TECH BOOK

SOFTWARE/BUSINESS

The Andsor Collection™

Unique concepts: creates complete, self-contained, window-based data management environment in one DOS file. Simplifies everything. Combine functions to create your own solutions in any application: calculations, database management, modeling, text processing, charts, data analysis, statistics, reports, labels, forms, presentations, mail-merge, etc. Simple enough for a PCjr, sophisticated enough for a PC AT. Superb, 400 page hard-cover manual, with many examples. From simple calculations, files, inquiries, to complex models, data structures, reports: when your favorite data manager/spreadsheet/word processor/integrated system cannot provide the solution you need, remember The Andsor Collection. 60 day money-back guarantee. US\$95 + \$5 s/h. Visa/MC/AmEx/Chk/MO/COD. Call or write now to order. IBM/PC/XT/AT/PCjr, 128K, one drive or hard disk, monochrome and/or color monitor, DOS 2.0+. Not copy-protected.



Andsor Research Inc.
181 University Avenue, Suite 1202
Toronto, Ontario, Canada M5H 3M7
(416) 364-8423

SOFTWARE/COMMUNICATIONS

PC SERIAL DATA ANALYZER

Use your IBM PC or compatible to analyze data streams between two serial devices (up to 9600 BAUD). Two windows display each device transmission in ASCII or HEX. PC can also act as a terminal for either device. Invaluable tool for debugging serial interfaces. Disk & manual \$150. Triple C Software
2897 SW 13th St.
Fort Lauderdale, FL 33312
(305) 583-0687

Programmable Emulator

Automate your communications. "Hooks" to operate communications functions automatically thru your own programs written in "C", Basic, Pascal. Supports PC to PC to mainframe link up. Memory resident mode, simultaneous COM1 and COM2, X-modem, full featured, VT100 and 13 other terminals. Bluestreak plus \$89.95. Lang-Allan, Inc.
2457 Aloma Ave. Suite B
Winter Park, FL 32792
(800) 541-2255 Tone 677-1539

SOFTWARE/DEVELOPMENT TOOLS

ROMable CODE on PC!

PCLOCATE allows PC users to develop ROM-based software from MS-DOS "Exe" files. The user specifies the physical location of all LOW-CHARTSsegments. Output files are compatible with most PROM programmers. PCLOCATE supports the 8086, 8088, 80186, 80188, and 80286 processors. MC/VISA.
ALDIA SYSTEMS INCORPORATED
P.O. Box 37634
Phoenix, AZ 85069
(602) 866-1786

REALIA COBOL SITES

REALFORM is the Screen Handler you have been looking for. It features interactive screen design, an on-line forms editor, relief of cursor control, expedites screen generation, supports numerous data field types, is easy to use and offers powerful data entry functionality. \$395. US.
CHARANDON COMPUTER SYSTEMS INC.
1600 Laperriere Avenue
Ottawa, Ontario, Canada K1Z 8P5
(613) 729-3003

FIRMWARE PRODUCTION ON PC

LINK&LOCATE enables PC users to produce ROM-based firmware for 8086/87/186 from object files generated by C, PL/M compilers & MASM. Provides full control of segments placement anywhere in memory. Supports output of INTEL hex file for PROM programmer, absolute object file for symbolic debugger & ICE, and MS-DOS EXE file. Includes an INTEL compatible linker, locator, librarian and hex formatters. \$350.



Systems & Software, Inc.
3303 Harbor Blvd., C11
Costa Mesa, CA 92626
(714) 241-8650

REPORT WRITER

All-language qPLEX-IV lets you select or sort your own special forms, reports, labels, bar graphs or queries. Exports your reports to spreadsheets and wordprocessors. Reads Basic, Assembler, Pascal, C, Fortran, Cobol, ASCII, Data Base Managers and more. Dealer demos available. MS-DOS, XENIX, UNIX
Snow Software Corporation
3330 Fisher Road
Clearwater, FL 33519
(813) 784-8899

C-INDEX

C-INDEX is a state-of-the-art data management library for C. Designed for serious product development. No Royalties. B+Tree, variable length records, multiple keys, and transportable source code. Call for our free info packet.


C-INDEX/PRO \$195 Partial Source
C-INDEX/PLUS \$395 Full Source

TRIO SYSTEMS

2210 Wilshire Blvd. Suite 289
Santa Monica, CA 90403
213-394-0796

FLOWCHARTS BY PROFLO

The fast, friendly, flowchart drawing program for the software professional. PROFLO speeds software development and reduces documentation costs. Lets you create, edit, and print clear, precise flowcharts, quickly and easily. Requires IBM PC (or clone) with DOS, 128K, graphics monitor & graphics printer. Program & Documentation \$49.95. Demo Disk \$10.00.



Star Systems
28 Topstone Drive
Bethel, CT 06801
(203) 744-0546

GENSCREEN FOR MS-COBOL

Cobol Source Code Generator for generating the screen section and data division cobol source code for Microsoft and IBM PC cobol. Screen Image Text files are run through GENSCREEN to produce all of the source code for your screen in less than a minute. Super fast programmer productivity tool \$69.99.

Personal Computer Development Corporation
P.O. Box 8556
Warwick, R.I. 02888-8556
(401) 333-8704

TURBO PASCAL GENERATOR

GTP APPLICATION DEVELOPMENT SYSTEM, version 2. Builds complete, working application systems. You give it spec's, it writes error-free code.

Indexed Data Bases	Multiple Screens
Context Sensitive	Memory-mapped
Help	Video
Global/Phonetic Search	Full Keyboard Supt

Easy to Use Price \$150.00 Visa/MC, ck, MO
AEF
P.O. Box 928
Katy, TX 77492
(713) 391-8570

SCREENWARE UTILITIES

FAST ELEGANT SCREEN CREATIONS FOR PC ASSEMBLY ROUTINES. Make new or edit existing screens, even those CAPTURED in OTHER pgms BY OUR PGM! Supports ALL color/char/att & monitors. Pop-up menus, help & file management. Creates binary & assembler-ready ASCII source files. Easy to link to main pgm & invokes w/little code. KBD template, charts, 50pg Man, PC/AT-128K, ONLY \$27!
Crosswinds Software
8621 Windjammer Drive, Suite M-56
Raleigh, NC 27609
(919) 847-1812

FORTRAN LIBRARY

A library of over 70 assembly language subroutines complementing MS Fortran compiler. Full range of powerful features, increasing the scope of programming possibilities. Control screen, keyboard, communications; add new language commands. Library includes subroutines for total control of HP LaserJet printer. Institutional purchase orders \$99.95, personal checks \$49.95 s/h \$5.
Psychometric Associates
3434 West Tulsa Street
Chandler, Arizona 85226

SOURCE DEBUGGER FOR LATTICE C

The MSD DeBugger™ is the last, and perhaps final, word in programming assistance for Lattice C users. C Debugger produces a high-level view of C programs via function names line numbers, variable names and C data types, plus a low-level view of machine addresses and instructions for testing assembler language functions. More features include:

- All documentation is prepared for programmers.
- Online help screen throughout the process.
- Capability to single step through your program.
- Set break points, examine registers and variables.

\$165.00 + \$3.50 shipping VISA/MC



MSD
214 1/2 West Main St.
St. Charles, IL 60174
(312) 377-5151

THE—SCREEN GENERATOR

Powerful Screen Designer and Memory Resident Screen Manager eliminates tedious screen management tasks from your program. Easy access to Screen Manager from your application. Uses disk screen libraries. No Royalties, Not Copy Protected. Uses with FORTRAN, C, BASIC, Turbo-PASCAL, BetterBASIC or Asm (Call if not listed). \$125
The West Chester Group
P.O. Box 1304
West Chester, PA 19380
(215) 644-4206

ADVANCED MODULA-2 TOOLS

REPETOIRE: \$64. includes 360K of Logitech or ITC Modula-2 source code: screen compiler and fast display system with input checking, help, windows, menus, colors; auto-adapts to hardware. Integrated multiwindow editor; natural-language analyzer. DOS & BIOS tools. FREE documentation & demo disk. MC/VISA
PMI
4536 SE 50th
Portland, OR 97206 (503) 293-7706
MCI Mail: PMI; Compuserve: 74706,262

WORK HORSE BY USERSOFT

The BASIC code generator that provides:
1) screen painting 2) help screens
3) structured programs 4) maintainable code
5) cuts programming time 6) INKEY\$ routine
7) merging 8) printing 9) cross-references
10) runs interpretively or can be compiled.
All this and more for just \$59.00.
USERSOFT, Inc.
P.O. Box 517
Manteo, NC 27954
(919) 473-1970

THE PL/M CONNECTION

• Develop PC software with your PL/M compiler.
• Complete Interface to PC-DOS and PC-BIOS
• Fast Graphics Routines example programs
• All source files are included
• 200 page Technical Reference Manual
• \$295.00 No Royalties.
CompuFirm Corporation
7841 Balboa Ave #108
San Diego, CA 92111
(619) 571-0228

TECH BOOK

BASIC PROGRAMMERS

ADD MORE HORSEPOWER TO YOUR PROGRAMS!! Use THE BASIC ENGINE™ to build YOUR programs in FAST compiled BASIC. Add your modules to a working core of assembly routines, menus, data screens, pop-up help, sort, more; over 60 subroutines. Complete source for two working programs, full instructions, \$79.95. Requires DOS 2+, MS-QuickBASIC compiler. Praxis Software Engineering Associates
370 Andrews St.
Green River, WY 82935-4846
(307) 875-9626

PRODUCTIVITY TOOLS

SRMS™ Software Revision Management System stores all versions of source code in a single library. Allows retrieval of any version of source and application of changes while recording when, why, and where changes were made with no duplication of common code. DOS pathname, directory, and environment variable support, typeset manual, much more.

New version (2.0).....\$125.00.

QMAKE™ is an intelligent system builder patterned after the UNIX make utility. Only compiles those routines that have changed since last build. Support for macros, multiple entry points, command line parameters. Integrates fully with SRMS™.....\$99.00.

MS/PC-DOS 2.0 (MN plus 6%) MC/VISA

QUILT™ COMPUTING

7048 Stratford Rd.
Woodbury, Minnesota 55125
(612) 739-4560

Better BASIC Programmers

BetterTOOLS 2.00 SPEEDS BetterBASIC 1.1/2.0 development. Includes: 190+ useful tools in 17 modules, manual, and source code. No royalties. Quicksort, screen builder, extended math, disk directories, display and printer routines, powerful input, data encryption, on-line error descriptions, much more. Only \$89. VISA, MC, COD.

SOFTWARE ASSOCIATES

6220 W. Airport Blvd.
Houston, TX 77035
(713) 726-0706

PC CROSS-ASSEMBLERS

Up to 10,000 lines per minute! Fast X-ref and Linker plus Macros and Librarian. Generates HEX, TEKHEK, S-records, and OBJ output records. Over 40 macros and XENIX, MS DOS, CPM 80 and ISIS versions. Accepts MOTOROLA and INTEL directives and Mnemonics.

RELMS™

P.O. Box 6719
San Jose, CA 95150
(408) 265-5411

SUPERTECH "PREP" \$19.95

Powerful, exceptionally flexible, language-independent pre-processor. Use it, for example, to write register, opcode and operator synonyms, nested macros, line-length identifiers, etc. with assemblers without such features built-in. OK to share. Phone 24 hrs. (Please add \$3 s/h, WA res. add 7.9% tax)

SUPERTECH

11410 NE 124 St. Suite 6143
Kirkland, WA 98034-4399
(206) 488-9253

SOURCE CODE LIBRARIAN

TLIB™ stores ALL versions of your source in ONE compact library file, even with hundreds of revisions. Updates (deltas), 5-7 times faster than Unix SCCS. Date & comments for each version, easy retrieval. LAN-shared libraries. "Free public domain MAKE (with source) by Landon Dyer." DOS 2.x/3.x \$99.95 \$3 s/h VISA/MC.

Burton Systems Software

P.O. Box 4156
Cary, NC 27511-4156
(919) 469-3068

LAZY ASSEMBLE

Batch program assembles/links multiple ASM's. Specify which error-free LST files you want printed. Delete form feeds from LST's if desired. Link only if all assemblies ok. Other utilities: link map re-arranger and case sens/insens high speed string search across editable file list.

\$49.95 (CK/M.O.)

Goldbrick Software

1376 Deerport Ave. #22
Fullerton, CA 92631
(714) 524-6040

SOFTWARE/EDIT

Lil'Jake

"The WORLD'S GREATEST Editor." That's what our users say about Lil'Jake.

*Edit multiple files

*DOS commands

*Comprehensive (terse/verbose) online help

*Programming support BASIC, DOS & BIOS

*MACRO facility

We're so sure you'll like it, we want to send you a copy for a free 60-day evaluation. \$49.95 + s/h To order: Write or CALL NOW!

Fooks Matthewson Company

P.O. Box 2424 (Oper-28)
Arlington, VA 22202
(703) 684-8284

SOFTWARE/ ENGINEERING

smARTWORK®

Printed-circuit artwork editor for double-sided boards up to 10" by 16", runs on an IBM-PC. Color display allows complete interactive control over the placement and routing process. 2X artwork can be made on a dot-matrix printer or pen-and-ink plotter, \$895. Write or call for a brochure.



WINTERK Corporation
1801 South Street
Lafayette, IN 47904-2993
(317) 742-8428

METAL FABRICATORS

PC/Cutlist takes input from your bill of material—Detail drawing and calculates the best cutting combination for any length stock and prints a shop ready cutting list and scrap report. Also an optimization feature finds best mult length for mill orders. Price \$300. Demo Disk \$25.00

THE JOSEPH ALBERT CO.

P.O. Box 611
Blue Island, Illinois 60406
(312) 349-9032

CREATE PCB'S EASILY

Easily create double-sided printed circuit board artwork of up to 21" square using PC-Layout on an IBM-PC, the artwork is created using a color artwork editor, the final artwork, solder mask and silk-screen (text) is produced using either a printer or a plotter. Price \$745. Demo disk/manual \$45. Demo disk credited to final purchase.

Draco Technology

7210 Jordan Ave., Suite D50

Canoga Park, CA 91303

(800) 235-6646 ext. 646 (outside CA)

(800) 235-6647 ext. 646 (CA only)

ENGINEERING DESIGN SOFTWARE

20+ handworking programs for Mechanical Engineers, Electrical, Energy, Hydraulic, Fire Sprinkler, Structural.

NEWLY UPDATED- Manual "J" Clg/Htg 7th Ed., Tree Fire Sprinkler Design, Fault Current.

PRIMARY DEVELOPERS

OF ENGINEERING SOFTWARE

MC2 Engineering Software

8107 S.W. 72 Ave. Ste. 425 Box 43098

Miami, FL 33143

(305) 665-0100

PC/8087 VECTOR PROCESSING

The VECTOR87 library is written in assembler, includes 60 routines to turbocharge your math & scientific programs. FFT, vector operations, convolution, etc. 1K real FFT takes only 1.2 second. Versions for Fortran (MS, R/M, Lahey), C (MS, Lattice), \$120 each version with source, no royalties. Write for technical information.

VECTORPLEX Data Systems Ltd.

P.O. Box 138, Station M

Calgary, Alberta, Canada T2P 2H6

(403) 248-1250

SOFTWARE/ FILE MANAGEMENT

Wilkes Database

For IBM-PC and compatibles. Paint screens to create/view/update/delete/sort/search/print/reformat/arithmetic manipulate new or extant files. ASCII, 16/32 bit integer and 32/64 bit floating point storage. Powerful key sort and report formatting. \$325. Demo \$40.

Wilkes Software

5231 Longwood Drive

Memphis, TN 38134

(901) 386-4712

SOFTWARE/FINANCIAL

FINANCIAL CALCULATOR

Memory resident software for PC/XT/AT or compatible computers. Non-resident version also available. Loan amortization, internal rate of return, IRA, real estate, savings, depreciation, and much more!!! FREE shipping in the U.S. 30 day money back guarantee.

NOT COPY PROTECTED. \$49.

OPUS Engineering

5825 Vargas Ct.

San Jose, CA 95120

(408) 997-1503

SOFTWARE/GENERAL

PUBLIC DOMAIN SOFTWARE IN C

Over 60 volumes of public domain software in CP/M & MS-DOS formats.

• editors & compilers

• text formatters

• communications packages

• many UNIX-like tools

Write or call for more details.



THE C USERS' GROUP

P.O. Box 97

McPherson, KS 67460

(316) 241-1065

SOFTWARE/GRAPHICS

TEKTRONIX 4010 EMULATION

High resolution screen/printer graphics for the IBM PC. Full interactive capabilities with file transfer and cross-hair control. Utilizes PLOT 10, protocols. OFF-line review of graphics output. Supports IBM color/graphic or Hercules cards. Easy to use 4010 emulation at an affordable price. \$80.00. Demo disk \$5.

Technological Systems Group

5044 Haley Court

Lilburn, GA 30247

(404) 923-4980

PLOTTER SOFTWARE

Presentation aides (word charts) are quick and easy to prepare using the DGI SIGNMAKER. With the DGI SIGNMAKER, your PC and plotter (IBM, HP, Hi, Epson) your overheads, text slides or signs will have that professional look. \$75. For additional information, ordering or to check compatibility contact:

Decision Graphics, Inc.

P.O. Box 2776

Littleton, CO 80161

303-796-0341

TECH BOOK

SCIENTIFIC DATA PLOTTING

SCI-GRAF creates graphs up to 1680 x 1712 dots (over 3 million pixels!) on Epson or IBM graphics printers. Supports log scaling, overlays, point-labeling, legend creation, batch mode, wide-carriage printers, and color graphs on a JX-80. Requires DOS 2 or 3, 256K. No credit cards. \$99.95

Microcomputer Systems Consultants (MSC)
27-P Forest Avenue
Port Jefferson Station, NY 11776
(516) 928-7493

FORTRAN GRAPHICS LIBRARY

MicroGlyph's SciPlot provides MicroSoft or IBM Professional FORTRAN graphics library on IBM PC/XT/AT under PC DOS. Features high resolution plots from printers (IBM/EPSON/Apple LaserWriter), or graphics displays (IBM Color/HERCULES-Monochrome/TECMAR-GM). Price: \$69.95 + \$3 shipping + 5% MASS tax.

MicroGlyph Systems
P.O. Box 1066
East Arlington, MA 02174-9998

COMPUTER AIDED GRAPHICS

Free form 2D full screen graphics editor for the IBM-PC and compatibles. Use it to create charts such as: Organization, Gantt, Flow and Pie. Also produces Graphs, Work area plans, Electronic schematics and more. Drives HP or compatible plotters. Only \$49.95 a price of a game. For more details send a long SASE to:

WorkWare
P.O. Box 661295
Sacramento, CA 95866-1295
(916) 922-5819

MetaWINDOW™/TurboWINDOW™

Advanced graphics toolkit provides Xerox Star/Apple Macintosh style graphics on your IBM PC. Supports most popular graphics cards. Allows you to create pop-up menus, windows & icons; use proportionally spaced fonts; rubberband & drag lines, text or bitmap images; supports mouse-cursor tracking. Tightly optimized for use with Turbo Pascal, IBM Pascal, C, Fortran.

METAGRAPHICS SOFTWARE CORP.
4575 Scotts Valley Drive
Scotts Valley, CA 95066
(408) 438-1550

SOFTWARE/LANGUAGES

EASY WAY TO MASTER DOS!

New handbook shows how, why, and when to use all 44 PC & MS DOS commands quickly and easily! Lively hands-on tutorial makes learning fun, for a change. Covers basic thru advanced topics. All versions up to 3.1. Lots of practical examples. 221 pages only \$15.95 at book-stores, or send check + \$1.00 S&H to:

LITTLE, BROWN & COMPANY PUBLISHERS
200 West Street, Code T-368121
Waltham, MA 02254
1-800-343-9204 (credit cards)

FREE 8088 TUTOR Monitor

Learn 8088 assembly language using the new book, IBM PC-8088 Assembly Language Programming, by Richard E. Haskell. Order the book for \$25 plus \$3 s/h and get the powerful TUTOR monitor software free. Load and examine any disk file, disassemble any 8088 code, debug EXE files. Satisfaction guaranteed.

REHL Books
54 N. Adams, Suite 130-T
Rochester Hills, MI 48063
(313) 853-1941

Simulation Language

TurboSim allows large discrete event simulations i.e., manufacturing systems, health-care systems, etc. to be run on a micro. It features a comprehensive final report, histograms, plots and multiple simulation runs in an unattended mode. Source code is written in Turbo Pascal and is included. Borland International's Turbo Pascal and an IBM/PC with 64K are required. \$49.95.

Micro Simulation
37 William J. Heights
Framingham, MA 01701
(617) 875-6098

SOFTWARE/ NETWORKING

LAN SOFTWARE

LAN software for your PC, XT or AT, allows you to connect to your VAX and other systems. Provides file transfer and terminal services at hundreds of kilobits/sec. TCP/IP or XNS protocols available; MS-DOS, XENIX, VENIX and PC/IX supported, many additional options, basic PC package only \$350.



NETWORK RESEARCH CORP.
2380 North Rose Avenue
Oxnard, CA 93030
(805) 485-2700, TLX 297579

SOFTWARE/ONE OF A KIND

INTRODUCING-JORJ

JORJ- The first and only phonetic dictionary! 50K words/15K definitions. Finds words super fast for both good/poor spellers. JOSE a fun word-game is included in initial release as a bonus. Requires IBM-PC DOS2 & Hard disk. Copy protected. Price \$100. JORJ demo disk \$10. Check/M.O. Mich. residents add 4% sales tax.
JORJ SOFTWARE CO.
4354 Fletcher Rd.
Manchester, MI 48158
(313) 428-8010

SOFTWARE/OPERATING SYSTEMS

UN/EMULATOR BY WAWA

Run CPM on your PC or clone at MACHINE SPEED. UN/EMULATOR runs native 8080 code and increases DOS performance by 10%. We include disk conversion software, terminal emulators, and serial transfer utility. Available in 5 MHz and 8 MHz. Starting at \$99.95 plus \$5 S&H. Dealer inquiries welcome. Call or write: WEITZMAN AND WOOD ASSOCIATES
580 N.W. 99th Way
Pembroke Pines, FL 33024
(305) 432-8025

SOFTWARE/PUBLIC DOMAIN

TURBO PASCAL™ SOFTWARE \$6

Write or call for information about:

- Systems & applications development tools
- Programs for home and business
- Communication tools & applications
- Games in specialized applications
- Scientific/engineering programs & routines
- Graphics including animation tools

TURBO S.I.X.
P.O. Box 8373
Waco, TX 76714
(817) 753-2182

SOFTWARE/SCIENTIFIC

SPARSE/DENSE MATRIX

MATRIX: Does to matrix what TK! solver did for numbers. Solves lin/nonlin/diff eqns. Programmable Matrix functions. \$59.95

SPARSEPACK: Turbo Pascal source code for user-transparent Sparse Matrix handling. Overcome 64K barrier and more. \$49.95. VISA/MC call 1-800-835-2246 ext. 80.

SoftTech Inc.
18505 W. 8 mile.
Detroit, MI 48219
1-313-544-8544

SOFTWARE/SECURITY

SECURE AT/XT/PC

Control system access, data access! FiXT/S. Control system boot for most popular XT/PC hard disk controllers. Vfeature for AT-and-XT-compatible HD controllers segments hard disk by volumes, controls access with passwords, supports hard disk expansion. \$80 \$120 + \$3 shpg. plus CA tax.



Golden Bow Systems
2870 Fifth Ave. Suite 201
San Diego, CA 92103
(619) 298-9349

SIDEVIEW: PC/AT MENU

Password protect your hard disk today! DOS 3.0/3.1 hard disk manager. Allows you to create code menus to run any program or DOS command. Prevent hard disk erasure. Works with XT's too. 25 pg manual. Money back guarantee. PO's & phone orders accepted. \$39 + \$3 shpg.

Keller Software
1825 Westcliff Drive
Newport Beach, CA 92660
714-642-5544

SMART COPY PROTECTION

In the past, copy-protecting your programs meant inconvenience to the end-user, limited or no hard disk support and a lot of added expense per product copy. Our new software based EVER-LOCK System solves these problems. For IBM and compatibles. Call for info.



Az-Tech Software, Inc.
426 Grandview
Richmond, MO 64085

"NEW" BIT-LOCK® SECURITY

Piracy SURVIVAL 4 YEARS proves effectiveness of powerful multilayered security. Uses rapid decryption algorithms and small reliable port for transparent security device. NOW AVAILABLE for PARALLEL or SERIAL port. NEW KEY-LOK™ security device available at HALF-PRICE.
MICROCOMPUTER APPLICATIONS
7805 S. Windermere Circle
Littleton, CO 80120
(303) 798-7683 or 922-6410

SOFTWARE/SERVICES

TAPE/DISK CONVERSIONS

Conversion services to or from over 500 computer systems:

- Magtapes
- Micro Computers
- Mini Computers
- Word Processors
- Typesetters

Our conversion capabilities surpass most in the industry.

Pivar Computing Services, Inc.
165 Arlington Hgts. Rd. #T
Buffalo Grove, IL 60089
(312) 459-6010

TAPE AND DISK CONVERSIONS

TO/FROM cards, disk, tape ASCII/EBCDIC specializing in IBM-PC/XT/AT and compatibles. Reasonable prices, satisfaction guaranteed. Total Data Processing services with in-house mainframe.

D.P. Modern Systems
804 N. Reeder Ave.
Covina, CA 91724
(818) 966-2628

TECH BOOK

RENT POPULAR SOFTWARE

Finally, you can rent popular software for your IBM or compatible. See how good that game really is. Try that business package before dish- ing out huge amounts of money. Not public do- main. No membership fee. Where else can you get \$75.00 programs for \$5.00? Send \$1.00 for complete catalog. R.S.D. Dept. TJ P.O. Box 272 Bronxville, NY 10708

SOFTWARE/STATISTICS

RATS!

RATS is the ultimate econometric software package. It is powerful, fast, accurate, and in- expensive. RATS performs regression analysis, time-series forecasting (including Box-Jenkins) and cross-section (including logit and probit). RATS supports a variety of data formats, includ- ing Lotus WKS files. RATS also offers a pro- gramming language that provides maximum flexibility and power. Spectral analysis and graphics are available as options. Base pro- gram \$200. Demo including 300 page manual \$40. MC/VISA. VAR Econometrics P.O. Box 19334 Minneapolis, MN 55419 (612) 822-9690

ELF—THE STATISTICAL PKG.

Interface with Dbase and Lotus files or will cre- ate its own. Factor analysis, stepwise regres- sion, discriminant analysis, 1&2 way anova crosstabs, correlations, t-test, frequencies, transformations unlimited observations, 500 variables in database. All new and improved manual. 30-day examination. Call for more. The Winchendon Group, Inc. P.O. Box 10339 Alexandria, VA 22310 (703) 960-2587

SOFTWARE/TERMINAL EMULATION

VT-102 & 4010 EMULATION

PC 102 turns an IBM PC/XT/AT/jr to a VT-102/ 100/52 terminal with printer/file transfer sup- port. Optional: 132 col., 4010 graphics support. Guaranteed compatibility with all VT-100/52 applications including EDT, WORD II, All-In-One, & UNIX. Easy to use. 3000+ sold. From \$89. MC/ VISA/COD. Call for free package! Moneyback guarantee. General Micro Systems P.O. Box 5330 Hopkins, MN 55343 (612) 944-0593

SOFTWARE/UTILITIES

AT/XT/PC HARD DISK EXPANSION

"Replace hard disk with a bigger one, or add a second drive! Vfeature BREAKS THE 33 MBYTE BARRIER on standard AT, XT, and compatible hard disk controllers. Includes multiple vol- umes, security features, selectable clusters, keyboard lock. \$80-\$120 + \$3 shipping + CA Tax"



Golden Bow Systems
2870 Fifth Avenue, Suite 201
San Diego, CA 92103
(619) 298-9349

DISK MECHANIC

THE ULTIMATE Floppy Disk Backup & Repair Utility. Can back up ALL software protected disks written on the IBM PC. Works manually or au- tomatically. Files or sectors can be restored, searched, examined & changed. Checks disk drive speed, req. IBM PC, XT, AT, DOS 1, 2, 3, 192K + 64K if only 1 floppy drive. \$73 ppd. USA MLI MICROSYSTEMS PO BOX 825, Dept TB2 Framingham, MA 01701 USA (617) 926-2055 for info MC/VISA

CHARACTER CUSTOMIZATION

CHARGENI 2.1 works with the IBM EGA to let you modify the character set, allowing many word processors to display technical material, equa- tions or other special characters. Also works on the Color/Graphics Adapter in graphics modes. Requires DOS 2.x or 3.x, IBM Standard or En- hanced Graphics Adapter. \$35 + \$2 s/h (MN add 6%). DK Micro Consultants P.O. Box 6714 Minneapolis, MN 55406 (612) 722-0931

PC-COMPANION

Menu subsystem, a must for any PC with a hard disk supporting multiple applications or users. Single key stroke execution of software. 15 en- tries per menu. Set drive, path, directory, printer. Password access to menus. Supports all types of command execution Command logging. Screen colors definable. Written in assembler for rapid access. Requires 32k MSDOS/PCDOS 2.0 or higher. \$39.95 (TX resident add 6.125% tax). BINARY ENGINEERING 12841 Jones Rd. Suite 101 Houston, TX 77070. (713) 955-3770 VISA/MC

TallScreen—DOS POWER

Natural extension of DOS. Scroll back through screen output, edit text on full screen, mark blocks to printer or file, recall commands & directories, enter multiple commands, capture screens from application programs, create user profiles. Solid tech support. A real bargain at \$49.95 VISA/MC



Qualitas, Inc.
8314 Thoreau Drive
Bethesda, MD 20817
(301) 369-8848

EXTENDED FILE UTILITIES

Replace MS-DOS COPY, DELETE, RENAME with these fast, powerful utilities (DOS 2.0 or later). File lists with commas, optional confirmation querying, access to hidden/system files, ASCII- mode copying. Just \$15 + \$1.95 s/h (MA res. add .75 tax), MC/VISA OK. Pocumtuck Valley Software P.O. Box 156-A South Deerfield, MA 01373

EFFICIENT DOS

PCED: Use DOS more efficiently without menus, batch files, keyboard enhancers. Command edi- tor with recall; synonyms execute one or many commands with batch-style variables; auto- matic parameter recall; command logging; MUCH more. Very flexible. Recommended by Doctor Dobbs and CPCUG. \$35 plus \$4 s/h; VISA/MC. The Cove Software Group P.O. Box 1072 Columbia, MD 21044 (301) 992-9371

CONCURRENT DOS BACKUP

BackPack™ runs like BACKUP/RESTORE and supports DOS and CP/M media as well as users. Backs up and restores up to 1000K/min. on an AT and 360K/min. on an XT. Supports release 4.1. Also available on CP/M-80 and CP/M plus. \$150. Bright Light, Inc. 520 Fellowship Rd. #C301 Mt. Laurel, NJ 08054 (609) 778-0772

Directory eXtended™

BE IN COMMAND! New version of very popular command-oriented file manager! POWERFUL batch file generation-perform any task! FLEXI- BLE file matching and sorting! CONTROL file at- tributes! TEST file integrity! MONITOR disk params; 2-col display! MUCH MORE! Send \$35+\$5 p&h (in TX, add tax); money back guarantee!

DIRECTORY EXTENDED™

ECONO-SOFT Dept. T66
9200 North Plaza # 1906
Austin, TX 78753

HELL uva SHELL

Most DOS interfaces are designed for IDIOTS! Get the BEST full-screen interactive directory around ... DOS command recall ... command aliasing ... multiple commands at DOS prompt ... find files anywhere on disk ... find complex text patterns in files ... browse files ... copy files based on time stamp & MORE. Only \$39! DOS 2.0+, uses 96K memory. NCP! Dwarf Nebula Software 666-SHELL P.O. Box 46, Dept. TJ Sugarland, TX 77487

EASYINDEXE PLUS™

Cross reference all source code by file name. Create index by page number. Unlimited num- ber of indexes and accessed files. Word or phrase indexes up to 59 characters. Table of contents generation, typesetting, and print formatting. Supports over 100 printers. \$39.95 \$3 shipping (CA. RES. ADD \$2.60 Tax) Foreman Software 977 Clayton St. D4 San Francisco, CA 94117 (415) 665-6414

TurboRef 4.0

Pascal programmers get organized with TurboRef! TurboRef will cross reference a source program and create a program listing. TurboRef can process a list of files, will read "include" files, identifies line number for each reference. New release now avail. IBM PC and jr., XT, AT or com- patible, only \$49.95; VISA/MC, or check.

GRACON SERVICES, INC.

GRACON Services Inc.
4632 Okemos Rd.
Okemos, MI 48864
(517) 349-4900

TURBO PACKAGE for Turbo Pascal

- *Crash the 64K barrier. Forget MODULA2.
- *1000 times faster than chains or overlays.
- *Precompiler turns short calls into long calls. Run 500K of memory resident code.
- *32 bit integer math toolbox, ASM.
- *Mix Turbo, TurboBCD, and Turbo-87.
- *Free information.
- *Turbo Package plus tools, \$39.95.

CONVERSATIONAL COMPUTER SYSTEMS
5371 Verbena Road
San Antonio, TX 78240
(512) 692-0353

LIST-IT

Make your IBM BASICA and IBM compiled Basic program readable with a pretty print. Cross ref- erences for statements and variables are in- cluded. While-wend, FOR-NEXT and IF-THEN- ELSE structures recognized. \$29.95. Calif. resi- dents add 6%. CHECK/MO/VISA/MC PCS 50 Cornell #9 Irvine, CA 92715 (714) 854-1282

TECH BOOK

SAVE THAT SCREEN!

Do you immediately reach for the PrtSc key to save screen info? What a waste of time and paper! Now, SCREENSNAP™ lets you save and recall up to 9 screens at the touch of a key. Friendly with other resident programs but unlike some it is compact; will run in as little as 5K. Also includes useful utilities to save and recall from files, programmer's interface and sample code. Build your own help screens with your text editor, then save and recall them with SCREENSNAP. \$39. Aldridge Real-Time Software Inc. Call 800-443-4160; NJ (201) 846-7242


FILE PRINT MANAGER

GLISTER™

- ★ Use DOS wildcards to build a list of up to 100 files to print
 - ★ Save/restore file lists
 - ★ Restart a file on any page after a printer jam
 - ★ Print multiple copies
 - ★ Control: margins, line/page length, spacing, user-formatted header/footer lines and more
 - ★ Prints files as fast as printer is capable \$49
- Aldridge Real-Time Software Inc.
Call 800-443-4160; NJ (201) 846-7242

REPEAT PERFORMANCE™

OUTSMARTS IBM PC KEYBOARD LIMITATIONS!® Smoothly ACCELERATES CURSOR MOVEMENT, speeds up editing. High speed scrolling. You set ADJUSTABLE REPEAT SPEED and DELAY. SKID SQUELCH™ feature auto-adjusts to match performance of word-processors/text editors/spreadsheets. Cursor & scrolling STOP INSTANTLY when key is released. EXPANDS TYPE-AHEAD BUFFER-type DOS commands while your programs compile. Less than 2K resident. WARNING: ADDICTIVE! IBM/PC/XT/AT compatibles. \$back guar. \$39.95 +\$5 p&h. VISA/MC/AMEX/CK. Site licensing from second copy!



Popular Demand Inc.
62 South 1025 East
Linden, UT 84062
(801) 785-0101

SOFTWARE/WORD PROCESSING

FORMATH™ TEXT-FORMATTER

For technical texts. Sizes & places equations, matrices, ratios, integrals, big symbols, footnotes. Macros, multiple fonts, 158 Greek/math symbols. Automatic hyphenation, section/equation/reference numbering, indexes, table of contents. Dot-matrix, daisywheel, laser printers, plain/graphics monitors. \$400. \$50 for demo.

$$\lim_{n \rightarrow \infty} \sum_{i=1}^n \left[\frac{1}{i(i+1)} - \frac{1}{2^i} \right] = \frac{1}{2} \left[\int_0^1 \frac{\log(1-x)}{-x} dx - 1 \right]$$

SHANTHA SOFTWARE, INC.
50 West 97th St. Room 11N
New York City 10025
212-222-7647

Touch-tone Toll-free: 950-1088-wait-FORMATH



REPRINTS AVAILABLE

Quantity reprints of articles appearing in PC Tech Journal are available and will be prepared to meet any special requirements. Inquiries should be directed to Eileen Pfeiffer, Reprints Dept., Ziff-Davis Publishing Co., 1 Park Ave., New York, New York 10016. Phone 212-503-5447.

TECH JOURNAL

Subscribe to PC Magazine and save 65%

You'll receive in-depth and comprehensive product evaluations and comparative hardware and software evaluations from PC Labs, the publishing industry's *only* testing laboratory.

You'll receive new applications, power tips and special reports designed to add more power and flexibility to your IBM/MS DOS-standard system.

And you'll network with other users and discover routines and techniques that can save you time and money.

Subscribe to *PC Magazine* today!

Send the coupon to: *PC Magazine* • P.O. Box 2443 • Boulder, Colorado 80322 or call Toll-Free; 1-800-852-5200 now!



Yes, send me PC Magazine for:

- ☐ 22 issues (one year) for \$24.97. Save 62%!
☐ 44 issues for only \$44.97. Save 65%!

Savings based on annual single-copy price of \$64.90.

Mr./Mrs./Ms. _____

please print full name

Company _____

Address _____

City _____

State _____

Zip _____

Add \$15 per year for postage outside USA, US currency only.

Please allow up to 60 days for delivery of first issue. Basic annual subscription price is \$34.97.


8ZD41

TECH MART

ATTENTION SOFTWARE DEVELOPERS!

More Users For Less Money!

Digitrol's software solution
to multi-user.



pcSHARE MULTI-USER O/S

pcSHARE allows your IBM-XT/AT or compatible to support up to 5 users running your vertical market programs and 1-2-3, dBASE, WordStar, and more on inexpensive serial CRTs. pcSHARE efficiently runs compiled Basic, dBASE, Pascal & C programs with full DOS 3.0 compatible record locking.

DIGITROL COMPUTERS INC.

440 Phillip Street,
Waterloo Ontario, CAN N2L 5R9
(519) 884-4541

IBM XT/AT, Lotus 1-2-3, dBASE, and WordStar are trademarks of IBM Corp.
Lotus Development Corp., Ashton-Tate and MicroPro International respectively.

CIRCLE 375 ON READER SERVICE CARD

Protect Your Private Parts.

Whether you're a software developer or an end user, whether you work alone on a PC or you're part of a 24-person project team, keeping new software or sensitive data from prying eyes is serious business.

Short of complicated, wizard-like protection schemes, or James Bond, you haven't had too many realistic alternatives. Until now.

Because Rainbow Technologies has developed simple, easy-to-use systems called Sentinels that say no to prying eyes. No matter how hard they look.

The key to Sentinel is just

that—a smart piece of plastic smaller than a best-selling cassette that plugs into the parallel port of your IBM PC/XT/AT or compatible.

There are two ways to go. The Software Sentinel™, that prevents anyone from using your licensed software program unless you give them a key. And the Data Sentinel™, Rainbow Technologies' newest prying eye-stopper, that automatically protects sensitive personal or project data as you enter it. The Sentinel Security Systems from Rainbow Technologies. The only hard part is the key.



17971 Skyway Circle, Suite E, Irvine, CA 92714
Phone (714) 261-0228 Telex: 386078

CIRCLE 378 ON READER SERVICE CARD

TERMINAL EMULATION

Softerm PC emulates over 30 popular terminals including the:

- DEC VT102, VT220
- Data General D200, D410
- IBM 3101-20 (block mode)
- Hewlett-Packard 2622A
- Honeywell VIP7801, VIP7803

Guaranteed Compatibility

Call for free product brief

\$195 MC-VISA-COD

For the IBM PC/XT/AT, DG1, NEC, Wang PC, TI Pro, Gridcase, Tandy

SEIFTRONICS

7899 Lexington Dr., Ste 210
Colorado Springs, CO 80918
(303) 593-9540

CIRCLE 380 ON READER SERVICE CARD

64K ■ 128K ■ 256K

DRAMS

80287-8 ■ 80287-3

8087-3 ■ 8087-2

8087-1

BITTNER



899 SOUTH COAST HIGHWAY
LAGUNA BEACH, CA 92651
(714) 497-6200

CALL NOW FOR **FREE CATALOG**

CIRCLE 376 ON READER SERVICE CARD

FORTRAN or PASCAL PROGRAMMER?

READ
THIS
AD



GRAPHICS

- Text/graphics generics
- 2D interactive
- 2D plots (full support) including auto-scaling, auto-axis generation, auto-labeling, tabular/log/parametric curves, splines, bars, pies, you name it, we have it.
- 3D Plots incl. 2 hidden line removal options—not just old-fashioned wire frame.

PEN PLOTS

- Standard plotter primitives plus
- FULL 2D support plus
- Interface to screen graphics,
- Limited 3D.

Clear and complete documentation.

GRAFATIC \$135.

PLOTMATIC 135.

MICROCOMPATIBLES

301 Prelude Drive
Silver Spring, MD 20901
(301) 593-0683

CIRCLE 389 ON READER SERVICE CARD



IBM PC, XT and AT programmers:

Don't give away results of your effort!
Don't waste your money buying
costly fingerprinted diskettes!

**You can have your programs
automatically protected against
piracy!**

- No special training needed!
- No confusing instructions!
- No discouraging procedures!

No Sales Tax on orders outside N.Y. State

\$180



YETIWARE CORP.
P.O. BOX 21152
MID TOWN STATION
NEW YORK N.Y. 10129

DEALER INQUIRIES INVITED

CIRCLE 377 ON READER SERVICE CARD

PERFECT COPIES GUARANTEED

Why risk duplicating your important programs on your computer, when our equipment is designed solely to duplicate disks and verify their perfection 100%?

Over 600 formats. 3 1/2", 5 1/4" and 8". Plus serialization, copy protection, labeling, packaging, shrink-wrapping and fast, personalized service.



**Western
Transdata Inc.**
DISK DUPLICATION

1701 E. Edinger Ave.
Building A4
Santa Ana, California 92705
(714) 547-3383 (Collect)

CIRCLE 379 ON READER SERVICE CARD

REPRINTS AVAILABLE


Quantity reprints of articles appearing in PC Tech Journal are available and will be prepared to meet any special requirements. Inquiries should be directed to Eileen Pfeiffer, Reprints Dept., Ziff-Davis Publishing Co., 1 Park Ave., New York, New York 10016, Phone 212-503-5447.

TECH
JOURNAL



TECH MART

Get the whole story on graphics terminal emulation.



To find out more about software that lets your PC emulate TEKTRONIX™ 4105/6/7/9 and DEC VT100™ terminals, call or write:

GRAFPPOINT

4340 Stevens Creeks Blvd., Suite 280,
San Jose, CA 95129 (408) 249-7951

CIRCLE 382 ON READER SERVICE CARD

NEW EPROM PROGRAMMER



EPROM 1
\$495

- *Programs all 28-Pin, 5-Volt EPROMs and EEPROMs.
- *Perfect for engineering workstations, field service and small production runs.
- *Simple keyboard and display for stand alone duplication.
- *Interface to your computer via an RS232C port.
- *PC control software included at no extra charge.

TO ORDER PHONE:

800-325-6028 Outside California

916-885-7262 Inside California

VISA AND MASTERCARD ACCEPTED



INTERNATIONAL
MICROSYSTEMS
INCORPORATED

11554 C Avenue, Auburn, CA 95603

CIRCLE 384 ON READER SERVICE CARD

the HD test

**Professional Test/Format
Program For
Hard Drives in PC/XT/AT**

- Setup interleave, step rate, etc.
- Surface analysis to flag bad tracks
- Load/save setup and bad track files
- Now supports AUTOCONFIG!
- Menu driven, with help windows
- Free PARK program included!
- Order HDTEST today for only \$99!

Proto PC inc.
612-644-4660

2424 Territorial Rd., St. Paul, MN 55114
Telex 910-380-7623

CIRCLE 387 ON READER SERVICE CARD

FREE DISK SPACE

**THE FILE STORAGE METHOD
USED BY PCTECHLINE.**

The ARC file archive utility can save up to 50% on disk storage, and modern transfer time.

- Not copy protected
- Program Sources Included

Only \$50

"A sophisticated and imminently useful product."

—PC Week

SYSTEM ENHANCEMENT ASSOCIATES
21 New Street, Wayne, NJ 07470
(201) 473-5153

CIRCLE 383 ON READER SERVICE CARD

MYSTIC PASCAL

Fastest Compiler on Earth

NOW ONLY \$16!!!

- 640K code, data and stack
- incremental compiler runs in background while you are editing
- effective compiler speed greater than 100,000 lines/min
- immediate execution of Pascal statements
- true multi-tasking for up to 100 Pascal procedures
- full screen editor
- complete Help windows

disk with condensed manual to print out \$16—
printed manual \$16—both \$32—for IBM PC 256K
Visa/MC/COD—add \$2 shipping, COD \$5,
overseas \$10

Mystic Canyon Software
P.O.B. 1010

Pecos, NM 87552 505/757-6344


CIRCLE 386 ON READER SERVICE CARD

TECH JOURNAL

TECH MART TECH BOOK

**THE CLASSIFIED ADVERTISER'S
FORMULA FOR SUCCESS IN
SELLING TO TECHNICAL
EXPERTS IN THE IBM
MARKETPLACE.**

**FOR RATES & INFO
CALL: (212) 503-5115**



Unprotected Software Makes the Best of Friends

The Software Industry cannot afford this kind of friendship. Estimates show that companies like yours are losing half their sales to pirates. Imagine your software sales doubling this month!

NEW

For Hard Disk Protection

- Fixed Disk Locker

For Disk Security

High Level Security


- PADLOCK II DISK
- SAFEGUARD DISKS
- COUPON DISKS

Low Level Security

User Installable Protection

- PC-PADLOCK

Why should your valuable data or useful software program become available in the Public Domain?



Call or write for more information.

GLENCO

ENGINEERING INC.

3920 Ridge / Arlington Hts., IL 60004
(312) 392-2492




ILLUSTRATION • DAVID FOWLAIS

JULY

July 7-11

APL '86

Manchester, England

Sponsor: British Computer Society and ACM SIGAPL
Contact: BISL Conference Department, The British Computer Society, 13 Mansfield Street, London W1M 0BP, England

July 8-11

UNIX: A Comprehensive Workshop

Washington, DC
Contact: Yolande Amundson, Integrated Computer Systems, 6305 Arizona Place, P.O. Box 45405, Los Angeles, CA 90045; 800/421-8166

July 9-11

PC EXPO

New York, NY
Contact: 333 Sylvan Avenue, Englewood Cliffs, NJ 07632; 201/569-8542

July 14-17

Software Trends for Executive Planning and Strategy

Boston, MA
Sponsor: Digital Consulting Associates, Inc.
Contact: Digital Consulting Associates, Inc., 6 Windsor Street, Andover, MA 01810; 617/470-3870

July 21-25

European Conference on Artificial Intelligence

Brighton, U.K.
Sponsor: European Coordinating Committee on Artificial Intelligence and the

Society for the Study of Artificial Intelligence and Simulation Behavior
Contact: Benedict du Boulay, ECAI, The University of Sussex, Cognitive Studies Programme, Brighton BN1 9QN, U.K.

July 21-26

Third International Conference on Logic Programming

London, England
Contact: Doug DeGroot, IBM Research, P.O. Box 218, Yorktown Heights, NY 10598

July 22-25

Ada Programming Workshop

Washington, DC
Sponsor: Integrated Computer Systems
Contact: Yolande Amundson, Integrated Computer Systems, 6305 Arizona Place, P.O. Box 45405, Los Angeles, CA 90045; 800/421-8166

July 27-31

Information Center Conference and Exposition

Anaheim, CA
Contact: Julia Stasio, Weingarten Publications, Inc., 38 Chauncy Street, Boston, MA 02111; 617/542-0146

AUGUST

August 4-6

LISP and Functional Programming

Cambridge, MA
Sponsor: ACM
Contact: Richard P. Gabriel, Lucid, Inc., 707 Laurel Street, Menlo Park, CA 94025

August 5-7

ACM SIGCOMM Futures in Communications Conference

Stowe, VT
Contact: Walter Kosinsky, Norwich University, Northfield, VT 05663; 802/485-5011, ext. 237

August 11-13

Symposium on Principles of Distributed Computing

Calgary, Alberta, Canada
Sponsor: ACM SIGACT-SIGOPS
Contact: ACM, 11 West 42nd Street, New York, NY 10036

August 18-22

13th Annual Conference on Computer Graphics and Interactive Techniques

Dallas, TX
Contact: SIGGRAPH '86 Conference Management, 111 E. Wacker Drive, #600, Chicago, IL 60601; 312/644-6610

SEPTEMBER

September 1-5

World Computer Conference

Dublin, Ireland
Sponsor: International Federation for Information Processing
Contact: IFIP Congress '86, 1899 Preston White Drive, Reston, VA 22091; 703/620-8900

September 8-10

NCC-Telecommunications Conference

Philadelphia, PA

Sponsor: AFIPS, ACM, DPMA, IEEE, SCS

Contact: Mike Sherman, AFIPS, 1899 Preston White Drive, Reston, VA 22091; 703/620-8935

September 30-October 2 Northcon '86

Seattle, WA
Contact: Dale Litherland, Education Director, 8110 Airport Blvd., Los Angeles, CA 90045; 800/421-6816, in California, 800/262-4208

CALLS FOR PAPERS

July 15, 1986

Expert Systems in Government Conference

McLean, VA (October 20-24)
Sponsor: IEEE-CS
Contact: Dr. Kamal N. Karna, Communications and Computer Graphics, 823 Flagler Drive, Gaithersburg, MD 20708; 301/921-0392

August 31, 1986


Computers and Applications Peking, China

(June 24-26)
Sponsor: IEEE-CS and Chinese Computer Federation
Submit papers to: Oscar N. Garcia, Department of EE and CS, Room T-637, The George Washington University, 801 22nd Street N.W., Washington, DC 20052; 202/676-7175

Sometimes Waiting For Large Corporations To Introduce New Technology Is Like Watching Apes Evolve

pc2
286

PC2/286
\$1545
PC/XT Size
Shown with
Optional
ALR EGA
Graphics



MOST OF US NEED SOLUTIONS NOW. . . . IN THIS MILLENNIUM!

Our engineers got tired of waiting for a product that could succeed the legendary PC. So with our experience in designing and manufacturing some of the most powerful PC/XT and AT compatibles, we've engineered a PC with today's technology to provide solutions for tomorrow's challenges.

Introducing the ALR PC2/286. The next generation.

A computer with processing power equal to the 8MHz IBM AT computer (introduced April 1986), so you can solve problems 500 times faster than with the original PC.

A computer with more storage capacity. The PC2/286 integrates modern floppy technology allowing you to store 3 times more information than you could before.

Evolutionary Winchester hard disk technology further enhances the power of the PC2/286.

The PC2/286 incorporates all the best hardware developments of yesterday while maintaining the vital link of total software compatibility through Phoenix Bios.


The economy of modern technology allows the PC2/286 to be priced lower than the original PC and most other primitive PC compatibles.

The Result is a \$1545 Complete System.

If you are tired of waiting for a maybe product, or you don't want to buy yesterday's technology, then treat yourself to the performance and features of the PC2/286.

Call and talk to our dealers or sales engineers for the product that says tomorrow.

ENGINEERING ADVANCED COMPUTERS



ALR IN CANADA 416-229-6477

DEALER INFORMATION CONTACT: MR. KIRKEY or MR. ANEIL

Advanced Logic Research, Inc.

10 Chrysler, Irvine, California 92718 - (714) 581-6770

FAX: (714) 581-9240 - TELEX: 5106014525, Answerback Advanced Logic

CIRCLE NO. 116 ON READER SERVICE CARD



EXTEND YOUR COMPUTING POWER



Remote lets you run almost any program, from any location, as if you were there.

Remote is the software that turns your personal computer into a host computer. You or anyone you choose can dial it up from almost any terminal in almost any location, and run most popular application programs such as word processing, spreadsheets, and data base managers.

You'll see the program on your remote terminal screen as if you were seated at the host PC.

While Remote itself becomes transparent in use, it offers some very tangible benefits:

- You don't need a second PC to do the job of two. Almost any terminal or terminal emulator will do. The only software you need is the software in your host PC.

- Each of several different users can call in from anywhere in the world and use the host PC and software. Remote includes a sophisticated electronic mail system with encrypted messages and individual password protection.

- You can transfer files to and from the host computer, using the Crosstalk or XMODEM protocol.

- Programmers and software vendors can use Remote to debug a client's software by phone, without leaving their own offices.

Imagine the potential Remote has in extending the power of your own PC. Ask your dealer about it, or write for details.

CROSSTALK and MICROSTUF are registered trademarks of Microstuf, Inc.
REMOTE is a trademark of Microstuf, Inc.

REMOTE™

MICROSTUF®

1000 Holcomb Woods Parkway
Roswell, Georgia 30076

CIRCLE NO. 167 ON READER SERVICE CARD